



GOVERNMENT OF INDIA
DEPARTMENT OF ARCHAEOLOGY
CENTRAL ARCHAEOLOGICAL
LIBRARY

CLASS ACC. No 2918
CALL No. 910 Str-Jon
Vol. 6





THE LOEB CLASSICAL LIBRARY

FOUNDED BY JAMES LOEB, LL.D.

EDITED BY

† T. E. PAGE, C.H., LITT.D.

E. CAPPS, PH.D., LL.D.

W. H. D. ROUSE, LITT.D.

L. A. POST, M.A.


E. H. WARMINGTON,

M.A., F.R.HIST.SOC.

THE GEOGRAPHY OF STRABO

VI





THE GEOGRAPHY OF STRABO-vol. 6

WITH AN ENGLISH TRANSLATION BY
HORACE LEONARD JONES, PH.D., LL.D.
CORNELL UNIVERSITY

IN EIGHT VOLUMES

VI



LONDON
WILLIAM HEINEMANN LTD
CAMBRIDGE, MASSACHUSETTS
HARVARD UNIVERSITY PRESS
MOML

*First printed 1929
Reprinted 1950*

CENTRAL ARCHAEOLOGICAL
LIBRARY, NEW DELHI.

Acc. No. ... 2918
Date... 30 ... 5 ... 55
Call No. 910 | 512 | Jan.

Printed in Great Britain

Benarby Sakh Bhanon, 1872-1875

CONTENTS

	PAGE
BOOK XIII	3
BOOK XIV	197
A PARTIAL DICTIONARY OF PROPER NAMES	387



THE
GEOGRAPHY OF STRABO
BOOK XIII

ΣΤΡΑΒΩΝΟΣ ΓΕΩΓΡΑΦΙΚΩΝ

ΙΓ'

I

C581 1. Μέχρι μὲν δεῦρο ἀφωρίσθω τὰ περὶ τῆς Φρυγίας· ἐπανιόντες δὲ πάλιν ἐπὶ τὴν Προποντίδα καὶ τὴν ἐφεξῆς τῷ Αἰσήπῳ παραλίαν τὴν αὐτὴν τῆς περιοδείας τάξιν ἀποδώσομεν. ἔστι δὲ Ἰρῶα πρώτη τῆς παραλίας ταύτης, ἣς τὸ πολυθρύλητον, καίπερ ἐν ἐρειπίοις καὶ ἐν ἐρημίᾳ λειπομένης, ὅμως πολυλογίαν οὐ τὴν τυχοῦσαν παρέχει τῇ γραφῇ. πρὸς τοῦτο δὲ συγγνώμης δεῖ καὶ παρακλησεως, ὅπως τὴν αἰτίαν τοῦ μήκους μὴ ἡμῖν μᾶλλον ἀνάπτωσιν¹ οἱ ἐντυγχάνοντες ἢ τοῖς σφόδρα ποθοῦσι τὴν τῶν ἐνδόξων καὶ παλαιῶν γνῶσιν· προσλαμβάνει δὲ τῷ μήκει καὶ τὸ πλῆθος τῶν ἐποικησάντων τὴν χώραν Ἑλλήνων τε καὶ βαρβάρων, καὶ οἱ συγγραφεῖς, οὐχὶ τὰ αὐτὰ γράφοντες περὶ τῶν αὐτῶν, οὐδὲ σαφῶς πάντα· ὧν ἐν τοῖς πρώτοις ἐστὶν Ὁμηρος, εἰκάζειν περὶ τῶν πλείστων παρέχων. δεῖ δὲ καὶ τὰ τούτου διαιτᾶν καὶ τὰ

¹ ἀνάπτωσιν, Kramer, for ἀναπτωεῖν F, ἀνάπτοιεν other MSS. ; so the later editors.

² The translator must here record his obligations to Dr. Walter Leaf for his monumental works on the Troad: his *Troy*, Macmillan and Co., 1912, and his *Strabo on the Troad*, Cambridge, 1923, and his numerous monographs in classical

THE GEOGRAPHY OF STRABO

BOOK XIII

I

1.¹ LET this, then, mark the boundary of Phrygia.² I shall now return again to the Propontis and the coast that comes next after the Aesepus River, and follow the same order of description as before. The first country on this seaboard is the Troad, the fame of which, although it is left in ruins and in desolation, nevertheless prompts in writers no ordinary prolixity. With this fact in view, I should ask the pardon of my readers and appeal to them not to fasten the blame for the length of my discussion upon me rather than upon those who strongly yearn for knowledge of the things that are famous and ancient. And my discussion is further prolonged by the number of the peoples who have colonised the country, both Greeks and barbarians, and by the historians, who do not write the same things on the same subjects, nor always clearly either; among the first of these is Homer, who leaves us to guess about most things. And it is necessary for me to arbitrate between his statements and

periodicals. The results of his investigations in the Troad prove the great importance of similar investigations, on the spot, of various other portions of Strabo's "Inhabited World."

² The reader will find a map of Asia Minor in Vol. V. (at end).

τῶν ἄλλων, ὑπογράφαντας πρότερον ἐν κεφαλαίῳ τὴν τῶν τόπων φύσιν.

2. Ἀπὸ δὴ¹ τῆς Κυζικηνῆς καὶ τῶν περὶ Αἷσηπον τόπων καὶ Γράνικον μέχρι Ἀβύδου καὶ Σηστοῦ τὴν τῆς Προποντίδος παραλίαν εἶναι συμβαίνει, ἀπὸ δὲ Ἀβύδου μέχρι Λεκτοῦ τὰ περὶ Ἴλιον καὶ Τένεδον καὶ Ἀλεξάνδρειαν τὴν Τρωάδα· πάντων δὴ τούτων ὑπέρεται ἡ Ἰδη τὸ ὄρος, μέχρι Λεκτοῦ καθήκουσα· ἀπὸ Λεκτοῦ δὲ μέχρι Καϊκου ποταμοῦ καὶ τῶν Κανῶν λεγομένων ἐστὶ τὰ περὶ Ἄσσον καὶ Ἀδραμύττιον καὶ Ἀταρνεά καὶ Πιάνην καὶ τὸν Ἐλαϊτικὸν κόλπον· οἷς πᾶσιν ἀντιπαρῆκει ἡ τῶν Λεσβίων νῆσος· εἰθ' ἐξῆς τὰ περὶ Κύμην μέχρι Ἑρμοῦ καὶ Φωκαίας, ἥπερ ἀρχὴ μὲν τῆς Ἰωνίας ἐστὶ, πέρας δὲ τῆς Αἰολίδος. τοιούτων δὲ τῶν τόπων ὄντων, ὁ μὲν ποιητὴς ἀπὸ τῶν περὶ Αἷσηπον τόπων καὶ τῶν περὶ τὴν νῦν Κυζικηνὴν χώραν ὑπαγορεύει μάλιστα τοὺς Τρῶας ἄρξαι μέχρι τοῦ Καϊκου ποταμοῦ διηρημένους κατὰ δυναστείας εἰς ὀκτὼ μερίδας ἢ καὶ ἐννέα· τὸ δὲ τῶν ἄλλων ἐπικούρων πλῆθος ἐν τοῖς συμμάχοις διαριθμεῖται.

3. Οἱ δ' ὕστερον τοὺς ὄρους οὐ τοὺς αὐτοὺς λέγουσι καὶ τοῖς ὀνόμασι χρῶνται διηλλαγμένως, αἰρέσεις² νέμοντες πλείους. μάλιστα δὲ αἱ τῶν Ἑλλήνων ἀποικίαι παρεσχέκασιν λόγον· ἦττον μὲν ἡ Ἰωνικὴ· πλείονι γὰρ διέστηκεν τῆς Τρωάδος· ἡ

¹ δὴ, Corais, for δέ; so the later editors.

² Meineke, following conj. of Corais, emends αἰρέσεις to διαιρέσεις.

those of the others, after I shall first have described in a summary way the nature of the region in question.

2. The seaboard of the Propontis, then, extends from Cyzicenê and the region of the Aesepus and Granicus Rivers as far as Abydus and Sestus, whereas the parts round Ilium and Tenedos and the Trojan Alexandria extend from Abydus to Lectum. Accordingly, Mt. Ida, which extends down to Lectum, lies above all these places. From Lectum to the Caïcus River, and to Canae,¹ as it is called, are the parts round Assus and Adramyttium and Atarneus and Pitanê and the Euxine Gulf; and the island of the Lesbians extends alongside, and opposite, all these places. Then come next the parts round Cymê, extending to the Hermus and Phocaea, which latter constitutes the beginning of Ionia and the end of Aeolis. Such being the position of the places, the poet indicates in a general way that the Trojans held sway from the region of the Aesepus River and that of the present Cyzicenê to the Caïcus River,² their country being divided by dynasties into eight, or nine, portions, whereas the mass of their auxiliary forces are enumerated among the allies.

3. But the later authors do not give the same boundaries, and they use their terms differently, thus allowing us several choices. The main cause of this difference has been the colonisations of the Greeks; less so, indeed, the Ionian colonisation, for it was farther distant from the Troad; but most of

¹ On the position of this promontory, see Leaf, *Ann. Brit. School at Athens*, XXII, p. 37, and *Strabo on the Troad*, p. xxxviii.

² See Leaf, *Strabo on the Troad*, p. xli.

δὲ τῶν Αἰολέων παντάπασι· καθ' ὅλην γὰρ ἐσκεδάσθη ἀπὸ τῆς Κυζικηνῆς μέχρι τοῦ Καΐκου καὶ ἐπέλαβεν ἔτι πλεόν τήν μεταξὺ τοῦ Καΐκου καὶ τοῦ Ἑρμου ποταμοῦ. τέτρασι γὰρ δὴ γενεαῖς πρεσβυτέραν φασὶ τὴν Αἰολικὴν ἀποικίαν τῆς Ἰωνικῆς, διατριβὰς δὲ λαβεῖν καὶ χρόνους μακροτέρους. Ὀρέστην μὲν γὰρ ἄρξαι τοῦ στόλου, τούτου δ' ἐν Ἀρκαδία τελευτήσαντος τὸν βίον, διαδέξασθαι τὸν υἱὸν αὐτοῦ Πενθίλον καὶ προελθεῖν μέχρι Θράκης ἐξήκοντα ἔτεσι τῶν Τρωικῶν ὕστερον, ὑπ' αὐτὴν τὴν τῶν Ἡρακλείδων εἰς Πελοπόννησον κάθοδον· εἴτ' Ἀρχέλαον, υἱὸν ἐκείνου, περαιῶσαι τὸν Αἰολικὸν στόλον εἰς τὴν νῦν Κυζικηνὴν τὴν περὶ τὸ Δασκύλιον· Γρᾶν δέ, τὸν υἱὸν τούτου τὸν νεώτατον, προελθόντα μέχρι τοῦ Γρανίκου ποταμοῦ καὶ παρεσκευασμένον ἄμεινον περαιῶσαι τὸ πλεόν τῆς στρατιᾶς εἰς Λέσβον καὶ κατασχεῖν αὐτήν· Κλεῦν δέ, τὸν Δώρον, καὶ Μαλαόν, καὶ αὐτοὺς ἀπογόνους ὄντας Ἀγαμέμνονος, συναγαγεῖν μὲν τὴν στρατιὰν κατὰ τὸν αὐτὸν χρόνον, καθ' ὃν καὶ Πενθίλος· ἀλλὰ τὸν μὲν τοῦ Πενθίλου στόλον φθῆναι περαιωθέντα ἐκ τῆς Θράκης εἰς τὴν Ἀσίαν, τούτους δὲ περὶ τὴν Λοκρίδα καὶ τὸ Φρίκιον ὄρος διατρίψαι πολὺν χρόνον, ὕστερον δὲ διαβάντας κτίσαι τὴν Κύμην τὴν Φρικωνίδα κληθεῖσαν ἀπὸ τοῦ Λοκρικοῦ ὄρους.

4. Τῶν Αἰολέων τοίνυν καθ' ὅλην σκεδασθέντων τὴν χώραν, ἣν ἔφαμεν ὑπὸ τοῦ ποιητοῦ λέγεσθαι Τρωικὴν, οἱ¹ ὕστερον οἱ μὲν πᾶσαν Αἰολίδα προσαγορεύουσιν, οἱ δὲ μέρος, καὶ Τροίαν

¹ ὅ, after οἱ, Corais suggests; so the later editors.

all that of the Aeolians, for their colonies were scattered throughout the whole of the country from Cyzicenê to the Caïcus River, and they went on still farther to occupy the country between the Caïcus and Hermus Rivers. In fact, the Aeolian colonisation, they say, preceded the Ionian colonisation by four generations, but suffered delays and took a longer time; for Orestes, they say, was the first leader of the expedition, but he died in Arcadia, and his son Penthilus succeeded him and advanced as far as Thrace sixty years after the Trojan War, about the time of the return of the Heracleidae to the Peloponnesus; and then Archelaüs¹ the son of Penthilus led the Aeolian expedition across to the present Cyzicenê near Dascylium; and Gras, the youngest son of Archelaüs, advanced to the Granicus River, and, being better equipped, led the greater part of his army across to Lesbos and occupied it. And they add that Cleues, son of Dorus, and Malaüs, also descendants of Agamemnon, had collected their army at about the same time as Penthilus, but that, whereas the fleet of Penthilus had already crossed over from Thrace to Asia, Cleues and Malaüs tarried a long time round Locris and Mt. Phricius, and only later crossed over and founded the Phryconian Cymê, so named after the Locrian mountain.

4. The Aeolians, then, were scattered throughout the whole of that country which, as I have said, the poet called Trojan. As for later authorities, some apply the name to all Aeolis, but others to only a part of it; and some to the whole of Troy,

¹ Pausanias (3. 2. 1) spells his name "Echelas."

οἱ μὲν ὅλην, οἱ δὲ μέρος αὐτῆς, οὐδὲν ἕλως ἀλλήλοισι ὁμολογοῦντες. εὐθὺς γὰρ ἐπὶ τῶν κατὰ τὴν Προποντίδα τόπων ὁ μὲν Ὅμηρος ἀπὸ Αἰσῆπον τὴν ἀρχὴν ποιεῖται τῆς Τρωάδος· Εὐδοξος δὲ ἀπὸ Πριάπου¹ καὶ Ἀρτάκης, τοῦ ἐν τῇ Κυζικηνῶν νήσῳ χωρίου ἀνταίροντος τῷ Πριάπῳ, συστέλλων ἐπ' ἑλαττον τοὺς ὅρους· Δαμάστης δ' ἔτι μᾶλλον συστέλλει ἀπὸ Παρίου· καὶ γὰρ οὗτος μὲν ἕως Λεκτοῦ προάγει, ἄλλοι δ' ἄλλως· Χάρων δ' ὁ Λαμψακηνὸς τριακοσίους ἄλλους ἀφαιρεῖ σταδίου, ἀπὸ Πρακτίου ἀρχόμενος· τοσοῦτοι γὰρ εἰσιν ἀπὸ Παρίου εἰς Πράκτιον· ἕως μέντοι Ἀδραμυτιτίου πρόεισι· Σκύλαξ δὲ ὁ Καρυανδεὺς ἀπὸ Ἀβύδου ἀρχεται· ὁμοίως δὲ τὴν Αἰολίδα Ἐφορος μὲν λέγει ἀπὸ Ἀβύδου μέχρι Κύμης, ἄλλοι δ' ἄλλως.

5. Τοπογραφεῖ δὲ κάλλιστα τὴν ὄντως λεγόμενὴν Τροίαν ἢ τῆς Ἰδης θέσις, ὅρους ὑψηλοῦ βλέποντος πρὸς δύσιν καὶ τὴν ταύτῃ θάλατταν, μικρὰ δ' ἐπιστρέφοντος² καὶ πρὸς ἄρκτον καὶ τὴν ταύτῃ παραλίαν. ἔστι δὲ αὕτη μὲν τῆς Προποντίδος ἀπὸ τῶν περὶ Ἀβυδὸν στενῶν ἐπὶ τὸν Αἰσῆπον καὶ τὴν Κυζικηνήν, ἢ δ' ἐσπερία θάλαττα ὃ τε Ἑλλήσποντός ἐστιν³ ὁ ἔξω⁴ καὶ τὸ Αἰγαῖον πέλαγος. πολλοὺς δ' ἔχουσα πρόποδας

¹ καὶ Ἀρτάκης . . . Πριάπῳ, Leaf, in *Journal of Hellenic Studies*, XXXVII., p. 22, would delete; so in his *Strabo on the Troad*, p. 2 (see his note on p. 47).

² ἐπιστρέφοντος Εἰς, ἐπιστραφέντος other MSS.

³ δ, before ἔξω, Kramer inserts: so the later editors.

⁴ ἔξω EF, ἐν ᾧ other MSS.

¹ *Iliad* 2. 824. See § 9 following.

but others to only a part of it, not wholly agreeing with one another about anything. For instance, in reference to the places on the Propontis, Homer makes the Troad begin at the Aesepus River,¹ whereas Eudoxus makes it begin at Priapus and Artacê, the place on the island of the Cyziceni that lies opposite Priapus,² and thus contracts the limits; but Damastes contracts the country still more, making it begin at Parium; and, in fact, Damastes prolongs the Troad to Lectum, whereas other writers prolong it differently. Charon of Lamp-sacus diminishes its extent by three hundred stadia more, making it begin at Practius,³ for that is the distance from Parium to Practius; however, he prolongs it to Adramyttium. Seylax of Caryanda makes it begin at Abydus; and similarly Ephorus says that Aeolis extends from Abydus to Cymê, while others define its extent differently.⁴

5. But the topography of Troy, in the proper sense of the term, is best marked by the position of Mt. Ida, a lofty mountain which faces the west and the western sea but makes a slight bend also towards the north and the northern seaboard.⁵ This latter is the seaboard of the Propontis, extending from the strait in the neighbourhood of Abydus to the Aesepus River and Cyzicenê, whereas the western sea consists of the outer Hellespont⁶ and the Aegean Sea. Mt. Ida has many foot-hills, is like

¹ See Leaf, *Strabo on the Troad*, p. 47.

² Whether city or river (see 13. 1. 21).

³ See Leaf's definition of the Troad (*Troy*, p. 171).

⁴ See Leaf, *Strabo on the Troad*, p. 48.

⁵ On the meaning of the term Hellespont, see Book VII, Frag. 57 (58), and Leaf (*Strabo on the Troad*), p. 50.

ἡ Ἰδῆ καὶ σκολοπενδρώδης οὖσα τὸ σχῆμα
 ἐσχάτοις ἀφορίζεται τούτοις, τῷ τε περὶ τὴν
 Ζέλειαν ἀκρωτηρίῳ καὶ τῷ καλουμένῳ Λεκτῷ, τῷ
 μὲν τελευτῶντι εἰς τὴν μεσόγαιαν μικρὸν ὑπὲρ
 τῆς Κυζικηνῆς· καὶ δὴ καὶ ἔστι νῦν ἡ Ζέλεια
 τῶν Κυζικηνῶν· τὸ δὲ Λεκτὸν εἰς τὸ πέλαγος
 καθήκει τὸ Αἰγαῖον, ἐν παράπλῳ κείμενον τοῖς ἐκ
 Τενέδου πλέουσιν εἰς Λέσβον.

Ἰδην δ' ἴκανον πολυπίδακα μητέρα θηρῶν,
 Λεκτόν, ὅθι¹ πρῶτον λιπέτην ἄλα

Ὑπνος καὶ ἡ Ἥρα, τοῖς οὖσιν οἰκείως τοῦ ποιητοῦ
 φράζοντος τὸ Λεκτόν· καὶ γὰρ ὅτι τῆς Ἰδῆς ἐστὶ
 τὸ Λεκτόν καὶ διότι πρώτη ἀπόβασις ἐκ θαλάττης
 αὕτη τοῖς ἐπὶ τὴν Ἰδην ἀνιούσιν, εἴρηκεν ὀρθῶς,²
 καὶ τὸ πολυπίδακον· εὐνδρότατον γὰρ κατὰ ταῦτα
 μάλιστα³ τὸ ὄρος, δηλοῖ δὲ τὸ πλῆθος τῶν
 ποταμῶν,

ὅσσοι ἀπ' Ἰδαίων ὀρέων ἄλαδε προρέουσι,
 Ῥῆσός θ' Ἑπτάπορός τε

καὶ οἱ ἐξῆς, οὓς ἐκεῖνος εἴρηκε καὶ ἡμῖν νυνὶ
 πάρεστιν ὁρᾶν. τοὺς δὴ πρόποδας τοὺς ἐσχά-
 τους ἐφ' ἐκάτερα φράζων⁴ οὕτως τὸ Λεκτόν καὶ
 τὴν Ζέλειαν, οἰκείως τούτων καὶ ἀκρώρειαν
 ἀφορίζει Γάργαρον, ἄκρον λέγων⁵ καὶ γὰρ νῦν

¹ ὅθι, Xylander, for ὅτι; so the later editors.

² καὶ τὸ . . . ὁρᾶν, ejected by Meineke.

³ κατὰ ταῦτα μάλιστα, Leaf brackets (see his note, *op. cit.*,
 p. 49).

⁴ φράζων, Meineke, from conj. of Kramer, for ὁρᾶν.

the scolopendra¹ in shape, and is defined by its two extreme limits: by the promontory in the neighbourhood of Zeleia and by the promontory called Lectum, the former terminating in the interior slightly above Cyzicenê (in fact, Zeleia now belongs to the Cyziceni), whereas Lectum extends to the Aegæan Sea, being situated on the coasting-voyage between Tenedos and Lesbos. When the poet says that Hypnos and Hera "came to many-fountained Ida, mother of wild beasts, to Lectum, where first the two left the sea,"² he describes Lectum in accordance with the facts; for he rightly states that Lectum is a part of Mt. Ida, and that Lectum is the first place of disembarkation from the sea for those who would go up to Mt. Ida, and also that the mountain is "many-fountained," for there in particular the mountain is abundantly watered, as is shown by the large number of rivers there, "all the rivers that flow forth from the Idaean mountains to the sea, Rhesus and Heptaporus"³ and the following,⁴ all of which are named by the poet and are now to be seen by us. Now while Homer thus describes Lectum⁵ and Zeleia⁶ as the outermost foot-hills of Mt. Ida in either direction, he also appropriately distinguishes Gargarus from them as a summit, calling it "topmost."⁷ And indeed at the present

¹ A genus of myriapods including some of the largest centipedes.

² *Iliad* 14. 283.

³ *Iliad* 12. 19.

⁴ The Granicus, Aesepus, Scamander, and Simoeis.

⁵ *Iliad* 14. 284.

⁶ *Iliad* 2. 824.

⁷ *Iliad* 14. 292, 352; 15. 152.

⁸ λέγων, Kramer, for τέρων CFμορ, τερον D with ε above τ man. sec., whence ἔτερον ἢ and Tzschucke.

Γάργαρον ἐν τοῖς ἄνω μέρεσι τῆς Ἰδῆς δείκνυται τόπος, ἀφ' οὗ τὰ νῦν Γάργαρα πόλις Αἰολικῇ. ἐντὸς μὲν οὖν τῆς Ζελείας καὶ τοῦ Λεκτοῦ πρῶτά ἐστιν ἀπὸ τῆς Προποντίδος ἀρξαμένοις τὰ¹ μέχρι τῶν κατ' Ἀβυδον στενῶν· εἴτ' ἔξω τῆς Προποντίδος τὰ μέχρι Λεκτοῦ.

C 584 6. Κάμφαντι δὲ τὸ Λεκτὸν ἀναχεῖται κόλπος μέγας, ὃν ἡ Ἰδῆ ποιεῖ πρὸς τὴν ἡπειρον ἀναχωροῦσα² ἀπὸ τοῦ Λεκτοῦ καὶ αἱ Κάναι, τὸ ἐκ θατέρου μέρους ἀντικείμενον ἀκρωτήριον τῷ Λεκτῷ· καλοῦσι δ' οἱ μὲν Ἰδαῖον κόλπον, οἱ δ' Ἀδραμυττηνόν. ἐν τούτῳ δὲ αἱ τῶν Αἰολέων πόλεις μέχρι τῶν ἐκβολῶν τοῦ Ἑρμου, καθάπερ εἰρήκαμεν. εἴρηται δὲ ἐν τοῖς ἔμπροσθεν ὅτι τοῖς ἐκ Βυζαντίου πλέουσι πρὸς νότον ἐπ' εὐθείας ἐστὶν ὁ πλοῦς, πρῶτον ἐπὶ Σηστὸν καὶ Ἀβυδον διὰ μέσης τῆς Προποντίδος, ἔπειτα τῆς παραλίας³ τῆς Ἀσίας μέχρι Καρίας. ταύτην δὲ φυλάττοντας χρὴ τὴν ὑπόθεσιν ἀκούειν τῶν ἐξῆς, κἂν λέγωμεν κόλπους τινὰς ἐν τῇ παραλίᾳ, τὰς τε ἄκρας δεῖ νοεῖν τὰς ποιούσας αὐτοὺς ἐπὶ τῆς αὐτῆς γραμμῆς κειμένας, ὥσπερ τινὸς μεσημβρινῆς.

7. Ἐκ δὲ τῶν ὑπὸ τοῦ ποιητοῦ λεγομένων εἰκάζουσιν οἱ φροντίσαντες περὶ τούτων πλέον τι, πᾶσαν τὴν παραλίαν ταύτην ὑπὸ τοῖς Ἑλλήσι γεγεμέναι, διηρημένην μὲν εἰς δυναστείας ἐννέα,

¹ τὰ, before μέχρι, Groskurd inserts; so the later editors.

² ἀναχωροῦσα E, ἀποχωροῦσα other MSS.; so Leaf.

³ τῆς παραλίας is indefensible; perhaps παρὰ τὴν παραλίαν (Kramer).

¹ See Leaf, *Strabo on the Troad*, p. xlv.

time people point out in the upper parts of Ida a place called Gargarum, after which the present Gargara, an Aeolian city, is named. Now between Zeleia and Lectum, beginning from the Propontis, are situated first the parts extending to the straits at Abydus, and then, outside the Propontis, the parts extending to Lectum.

6. On doubling Lectum one encounters a large wide-open gulf, which is formed by Mt. Ida as it recedes from Lectum to the mainland, and by Canae, the promontory opposite Lectum on the other side. Some call it the Idaean Gulf, others the Adramytene. On this gulf¹ are the cities of the Aeolians, extending to the outlets of the Hermus River, as I have already said.² I have stated in the earlier parts of my work³ that, as one sails from Byzantium towards the south, the route lies in a straight line, first to Sestus and Abydus through the middle of the Propontis, and then along the coast of Asia as far as Caria. It behooves one, then, to keep this supposition in mind as one listens to the following; and, if I speak of certain gulfs on the coast, one must think of the promontories which form them as lying in the same line, a meridian-line, as it were.

7. Now as for Homer's statements, those who have studied the subject more carefully⁴ conjecture from them that the whole of this coast became subject to the Trojans, and, though divided into nine dynasties, was under the sway of Priam at the

¹ 13. 1. 2 (see Leaf's article cited in foot-note there).

² Strabo refers to his discussion of the meridian-line drawn by Eratosthenes through Byzantium, Rhodes, Alexandria, Syenê, and Meroë (see 2. 5. 7 and the *Frontispiece* in Vol. I).

⁴ Strabo refers to Demetrius of Scepsis and his followers.

ὑπὸ δὲ τῷ Πριάμῳ τεταγμένην κατὰ τὸν Ἰλιακὸν πόλεμον καὶ λεγομένην Τροίαν· δῆλον δὲ ἐκ τῶν κατὰ μέρος. οἱ γὰρ περὶ τὸν Ἀχιλλέα τειχήρεις ὀρώντες τοὺς Ἰλίας κατ' ἀρχάς, ἔξω ποιεῖσθαι τὸν πόλεμον ἐπεχείρησαν καὶ περιόντες ἀφαιρεῖσθαι τὰ κύκλῳ·

δώδεκα δὴ σὺν νηυσὶ πόλεις ἀλάπαξ' ἀνθρώπων,

πεζὸς δ' ἑνδεκά φημι κατὰ Τροίην ἐρίβωλον.

Τροίαν γὰρ λέγει τὴν πεπορθημένην ἡπειρον· πεπόρθηται δὲ σὺν ἄλλοις τόποις καὶ τὰ ἀντικείμενα τῇ Λέσβῳ τὰ περὶ Θήβην καὶ Λυρνησσὸν καὶ Πήδασον τὴν τῶν Λελέγων καὶ ἔτι ἢ τοῦ Εὐρυπύλου τοῦ Τηλέφου παιδός·

ἄλλ' οἷον τὸν Τηλεφίδην κατενῆρατο χαλκῷ, ὁ Νεοπτόλεμος, ἦρω Εὐρύπυλον. ταῦτα δὴ πεπορθῆσθαι λέγει καὶ αὐτὴν τὴν Λέσβον·

ὅτε Λέσβον εὐκτιμένην ἔλεν¹ αὐτός· καὶ

πέρσε δὲ Λυρνησσὸν καὶ Πήδασον· καὶ

Λυρνησσὸν διαπορθήσας καὶ τείχεα Θήβης. ἐκ μὲν Λυρνησσοῦ ἢ Βρισηὶς ἐάλω

τὴν ἐκ Λυρνησσοῦ ἐξείλετο·

ἣς ἐν τῇ ἀλώσει τὸν Μύνητα² καὶ τὸν Ἐπίστροφον πεσεῖν, φησὶν, ὡς ἢ Βρισηὶς θρηνοῦσα τὸν Πάτροκλον δηλοῖ·

time of the Trojan War and was called Troy. And this is clear from his detailed statements. For instance, Achilles and his army, seeing at the outset that the inhabitants of Ilium were enclosed by walls, tried to carry on the war outside and, by making raids all round, to take away from them all the surrounding places: "Twelve cities of men I have laid waste with my ships, and eleven, I declare, by land throughout the fertile land of Troy."¹ For by "Troy" he means the part of the mainland that was sacked by him; and, along with other places, Achilles also sacked the country opposite Lesbos in the neighbourhood of Thebê and Lyrnessus and Pedasus,² which last belonged to the Leleges, and also the country of Eurypylus the son of Telephus. "But what a man was that son of Telephus who was slain by him with the bronze,"³ that is, the hero Eurypylus, slain by Neoptolemus. Now the poet says that these places were sacked, including Lesbos itself: "when he himself took well-built Lesbos"; and "he sacked Lyrnessus⁴ and Pedasus";⁵ and "when he laid waste Lyrnessus and the walls of Thebê."⁶ It was at Lyrnessus that Briseïs was taken captive, "whom he carried away from Lyrnessus";⁷ and it was at her capture, according to the poet, that Mynes and Epistrophus fell, as is shown by the lament of Briseïs over

¹ *Iliad* 9. 328.² *Iliad* 20. 92.³ *Odyssey* 11. 518.⁴ *Iliad* 9. 129.⁵ *Iliad* 20. 92.⁶ *Iliad* 2. 691.⁷ *Iliad* 2. 690.¹ *ἐλεν*, Xylander, for *ἐλες*; so the later editors.² *καὶ τὸν Ἐπίστροφον*, Meineke ejects.

οὐδὲ μὲν οὐδέ μ' ἔασκες, ὅτ' ἄνδρ' ἐμὸν ὤκυν
 Ἀχιλλεὺς
 ἔκτεινεν, πέρσεν δὲ πόλιν θείοιο Μύνητος,
 κλαίειν·

C 585 ἐμφαίνει γὰρ τὴν Λυρνησσὸν λέγων πόλιν θείοιο
 Μύνητος, ὡς ἂν δυναστευομένην ὑπ' αὐτοῦ, καὶ
 ἐνταῦθα πεσεῖν αὐτὸν μαχόμενον· ἐκ δὲ τῆς Θήβης
 ἡ Χρυσῆις ἐλήφθη·

ὥχόμεθ' ἐς Θήβην ἱερὴν πόλιν Ἡετίωνος·
 ἐκ δὲ τῶν ἀχθέντων ἐκεῖθεν φησιν εἶναι τὴν
 Χρυσῆίδα. ἐνθένδε δ' ἦν καὶ ἡ Ἀνδρομάχη¹

Ἀνδρομάχη θυγάτηρ μεγαλήτορος Ἡετίωνος·
 Ἡετίων, ὃς ἔναιεν ὑπὸ Πλάκῳ ὑληέσση,
 Θήβῃ Ὑποπλακίῃ, Κιλίκεσσ' ἀνδρεσσιν ἀνάσ-
 σων.

δευτέρα οὖν αὕτη δυναστεία Τρωικὴ μετὰ τὴν
 ὑπὸ Μύνητι. οἰκείως δὲ τούτοις καὶ τὸ ὑπὸ τῆς
 Ἀνδρομάχης λεχθὲν οὕτως,

Ἔκτορ, ἐγὼ δύστηνος· ἰὴ ἄρα γεινόμεθ' αἴση
 ἀμφότεροι, σὺ μὲν ἐν Τροίῃ Πριάμου ἐνὶ οἴκῳ,
 αὐτὰρ ἐγὼ Θήβησιν,

οὐκ οἶονται δεῖν ἐξ εὐθείας ἀκούειν, σὺ μὲν ἐν
 Τροίῃ, αὐτὰρ ἐγὼ Θήβησιν ἢ Θήβηθεν,² ἀλλὰ καθ'
 ὑπερβατόν· ἀμφότεροι ἐν Τροίῃ,³ σὺ μὲν Πριάμου
 ἐνὶ οἴκῳ, αὐτὰρ ἐγὼ Θήβησι. τρίτη δ' ἐστὶν
 ἡ τῶν Λελέγων, καὶ αὕτη Τρωικὴ,

Ἄλτεω, ὃς Λελέγεσσι φιλοπτολέμοισιν ἀνάσ-
 σει·

οὗ τῇ θυγατρὶ συνελθὼν Πριάμος γεννᾷ τὸν

Patroclus: "thou wouldst not even, not even, let me weep when swift Achilles slew my husband and sacked the city of divine Mynes";¹ for in calling Lyrnessus "the city of divine Mynes" the poet indicates that Mynes was dynast over it and that he fell in battle there. But it was at Thebê that Chryseïs was taken captive: "We went into Thebê, the sacred city of Eëtion";² and the poet says that Chryseïs was part of the spoil brought from that place.³ Thence, too, came Andromachê: "Andromachê, daughter of great-hearted Eëtion; Eëtion who dwelt 'neath wooded Placus in Thebê Hypoplacia,"⁴ and was lord over the men of Cilicia."⁵ This is the second Trojan dynasty after that of Mynes. And consistently with these facts writers think that the following statement of Andromachê, "Hector, woe is me! surely to one doom we were born, both of us—thou in Troy in the house of Priam, but I at Thebae,"⁶ should not be interpreted strictly, I mean the words "thou in Troy, but I at Thebae" (or Thebê), but as a case of hyperbaton, meaning "both of us in Troy—thou in the house of Priam, but I at Thebae." The third dynasty was that of the Leleges, which was also Trojan: "Of Altes, who is lord over the war-loving Leleges,"⁷ by whose daughter Priam begot Lycaon and Polydorus.

¹ *Iliad* 19. 295.² *Iliad* 1. 366.³ *Iliad* 1. 369.⁴ The epithet means "'neath Placus."⁵ *Iliad* 22. 477.⁶ *Iliad* 22. 477.⁷ *Iliad* 21. 86.¹ ἐνθ' ἔνδε . . . Ἀνδρομάχῃ, found only in the Epitome.² σὺ μὲν . . . Θήβῃθεν, Meineke ejects.³ ἐν Τροίῃ Epitome, ἐκ Τροίης MSS.

Λυκάονα καὶ Πολύδωρον. καὶ μὴν οἳ γε ὑπὸ τῷ
"Ἐκτορι ἐν τῷ καταλόγῳ ταπτόμενοι λέγονται
Τρῶες·

Τρωσὶ μὲν ἡγεμόνευε μέγας κορυθαίολος Ἐκτωρ.
εἶθ' οἱ ὑπὸ τῷ Αἰνεΐᾳ·

Δαρδανίων αὐτ' ἦρχεν ἐὺς παῖς Ἀγχίσαο·
καὶ οὗτοι Τρῶες· φησὶ γοῦν·

Αἰνεΐα, Τρώων βουληφόρε.
εἶθ' οἱ ὑπὸ Πανδάρῳ Λύκιοι, οὓς καὶ αὐτοὺς καλεῖ
Τρῶας·

οἱ δὲ Ζέλειαν ἔναιον ὑπαὶ πόδα νεΐατον Ἴδης,
Ἀφνειοί, πίνοντες ὕδωρ μέλαν Αἰσήμειο,
Τρῶες· τῶν αὐτ' ἦρχε Λυκάονος ἀγλαὸς υἱός,
Πάνδαρος.

ἕκτη δ' αὕτη δυναστεία. καὶ μὴν οἳ γε μεταξὺ
τοῦ Αἰσήμεου καὶ Ἀβύδου Τρῶες· ὑπὸ μὲν γὰρ
τῷ Ἀσίῳ ἐστὶ τὰ περὶ Ἀβυδον·

οἱ δ' ἄρα Περκώτην καὶ Πράκτιον ἀμφενέ-
μοντο,
καὶ Σηστὸν καὶ Ἀβυδον ἔχον καὶ διὰν Ἀρίσβην,
τῶν αὐτ' Ἐρτακίδης ἦρχ' Ἀσιος·

ἄλλ' ἐν Ἀβύδῳ μὲν υἱὸς τοῦ Πριάμου διέτριβεν,
ἵππους νέμων, πατρῶας δηλονότι·

ἄλλ' υἱὸν Πριάμοιο νόθον βάλε Δημοκόωντα,
ὃς οἱ Ἀβυδόθεν ἦλθε παρ' ἵππων ὠκείων·

C 586 ἐν δὲ Περκώτῃ υἱὸς Ἰκετάονος ἐβουνόμει, οὐκ
ἀλλοτρίας οὐδ' οὗτος βοῦς·

And indeed those who are placed under Hector in the *Catalogue* are called Trojans: "The Trojans were led by great Hector of the flashing helmet."¹ And then come those under Aeneias: "The Dardanians in turn were commanded by the valiant son of Anchises";² and these, too, were Trojans; at any rate, the poet says, "Aeneias, counsellor of the Trojans."³ And then come the Lycians under Pandarus, and these also he calls Trojans: "And those who dwelt in Zeleia beneath the nethermost foot of Ida, Aphneii,⁴ who drink the dark water of the Aesepus, Trojans; these in turn were commanded by Pandarus, the glorious son of Lycaon."⁵ And this was the sixth dynasty. And indeed those who lived between the Aesepus River and Abydus were Trojans; for not only were the parts round Abydus subject to Asius, "and they who dwelt about Percotê and Practius⁶ and held Sestus and Abydus and goodly Arisbê⁷—these in turn were commanded by Asius the son of Hyrtacus,"⁸ but a son of Priam lived at Abydus, pasturing mares, clearly his father's: "But he smote Democoön, the bastard son of Priam, for Priam had come from Abydus from his swift mares";⁹ while in Percotê a son of Hicetaon was pasturing kine, he likewise pasturing kine that

¹ *Iliad* 2. 816.² *Iliad* 2. 819.³ *Iliad* 20. 83.⁴ Aphneii is now taken merely as an adjective, meaning "wealthy" men, but Strabo seems to concur in the belief that the people in question were named "Aphneii" after Lake "Aphnitis" (see 13. 1. 9).⁵ *Iliad* 2. 824.⁶ Whether city or river (see 13. 1. 21).⁷ On Arisbê, see Leaf, *Troy*, 193 ff.⁸ *Iliad* 2. 835.⁹ *Iliad* 4. 499.

πρῶτον δ' Ἴκεταονίδην ἐνέειπεν¹
 Ἰφθιμον Μελάνιππον· ὁ δ' ὄφρα μὲν εἰλίποδας
 βοῦς

βόσκ' ἐν Περκώτῃ·

ὥστε καὶ αὕτη ἂν εἴη Τρωὰς καὶ ἡ ἐφεξῆς ἕως
 Ἀδραστείας· ἦρχον γὰρ αὐτῆς

ὡς δὴ δύο Μέροπος Περκωσίου.

πάντες μὲν δὴ Τρῶες οἱ ἀπὸ Ἀβύδου μέχρι Ἀδρα-
 στείας, δίχα μέντοι διηρημένοι, οἱ μὲν ὑπὸ τῷ
 Ἀσίῳ, οἱ δ' ὑπὸ τοῖς Μεροπίδαις· καθάπερ καὶ ἡ
 τῶν Κιλικίων διττή, ἡ μὲν Θηβαϊκή, ἡ δὲ Λυρνησ-
 σίς· ἐν αὐτῇ² δ' ἂν λεχθείη ἡ ὑπὸ Εὐρυπύλῳ
 ἐφεξῆς οὖσα τῇ Λυρνησιίδι. ὅτι δὲ τούτων
 ἀπάντων ἦρχεν ὁ Πρίαμος, οἱ τοῦ Ἀχιλλέως
 λόγοι πρὸς τὸν Πρίαμον σαφῶς ἐμφανίζουσι·

καὶ σε, γέρον, τὸ πρὶν μὲν ἀκούομεν ὄλβιον
 εἶναι,

ὅσσον Λέσβος ἄνω Μάκαρος πόλις ἐντὸς
 ἑέργει,

καὶ Φρυγίῃ καθύπερθε, καὶ Ἑλλήσποντος
 ἀπείρων.³

¹ ἐνέειπεν, Kramer, for ἐνεειπεν x, ἐνέειπεν other MSS.

² For ἐν αὐτῇ, Madvig conj. ἐνάτῃ.

³ After ἀπείρων Müller-Dübner add another line (546) from Homer, τῶν σε, γέρον, πλοῦτόν τε καὶ υἱάσι φασι κεκάσθαι, as necessary to the sense; so Leaf (*Strabo on the Troad*, pp. 6 and 57).

¹ i.e. the kine belonged to Priam. This son of Hicetaon, a kinsman of Hector (*Iliad* 15. 545), "dwelt in the house of Priam, who honoured him equally with his own children" (*Iliad* 15. 551).

belonged to no other:¹ "And first he rebuked mighty Melanippus the son of Hicetaon, who until this time had been wont to feed the kine of shambling gait in Percotê";² so that this country would be a part of the Troad, as also the next country after it as far as Adrasteia, for the leaders of the latter were "the two sons of Merops of Percotê."³ Accordingly, the people from Abydus to Adrasteia were all Trojans, although they were divided into two groups, one under Asius and the other under the sons of Merops, just as Cilicia⁴ also was divided into two parts, the Theban Cilicia and the Lyrnessian;⁵ but one might include in the Lyrnessian Cilicia the territory subject to Eurypylus, which lay next to the Lyrnessian Cilicia.⁶ But that Priam was ruler of these countries, one and all, is clearly indicated by Achilles' words to Priam: "And of thee, old sire, we hear that formerly thou wast blest; how of all that is enclosed by Lesbos, out at sea, city of Macar, and by Phrygia in the upland, and by the boundless Hellespont."⁷

¹ *Iliad* 15. 546.

² *Iliad* 2. 831.

³ The Trojan Cilicia (see 13. I. 70).

⁴ See 13. I. 60-61.

⁵ The eight dynasties were (1) that of Mynes, (2) that of Estion, (3) that of Altes, (4) that of Hector, (5) that of Acneias, (6) that of Pandarus, (7) that of Asius, and (8) that of the two sons of Merops. If, however, there were *nine* dynasties (see 13. I. 2), we may assume that the ninth was that of Eurypylus (see 13. I. 70), unless, as Choiseul-Gouffier (*Voyage Pittoresque de la Grèce*, vol. ii, cited by Gosselin) think, it was that of the island of Lesbos.

⁷ *Iliad* 24. 543. The quotation is incomplete without the following words of Homer: "o'er all these, old sire, thou wast pre-eminent, they say, because of thy wealth and thy sons."

8. Τότε μὲν οὖν τοιαῦτα ὑπῆρχεν, ὕστερον δὲ ἠκολούθησαν μεταβολαὶ παντοῖαι. τὰ μὲν γὰρ περὶ Κύζικον Φρύγες ἐπάκησαν ἕως Πρακτίου, τὰ δὲ περὶ Ἀβυδον Θράκες· ἔτι δὲ πρότερον τούτων ἀμφοῖν Βέβρυκες καὶ Δρύορες.¹ τὰ δ' ἐξῆς Τρήρες, καὶ οὗτοι Θράκες· τὸ δὲ Θήβης πεδίον Λυδοί, οἱ τότε Μήρονες, καὶ Μυσῶν οἱ περιγεγόμενοι τῶν ὑπὸ Τηλέφῳ πρότερον καὶ Τεύθραντι. οὕτω δὴ τοῦ ποιητοῦ τὴν Αἰολίδα καὶ τὴν Τροίαν εἰς ἓν συντιθέντος, καὶ τῶν Αἰολέων τὴν ἀπὸ τοῦ Ἑρμου πᾶσαν μέχρι τῆς κατὰ Κύζικον παραλίας κατασχόντων καὶ πόλεις κτισάντων, οὐδ' ἂν ἡμεῖς ἀτόπως περιοδεύσαιμεν, εἰς ταῦτ' οὐ συντιθέντες² τὴν τε Αἰολίδα νῦν ἰδίως λεγομένην τὴν ἀπὸ τοῦ Ἑρμου μέχρι Λεκτοῦ καὶ τὴν ἐφεξῆς μέχρι τοῦ Αἰσηπον· ἐν γὰρ τοῖς καθ' ἕκαστα διακρινοῦμεν πάλιν, παρατιθέντες ἅμα τοῖς νῦν οὖσι τὰ ὑπὸ τοῦ ποιητοῦ καὶ τῶν ἄλλων λεγόμενα.

9. Ἔστιν οὖν μετὰ τὴν τῶν Κυζικηνῶν πόλιν καὶ τὸν Αἰσηπον ἀρχὴ τῆς Τρωάδος καθ' Ὅμηρον. λέγει δ' ἐκεῖνος μὲν οὕτω περὶ αὐτῆς·

οὐ δὲ Ζέλειαν ἔναιον ὑπαὶ πόδα νεΐατον Ἰδης
Ἀφνειοί, πίνοντες ὕδωρ μέλαν Αἰσηπιοιο,
Τρῶες· τῶν αὐθ' ἦρχε Λυκάονος ἀγλαὸς υἱός,
Πάνδαρος.

C 587 τούτους δὲ ἐκάλει καὶ Λυκίους· Ἀφνειοὺς δὲ ἀπὸ

¹ For Δρύορες Leaf conj. Δολιόρες.

² EFmaz have συνθέντες.

¹ Leaf (*Strabo on the Troad*, p. 61) makes a strong case for emending "Dryopes" to "Doliones," but leaves the Greek text (p. 7) unchanged.

8. Now such were the conditions at the time of the Trojan War, but all kinds of changes followed later; for the parts round Cyzicus as far as the Practius were colonised by Phrygians, and those round Abydus by Thracians; and still before these two by Bebryces and Dryopes.¹ And the country that lies next was colonised by the Treres, themselves also Thracians; and the Plain of Thebê by² Lydians, then called Maeonians, and by the survivors of the Mysians who had formerly been subject to Telephus and Teuthras. So then, since the poet combines Aeolis and Troy, and since the Aeolians held possession of all the country from the Hermus River² to the seaboard at Cyzicus, and founded their cities there, I too might not be guilty of describing them wrongly if I combined Aeolis, now properly so called, extending from the Hermus River to Lectum, and the country next after it, extending to the Aesepus River; for in my detailed treatment of the two, I shall distinguish them again, setting forth, along with the facts as they now are, the statements of Homer and others.

9. According to Homer, then, the Troad begins after the city of the Cyziceni and the Aesepus River. And he so speaks of it: "And those who dwelt in Zeleia beneath the nethermost foot of Ida, Aphneii,³ who drink the dark water of the Aesepus, Trojans; these in turn were commanded by Pandarus the glorious son of Lycaon."⁴ These he also calls Lycians.⁵ And they are thought to have been

¹ See 13. 1. 1, and p. 40 of Leaf's first article cited in foot-note there.

² See foot-note on Aphneii in 13. 1. 7.

⁴ *Iliad* 2. 824.

⁵ See 13. 1. 7.

τῆς Ἀφνίτιδος νομίζουσι λίμνης· καὶ γὰρ οὕτω καλεῖται ἡ Δασκυλίτις.

10. Ἡ μὲν δὴ Ζέλεια ἐν τῇ παρωρείᾳ τῇ ὑστάτῃ τῆς Ἰδῆς ἐστίν, ἀπέχουσα Κυζίκου μὲν σταδίους ἐνενήκοντα καὶ ἑκατόν, τῆς δ' ἐγγυτάτῃ θαλάττης, καθ' ἣν ἐκδίδωσιν Αἷσηπος, ὅσον ὀγδοήκοντα. ἐπιμερίζει δὲ συνεχῶς τὰ κατὰ τὴν παραλίαν τὴν μετὰ τὸν Αἷσηπον·

οἱ δ' Ἀδρήστειάν τ' εἶχον καὶ δῆμον Ἀπαισοῦ, καὶ Πιτύαν εἶχον¹ καὶ Τηρείης ὄρος αἰπύ, τῶν ἡρχ' Ἀδρηστός τε καὶ Ἀμφίος λινοθώρηξ, υἱε δὲ Μέρωπος Περκωσίου.

ταῦτα δὲ τὰ χωρία τῇ Ζελεῖᾳ μὲν ὑποπέπτωκε, ἔχουσι δὲ Κυζικηνοὶ τε καὶ Πριαπηνοὶ μέχρι καὶ τῆς παραλίας. περὶ μὲν οὖν τὴν Ζελεῖαν ὁ Τάρσιός ἐστι ποταμός, εἴκοσιν ἔχων διαβάσεις τῇ αὐτῇ ὁδῷ, καθάπερ ὁ Ἑπτάπορος, ὃν φησιν ὁ ποιητής.² ὁ δ' ἐκ Νικομηδεῖας εἰς Νίκαιαν τέτταρας καὶ εἴκοσι, πολλοὺς δὲ καὶ ὁ ἐκ Φολόης εἰς τὴν Ἠλείαν . . . Σκάρθων πέντε καὶ εἴκοσι,

¹ Πιτύειαν ἔχον is the reading of the Homeric MSS., but see Πίτυα in § 15 below.

² ὁ δ' ἐκ . . . Ταύρου, Meineke ejects.

¹ On the site of Zeleia, see Leaf, *Strabo on the Troad*, p. 66.

² *Iliad* 2. 828.

³ The places in question appear to have belonged to Zeleia. Leaf (*op. cit.*, p. 65) translates: "are commanded by Zeleia"; but the present translator is sure that, up to the present passage, Strabo has always used *ἐποικίτω* in a purely geographical sense (e.g., cf. 9. 1. 15, and especially 12. 4. 6, where Strabo makes substantially the same statement

called "Aphneii" after Lake "Aphnitis," for Lake Dascylitis is also called by that name.

10. Now Zeleia¹ is situated on the farthestmost foot-hill of Mt. Ida, being one hundred and ninety stadia distant from Cyzicus and about eighty stadia from the nearest part of the sea, where the Aesepus empties. And the poet mentions severally, in continuous order, the places that lie along the coast after the Aesepus River: "And they who held Adrasteia and the land of Apaesus, and held Pityeia and the steep mountain of Tereia—these were led by Adrastus and Amphius of the linen corslet, the two sons of Merops of Percotê."² These places lie below Zeleia,³ but they are occupied by Cyziceni and Priapeni even as far as the coast. Now near Zeleia is the Tarsius River,⁴ which is crossed twenty times by the same road, like the Heptaporus River,⁵ which is mentioned by the poet.⁶ And the river that flows from Nicomedeia into Nicaea is crossed twenty-four times, and the river that flows from Pholoê into the Eleian country⁷ is crossed many times . . . Scarthion twenty-five times,⁸ and the river that flows from the

concerning Zeleia as in the present passage). But see Leaf's note (*op. cit.*), p. 67.

⁴ On this river see Leaf, work last cited, p. 67.

⁵ Strabo does not mean that the Heptaporus was crossed *twenty* times. The name itself means the river of "seven fords" (or ferries).

⁶ *Iliad* 12. 20.

⁷ i.e. Elis, in the Peloponnesus.

⁸ The text is corrupt; and "Scarthion," whether it applies to a river or a people, is otherwise unknown. However, this whole passage, "And the river that flows from Nicomedeia . . . crossed seventy-five times," appears to be a gloss, and is ejected from the text by Kramer and Meineke (see Leaf's *Strabo and the Troad*, p. 66, note 4).

πολλοὺς δὲ καὶ ὁ ἐκ Κοσκινίων εἰς Ἀλάβανδα, πέντε δὲ καὶ ἐβδομήκοντα ὁ ἐκ Τυάνων εἰς Σόλους διὰ τοῦ Ταύρου.

11. Ὑπὲρ δὲ τῆς ἐκβολῆς τοῦ Αἰσήπου σχεδὸν τι . . .¹ σταδίοις κολωνός ἐστιν, ἐφ' ᾧ τάφος δέικνται Μέμνονος τοῦ Τιθωνοῦ· πλησίον δ' ἐστὶ καὶ ἡ Μέμνονος κώμη. τοῦ δὲ Αἰσήπου καὶ τοῦ Πριάπου μεταξὺ ὁ Γράνικος ῥεῖ, τὰ πολλὰ δι' Ἀδραστείας πεδίου, ἐφ' ᾧ Ἀλέξανδρος τοὺς Δαρείου σατράπας ἀνὰ κράτος ἐνίκησε συμβαλὼν, καὶ πᾶσαν τὴν ἐντὸς τοῦ Ταύρου καὶ τοῦ Εὐφράτου παρέλαβεν. ἐπὶ δὲ Γρανίκῳ πόλις ἦν Σιδηνή, χώραν ἔχουσα πολλὴν ὁμώνυμον, κατέσπασται δὲ νῦν. ἐν δὲ τῇ μεθορίᾳ τῆς Κυζικηνῆς καὶ τῆς Πριαπηνῆς ἐστὶ τὰ Ἀρπάγια² τόπος, ἐξ οὗ τὸν Γανυμήδην μυθεύουσιν ἡρπάχθαι· ἄλλοι δὲ περὶ Δαρδάνιον ἄκραν, πλησίον Δαρδάνου.

12. Πριάπος δ' ἐστὶ πόλις ἐπὶ θαλάττῃ καὶ λιμνῇ· κτίσμα δ' οἱ μὲν Μιλησίων φασίν, οἵπερ καὶ Ἀβυδὸν καὶ Προκόννησον συνώκισαν κατὰ τὸν αὐτὸν καιρόν, οἱ δὲ Κυζικηνῶν ἐπώνυμος δ' ἐστὶ τοῦ Πριάπου τιμωμένου παρ' αὐτοῖς, εἴτ' ἐξ Ὀρνεῶν τῶν περὶ Κόρινθον μετενηνεγμένου τοῦ ἱεροῦ, εἴτε τῷ λέγεσθαι Διουόσου καὶ νύμφης τὸν θεὸν ὀρμησάντων ἐπὶ τὸ τιμᾶν αὐτὸν τῶν ἀνθρώπων, ἐπεὶ δὲ σφόδρα εὐάμπελός ἐστιν ἡ χώρα καὶ

¹ After τι there is a lacuna in the MSS. except Fⁱ, i reading ἐν εἰκοσι.

² Ἀρπάγια, the spelling in Stephanus; Ἀρπάγια F, Ἀρπαχεια (unaccented) D, Ἀρπαχεια other MSS.

¹ The number of stadia has fallen out of the MSS.

country of the Coscinii into Alabanda is crossed many times, and the river that flows from Tyana into Soli through the Taurus is crossed seventy-five times.

11. About . . .¹ stadia above the outlet of the Aesepus River is a hill, where is shown the tomb of Memnon, son of Tithonus; and near by is the village of Memnon. The Granicus River flows between the Aesepus River and Priapus, mostly through the plain of Adrasteia,² where Alexander utterly defeated the satraps of Darius in battle, and gained the whole of the country inside the Taurus and the Euphrates River. And on the Granicus was situated the city Sidenê, with a large territory of the same name; but it is now in ruins. On the boundary between the territory of Cyzicus and that of Priapus is a place called Harpagia,³ from which, according to some writers of myths, Ganymede was snatched, though others say that he was snatched in the neighbourhood of the Dardanian Promontory, near Dardanus.

12. Priapus⁴ is a city on the sea, and also a harbour. Some say that it was founded by Milesians, who at the same time also colonised Abydus and Proconnesus, whereas others say that it was founded by Cyziceni. It was named after Priapus, who was worshipped there; then his worship was transferred thither from Orneae near Corinth, or else the inhabitants felt an impulse to worship the god because he was called the son of Dionysus and a nymph; for their country is abundantly supplied with the vine, both theirs

² See Leaf, work last cited, p. 70.

³ The root *harpag* means "snatch away."

⁴ On the site of Priapus, see Leaf, p. 73.

αὕτη καὶ ἡ¹ ἐφεξῆς ὁμορος ἢ τε τῶν Παριανῶν
καὶ ἡ τῶν Λαμψακηνῶν· ὁ γοῦν Ξέρξης τῷ Θεμισ-
τοκλεῖ εἰς οἶνον ἔδωκε τὴν Λάμψακον. ἀπεδείχθη
δὲ θεὸς οὗτος ὑπὸ τῶν νεωτέρων· οὐδὲ γὰρ
C 588 Ἡσίοδος οἶδε Πριάπον, ἀλλ' εἴοικε τοῖς Ἀττικοῖς
Ὀρθάνῃ καὶ Κονισάλῳ καὶ Τύχωνι καὶ τοῖς
τοιούτοις.

13. Ἐκαλεῖτο δ' ἡ χώρα αὕτη Ἀδράστεια καὶ
Ἀδραστείας πεδῖον, κατὰ ἔθος τι οὕτω λεγόντων
τὸ αὐτὸ χωρίον διττῶς, ὥς καὶ Θήβην καὶ Θήβης
πεδῖον, καὶ Μυγδονίαν καὶ Μυγδονίας πεδῖον.
φησὶ δὲ² Καλλισθένης ἀπὸ Ἀδράστου βασιλέως,
ὃς πρῶτος Νεμέσεως ἱερὸν ἰδρύσατο, καλεῖσθαι
Ἀδράστειαν. ἡ μὲν οὖν πόλις μεταξὺ Πριάπου
καὶ Παρίου, ἔχουσα ὑποκείμενον πεδῖον ἐπώνυμον,
ἐν ᾧ καὶ μαντεῖον ἦν Ἀπόλλωνος Ἀκταίου καὶ
Ἀρτέμιδος κατὰ τὴν³ εἰς δὲ Πάριον μετη-
νέχθη πᾶσα ἡ κατασκευὴ καὶ λιθία⁴ κατα-
σπασθέντος τοῦ ἱεροῦ, καὶ ᾠκοδομήθη ἐν τῷ Παρίῳ
βωμός, Ἐρμοκρέοντος ἔργον, πολλῆς μνήμης
ἄξιον κατὰ τὸ⁵ μέγεθος καὶ κάλλος· τὸ δὲ μαντεῖον
ἐξηλείφθη,⁶ καθάπερ καὶ τὸ ἐν Ζελεῖα. ἐνταῦθα
μὲν οὖν οὐδὲν ἱερὸν Ἀδραστείας δέικνυται, οὐδὲ δὴ

¹ ἡ, Meineke inserts.

² καί, before Καλλισθένης, Corais and Meineke omit.

³ κατὰ τὴν Πυκτὴν (omitted by Cx), after Ἀρτέμιδος, is corrupt; κατὰ τὴν τόκατιν Διί; κατὰ τὴν ἐπακτίαν, conj. Voss on Scylax, p. 85; κατὰ τὴν ἀκτὴν, conj. Berkel on Stephanus, s.v. Ἀκτὴ (Kramer approving); κατὰ τὴν πυμάτην ἀκτὴν, Groskurd; κατὰ τὴν Πακτύην, conj. Meineke; κατὰ τὴν Πιτυάτιν, conj. Corais.

⁴ λιθία, Meineke emends to λιθία.

⁵ Instead of τὸ μοῖον read τε; so Corais and Meineke.

and the countries which border next upon it, I mean those of the Pariani and the Lampsaceni. At any rate, Xerxes gave Lampsacus to Themistocles to supply him with wine. But it was by people of later times that Priapus was declared a god, for even Hesiod does not know of him; and he resembles the Attic deities Orthanê, Conisalus, Tychon, and others like them.

13. This country was called "Adrasteia"¹ and "Plain of Adrasteia," in accordance with a custom whereby people gave two names to the same place, as "Thebê" and "Plain of Thebê," and "Mygdonia" and "Plain of Mygdonia." According to Callisthenes, among others, Adrasteia was named after King Adrastus, who was the first to found a temple of Nemesis. Now the city is situated between Priapus and Parium; and it has below it a plain that is named after it, in which there was an oracle of Apollo Actaeus and Artemis. . . .² But when the temple was torn down, the whole of its furnishings and stone-work were transported to Parium, where was built an altar,³ the work of Hermocreon, very remarkable for its size and beauty; but the oracle was abolished like that at Zeleia. Here, however, there is no temple of Adrasteia, nor yet of Nemesis,

¹ On the site of Adrasteia, see Leaf, p. 77.

² Three words in the Greek text here are corrupt. Strabo may have said that this temple was "on the shore," or "in the direction of Pitycia" (the same as Pitya; see § 15 following), or "in the direction of Pactyê" (see critical note).

³ This altar was a stadium (about 600 feet) in length (10. 5. 7).

⁴ *ἐξηλείφθη* is emended by Müller-Dübner and Meineke to *ἐξελεῖσθαι*.

Νεμέσεως, περὶ δὲ Κύζικόν ἐστιν Ἀδραστείας ἱερὸν.
Ἀντίμαχος δ' οὕτω φησὶν·

ἔστι δέ τις Νέμεσις μεγάλη θεός, ἥ τάδε πάντα
πρὸς μακάρων ἔλαχεν· βωμόν δέ οἱ εἶσατο
πρῶτος

Ἄδρηστος ποταμοῖο παρὰ ῥέον Αἰσήποιο,
ἐνθα τετίμηται τε καὶ Ἀδρήστεια καλεῖται.

14. Ἔστι δὲ καὶ τὸ Πάριον πόλις ἐπὶ θαλάττῃ,
λιμένα ἔχουσα μεῖζω τῆς Πριάπου, καὶ ἠϋξημένη
γε ἐκ ταύτης· θεραπεύοντες γὰρ οἱ Παριανοὶ
τοὺς Ἀτταλικούς, ὑφ' οἷς ἐτέτακτο ἡ Πρια-
πηνή, πολλὴν αὐτῆς ἀπετέμοντο, ἐπιτρεπόντων
ἐκείνων. ἐνταῦθα μυθεύουσι τοὺς Ὀφιογενεῖς
συγγένειάν τινα ἔχειν πρὸς τοὺς ὄφεις· φασὶ δ'
αὐτῶν τοὺς ἄρρενας τοῖς ἐchioθήκτοις ἄκος εἶναι
συνεχῶς ἐφαπτομένους, ὥσπερ τοὺς ἐπιδούς,
πρῶτον μὲν τὸ πελίωμα εἰς ἑαυτοὺς μεταφέροντας,
εἶτα καὶ τὴν φλεγμονὴν παύοντας καὶ τὸν πόνον.
μυθεύουσι δὲ τὸν ἀρχηγέτην τοῦ γένους ἡρώα τινα
ἐξ ὄφews μεταβαλεῖν· τάχα δὲ τῶν Ψύλλων τις
ἦν τῶν Λιβυκῶν, εἰς δὲ τὸ γένος διέτεινεν ἡ
δύναμις μέχρι ποσοῦ. κτίσμα δ' ἐστὶ τὸ Πάριον
Μιλησίων καὶ Ἐρυθραίων καὶ Παρίων.

15. Πίτρυα ¹ δ' ἐστὶν ἐν Πιτυοῦντι τῆς Παριανῆς,

¹ Instead of Πίτρυα, the Epitome, following the Homeric MSS. (see § 10 above), reads Πιρύεια.

¹ A not uncommon appellation of the gods.

² Note the variant spelling of the name.

³ "Serpent-born."

⁴ See Leaf, work last cited, p. 85.

⁵ See 17. 1. 44.

⁶ See Fraser, *Totemism and Exogamy*, 1. 20, 2. 54 and 4. 178.

⁷ According to the Scholiast on Apollonius Rhodius (1.

to be seen, although there is a temple of Adrasteia near Cyzicus. Antimachus says as follows: "There is a great goddess Nemesis, who has obtained as her portion all these things from the Blessed.¹ Adrestus² was the first to build an altar to her beside the stream of the Aesepus River, where she is worshipped under the name of Adresteia."

14. The city Parium is situated on the sea; it has a larger harbour than Priapus, and its territory has been increased at the expense of Priapus; for the Parians curried favour with the Attalic kings, to whom the territory of Priapus was subject, and by their permission cut off for themselves a large part of that territory. Here is told the mythical story that the Ophiogeneis³ are akin to the serpent tribe;⁴ and they say that the males of the Ophiogeneis cure snake-bitten people by continuous stroking, after the manner of enchanters, first transferring the livid colour to their own bodies and then stopping both the inflammation and the pain. According to the myth, the original founder of the tribe, a certain hero, changed from a serpent into a man. Perhaps he was one of the Libyan Psylli,⁵ whose power persisted in his tribe for a certain time.⁶ Parium was founded by Milesians and Erythraeans and Parians.

15. Pitya⁷ is in Pityus in the territory of Parium,

933), cited by Leaf (*Troy*, p. 187), "Lampsacus was formerly called Pityeia, or, as others spell it, Pitya. Some say that Phrixus stored his treasure there and that the city was named after the treasure, for the Thracian word for treasure is 'pitye'" (but cf. the Greek word "pitys," "pine tree"). Strabo, however, places Pitya to the east of Parium, whereas Lampsacus lies to the west (see Leaf, *l.c.*, pp. 185 ff.; and his *Strabo on the Troad*, p. 87). In § 18 (following) Strabo says that "Lampsacus was formerly called Pityussa."

ὑπερκείμενον ἔχουσα πιτυῶδες ὄρος· μεταξὺ δὲ κεῖται Παρίου καὶ Πριάπου κατὰ Λῖνον, χωρίον ἐπὶ θαλάττῃ, ὅπου οἱ Λινούσιοι κοχλῖαι ἀριστοὶ τῶν πάντων ἀλίσκονται.

16. Ἐν δὲ τῷ παράπλῳ τῷ ἀπὸ Παρίου εἰς Πριάπον ἢ τε παλαιὰ Προκόννησός ἐστι καὶ ἡ νῦν Προκόννησος, πόλιν ἔχουσα καὶ μέταλλον
C 589 μέγα λευκοῦ λίθου σφόδρα ἐπαινούμενον· τὰ γοῦν κάλλιστα τῶν ταύτῃ πόλεων ἔργα, ἐν δὲ τοῖς πρῶτα¹ τὰ ἐν Κυζίκῳ, ταύτης ἐστὶ τῆς λίθου. ἐντεῦθεν ἐστὶν Ἀριστέας,² ὁ ποιητὴς τῶν Ἀριμασπείων καλουμένων ἐπῶν, ἀνὴρ γόης, εἴ τις ἄλλος.

17. Τὸ δὲ Τηρείης³ ὄρος οἱ μὲν τὰ ἐν Πειρωσσῷ ὄρῃ φασίν, ἃ ἔχουσιν οἱ Κυζικηνοὶ τῇ Ζελεΐᾳ προσεχῇ, ἐν οἷς βασιλικὴ θήρα κατεσκευάστο τοῖς Λυδοῖς, καὶ Πέρσαις ὕστερον· οἱ δ' ἀπὸ τετταράκοντα σταδίων Λαμφάκου δεικνύουσι λόφον, ἐφ' ᾧ Μητρὸς θεῶν ἱερόν ἐστιν ἅγιον, Τηρείης⁴ ἐπικαλούμενον.

18. Καὶ ἡ Λαμφακὸς δ' ἐπὶ θαλάττῃ πόλις ἐστὶν εὐλίμενος καὶ ἀξιόλογος, συμμένουσα καλῶς, ὥσπερ καὶ ἡ Ἀβυδος· διέχει δ' αὐτῆς ὅσον

¹ πρῶτα, Corais, for πρῶτον; so the later editors.

² Ἀριστέας, Casaubon, for Ἀρισταῖος; so the later editors.

³ Τηρείης, in margin of E, for βερείης C, τῆς βερείης other MSS.

⁴ Τηρείης, the editors, for τῆς βερείης.

¹ Leaf (*l.c.*) translates, "hill shaped like a pine tree," adding (p. 187) that "the resemblance to a pine tree, so far as my personal observation went, means no more than that the hill slopes gently up to a rounded top." However, the Greek adjective probably means in the present passage

lying below a pine-covered mountain;¹ and it lies between Parium and Priapus in the direction of Linum, a place on the seashore, where are caught the Linusian snails, the best in the world.

16. On the coasting-voyage from Parium to Priapus lie both the old Proconnesus and the present Proconnesus, the latter having a city and also a great quarry of white marble that is very highly commended; at any rate, the most beautiful works of art² in the cities of that part of the world, and especially those in Cyzicus, are made of this marble. Aristæas was a Proconnesian—the author of the Arimaspean Epic, as it is called—a charlatan if ever there was one.³

17. As for “the mountain of Tereia,”⁴ some say that it is the range of mountains in Peirossus which are occupied by the Cyziceni and are adjacent to Zeleia, where a royal hunting-ground was arranged by the Lydians, and later by the Persians;⁵ but others point out a hill forty stadia from Lampsacus, on which there is a temple sacred to the mother of the gods, entitled “Tereia’s” temple.

18. Lampsacus,⁶ also, is a city on the sea, a notable city with a good harbour, and still flourishing, like Abydos. It is about one hundred and seventy

“pine-covered” (cf. the use of the same adjective in 8. 6. 22, where it applies to a sacred precinct on the Isthmus of Corinth).

² i.e. buildings, statues, and other marble structures (see 5. 2. 5 and 5. 3. 8, and the foot-notes on “works of art”).

³ See 1. 2. 10, and Herodotus, 4. 13.

⁴ The mountain mentioned in *Iliad* 2. 829.

⁵ Xenophon (*Hellenica* 4. 1. 15) speaks of royal hunting-grounds, “some in enclosed parks, others in open regions.”

⁶ Now Lapsaki. On the site, see Leaf, p. 92.

ἑβδομήκοντα καὶ ἑκατὸν σταδίους· ἐκαλεῖτο δὲ πρότερον Πιτυούσσα, καθάπερ καὶ τὴν Χίον φασίν· ἐν δὲ τῇ περαία¹ τῆς Χερρονήσου πολίχνην ἐστὶ Καλλίπολις· κεῖται δ' ἐπ' ἀκτῆς, ἐκκειμένη² πολὺ πρὸς τὴν Ἀσίαν κατὰ τὴν Λαμφακηνῶν πόλιν, ὥστε τὸ διάγραμμα μὴ πλεονεῖναι τετταράκοντα σταδίων.

19. Ἐν δὲ τῷ μεταξὺ Λαμφάκου καὶ Παρίου Παισὸς ἦν πόλις καὶ ποταμός· κατέσπασται³ δ' ἡ πόλις· οἱ δὲ Παισηνοὶ μετόκησαν εἰς Λάμφακον, Μιλησίων ὄντες ἀποικοὶ καὶ αὐτοί, καθάπερ καὶ οἱ Λαμφακηνοί· ὁ δὲ ποιητὴς εἴρηκεν ἀμφοτέρως, καὶ προσθεὶς τὴν πρώτην συλλαβὴν,

καὶ δῆμον Ἀπαισοῦ,

καὶ ἀφελών,

ὅς ῥ' ἐνὶ Παισῷ

ναῖε πολυκτῆμων.

καὶ ὁ ποταμὸς νῦν οὕτω καλεῖται. Μιλησίων δ' εἰσὶ καὶ αἱ Κολωναὶ αἱ ὑπὲρ Λαμφάκου ἐν τῇ μεσογαίᾳ τῆς Λαμφακηνῆς· ἄλλαι δ' εἰσὶν ἐπὶ τῇ ἐκτὸς Ἑλλησποντίᾳ θαλάττῃ, Ἰλίου διέχουσαι σταδίους τετταράκοντα πρὸς τοῖς ἑκατόν· ἐξ ὧν τὸν Κύκνον φασίν. Ἀναξιμένης δὲ καὶ ἐν τῇ Ἐρυθραίᾳ φησὶ λέγεσθαι Κολωνὰς καὶ ἐν τῇ Φωκίδι καὶ ἐν Θετταλίᾳ· ἐν δὲ τῇ Παριανῇ ἐστὶν Ἰλιοκολώνη. ἐν δὲ τῇ Λαμφακηνῇ τόπος εὐάμπελος Γεργίθιον· ἦν δὲ καὶ πόλις Γέργιθα, ἐκ τῶν ἐν τῇ Κυμαίᾳ Γεργίθων· ἦν γὰρ κακὴ πόλις

¹ περαία, Xylander, for στερεά; so the later editors.

² πορ read ἐκκειμένης.

³ κατέσπασται For, κατέσπαστο CDhriox.

stadia distant from Abydus; and it was formerly called Pityussa, as also, it is said, was Chios. On the opposite shore of the Chersonesus is Callipolis, a small town. It is on the headland and runs far out towards Asia in the direction of the city of the Lampsaceni, so that the passage across to Asia from it is no more than forty stadia.

19. In the interval between Lampsacus and Parium lay a city and river called Paesus; but the city is in ruins. The Paeseni changed their abode to Lampsacus, they too being colonists from the Milesians, like the Lampsaceni. But the poet refers to the place in two ways, at one time adding the first syllable, "and the land of Apaesus,"¹ and at another omitting it, "a man of many possessions, who dwelt in Paesus."² And the river is now spelled in the latter way. Colonae,³ which lies above Lampsacus in the interior of Lampsacenê, is also a colony of the Milesians; and there is another Colonae on the outer Hellespontine sea, which is one hundred and forty stadia distant from Ilium and is said to be the birthplace of Cyrenus.⁴ Anaximenes says that there are also places in the Erythraean territory and in Phocis and in Thessaly that are called Colonae. And there is an Iliocolonê in the territory of Parium. In the territory of Lampsacus is a place called Gergithium⁵ which is rich in vines; and there was also a city called Gergitha from Gergithes in the territory of Cymê, for here too

¹ *Iliad* 2. 828.

² *Iliad* 5. 612.

³ On the site of Colonae, see Leaf (*Strabo and the Troad*), p. 101.

⁴ King of Colonae, slain by Achilles in the Trojan War.

⁵ On Gergithium, see Leaf, p. 102.

πληθυντικῶς καὶ θηλυκῶς λεγομένη αἱ Γέργιθες, ὅθεν περ ὁ Γεργίθιος ἦν Κεφάλων καὶ νῦν ἔτι δέικνυται τόπος ἐν τῇ Κυμαίᾳ Γεργίθιον πρὸς Λαρίσση. ἐκ Παρίου μὲν οὖν ὁ γλωσσογράφος κληθεὶς ἦν Νεοπτόλεμος μνήμης ἄξιος, ἐκ Λαμφάκου δὲ Χάρων τε ὁ συγγραφεὺς καὶ Ἀδείμαντος καὶ Ἀναξιμένης ὁ ῥήτωρ καὶ Μητρόδωρος, ὁ τοῦ Ἐπικούρου ἑταῖρος, καὶ αὐτὸς δ' Ἐπίκουρος τρόπον τινὰ Λαμφακηνὸς ὑπῆρξε, διατρίψας ἐν Λαμφάκῳ καὶ φίλοις χρησάμενος τοῖς ἀρίστοις
 C 590 τῶν ἐν τῇ πόλει ταύτῃ, τοῖς περὶ Ἰδομενέα καὶ Λεοντέα. ἐντεῦθεν δὲ μετήνεγκεν Ἀγρίππας τὸν πεπτωκότα λέοντα, Λυσίππου ἔργον· ἀνέθηκε δὲ ἐν τῷ ἄλλει τῷ μεταξὺ τῆς λίμνης καὶ τοῦ εὐρίπου.
 20. Μετὰ δὲ Λάμφακόν ἐστιν Ἀβυδος καὶ τὰ μεταξὺ χωρία, περὶ ὧν οὕτως εἶρηκε συλλαβὼν ὁ ποιητὴς καὶ τὴν Λαμφακηνὴν καὶ τῆς Παριανῆς τινὰ (οὐπω γὰρ ἦσαν αὗται αἱ πόλεις κατὰ τὰ Τρωικά).

οἱ δ' ἄρα Περκώτην καὶ Πρίκτιον ἀμφεμένοντο, καὶ Σηστόν καὶ Ἀβυδὸν ἔχον καὶ διὰν Ἀρίσβην.

τῶν αὐθ' Ἑρτακίδης ἦρχ' Ἀσιος, φησὶν,

δν Ἀρίσβηθεν φέρον ἵπποι
 αἰθωνες μεγάλοι ποταμοῦ ἄπο Σελλήεντος.

¹ Fl. in the Alexandrian period; author of works entitled *Glosses* and *On Epigrams*.

² Early historian; author of *Persian History* and *Annals of the Lampsaceni*.

³ Known only as courtier of Demetrius Poliorcetes.

⁴ See Frazer's note on Pausanias, 6. 18. 2.

there was a city called Gergithes, in the feminine plural, the birthplace of Cephalon the Gergithian. And still to-day a place called Gergithium is pointed out in the territory of Cymé near Larissa. Now Neoptolemus,¹ called the Glossographer, a notable man, was from Parium; and Charon the historian² and Adeimantus³ and Anaximenes the rhetorician⁴ and Metrodorus the comrade of Epicurus were from Lampsacus; and Epicurus himself was in a sense a Lampsacenean, having lived in Lampsacus and having been on intimate terms with the ablest men of that city, Idomeneus and Leonteus and their followers. It was from here that Agrippa transported the Fallen Lion, a work of Lysippus; and he dedicated it in the sacred precinct between the Lake and the Euripus.⁵

20. After Lampsacus come Abydos and the intervening places of which the poet, who comprises with them the territory of Lampsacus and part of the territory of Parium (for these two cities were not yet in existence in the Trojan times), speaks as follows: "And those who dwelt about Percoté and Practus, and held Sestus and Abydos and goodly Arisbê—these in turn were led by Asius, the son of Hyrtacus, . . . who was brought by his large sorrel horses from Arisbê, from the River Sellêeis."⁶ In

¹ "The Lake" seems surely to be the Stagnum Agrippae mentioned by Tacitus (*Annals* 15. 37), i.e. the Nêmus Caesarum on the right bank of the Tiber (see A. Häbler, *Hermes* 19 (1884), p. 235). "The Stagnum Agrippae was apparently a pond constructed by Agrippa in connection with the Aqua Virgo and the canal called Euripus in the neighbourhood of the Pantheon" (C. G. Ramsay, *Annals of Tacitus*, 15. 37), or, as Leaf (*op. cit.*, p. 108) puts it, "The Euripus is the channel filled with water set up by Caesar round the arena of the Circus Maximus at Rome to protect the spectators from the wild beasts." ⁶ *Iliad* 2. 835.

οὕτω δ' εἰπὼν ἔοικε τὸ βασίλειον ἀποφαίνειν τοῦ Ἀσίου τὴν Ἀρίσβην, ὅθεν ἤκειν αὐτόν φησιν·

ὅν Ἀρίσβηθεν φέρον ἵπποι
ποταμοῦ ἀπο Σελλήεντος.

οὕτω δ' ἀφανῆ τὰ χωρία ταῦτά ἐστιν, ὥστε οὐδ' ὁμολογοῦσι περὶ αὐτῶν οἱ ἱστοροῦντες, πλὴν ὅτι περὶ Ἀβυδὸν καὶ Λάμψακόν ἐστι καὶ Πάριον, καὶ ὅτι ἡ πάλαι Περκώτη¹ μετωνομάσθη, ὁ τόπος.

21. Τῶν δὲ ποταμῶν τὸν μὲν Σελλήεντά φησιν ὁ ποιητὴς πρὸς τῇ Ἀρίσβῃ ρεῖν, εἵπερ ὁ Ἀσιος Ἀρίσβηθέν τε ἤκε καὶ ποταμοῦ ἀπο Σελλήεντος. ὁ δὲ Πράκτιος ποταμὸς μὲν ἐστι, πόλις δ' οὐχ εὐρίσκεται, ὥς τινες ἐνόμισαν· ρεῖ δὲ καὶ οὗτος μεταξὺ Ἀβύδου καὶ Λαμψάκου· τὸ οὖν

καὶ Πράκτιον ἀμφενέμοντο,

οὕτω δεκτέον, ὡς περὶ ποταμοῦ, καθάπερ καὶ κεῖνα·

οἷ τ' ἄρα παρ ποταμὸν Κηφισὸν διὸν ἔναιον,
καὶ

ἀμφί τε Παρθένιον ποταμὸν κλυτὰ ἔργ' ἐνέ-
μοντο.²

ἦν δὲ καὶ ἐν Λέσβῳ πόλις Ἀρίσβα, ἥς τὴν χώραν ἔχουσι Μηθυμναῖοι· ἐστὶ δὲ καὶ ποταμὸς Ἀρισβος ἐν Θράκῃ, ὥσπερ εἴρηται, καὶ τούτου

¹ After Περκώτη Leaf inserts μετακίσθη καὶ Περκώπη (see his *Strabo on the Troad*, p. 11, footnote 3 on p. 108, and note on Percotê, p. 111). Thus, according to him, "the old Percotê was transplanted and the name of its site changed to Percopê."

speaking" thus, the poet seems to set forth Arisbê, whence he says Asius came, as the royal residence of Asius: "who was brought by his horses from Arisbê, from the River Sellêeis." But these places¹ are so obscure that even investigators do not agree about them, except that they are in the neighbourhood of Abydus and Lampsacus and Parium, and that the old Percotê,² the site, underwent a change of name.³

21. Of the rivers, the Sellêeis flows near Arisbê, as the poet says, if it be true that Asius came both from Arisbê and from the Sellêeis River. The River Practius is indeed in existence, but no city of that name is to be found, as some have wrongly thought. This river also⁴ flows between Abydus and Lampsacus. Accordingly, the words, "and dwelt about Practius," should be interpreted as applying to a river, as should also those other words, "and those who dwelt beside the goodly Cephisus River,"⁵ and "those who had their famed estates about the Parthenius River."⁶ There was also a city Arisba in Lesbos, whose territory is occupied by the Methymnacans. And there is an Arisbus River in Thrace, as I have said before,⁷ near

¹ i.e. Arisbê, Percotê, and the Sellêeis. Strabo himself locates the Practius (13. 1. 4, 7, 8, 21). On the sites of these places, see Leaf's *Troy*, pp. 188 ff., his note in *Jour. Hellenic Studies*, XXXVII (1917), p. 26, and his *Strabo on the Troad*, pp. 108 ff.

² Homer's Percotê, on the sea.

³ See critical note.

⁴ i.e. as well as the Sellêeis.

⁵ *Iliad* 2. 522.

⁶ *Iliad* 2. 854 (see critical note).

⁷ Obviously in the lost portion of Book VII.

⁸ Instead of ἔργ' ἐνέμοντο the Homeric MSS. have δώματ' ἔναον, and Strabo himself so cites in 12. 3. 5. Eustathius (note on *Iliad* 2. 835) cites as in the present passage.

πλησίον οἱ Κεβρήνιοι Θράκες. πολλὰ δ' ὁμω-
 νυμῖαι Θραξὶ καὶ Τρωσίν, οἷον Σκαιοὶ Θράκες
 τινες καὶ Σκαιὸς ποταμὸς καὶ Σκαιὸν τεῖχος καὶ
 ἐν Τροίᾳ Σκαιαὶ πύλαι· Ξάνθιοι Θράκες, Ξάνθος
 ποταμὸς ἐν Τροίᾳ· Ἀρισβος ὁ ἐμβάλλων εἰς τὸν
 Ἑβρον, Ἀρίσβη ἐν Τροίᾳ· Ῥῆσος ποταμὸς ἐν
 Τροίᾳ, Ῥῆσος δὲ καὶ ὁ βασιλεὺς τῶν Θρακῶν.
 ἔστι δὲ καὶ τῷ Ἀσίῳ ὁμώνυμος ἕτερος παρὰ τῷ
 ποιητῇ Ἀσιος,

ὃς μήτρως ἦν Ἐκτορος ἵπποδάμοιο,
 αὐτοκασίγνητος Ἐκάβης, υἱὸς δὲ Δύμαντος,
 ὃς Φρυγίην ναίεσκε ῥοῆς ἐπὶ Σαγγαρίοιο.

22. Ἀβυδος δὲ Μιλησίων ἐστὶ κτίσμα, ἐπι-
 τρέψαντος Γύγου, τοῦ Λυδῶν βασιλέως· ἦν γὰρ
 ἐπ' ἐκείνῳ τὰ χωρία καὶ ἡ Τρωὰς ἅπασα,
 ὀνομάζεται δὲ καὶ ἄκρωτήριόν τι πρὸς Δαρδάνῳ
 C591 Γύγας· ἐπικεῖται δὲ τῷ στόματι τῆς Προποντίδος
 καὶ τοῦ Ἑλλησπόντου, διέχει δὲ τὸ ἴσον Λαμψά-
 κου καὶ Ἰλίου, σταδίους περὶ ἑβδομήκοντα καὶ
 ἑκατόν. ἐνταῦθα δ' ἐστὶ τὸ ἑπταστάδιον, ὅπερ
 ἔξευξε Ξέρξης, τὸ διόριζον τὴν Εὐρώπην καὶ τὴν
 Ἀσίαν. καλεῖται δ' ἡ ἄκρα τῆς Εὐρώπης Χερ-
 ρόνησος διὰ τὸ σχῆμα, ἡ ποιοῦσα τὰ στενὰ τὰ
 κατὰ τὸ ζεῦγμα· ἀντίκειται δὲ τὸ ζεῦγμα τῇ
 Ἀβύδῳ. Σηστὸς δὲ ἀρίστη¹ τῶν ἐν Χερρονήσῳ
 πόλεων· διὰ δὲ τὴν γειτοσύνην ὑπὸ τῷ αὐτῷ

¹ For ἀρίστη Meineke conj. κρατίστη.

¹ *Iliad* 16. 717.

² On the site of Abydus, see Leaf, *Strabo on the Troad*, p. 117.

which are situated the Thracian Cebrenians. There are many names common to the Thracians and the Trojans; for example, there are Thracians called Scaeans, and a river Scaeus, and a Scaean Wall, and at Troy the Scaean Gates. And there are Thracian Xanthians, and in Troy-land a river Xanthus. And in Troy-land there is a river Arisbus which empties into the Hebrus, as also a city Arisbê. And there was a river Rhesus in Troy-land; and there was a Rhesus who was the king of the Thracians. And there is also, of the same name as this Asius, another Asius in Homer, "who was maternal uncle to horse-taming Hector, and own brother to Hecabê, but son of Dymas, who dwelt in Phrygia by the streams of the Sangarius."¹

22. Abydus was founded by Milesians, being founded by permission of Gyges, king of the Lydians; for this district and the whole of the Troad were under his sway; and there is a promontory named Gygas near Dardanus. Abydus lies at the mouth of the Propontis and the Hellespont; and it is equidistant from Lampsacus and Ilium, about one hundred and seventy stadia.² Here, separating Europe and Asia, is the Heptastadium,³ which was bridged by Xerxes. The European promontory that forms the narrows at the place of the bridge is called the Chersonesus⁴ because of its shape. And the place of the bridge lies opposite Abydus. Sestus⁵ is the best of the cities in the Chersonesus; and, on account of its proximity to Abydus, it was assigned to the same governor as

¹ i.e. "Strait of seven stadia."

² i.e. "Land-island" or "Peninsula."

³ On its site, see Leaf, work last cited, p. 119.

ἡγεμόνι καὶ αὕτη ἐτέτακτο οὕπω ταῖς ἡπείροις
διοριζόντων τῶν τότε τὰς ἡγεμονίας. ἡ μὲν οὖν
Ἄβυδος καὶ ἡ Σηστός διέχουσιν ἀλλήλων τριά-
κοντά που σταδίους ἐκ λιμένος εἰς λιμένα, τὸ δὲ
ζεῦγμά ἐστι μικρὸν ἀπὸ τῶν πόλεων παραλλά-
ξαντι ἐξ Ἄβυδου μὲν ὥς ἐπὶ τὴν Προποντίδα, ἐκ
δὲ Σηστοῦ εἰς τὸναναντίον· ὀνομάζεται δὲ πρὸς τῇ
Σηστῷ τόπος Ἀποβάθρα, καθ' ὃν ἐξεύγνυτο ἡ
σχεδιά· ἐστὶ δὲ ἡ Σηστός ἐνδοτέρω κατὰ τὴν
Προποντίδα ὑπερδέξιος τοῦ ροῦ τοῦ ἐξ αὐτῆς·
διὸ καὶ εὐπετέστερον ἐκ τῆς Σηστοῦ διαίρουσι
παραλεξάμενοι¹ μικρὸν ἐπὶ τὸν τῆς Ἡροῦς
πύργον κάκειθεν ἀφιέντες τὰ πλοῖα συμπράττοντος
τοῦ ροῦ πρὸς τὴν περαιώσιν· τοῖς δ' ἐξ Ἄβυδου
περαιουμένοις παραλεκτέον² ἐστὶν εἰς τὰναντία
ὀκτώ που σταδίους ἐπὶ πύργον τινὰ κατ' ἀντικρὺ
τῆς Σηστοῦ, ἔπειτα διαίρειν πλάγιον καὶ μὴ
τελέως ἐναντίον ἔχουσιν τὸν ροῦν. ᾧκουν δὲ τὴν
Ἄβυδον μετὰ τὰ Ἰρωικὰ Θράκες, εἶτα Μιλήσιοι.
τῶν δὲ πόλεων ἐμπρησθεισῶν ὑπὸ Δαρείου, τοῦ
Ξέρξου πατρός, τῶν κατὰ τὴν Προποντίδα,
ἐκοινώνησε καὶ ἡ Ἄβυδος τῆς αὐτῆς συμφορᾶς.
ἐνέπρησε δὲ πυθόμενος μετὰ τὴν ἀπὸ τῶν Σκυθῶν
ἐπάνοδον, τοὺς νομάδας παρασκευάζεσθαι δια-
βαίνειν ἐπ' αὐτὸν κατὰ τιμωρίαν ὧν ἔπαθον,
δεδιὼς μὴ αἱ πόλεις πορθμεῖα παράσχοιεν τῇ
στρατιᾷ. συνέβη δὲ πρὸς ταῖς ἄλλαις μετα-
βολαῖς καὶ τῷ χρόνῳ καὶ τοῦτο αἴτιον τῆς

¹ παραλεξάμενοι, Kramer restores, for παραλαξάμενοι C, παραλαξάμενοι rio, Xylander, and other editors.

² παραλεκτέον, Kramer restores, for παραλλακτέον, earlier editors.

Abydus in the times when governorships had not yet been delimited by continents. Now although Abydus and Sestus are about thirty stadia distant from one another from harbour to harbour, yet the line of the bridge across the strait is short, being drawn at an angle to that between the two cities, that is, from a point nearer than Abydus to the Propontis on the Abydus side to a point farther away from the Propontis on the Sestus side. Near Sestus is a place named Apobathra,¹ where the pontoon-bridge was attached to the shore. Sestus lies farther in towards the Propontis, farther up the stream that flows out of the Propontis. It is therefore easier to cross over from Sestus, first coasting a short distance to the Tower of Hero and then letting the ships make the passage across by the help of the current. But those who cross over from Abydus must first follow the coast in the opposite direction about eight stadia to a tower opposite Sestus, and then sail across obliquely and thus not have to meet the full force of the current. After the Trojan War Abydus was the home of Thracians, and then of Milesians. But when the cities were burned by Dareius, father of Xerxes, I mean the cities on the Propontis, Abydus shared in the same misfortune. He burned them because he had learned after his return from his attack upon the Scythians that the nomads were making preparations to cross the strait and attack him to avenge their sufferings, and was afraid that the cities would provide means for the passage of their army. And this too, in addition to the other changes and to the lapse of time, is a cause of the confusion into which the topography of

¹ i.e., "Place of Disembarkation."

συγχύσεως τῶν τόπων. περὶ δὲ Σηστοῦ καὶ τῆς ὅλης Χερρονήσου προείπομεν ἐν τοῖς περὶ τῆς Θράκης τόποις,¹ φησὶ δὲ τὴν Σηστὸν Θεόπομπος Βραχεῖαν μὲν, εὐερκῇ δέ, καὶ σκέλει διπλέθρων συνάπτειν πρὸς τὸν λιμένα, καὶ διὰ ταῦτ' οὖν καὶ διὰ τὸν ῥοῦν κυρίαν εἶναι τῶν παρόδων.

23. Ὑπέρκειται δὲ τῆς τῶν Ἀβυδηνῶν χώρας ἐν τῇ Τρωάδι τὰ Ἀστυρα, ἃ νῦν μὲν Ἀβυδηνῶν ἐστὶ, κατεσκαμμένη πόλις, πρότερον δὲ ἦν καθ' αὐτά, χρυσεῖα ἔχοντα, ἃ νῦν σπάνιά ἐστιν ἐξαναλωμένα, καθάπερ τὰ ἐν τῷ Τμώλῳ τὰ περὶ τὸν Πакτωλόν. ἀπὸ Ἀβύδου δ' ἐπὶ Αἰσηπὸν περὶ ἑπτακοσίους φασὶ σταδίους, εὐθυπλοῖα δὲ ἐλάττους.

C 592 24. Ἐξω δὲ Ἀβύδου τὰ περὶ τὸ Ἰλιόν ἐστι, τὰ τε παράλια ἕως Λέκτου καὶ τὰ ἐν τῷ Τρωικῷ πεδίῳ καὶ τὰ παρῳρεῖα τῆς Ἰδης τὰ ὑπὸ τῷ Αἰνεΐα. διττῶς δὲ ταῦτ' ὀνομάζει ὁ ποιητής, τότε μὲν οὕτω λέγων·

Δαρδανίων αὐτ' ἦρχεν εὔς παῖς Ἀγχίσαο,
Δαρδανίους καλῶν, τότε δὲ Δαρδάνους,
Τρῶες καὶ Λύκιοι καὶ Δάρδανοι ἀγχιμαχηταί.

¹ Kramer suspects that τόποις should be ejected. Meineke conj. λόγοις, but retains τόποις in his text. Cp. *Frag.* 55a, Vol. III, p. 378.

¹ See Vol. III, *Frag.* 51 (p. 373), 55b (p. 379), and 51a, 52, and 53 (p. 375).

² i.e. about 200 feet (in breadth).

³ According to Leaf (*l.c.*, p. 135), the *shortest* course of a vessel between Abydus and the mouth of the Aesepus measures just about 700 stadia. Hence Strabo's authorities for his statement are in error if, as usual, the *longer* voyage

the country has fallen. As for Sestus and the Chersonesus in general, I have already spoken of them in my description of the region of Thrace.¹ Theopompus says that Sestus is small but well fortified, and that it is connected with its harbour by a double wall of two plethra,² and that for this reason, as also on account of the current, it is mistress of the passage.

23. Above the territory of the Abydeni, in the Troad, lies Astyra. This city, which is in ruins, now belongs to the Abydeni, but in earlier times it was independent and had gold mines. These mines are now scant, being used up, like those on Mt. Tmolus in the neighbourhood of the Pactolus River. From Abydus to the Aesepus the distance is said to be about seven hundred stadia, but less by straight sailing.³

24. Outside Abydus lies the territory of Ilium—the parts on the shore extending to Lectum, and the places in the Trojan Plain, and the parts on the side of Mt. Ida that were subject to Aeneias. The poet names these last parts in two ways, at one time saying as follows: "The Dardanii in turn were led by the valiant son of Anchises,"⁴ calling the inhabitants "Dardanii"; and at another time, "Dardani": "The Trojans and Lycians and Dardani that fight in close combat." And it is reason-

is a *coasting* voyage, following the sinuosities of the gulfs, as against the *shorter*, or more direct, voyage. Leaf, however, forces the phrase "by straight sailing" to mean "a straight course wholly over the land," adding that "the meaning must be that it would be shorter if one could sail straight," and that "the expression is singularly infelicitous as applied to a journey by land in contrast to one by sea."

⁴ *Iliad*. 2. 819.

εἰκὸς δ' ἐνταῦθα ἰδρῦσθαι τὸ παλαιὸν τὴν λεγομένην ὑπὸ τοῦ ποιητοῦ Δαρδανίαν·

Δάρδανον αὖ πρῶτον τέκετο νεφεληγερέτα
Ζεὺς,
κτίσσε δὲ Δαρδανίην.

νῦν μὲν γὰρ οὐδ' ἴχνος πόλεως σώζεται αὐτόθι.

25. Εἰκάζει δὲ Πλάτων μετὰ τοὺς κατακλυσμοὺς τρία πολιτείας εἶδη συνίστασθαι· πρῶτον μὲν τὸ ἐπὶ τὰς ἀκρωρείας ἀπλοῦν τι καὶ ἄγριον, δεδιότων τὰ ὕδατα ἐπιπολάζοντα ἀκμὴν ἐν τοῖς πεδίοις· δεύτερον δὲ τὸ ἐν ταῖς ὑπωρείαις, θαρρύντων ἤδη κατὰ μικρόν, ἅτε δὴ καὶ τῶν πεδίων ἀρχομένων ἀναψύχεσθαι· τρίτον δὲ τὸ ἐν τοῖς πεδίοις. λέγοι δ' ἂν τις καὶ τέταρτον καὶ πέμπτον ἴσως καὶ πλείω, ὕστατον δὲ τὸ ἐν τῇ παραλίᾳ καὶ ἐν ταῖς νήσοις, λελυμένου παντὸς τοῦ τοιοῦτου φόβου. τὸ γὰρ μᾶλλον καὶ ἥττον θαρρεῖν πλησιάζειν τῇ θαλάττῃ πλείους ἂν ὑπογράφοι διαφορὰς πολιτειῶν καὶ ἠθῶν, καθάπερ¹ τῶν ἀγαθῶν² τε καὶ τῶν ἀγρίων ἔτι πως³ ἐπὶ τὸ ἡμέρον τῶν δευτέρων ὑποβεβηκότων. ἔστι δέ⁴ τις διαφορὰ καὶ παρὰ τούτοις τῶν ἀγροίκων καὶ μεσαγροίκων καὶ πολιτικῶν· ἀφ' ὧν ἤδη καὶ ἐπὶ τὸ ἀστεῖον καὶ ἄριστον ἦθος ἐτελεύτησεν ἡ τῶν ὀνομάτων κατ' ὀλίγον μετά-

¹ καθάπερ, Xylander, for καὶ ἅπερ; so the later editors.

² ἀγαθῶν MSS., Leaf (op. cit. pp. 13, 140) restores, for ἀπλῶν, emendation of Groskurd accepted by other later editors. Plato (*Laus* 679 C) says: ἀγαθοὶ μὲν διὰ ταῦτα (i.e. the absence of riches, poverty, insolence, injustice, and envy) τε ἦσαν καὶ διὰ τὴν λεγομένην εὐήθειαν.

³ ἔτι πως, the editors in general, for ἐστὶ πως ποτ', ἔτι πῶς

able to suppose that this was in ancient times the site of the Dardania mentioned by the poet when he says, "At first Dardanus was begotten by Zeus the cloud-gatherer, and he founded Dardania";¹ for at the present time there is not so much as a trace of a city preserved in that territory.²

25. Plato³ conjectures, however, that after the time of the floods three kinds of civilisation were formed: the first, that on the mountain-tops, which was simple and wild, when men were in fear of the waters which still deeply covered the plains; the second, that on the foot-hills, when men were now gradually taking courage because the plains were beginning to be relieved of the waters; and the third, that in the plains. One might speak equally of a fourth and fifth, or even more, but last of all that on the sea-coast and in the islands, when men had been finally released from all such fear; for the greater or less courage they took in approaching the sea would indicate several different stages of civilisation and manners, first as in the case of the qualities of goodness⁴ and wildness, which in some way further served as a foundation for the milder qualities in the second stage. But in the second stage also there is a difference to be noted, I mean between the rustic and semi-rustic and civilised qualities; and, beginning with these last qualities, the gradual assumption of new names ended in the polite and highest

¹ *Iliad* 20. 215.

² On the boundaries of Dardania, see Leaf (*l.c.*, p. 137).

³ *Laws* 677-679.

⁴ See critical note.

other MSS.; omitted by Corais; ἡδὴ πῶς, Groskurd; ἐτέρας Leaf.

⁴ 34, after ἑστῇ, Leaf omits.

ληψεις, κατὰ τὴν τῶν ἡθῶν ἐπὶ τὸ κρεῖττον
μετάστασιν, παρὰ τὰς τῶν τόπων καὶ τῶν βίων
μεταβολάς. ταύτας δὲ τὰς διαφορὰς ὑπογράφειν
φησὶ τὸν ποιητὴν ὁ Πλάτων, τῆς μὲν πρώτης
πολιτείας παράδειγμα τιθέντα τὸν τῶν Κυκλώπων
βίον, αὐτοφυεῖς νεμομένων καρποὺς καὶ τὰς
ἄκρωρείας κατεχόντων ἐν σπηλαίοις τισίν·

ἀλλὰ τά γ' ἄσπαρτα καὶ ἀνήροτα πάντα
φύονται,

φησὶν, αὐτοῖς·

τοῖσιν δ' οὐκ ἀγοραὶ βουλευφόροι, οὔτε
θέμιστες·

ἀλλ' οἳ γ' ὑψηλῶν ὀρέων ναίουσι κάρηνα,
ἐν σπέσσι γλαφυροῖσι, θεμιστεύει δὲ ἕκαστος
παίδων ἢ δ' ἀλόχων.

τοῦ δὲ δευτέρου τὸν ἐπὶ¹ τοῦ Δαρδάνου·

C 593 κτίσσε δὲ Δαρδανίην, ἐπεὶ οὐπω Ἴλιος ἱρή
ἐν πεδίῳ πεπόλιστο, πόλις μερόπων ἀνθρώ-
πων,

ἀλλ' ἔθ' ὑπωρείας ᾤκεον² πολυπιδάκου Ἰδης.

τοῦ δὲ τρίτου ἐπὶ τοῦ Ἴλου τὸν ἐν τοῖς πεδίοις.
τοῦτον γὰρ παραδιδόασι τοῦ Ἰλίου κτίστην, ἀφ'
οὗ καὶ τὴν ἐπωνυμίαν λαβεῖν τὴν πόλιν· εἰκὸς
δὲ καὶ διὰ τοῦτο ἐν μέσῳ τῷ πεδίῳ τεθάφθαι
αὐτόν, ὅτι πρῶτος ἐθάρρησεν ἐν τοῖς πεδίοις
θέσθαι τὴν κατοικίαν·

οἱ δὲ παρ' Ἴλου σῆμα παλαιοῦ Δαρδανίδαο
μέσσον καὶ πεδίον παρ' ἐρινεὸν ἐσσεύοντο.

culture, in accordance with the change of manners for the better along with the changes in places of abode and in modes of life. Now these differences, according to Plato,¹ are suggested by the poet, who sets forth as an example of the first stage of civilisation the life of the Cyclopes, who lived on uncultivated fruits and occupied the mountain-tops, living in caves: "but all these things," he says, "grow unsown and unploughed" for them. . . . "And they have no assemblies for council, nor appointed laws, but they dwell on the tops of high mountains in hollow caves, and each is lawgiver to his children and his wives."² And as an example of the second stage, the life in the time of Dardanus, who "founded Dardania; for not yet had sacred Ilios been builded to be a city of mortal men, but they were living on the foot-hills of many-fountained Ida."³ And of the third stage, the life in the plains in the time of Ilus;⁴ for he is the traditional founder of Ilium, and it was from him that the city took its name. And it is reasonable to suppose, also, that he was buried in the middle of the plain for this reason—that he was the first to dare to settle in the plains: "And they sped past the tomb of ancient Ilus, son of Dardanus, through the middle of the plain past the wild fig tree."⁵ Yet even Ilus did not have full

¹ *Laws* 3. 680.

² *Odyssey* 9. 109, 112–114 (quoted by Plato in *Laws* 3. 680).

³ *Iliad* 20. 216 (quoted by Plato in *Laws* 3. 681).

⁴ *Laws* 3. 682.

⁵ *Iliad* 11. 166.

¹ *ἔρι*, Corais, for *ἐκ*; so the later editors.

² Instead of *ῥέον*, *mor* read *ῥέον*.

οὐδ' οὗτος δὲ τελείως ἐθάρρησεν· οὐ γὰρ ἐνταῦθα ἴδρυσεν τὴν πόλιν, ὅπου νῦν ἐστίν, ἀλλὰ σχεδόν τι τριάκοντα σταδίοις ἀνωτέρω πρὸς ἔω καὶ πρὸς τὴν Ἴδην καὶ τὴν Δαρδανίαν κατὰ τὴν νῦν καλουμένην Ἰλίων Κώμην. οἱ δὲ νῦν Ἰλιεῖς φιλοδοξοῦντες καὶ θέλοντες εἶναι ταύτην τὴν παλαιὰν παρεσχήκασιν λόγον τοῖς ἐκ τῆς Ὀμήρου ποιήσεως τεκμαιρομένοις· οὐ γὰρ ἔοικεν αὕτη εἶναι ἢ καθ' Ὀμηρον. καὶ ἄλλοι δὲ ἱστοροῦσι πλείους μεταβεβληκέναι τόπους τὴν πόλιν, ὥστατα δ' ἐνταῦθα συμμεῖναι κατὰ Κροῖσον¹ μάλιστα. τὰς δὲ τοιαύτας μεταβάσεις εἰς τὰ κάτω μέρη τὰς τότε συμβαινούσας ὑπολαμβάνω καὶ βίων καὶ πολιτειῶν ὑπογράφειν διαφοράς, ἀλλὰ ταῦτα μὲν καὶ ἄλλοτε ἐπισκεπτέον.

26. Τὴν δὲ τῶν Ἰλίων πόλιν τῶν νῦν τέως μὲν κώμην εἶναί φασι, τὸ ἱερὸν ἔχουσαν τῆς Ἀθηνᾶς μικρὸν καὶ εὐτελές, Ἀλέξανδρον δὲ ἀναβάντα μετὰ τὴν ἐπὶ Γρανίκῳ νίκην, ἀναθήμασί τε κοσμήσαι τὸ ἱερὸν καὶ προσαγορεῦσαι πόλιν καὶ οἰκοδομίαις ἀναλαβεῖν προστάξαι τοῖς ἐπιμεληταῖς ἐλευθέραν τε κρίναι καὶ ἄφορον, ὥστερον δὲ μετὰ τὴν κατάλυσιν τῶν Περσῶν ἐπιστολὴν καταπέμψαι φιλάνθρωπον, ὑπισχνούμενον πόλιν τε ποιῆσαι μεγάλην καὶ ἱερὸν ἐπισημότατον, καὶ ἀγῶνα ἀποδείξειν ἱερόν. μετὰ δὲ τὴν ἐκείνου

¹ For Κροῖσον *so* reads μικρόν, *nos* χρησμόν.

¹ Schliemann's excavations, however, identify Hisarlik as the site of Homer's Troy. Hence "the site of Homer's Troy at 'the village of Ilians' is a mere figment" (Leaf, *l.c.*, p. 141).

courage, for he did not found the city at the place where it now is, but about thirty stadia higher up towards the east, and towards Mt. Ida and Dardania, at the place now called "Village of the Ilians."¹ But the people of the present Ilium, being fond of glory and wishing to show that their Ilium was the ancient city, have offered a troublesome argument to those who base their evidence on the poetry of Homer, for their Ilium does not appear to have been the Homeric city. Other inquirers also find that the city changed its site several times, but at last settled permanently where it now is at about the time of Croesus.² I take for granted, then, that such removals into the parts lower down, which took place in those times, indicate different stages in modes of life and civilisation; but this must be further investigated at another time.

26. It is said that the city of the present Ilians was for a time a mere village, having its temple of Athena, a small and cheap temple, but that when Alexander went up there after his victory at the Granicus³ River he adorned the temple with votive offerings, gave the village the title of city, and ordered those in charge to improve it with buildings, and that he adjudged it free and exempt from tribute; and that later, after the overthrow of the Persians, he sent down a kindly letter to the place, promising to make a great city of it, and to build a magnificent sanctuary, and to proclaim sacred games.⁴ But after

¹ King of Lydia, 560-546 B.C.

² The first of the three battles by which he overthrew the Persian empire (334 B.C.).

⁴ *e.g.* like the Olympic Games. But his untimely death prevented the fulfilment of this promise.

τελευτήν Λυσίμαχος μάλιστα τῆς πόλεως ἐπε-
μελήθη καὶ νεὼν κατεσκεύασε καὶ τεῖχος περιε-
βάλετο ὅσον τετταράκοντα σταδίων, συνώκισέ
τε εἰς αὐτὴν τὰς κύκλῳ πόλεις ἀρχαίας ἤδη
κεκακωμένας, ὅτε καὶ Ἀλεξανδρείας ἤδη ἐπε-
μελήθη, συνωκισμένης μὲν ἤδη ὑπ' Ἀντιγόνου
καὶ προσηγορευμένης Ἀντιγονίας, μεταβαλούσης
δὲ τοῦνομα, ἔδοξε γὰρ εὐσεβὲς εἶναι τοὺς Ἀλέ-
ξανδρον διαδεξαμένους ἐκείνου πρότερον κτίζειν
ἐπωνύμους πόλεις, εἰθ' ἑαυτῶν. καὶ δὴ καὶ
συνέμεινε καὶ αὖξησιν ἔσχε, νῦν δὲ καὶ Ῥωμαίων
ἀποικίαν δέδεκται καὶ ἔστι τῶν ἐλλογίμων
πόλεων.

C 594 27. Καὶ τὸ Ἴλιον δ', ὃ νῦν ἔστι, κωμόπολις
τις ἦν, ὅτε πρῶτον Ῥωμαῖοι τῆς Ἀσίας ἐπέβησαν
καὶ ἐξέβαλον Ἀντίοχον τὸν μέγαν ἐκ τῆς ἐντὸς
τοῦ Ταύρου. φησὶ γοῦν Δημήτριος ὁ Σκήψιος,
μειράκιον ἐπιδημήσας εἰς τὴν πόλιν κατ' ἐκείνους
τοὺς καιροὺς, οὕτως ὠλιγωρημένην ἰδεῖν τὴν
κατοικίαν, ὥστε μηδὲ κεραμωτὰς ἔχειν τὰς στέγας.
Ἡγησιάνῃ δὲ τοὺς Γαλάτας περαιωθέντας ἐκ
τῆς Εὐρώπης ἀναβῆναι μὲν εἰς τὴν πόλιν
δεομένους ἐρύματος, παραχρῆμα δ' ἐκλιπεῖν διὰ

¹ Either Strabo, or his authority, Demetrius of Scepsis, or the Greek text as it now stands, seems guilty of inconsistency in the passage "devoted special attention to the city . . . and then cities bearing their own." Grote (Vol. I, chapter xv) rearranges the Greek text in the following order: "devoted especial attention to Alexandria" (not Ilium), "which had indeed already been founded by Antigonos and called Antigonos, but changed its name (for it was thought to be . . . then cities bearing their own name), and he built a

his death Lysimachus¹ devoted special attention to the city, and built a temple there and surrounded the city with a wall about forty stadia in circuit, and also incorporated into it the surrounding cities, which were now old and in bad plight. At that time he had already devoted attention to Alexandreia, which had indeed already been founded by Antigonos and called Antigonía, but had changed its name, for it was thought to be a pious thing for the successors of Alexander to found cities bearing his name before they founded cities bearing their own. And indeed the city endured and grew, and at present it not only has received a colony of Romans but is one of the notable cities of the world.

27. Also the Ilium of to-day was a kind of village-city when the Romans first set foot on Asia and expelled Antiochus the Great from the country this side of Taurus. At any rate, Demetrius of Scepsis says that, when as a lad he visited the city about that time, he found the settlement so neglected that the buildings did not so much as have tiled roofs. And Hegesianax says that when the Galatae crossed over from Europe they needed a stronghold and went up into the city for that reason, but

temple . . . forty stadia in circuit." He omits "at that time he had already devoted attention to Alexandreia," and so does Leaf (*op. cit.*, p. 142); but the latter, instead of rearranging the text, simply inserts "Alexandreia" after "city" in the first clause of the passage. Leaf (p. 143) adds the following important argument to those of Grote: "There is no trace whatever of any great wall at Ilium, though remains of one 40 stades in length could hardly have escaped notice. But there is at Alexandreia such a wall which is exactly the length mentioned by Strabo, and which is clearly referred to."

τὸ ἀτείχιστον ὕστερον δ' ἐπανόρθωσιν ἔσχε πολλήν. εἴτ' ἐκάκωσαν αὐτὴν πάλιν οἱ μετὰ Φιμβρίου Ῥωμαῖοι, λαβόντες ἐκ πολιορκίας ἐν τῷ Μιθριδατικῷ πολέμῳ. συνεπέμφθη δὲ ὁ Φιμβρίας ὑπάτω Οὐαλερίῳ Φλάκκῳ ταμίας, προχειρισθέντι ἐπὶ τὸν Μιθριδάτην· καταστασιάσας δὲ καὶ ἀνελὼν τὸν ὕπατον κατὰ Βιθυνίαν αὐτὸς κατεστάθη κύριος τῆς στρατιᾶς, καὶ προσελθὼν εἰς Ἴλιον, οὐ δεχομένων αὐτὸν τῶν Ἰλιέων, ὥς ληστήν, βίαν τε¹ προσφέρει καὶ ἐνδεκαταίους² αἰρεῖ· κανχωμένου δ', ὅτι, ἦν Ἀγαμέμνων πόλιν δεκάτῳ ἔτει μόλις εἶλε τὸν χιλιόναυν στόλον ἔχων καὶ τὴν σύμπασαν Ἑλλάδα συστρατεύουσιν, ταύτην αὐτὸς ἐνδεκάτῃ ἡμέρᾳ χειρώσαιο, εἶπέ τις τῶν Ἰλιέων· Οὐ γὰρ ἦν Ἐκτωρ ὁ ὑπερμαχὼν τῆς πόλεως. τοῦτον μὲν οὖν ἐπελθὼν Σύλλας κατέλυσε, καὶ τὸν Μιθριδάτην κατὰ συμβάσεις εἰς τὴν οἰκίαν ἀπέπεμψε, τοὺς δ' Ἰλιέας παρεμυθήσατο πολλοῖς ἐπανορθώμασι. καθ' ἡμᾶς μέντοι Καῖσαρ ὁ Θεὸς πολὺ πλεον αὐτῶν προνόησε, ζηλώσας ἅμα καὶ Ἀλέξανδρον· ἐκεῖνος γὰρ κατὰ συγγενείας ἀνανέωσιν ὥρμησε προνοεῖν αὐτῶν, ἅμα καὶ φιλόμηρος ὢν. φέρεται γοῦν τις διόρθωσις τῆς Ὀμήρου ποιήσεως, ἥ ἐκ τοῦ νάρθηκος λεγομένη, τοῦ Ἀλεξάνδρου μετὰ τῶν περὶ Καλλισθένη καὶ Ἀνάξαρχον ἐπελθόντος καὶ σημειωσαμένου τινά,

¹ βίαν τε, conj. of Casaubon, for μηχανάς τε ἰ, μάχην τε, ἀνάγκην τε, omitted in *moz*, μάντι other MSS.; so Meineke.

² For ἐνδεκαταίους the Epit. has ἐν ἡμέραις δεκα.

¹ i.e. in 86 B.C. by Cinna the consul, the leader of the popular party at Rome.

left it at once because of its lack of walls. But later it was greatly improved. And then it was ruined again by the Romans under Fimbria, who took it by siege in the course of the Mithridatic war. Fimbria had been sent as quaestor with Valerius Flaccus the consul when the latter was appointed¹ to the command against Mithridates; but Fimbria raised a mutiny and slew the consul in the neighbourhood of Bithynia, and was himself set up as lord of the army; and when he advanced to Ilium, the Ilians would not admit him, as being a brigand, and therefore he applied force and captured the place on the eleventh day. And when he boasted that he himself had overpowered on the eleventh day the city which Agamemnon had only with difficulty captured in the tenth year, although the latter had with him on his expedition the fleet of a thousand vessels and the whole of Greece, one of the Ilians said: "Yes, for the city's champion was no Hector." Now Sulla came over and overthrew Fimbria, and on terms of agreement sent Mithridates away to his homeland, but he also consoled the Ilians by numerous improvements. In my time, however, the deified Caesar² was far more thoughtful of them, at the same time also emulating the example of Alexander; for Alexander set out to provide for them on the basis of a renewal of ancient kinship, and also because at the same time he was fond of Homer; at any rate, we are told of a recension of the poetry of Homer, the Recension of the Casket, as it is called, which Alexander, along with Callisthenes and Anaxarchus, perused and to a

² Julius Caesar.

ἔπειτα καταθέντος εἰς νάρθηκα, ὃν ἡῦρεν ἐν τῇ
 Περσικῇ γάζῃ, πολυτελῶς κατεσκευασμένον.
 κατὰ τε δὴ τὸν τοῦ ποιητοῦ ζῆλον καὶ κατὰ τὴν
 συγγένειαν τὴν ἀπὸ τῶν Αἰακιδῶν τῶν ἐν
 Μολοττοῖς βασιλευσάντων, παρ' οἷς καὶ τὴν
 Ἀνδρομάχην ἱστοροῦσι βασιλεῦσαι, τὴν Ἐκτορος
 γενομένην γυναῖκα, ἐφιλοφρονεῖτο¹ πρὸς τοὺς
 Ἰλίας ὁ Ἀλέξανδρος· ὁ δὲ Καῖσαρ καὶ φιλαλέ-
 ξανδρος ὢν καὶ τῆς πρὸς τοὺς Ἰλίας συγγενείας
 γνωριμώτερα² ἔχων τεκμήρια ἐπερρώσθη πρὸς
 τὴν εὐεργεσίαν νεανικῶς· γνωριμώτερα δέ, πρῶτον
 C 595 μὲν ὅτι Ῥωμαῖος· οἱ δὲ Ῥωμαῖοι τὸν³ Αἰνεῖαν
 ἀρχηγέτην ἡγοῦνται· ἔπειτα ὅτι Ἰούλιος ἀπὸ
 Ἰούλου τινὸς τῶν προγόνων· ἐκεῖνος δ' ἀπὸ
 Ἰούλου⁴ τὴν προσωνυμίαν⁵ ἔσχε ταύτην, τῶν
 ἀπογόνων εἰς ὧν τῶν ἀπὸ Αἰνεῖου. χώραν τε
 δὴ προσένειμεν αὐτοῖς καὶ τὴν ἐλευθερίαν καὶ
 τὴν ἀλειουργησίαν αὐτοῖς συνεφύλαξε, καὶ
 μέχρι νῦν συμμένουσιν ἐν τούτοις. ὅτι δ' οὐκ
 ἐνταῦθα⁶ ἱδρύται τὸ παλαιὸν Ἴλιον καθ'
 Ὅμηρον σκοποῦσιν, ἐκ τῶν τοιῶνδε τεκμαίρονται.
 πρότερον δὲ ὑπογραπτέον τοὺς τόπους ἀπὸ τῆς
 παραλίας ἀρξαμένους, ἀφ' ἧσπερ ἐλίπομεν.

¹ All MSS. except Dhi read γάρ before πρὸς.

² γνωριμώτερα, Corais, for γνωριμώτατα; so the later editors.

³ All MSS. except *oxen* have τ' before Αἰνεῖαν.

⁴ *ix* read Ἴλιον instead of Ἰούλου.

⁵ F reads προσηγορίαν instead of προσωνυμίαν.

⁶ Dhi add νῦν after ἐνταῦθα; A reads ἱδρυτο, and so Corais.

¹ According to Plutarch (*Alexander* 8), "Alexander took with him Aristotle's recension of the poem, called the *Iliad* of the Casket, and always kept it lying beside his dagger

certain extent annotated, and then deposited in a richly wrought casket which he had found amongst the Persian treasures.¹ Accordingly, it was due both to his zeal for the poet and to his descent from the Aeacidae who reigned as kings of the Molossians—where, as we are also told, Andromachê, who had been the wife of Hector, reigned as queen—that Alexander was kindly disposed towards the Ilians. But Caesar, not only being fond of Alexander, but also having better known evidences of kinship with the Ilians, felt encouraged to bestow kindness upon them with all the zest of youth: better known evidences, first, because he was a Roman, and because the Romans believe Aeneias to have been their original founder; and secondly, because the name Iulius was derived from that of a certain Iulus who was one of his ancestors,² and this Iulus got his appellation from the Iulus³ who was one of the descendants of Aeneas. Caesar therefore allotted territory to them and also helped them to preserve their freedom and their immunity from taxation; and to this day they remain in possession of these favours. But that this is not the site of the ancient Ilium, if one considers the matter in accordance with Homer's account, is inferred from the following considerations. But first I must give a general description of the region in question, beginning at that point on the coast where I left off.

under his pillow, as Onesicritus informs us"; and "the casket was the most precious of the treasures of Dareius" (*ibid.* 26).

² *i.e.* of the Julian gens.

³ On "Iulus," or Ilius, see critical note.

28. Ἔστι τοίνυν μετ' Ἀβυδον ἢ τε Δαρδανὶς ἄκρα, ἣς μικρόν¹ πρότερον ἐμνήσθημεν, καὶ ἡ πόλις ἡ Δάρδανος, διέχουσα τῆς Ἀβύδου ἐβδομήκοντα σταδίου. μεταξύ τε ὁ Ῥοδῖος ἐκπίπτει ποταμός, καθ' ὃν ἐν τῇ Χερρονήσῳ τὸ Κυνὸς σήμ' ἐστίν, ὃ φασιν Ἐκάβης εἶναι τάφον· οἱ δὲ τὸν Ῥοδίον εἰς τὸν Αἴσηπον ἐμβάλλειν φασίν· εἰς δ' ἐστὶ τῶν ὑπὸ τοῦ ποιητοῦ λεγομένων καὶ οὗτος·

Ῥήσός θ' Ἐπτάπορος τε Κάρησός τε Ῥοδῖος τε.

ἡ δὲ Δάρδανος κτίσμα ἀρχαῖον, οὕτω δ' εὐκαταφρόνητον, ὥστε πολλάκις οἱ βασιλεῖς οἱ μὲν μετώκιζον αὐτὴν εἰς Ἀβυδον, οἱ δὲ ἀνώκιζον πάλιν εἰς τὸ ἀρχαῖον κτίσμα. ἐνταῦθα δὲ συνῆλθον Σύλλας τε Κορνήλιος, ὁ τῶν Ῥωμαίων ἡγεμών, καὶ Μιθριδάτης ὁ κληθεὶς Εὐπάτωρ, καὶ συνέβησαν πρὸς ἀλλήλους ἐπὶ καταλύσει τοῦ πολέμου.

29. Πλησίον δ' ἐστὶ τὸ Ὀφρύνιον,² ἐφ' ᾧ τὸ τοῦ Ἐκτορος ἄλσος ἐν περιφανεί τύπῳ· καὶ ἐφεξῆς λίμνη³ Πτελεώς.

30. Εἴτα Ῥοίτειον πόλις ἐπὶ λόφῳ κειμένη καὶ τῷ Ῥοιτείῳ⁴ συνεχῆς ἡιῶν ἀλιτενής,⁵ ἐφ' ἣ μνήμα καὶ ἱερὸν Αἴαντος καὶ ἀνδριάς, ὃν ἄραντος Ἀντωνίου κομισθέντα εἰς Αἴγυπτον ἀπέδωκε τοῖς Ῥοιτειεῦσι⁶ πάλιν, καθάπερ καὶ

¹ *moxx* read μικρῶ instead of μικρόν.

² Ὀφρύνιον E and Epit., Ὀφρούνιον other MSS.

³ λίμνη, Leaf (see his note, *Troad*, p. 154), following Calvert, whom he quotes fully, emends to λιμὴν.

⁴ Ῥοιτίῳ Cf. *moxx*, Ῥοιτίῳ D, Ῥοιτίῳ *hi*, Ῥοιτείῳ other MSS.

28. After Abydus, then, comes the Dardanian Promontory, which I mentioned a little while ago,¹ and also the city Dardanus, which is seventy stadia distant from Abydus. Between the two places empties the Rhodius River, opposite which, in the Chersonesus, is Cynos-Sema,² which is said to be the tomb of Hecabê. But some say that the Rhodius empties into the Aesepus. This too is one of the rivers mentioned by the poet: "Rhesus, Heptaporus, Caresus, and Rhodius."³ Dardanus was an ancient settlement, but it was held in such contempt that it was oftentimes transplanted by some of the kings to Abydus and then resettled again by others on the ancient site. It was here that Cornelius Sulla, the Roman commander, and Mithridates surnamed Eupator met and arranged the terms for the conclusion of the war.

29. Near by is Ophrynum, near which, in a conspicuous place, is the sacred precinct of Hector.⁴ And next comes the Lake⁵ of Pteleos.

30. Then come Rhoeteium, a city situated on a hill, and, adjacent to Rhoeteium, a low-lying shore, on which are a tomb and temple of Aias, and also a statue of him, which was taken up by Antony and carried off to Aegypt; but Augustus Caesar gave it back again to the Rhoeteians, just as he gave

¹ 13. 1. 11.

² See "Cynos-Sema" and foot-note in Vol. III, p. 377.

³ *Iliad* 12. 20.

⁴ On the site of Ophrynum, see Leaf, p. 153.

⁵ Leaf, p. 154, following Calvert, emends "Lake" to "Harbour."

⁵ Αἰδοντεῖον, after ἀλιντενής, Jones deletes.

⁶ Ποιτειεῖσι, the editors, for Ποριεῖσι.

ἄλλοις ἄλλους,¹ ὁ Σεβαστὸς Καῖσαρ. τὰ γὰρ κάλλιστα ἀναθήματα ἐκ τῶν ἐπιφανεστάτων ἱερῶν ὁ μὲν ἦρε, τῇ Αἰγυπτίᾳ χαριζόμενος, ὁ δὲ θεοῖς ἀπέδωκε.

31. Μετὰ δὲ τὸ 'Ροίτειόν² ἐστὶ τὸ Σίγειον,³ κατεσπασμένη πόλις, καὶ τὸ ναύσταθμον καὶ ὁ 'Αχαιῶν λιμὴν καὶ τὸ 'Αχαϊκὸν στρατόπεδον καὶ ἡ Στομαλίμνη καλουμένη καὶ αἱ τοῦ Σκαμάνδρου ἐκβολαί. συμπεσόντες γὰρ ὁ τε Σιμόεις καὶ ὁ Σκάμανδρος ἐν τῷ πεδίῳ, πολλὴν καταφέροντες ἰλύν, προσχοῦσι τὴν παραλίαν καὶ τυφλὸν στόμα τε καὶ λιμνοθαλάττας καὶ ἔλη ποιοῦσι. κατὰ δὲ τὴν Σιγειαῖδα⁴ ἄκραν ἐστὶν ἐν τῇ Χερρονήσῳ τὸ Πρωτεσιλάειον⁵ καὶ ἡ 'Ελεοῦσσα,⁶ περὶ ὧν εἰρήκαμεν ἐν τοῖς Θρακίοις.

32. Ἔστι δὲ τὸ μῆκος τῆς παραλίας ταύτης, ἀπὸ τοῦ 'Ροίτειου⁷ μέχρι Σιγείου καὶ τοῦ 'Αχιλλέως μνήματος εὐθυπλοούντων, ἐξήκοντα C 596 σταδίων· ὑποπέπτωκε δὲ τῷ 'Ιλίῳ πᾶσα, τῷ μὲν νῦν κατὰ τὸν 'Αχαιῶν λιμένα ὅσον δώδεκα σταδίοις διέχουσα, τῷ δὲ προτέρῳ τριάκοντα ἄλλοις σταδίοις ἀνωτέρῳ κατὰ τὸ πρὸς τὴν 'Ιδην μέρος. τοῦ μὲν οὖν 'Αχιλλέως καὶ ἱερὸν ἐστὶ καὶ μνῆμα πρὸς τῷ Σιγείῳ, Πατρόκλου δὲ καὶ 'Αντιλόχου μνήματα, καὶ ἐναγίζουσιν οἱ 'Ιλιεῖς πᾶσι καὶ τούτοις καὶ τῷ Αἴαντι. 'Ηρακλέα δ' οὐ τιμῶσιν,

¹ ἄλλους, omitted by the MSS., Kramer inserts (x reads ἄλλα); so the later editors.

² 'Ροίτειον, the editors, for 'Ροίτιον h, 'Ρύτιον other MSS., except that D has oi over v.

³ Σίγειον E, Σίγιον other MSS.

⁴ Σιγειαῖδα E, Σιγιάδα other MSS.

back other statues to their owners. For Antony took away the finest dedications from the most famous temples, to gratify the Egyptian woman,¹ but Augustus gave them back to the gods.

31. After Rhoeteium come Sigeium, a destroyed city, and the Naval Station and the Harbour of the Achaeans and the Achaean Camp and Stomalimnê,² as it is called, and the outlets of the Scamander; for after the Simoeis and the Scamander meet in the plain, they carry down great quantities of alluvium, silt up the coast, and form a blind mouth, lagoons, and marshes. Opposite the Sigeian Promontory on the Chersonesus are Eleussa³ and the temple of Protesilaüs, both of which I have mentioned in my description of Thrace.⁴

32. The length of this coast, I mean on a straight voyage from Rhoeteium to Sigeium, and the monument of Achilles, is sixty stadia; and the whole of it lies below Ilium, not only the present Ilium, from which, at the Harbour of the Achaeans, it is about twelve stadia distant, but also the earlier Ilium, which lies thirty stadia farther inland in the direction of Mt. Ida. Now there are a temple and a monument of Achilles near Sigeium, as also monuments of Patroclus and Antilochus; and the Ilians offer sacrifices to all four heroes, both to these and to Aias. But they do not honour Heracles, giving

¹ Cleopatra. ² "Mouth-of-the-marsh."

³ "Eleussa" appears to be an error for "Eleus."

⁴ Book VII, *Frags.* 51, 54, 55.

⁵ Πρωτεσιλαίων Ε, Πρωτεσίλαιον Forz, Πρωτεσιλαίων C, Πρωτεσιλαίων Dhl.

⁶ 'Ελεοῦσσα. Corais emends to 'Ελαιούσσα.

⁷ 'Ροιτίου Dhl, 'Ροτίου C, 'Ροιτείου other MSS.

αἰτιώμενοι τὴν ὑπ' αὐτοῦ πόρθησιν. ἀλλ' ἐκεῖνος
 μέν, φαίη τις ἄν, οὕτως ἐπόρθησεν, ὥστ' ἀπο-
 λιπεῖν τοῖς ὕστερον ἐκπορθήσουσι κεκακωμένην
 μέν, πόλιν δέ διδὸ καὶ οὕτως εἴρηκεν ὁ ποιητής·

Ἰλίου ἐξαλάπαξε πόλιν, χήρωσε δ' ἀγυιάς.

ἡ γὰρ χηρεία λειπανδρία τίς ἐστιν, οὐκ
 ἀφανισμὸς τέλειος· οὗτοι δ' ἠφάνισαν τελείως,
 οἷς ἐναγίξειν ἀξιούσι καὶ τιμᾶν ὡς θεούς· εἰ μὴ
 τοῦτ' αἰτιάσαιντο, διότι οὗτοι μὲν δίκαιον
 πόλεμον ἐξήνεγκαν, ἐκεῖνος δὲ ἄδικον, ἔνεχ'
 ἵππων Λαομέδοντος· πρὸς τοῦτο δὲ πάλιν ἀν-
 τιτίθεται μῦθος· οὐ γὰρ ἔνεκα ἵππων, ἀλλὰ
 μισθοῦ ὑπὲρ τῆς Ἡσιόνης καὶ τοῦ κήτους. ἀλλ'
 εἰσώμεν ταῦτα· εἰς γὰρ μύθων ἀνασκευὰς
 ἐκπίπτει· τάχα δὲ λανθάνουσί τινες ἡμᾶς αἰτίαι
 πιστότεραι, δι' ἃς τοῖς Ἰλιεῦσιν ἐπῆλθε τοὺς
 μὲν τιμᾶν, τοὺς δὲ μῆ. εἶοικε δὲ ὁ ποιητής
 μικρὰν ἀποφαίνειν τὴν πόλιν ἐν τῷ περὶ
 Ἡρακλέους λόγῳ, εἶπερ

ἐξ οἷης σὺν νηυσὶ καὶ ἀνδράσι παυροτέροισιν
 Ἰλίου ἐξαλάπαξε πόλιν.

καὶ φαίνεται ὁ Πρίαμος τῷ τοιούτῳ λόγῳ μέγας
 ἐκ μικροῦ γεγονώς καὶ βασιλεὺς βασιλέων, ὡς
 ἔφαμεν. μικρὸν δὲ προελθοῦσιν ἀπὸ τῆς παρα-
 λίας ταύτης ἐστὶ τὸ Ἀχαιῖον, ἥδη τῆς Τενεδίων
 περαιᾶς ὑπαρχον.

¹ *Iliad* 5, 642.

² *Iliad* 5, 640.

³ To appease the anger of Poseidon, Laomedon exposed his daughter Hesione on the promontory Agameia (see Stephanus s.v.) to be devoured by a sea-monster. Heracles promised to kill the monster and save Hesione if Laomedon

as their reason his sacking of the city. But one might say that, although Heracles did sack it, yet he sacked it in such a way as still to leave it a city, even though damaged, for those who were later to sack it utterly; and for this reason the poet states it thus: "He sacked the city of Ilios and widowed her streets";¹ for "widowed" means a loss of the male population, not a complete annihilation. But the others, whom they think fit to worship with sacrifices and to honour as gods, completely annihilated the city. Perhaps they might give as their reason for this that these waged a just war, whereas Heracles waged an unjust one "on account of the horses of Laomedon."² But writers set over against this reason the myth that it was not on account of the horses but of the reward offered for Hesione and the sea-monster.³ But let us disregard these reasons, for they end merely in controversies about myths. And perhaps we fail to notice certain more credible reasons why it occurred to the Ilians to honour some and not others. And it appears that the poet, in what he says about Heracles, represents the city as small, if it be true that "with only six ships and fewer men he sacked the city of Ilium."⁴ And it is clearly shown by this statement that Priam became great and king of kings from a small beginning, as I have said before.⁵ Advancing a little farther along this shore, one comes to the Achæum, where begins the part of the mainland that belongs to Tenedos.

would give him his immortal horses. Laomedon agreed. Heracles fulfilled his promise, but Laomedon refused to give up the horses, and hence the war.

¹ *Iliad* 5. 641.

² 12. 8. 7, 13. 1. 7.

33. Τοιούτων δὲ τῶν ἐπὶ τῇ θαλάττῃ τόπων ὄντων, ὑπέρκειται τούτων τὸ Τρωικὸν πεδίον μέχρι τῆς Ἰδῆς ἀνήκον ἐπὶ πολλοὺς σταδίους κατὰ τὸ πρὸς ἑω μέρος. τούτου δ' ἡ μὲν παρῳρείος ἐστὶ στενὴ, τῇ μὲν ἐπὶ τὴν μεσημβρίαν τεταμένη μέχρι τῶν κατὰ Σκῆψιν τόπων, τῇ δ' ἐπὶ τὰς ἀρκτους μέχρι τῶν κατὰ Ζέλειαν Λυκίων. ταύτην δ' ὁ ποιητὴς ὑπ' Αἰνεΐα τάττει καὶ τοῖς Ἀντηνορίδαις, καλεῖ δὲ Δαρδανίαν. ὑπὸ δὲ ταύτῃ Κεβρηνία, πεδιάς ἢ πλείστη, παράλληλός πως τῇ Δαρδανίᾳ· ἣν δὲ καὶ πόλις ποτὲ Κεβρήνη. ὑπονοεῖ δ' ὁ Δημήτριος μέχρι δεῦρο διατείνειν τὴν περὶ τὸ Ἴλιον χώραν τὴν ὑπὸ τῷ Ἑκτορι, ἀνήκουσαν ἀπὸ τοῦ ναυστάθμου μέχρι Κεβρηνίας· τάφον τε γὰρ Ἀλεξάνδρου δείκνυσθαι φησιν αὐτόθι καὶ Οἰνῶνης, ἣν ἱστοροῦσι γυναῖκα γεγενέναι τοῦ Ἀλεξάνδρου, πρὶν Ἑλένην ἀρπάσαι· λέγειν τε τὸν ποιητὴν¹

Κεβριόνην νόθον υἱὸν ἀγακλῆος Πριάμοιο,

Ο 597 ὃν εἰκὸς εἶναι ἐπώνυμον τῆς χώρας ἢ καὶ πόλεως, ὅπερ πιθανώτερον· τὴν δὲ Κεβρηνίαν διήκειν μέχρι τῆς Σκηψίας, ὅριον δ' εἶναι τὸν Σκάμανδρον μέσον αὐτῶν ρέοντα· ἔχθραν δ' αἰεὶ καὶ πόλεμον εἶναι τοῖς τε Κεβρηνοῖς καὶ τοῖς Σκηψίοις, ἕως Ἀντίγονος αὐτοὺς συνώκισεν εἰς τὴν τότε μὲν Ἀντιγονίαν, νῦν δὲ Ἀλεξανδρείαν· τοὺς μὲν οὖν Κεβρηνίας² συμμεῖναι τοῖς ἄλλοις ἐν τῇ Ἀλεξανδρείᾳ, τοὺς δὲ Σκηψίους ἐπανελθεῖν εἰς τὴν οἰκείαν, ἐπιτρέψαντος Λυσιμάχου.

¹ λέγειν τε τὸν ποιητὴν F, λέγει δ ποιητῆς καὶ x; CDhl omit τε, nos read τε καί.

² Instead of Κεβρηνίας im-xc read Κεβρήνους.

33. Such are the places on the sea. Above these lies the Trojan Plain, which extends inland for many stadia in the direction of the east as far as Mt. Ida. The part of this plain alongside the mountain is narrow, extending on one side towards the south as far as the region of Scepsis, and on the other towards the north as far as the Lycians of Zeleia. This is the country which the poet makes subject to Aeneias and the sons of Antenor, calling it Dardania; and below this is Cebrenia, which is level for the most part and lies approximately parallel to Dardania; and in it there was once a city called Cebrenê.¹ Demetrius suspects that the territory of Ilium subject to Hector extended inland from the naval station as far as Cebrenia, for he says that the tomb of Alexander² is pointed out there, as also that of Oenonê, who, according to historians, had been the wife of Alexander before he carried off Helen. And, he continues, the poet mentions "Cebriones, bastard son of glorious Priam,"³ after whom, as one may suppose, the country was named—or the city too, which is more plausible; and Cebrenia extends as far as the territory of Scepsis; and the Scamander, which flows between, is the boundary; and the Cebreni and Scepsians were always hostile to one another and at war until Antigonus settled both peoples together in Antigonía, as it was then called, or Alexandreia, as it is now called; now the Cebreni, he adds, remained with the rest in Alexandreia, but the Scepsians, by permission of Lysimachus, went back to their homeland.

¹ So the name is spelled in § 47, but "Cebren" in § 52.

² Paris.

³ *Iliad* 16. 738.

34. Ἀπὸ δὲ τῆς κατὰ τούτους¹ τοὺς τόπους Ἰδαίας ὀρεινῆς δύο φησὶν ἀγκῶνας ἐκτείνεσθαι πρὸς θάλατταν, τὸν μὲν εὐθὺ Ῥοιτείου,² τὸν δὲ Σιγείου, ποιοῦντας ἕξ ἀμφοῖν γραμμὴν ἡμικυκλιώδη· τελευτᾶν δ' ἐν τῷ πεδίῳ, τοσοῦτον ἀπέχοντας τῆς θαλάττης, ὅσον τὸ νῦν Ἴλιον. τοῦτο μὲν δὴ μεταξὺ τῆς τελευτῆς τῶν λεχθέντων ἀγκῶνων εἶναι, τὸ δὲ παλαιὸν κτίσμα μεταξὺ τῆς ἀρχῆς μεταλαμβάνεσθαι³ δ' ἐντὸς τοῦ Σιμοείσιον πεδίου, δι' οὗ ὁ Σιμόεις φέρεται, καὶ τὸ Σκαμάνδριον, δι' οὗ Σκάμανδρος ῥεῖ. τοῦτο δὲ καὶ ἰδίως Τρωικὸν λέγεται, καὶ τοὺς πλείστους ἀγκῶνας ὁ ποιητὴς ἐνταῦθα ἀποδίδωσι, πλατύτερον γάρ ἐστι, καὶ τοὺς ὀνομαζομένους τόπους ἐνταῦθα δεικνυμένους ὀρώμεν, τὸν Ἐρινεόν, τὸν τοῦ Αἰσυνήτου τάφον, τὴν Βατίειαν,⁴ τὸ τοῦ Ἴλου σῆμα. οἱ δὲ ποταμοὶ ὃ τέ Σκάμανδρος καὶ ὁ Σιμόεις, ὁ μὲν τῷ Σιγείῳ πλησιάσας, ὁ δὲ τῷ Ῥοιτείῳ, μικρὸν ἔμπροσθεν τοῦ νῦν Ἰλίου συμβάλλουσιν, εἴτ' ἐπὶ τὸ Σίγειον ἐκδιδῶσι καὶ ποιοῦσι τὴν Στομαλίμνην καλουμένην. διείργει δ' ἐκάτερον τῶν λεχθέντων πεδίων ἀπὸ θατέρου μέγας τις αὐχὴν τῶν εἰρημένων ἀγκῶνων ἐπ' εὐθείας, ἀπὸ τοῦ νῦν Ἰλίου τὴν ἀρχὴν ἔχων, συμφυὲς αὐτῷ, τεινόμενος δ' ἕως τῆς Κεβρηνίας καὶ ἀποτελὼν τὸ ζ γράμμα πρὸς τοὺς ἐκατέρωθεν ἀγκῶνας.

¹ τούτους, before τούς, Groskurd inserts; so Müller-Dübner, Meineke, and Leaf.

² Ῥοιτείου, the editors, for Ῥοιτίου ODFH, Ῥοτίου other MSS.

³ μεταλαμβάνεσθαι, all MSS. except E, which reads μεταλάσσεσθαι, Leaf rightly restores, instead of ἀπολαμβάνεσθαι Meineke, καταλαμβάνεσθαι Corais.

34. From the mountain range of Ida in this region, according to Demetrius, two spurs extend to the sea, one straight to Rhoeteium and the other straight to Sigeium, forming together a semicircular line, and they end in the plain at the same distance from the sea as the present Ilium; this Ilium, accordingly, lies between the ends of the two spurs mentioned, whereas the old settlement lies between their beginnings; and, he adds, the spurs include both the Simoeisian Plain, through which the Simoeis runs, and the Scamandrian Plain, through which the Scamander flows. This is called the Trojan Plain in the special sense of the term; and here it is that the poet represents most of the fights as taking place, for it is wider; and here it is that we see pointed out the places named by the poet—Erineus,¹ the tomb of Aesyetes,² Baticia,³ and the monument of Ilus.⁴ The Scamander and Simoeis Rivers, after running near to Sigeium and Rhoeteium respectively, meet a little in front of the present Ilium, and then issue towards Sigeium and form Stomalimné,⁵ as it is called. The two plains above mentioned are separated from each other by a great neck of land which runs in a straight line between the aforesaid spurs, starting from the present Ilium, with which it is connected, and stretches as far as Cebrenia and, along with the spurs on either side,⁶ forms a complete letter ζ.⁷

¹ "Fig tree." *Iliad* 6. 433.

² *Iliad* 2. 793.

³ *Iliad* 2. 813.

⁴ *Iliad* 10. 415.

⁵ See 13. I. 31 and foot-note.

⁶ These spurs forming a semi-circular line, as stated above.

⁷ *i.e.* the uncial letter written backwards (z). See Leaf's diagram, p. 175.

⁴ *Baticia*, Xylander, for *Báreia*; so the later editors.

35. Ὑπὲρ δὲ τούτου μικρὸν ἢ τῶν Ἰλίων κώμη ἐστίν, ἐν ᾗ νομίζεται τὸ παλαιὸν Ἴλιον ἰδρῦσθαι πρότερον, τριάκοντα σταδίους διέχων ἀπὸ τῆς νῦν πόλεως. ὑπὲρ δὲ τῆς Ἰλίων κώμης δέκα σταδίους ἐστίν ἡ Καλλικολώνη, λόφος τις, παρ' ὃν ὁ Σιμόεις ρεῖ, πενταστάδιον διέχων¹ γίνεται οὖν εὐλογον πρῶτον μὲν τὸ ἐπὶ τοῦ Ἀρεος·

ὦρτο δ' Ἀρης ἐτέρωθεν ἐρεμνῇ λαίλαπι ἴσος,
ὀξὺ κατ' ἀκροτάτης πόλιος Ἑρώεσσι κελεύων,
ἄλλοτε παρ Σιμόεντι θέων ἐπὶ Καλλικολώνη.

C 598 τῆς γὰρ μάχης ἐπὶ τῷ Σκαμανδρίῳ πεδίῳ συντελουμένης, πιθανῶς ἂν ὁ Ἀρης ἄλλοτε μὲν τὴν ἐγκέλευσιν ἀπὸ τῆς ἀκροπόλεως ποιοῖτο, ἄλλοτε δ' ἐκ τῶν πλησίον τόπων τοῦ τε Σιμόεντος καὶ τῆς Καλλικολώνης, μέχρι οὗ εἰκὸς καὶ τὴν μάχην παρατετάσθαι. τετταράκοντα δὲ σταδίους διεχούσης τῆς Καλλικολώνης ἀπὸ τοῦ νῦν Ἰλίου, τί χρήσιμον ἐπὶ τοσοῦτον μεταλαμβάνεσθαι τοὺς τόπους, ἐφ' ὅσον ἡ διάταξις οὐ διέτεινε; τό τε

πρὸς Θύμβρης δ' ἔλαχον Λύκιοι

οἰκειότερόν ἐστι τῷ παλαιῷ κτίσματι· πλησίον γάρ ἐστι τὸ πεδίον ἢ Θύμβρα καὶ ὁ δι' αὐτοῦ ῥέων ποταμὸς Θύμβριος, ἐμβάλλων εἰς τὸν Σκάμανδρον κατὰ τὸ Θυμβραίου Ἀπόλλωνος ἱερόν, τοῦ δὲ νῦν Ἰλίου καὶ πεντήκοντα σταδίους

¹ διέχων, Corais, from conj. of Palmer, for ἔχων; i has κύκλεω after ἔχων, and so Eustathius reads (note on *Iliad* 20. 47, 53). The scholiast (quoted by C. Müller, *Ind. Var. Lect.* p. 1024) quotes Demetrius as saying that this hill is "five stadia in

35. A little above this¹ is the Village of the Ilians, where the ancient Ilium is thought to have been situated in earlier times, at a distance of thirty stadia from the present city. And ten stadia above the Village of the Ilians is Callicoloné, a hill, past which, at a distance of five stadia, flows the Simoeis.² It therefore becomes easy to understand, first, the reference to Ares: "And over against her leaped Ares, like unto a dreadful whirlwind, in shrill tones cheering the Trojans from the topmost part of the city, and now again as he sped alongside Simoeis o'er Callicoloné";³ for if the battle was fought on the Scamandrian Plain, it is plausible that Ares should at one time shout his cheers from the acropolis and at another from the region near the Simoeis and Callicoloné, up to which, in all probability, the battle would have extended. But since Callicoloné is forty stadia distant from the present Ilium, for what useful purpose would the poet have taken in places so far away that the line of battle could not have reached them? Again, the words, "And towards Thymbra fell the lot of the Lycians,"⁴ are more suitable to the ancient settlement, for the plain of Thymbra is near it, as also the Thymbrus River, which flows through the plain and empties into the Scamander at the temple of the Thymbraean Apollo, but Thymbra is actually fifty stadia distant from the

¹ *i.e.* a little farther inland than the country which has the shape of the letter in question.

² See critical note.

³ *Iliad* 20. 51.

⁴ *Iliad* 10. 430.

perimeter . . . , five stadia distant from the Simoeis, and ten stadia distant from the village of the Ilians."

διέχει. ὃ τε Ἑρινεός, τραχύς τις τόπος καὶ ἐρινεώδης, τῷ μὲν ἀρχαίῳ κτίσματι ὑποπέπτωκεν, ὥστε τὸ

λαὸν δὲ στήσων παρ' Ἑρινεόν, ἔνθα μάλιστα ἄμβατός ἐστι πόλις καὶ ἐπίδρομον ἔπλετο τεῖχος

οἰκείως ἂν λέγοι¹ ἡ Ἀνδρομάχη, τῆς δὲ νῦν πόλεως πάμπολυ ἀφέστηκε.² καὶ ὁ Φηγὸς δὲ μικρὸν κατωτέρω ἐστὶ τοῦ Ἑρινεοῦ, ἐφ' οὗ φησὶν ὁ Ἀχιλλεύς,

ὄφρα δ' ἐγὼ μετ' Ἀχαιοῖσιν πολέμιζον,
οὐκ ἐθέλεσκε μάχην ἀπὸ τείχεος ὀρνύμεν
Ἐκτωρ,
ἀλλ' ὅσον ἐς Σκαιάς τε πύλας καὶ Φηγὸν
ἵκανεν.³

36. Καὶ μὴν τό γε ναύσταθμον τὸ νῦν ἔτι λεγόμενον πλησίον οὕτως ἐστὶ τῆς νῦν πόλεως, ὥστε θαυμάζειν εἰκότως ἂν τινα τῶν μὲν τῆς ἀπονοίας, τῶν δὲ τούναντίον τῆς ἀψυχίας· ἀπονοίας μὲν, εἰ εἰς⁴ τοσοῦτον χρόνον ἀτείχιστον αὐτὸ εἶχον, πλησίον οὔσης τῆς πόλεως καὶ τοσοῦτον πλήθους, τοῦ τ' ἐν αὐτῇ καὶ τοῦ ἐπικουρικοῦ· νεωστὶ γὰρ γεγονέναι φησὶ τὸ τεῖχος (ἢ οὐδ' ἐγένετο, ὁ δὲ πλάσας ποιητῆς ἠφάνισεν, ὡς Ἀριστοτέλης φησὶν) ἀψυχίας δέ, εἰ, γενομένου τοῦ τείχους, ἐτειχομάχουν καὶ⁵ εἰσέπεσον εἰς αὐτὸ τὸ ναύσταθμον καὶ προσεμάχοντο ταῖς ναυσίν, ἀτείχιστον δὲ ἔχοντες, οὐκ ἐθάρρουν προσιόντες πολιορκεῖν, μικροῦ τοῦ

¹ Some of the MSS. read λέγοιτο instead of λέγοι.

present Ilium. And again, Erineus,¹ a place that is rugged and full of wild fig trees, lies at the foot of the ancient site, so that Andromachê might appropriately say, "Stay thy host beside Erineus, where best the city can be approached and the wall scaled,"² but Erineus stands at a considerable distance from the present Ilium. Further, a little below Erineus is Phegus,³ in reference to which Achilles says, "But so long as I was carrying on war amid the Achaeans, Hector was unwilling to rouse battle away from the wall, but would come only as far as the Scaean Gates and Phegus."⁴

36. However, the Naval Station, still now so called, is so near the present Ilium that one might reasonably wonder at the witlessness of the Greeks and the faint-heartedness of the Trojans; witlessness, if the Greeks kept the Naval Station unvalled for so long a time, when they were near to the city and to so great a multitude, both that in the city and that of the allies; for Homer says that the wall had only recently been built (or else it was not built at all, but fabricated and then abolished by the poet, as Aristotle says); and faint-heartedness, if the Trojans, when the wall was built, could besiege it and break into the Naval Station itself and attack the ships, yet did not have the courage to march up and besiege the station when it was still unvalled and only

¹ See foot-note on "Erineus," § 34 above.

² *Iliad* 6. 433.

³ Oak tree.

⁴ *Iliad* 9. 352.

² ἀφίστηναι (the reading of Eustathius, note on *Iliad* 6. 433), Casaubon, for ἀπείσσει; so Kramer and Meineke.

³ Ἰκαίην, Xylander, for Ἰκέρην; so the later editors.

⁴ els, Meineke omits.

⁵ καί, Meineke and Leaf, from conj. of Kramer, for ὥς.

διαστήματος ὄντος· ἔστι γὰρ τὸ ναύσταθμον
 πρὸς Σιγείῳ, πλησίον δὲ καὶ ὁ Σκάμανδρος
 ἐκδίδωσι, διέχων τοῦ Ἰλίου σταδίους εἴκοσιν.
 εἰ δὲ φήσῃ τις τὸν νῦν λεγόμενον Ἀχαιῶν
 λιμένα εἶναι τὸ ναύσταθμον, ἐγγυτέρω τινὰ λέξει
 τόπον, ὅσον δώδεκα σταδίους διεστώτα τῆς
 πόλεως, τὸ¹ ἐπὶ θαλάττῃ πεδίον συμπροστιθείς,²
 διότι τοῦτο πᾶν πρόσχωμα³ τῶν ποταμῶν ἐστὶ, τὸ
 πρὸ τῆς πόλεως ἐπὶ θαλάττῃ πεδίον· ὥστε, εἰ
 δωδεκαστάδιόν ἐστι νῦν τὸ μεταξύ, τότε καὶ τῷ
 ἡμίσει ἔλαττον ὑπῆρχε. καὶ ἡ διήγησις δ' ἡ
 C 599 πρὸς τὸν Εὐμαιοῖν ὑπὸ τοῦ Ὀδυσσεύος διασκευασ-
 θεῖσα μέγα ἐμφαίνει τὸ διάστημα τὸ μέχρι
 τῆς πόλεως ἀπὸ τοῦ ναυστάθμου·

ὥς ὅθ' ὑπὸ Ἴρῳι λόχον ἤγομεν·
 φησὶ γὰρ ὑποβάς·

λίην γὰρ νηῶν ἐκὰς ἤλθομεν.
 ἐπὶ τε τὴν κατασκοπὴν πέμπονται γνωσόμενοι,
 ποτέρον μενοῦσι παρὰ νηυσὶν ἀπόπροθεν πολὺ
 ἀπεσπασμένοι τοῦ οἰκείου τείχους,

ἢ πόλινδε

ἂψ ἀναχωρήσουσι.

καὶ ὁ Πολυδάμας,

ἀμφὶ μᾶλα φράζεσθε, φίλοι· κέλομαι γὰρ
 ἔγωγε

ἄστυδε νῦν ἰέναι,

φησὶν,

ἐκὰς δ' ἀπὸ τείχεός εἰμεν.

παρατίθῃσι δ' ὁ Δημήτριος καὶ τὴν Ἀλεξανδρινὴν
 Ἑστιάαν μάρτυρα, τὴν συγγράψασαν περὶ τῆς
 Ὀμήρου Ἰλιάδος, πυνθανομένην, εἰ περὶ τὴν νῦν

a slight distance away; for it is near Sigeium, and the Scamander empties near it, at a distance of only twenty stadia from Ilium. But if one shall say that the Harbour of Achacans, as it is now called, is the Naval Station, he will be speaking of a place that is still closer, only about twelve stadia distant from the city, even if one includes the plain by the sea, because the whole of this plain is a deposit of the rivers—I mean the plain by the sea in front of the city; so that, if the distance between the sea and the city is now twelve stadia, it must have been no more than half as great at that time. Further, the feigned story told by Odysseus to Eumachus clearly indicates that the distance from the Naval Station to the city is great, for after saying, “as when we led our ambush¹ beneath the walls of Troy,” he adds a little below, “for we went very far from the ships.” And spies are sent forth to find whether the Trojans will stay by the ships “far away,” far separated from their own walls, “or will withdraw again to the city.”² And Polydamas says, “on both sides, friends, bethink ye well, for I, on my own part, bid you now to go to the city; afar from the walls are we.”³ Demetrius cites also Hestiaea of Alexandreia as a witness, a woman who wrote a work on Homer’s *Iliad* and inquired whether

¹ *Odyssey* 14. 469.² *Iliad* 10. 209.³ *Iliad* 18. 254.¹ τό, before ἐπὶ, Groskurd inserts; so the later editors.² συμπροστίθεις, Meineke, for νῦν προστίθεις; Leaf omits ἐπὶ . . . προστίθεις; Kramer conj. οὐκ εἶδ after προστίθεις.³ πρόσχωμα Crows, πρόχωμα other MSS.

πόλιν ὁ πόλεμος συνέστη καὶ¹ τὸ Τρωικὸν πεδίον, ὃ μεταξὺ τῆς πόλεως καὶ τῆς θαλάττης ὁ ποιητὴς φράζει· τὸ μὲν γὰρ πρὸ τῆς νῦν πόλεως ὁρώμενον πρόσχωμα εἶναι τῶν ποταμῶν ὕστερον γεγονός.

37. "Ο τε Πολίτης,

ὃς Τρώων σκοπὸς ἴξε, ποδωκείησι πεποιθώς,
τύμβῳ ἐπ' ἀκροτάτῳ Αἰσυνήταο γέροντος,

μάταιος ἦν. καὶ γὰρ εἰ ἐπ' ἀκροτάτῳ, ὅμως ἀπὸ² πολὺ ἂν μείζονος ὕψους τῆς ἀκροπόλεως ἐσκόπευεν, ἐξ ἴσου σχεδόν τι διαστήματος, μὴ δεόμενος μηδὲν τῆς ποδωκείας τοῦ ἀσφαλούς χάριν· πέντε γὰρ διέχει σταδίους ὁ νῦν δεικνύμενος τοῦ Αἰσυνήτου τάφος κατὰ τὴν εἰς Ἀλεξάνδρειαν ὁδόν. οὐδ' ἡ τοῦ Ἑκτορος δὲ περιδρομὴ ἢ περὶ τὴν πόλιν ἔχει τι εὐλογον, οὐ γὰρ ἐστὶ περιδρομος ἢ νῦν, διὰ τὴν συνεχῆ ῥάχιν· ἢ δὲ παλαιὰ ἔχει περιδρομὴν.

38. Οὐδὲν δ' ἔχνος σώζεται τῆς ἀρχαίας πόλεως· εἰκότως· ἅτε γὰρ ἐκπεπορθημένων τῶν κύκλῳ πόλεων, οὐ τελέως δὲ κατεσπασμένων, ταύτης δ' ἐκ βάθρων ἀνατετραμμένης, οἱ λίθοι πάντες εἰς τὴν ἐκείνων ἀνάληψιν μετηνέχθησαν. Ἀρχαϊάνακτα γοῦν φασι τὸν Μιτυληναῖον ἐκ τῶν ἐκείθεν λίθων τὸ Σίγειον τειχίσαι. τοῦτο δὲ κατέσχον μὲν Ἀθηναῖοι, Φρύνωνα τὸν Ὀλυμπιονίκην πέμψαντες, Λεσβίων ἐπιδικαζομένων σχεδόν τι τῆς συμπάσης Τρωάδος· ὧν δὴ καὶ

¹ After καὶ Groskurd inserts ποῦ ἐστὶ, Kramer conj. ποῦ or τί, Meineke indicates a lacuna, and Leaf omits altogether τὸ Τρωικὸν πεδίον . . . ὕστερον γεγονός.

the war took place round the present Ilium and the Trojan Plain, which latter the poet places between the city and the sea; for, she says, the plain now to be seen in front of the present Ilium is a later deposit of the rivers.

37. Again, Polites, "who was wont to sit as a sentinel of the Trojans, trusting in his fleetness of foot, on the topmost part of the barrow of aged Aesyetes,"¹ was doing a foolish thing, for even though he sat on the topmost part of it, still he might have kept watch from the much greater height of the acropolis, at approximately the same distance, with no need of fleetness of foot for safety; for the barrow of Aesyetes now pointed out is five stadia distant on the road to Alexandreia. Neither is the "clear running space"² of Hector round the city easy to understand, for the present Ilium has no "clear running space," on account of the ridge that joins it. The ancient city, however, has a "clear running space" round it.

38. But no trace of the ancient city survives; and naturally so, for while the cities all round it were sacked, but not completely destroyed, yet that city was so utterly demolished that all the stones were taken from it to rebuild the others. At any rate, Archaeanax of Mitylenê is said to have built a wall round Sigeium with stones taken from there. Sigeium was seized by Athenians under Phrynon the Olympian victor, although the Lesbians laid claim to almost the whole of the Troad. Most of the settlements in

¹ *Iliad* 2. 792.

² See *Iliad* 2. 812.

² ἀπό, before πολύ, Corais inserts; and so Meineke. Kramer and Leaf insert ἀφ' before ὕψους.

C 600 κτίσματά εἰσιν αἱ πλεῖσται τῶν κατοικιῶν, αἱ μὲν συμμένουσai καὶ νῦν, αἱ δ' ἠφανισμέναι. Πιττακὸς δ' ὁ Μιτυληναῖος, εἰς τῶν ἑπτὰ σοφῶν λεγομένων, πλεύσας ἐπὶ τὸν Φρύνωνα στρατηγὸν διεπολέμει τέως, διατιθεὶς καὶ πάσχων κακῶς, ὅτε καὶ Ἀλκαῖος φησιν ὁ ποιητής, ἑαυτὸν ἔν τινι ἀγῶνι κακῶς φερόμενον τὰ ὄπλα ῥίψαντα φυγεῖν· λέγει δὲ πρὸς τινα κήρυκα, κελεύσας ἀγγεῖλαι τοῖς ἐν οἴκῳ, Ἀλκαῖος σόος Ἄρει ἔν τεα δ' † οὐκὺτὸν ἀληκτορὶν ἐς Γλαυκωποῦ ἱερὸν ἀνεκρέμασαν Ἀττικοί,¹ ὕστερον δ' ἐκ μονομαχίας, προκαλεσαμένου² τοῦ Φρύνωνος, ἀλιευτικὴν ἀναλαβὼν σκευὴν συνέδραμε, καὶ τῷ μὲν ἀμφιβλήστρῳ περιέβαλε, τῇ τριαίνῃ δὲ καὶ τῷ ξιφιδίῳ ἔπειρε καὶ ἀνεῖλε. μένοντος δ' ἔτι τοῦ πολέμου, Περίανδρος διαιτητὴς αἰρεθεὶς ὑπὸ ἀμφοῖν ἔλυσε τὸν πόλεμον.

39. Τίμαιον δὲ ψεύσασθαί φησιν ὁ Δημήτριος, ἱστοροῦντα ἐκ τῶν λίθων τῶν ἐξ Ἰλίου Περίανδρον ἐπιτειχίσαι³ τὸ Ἀχίλλειον τοῖς Ἀθηναίοις, βοηθοῦντα τοῖς περὶ Πιττακόν· ἐπιτειχισθῆναι μὲν γὰρ ὑπὸ τῶν Μιτυληναίων τὸν τόπον τοῦτον τῷ Σιγείῳ, οὐ μὴν ἐκ λίθων τοιούτων, οὐδ' ὑπὸ τοῦ

¹ Meineke, following conj. of Kramer, ejects ὅτε . . . Ἀττικοί. The passage Ἀλκαῖος . . . Ἀττικοί, from σόος to ἀνεκρέμασαν, has been so badly mutilated by the copyists that it is impossible to do more in a translation than to give the general sense of it. For conjectural restorations see Kramer, C. Müller (*Ind. Var. Lect.* p. 1025), and Bergk (Vol. III. Frag. 32 of Alcaeus), who reads ἐνθαδ' οὐκὺτὸν ἀληκτορὶν ἐς γλαυκωπὸν ἱερὸν ὃν ἐκρέμασαν Ἀττικοί. Meineke and Leaf omit the whole passage.

² προκαλεσαμένου F, other MSS. προσκαλεσαμένου.

³ ἐπιτειχίσαι, Corais, for περιτειχίσαι; so the later editors.

the Troad belong, in fact, to the Lesbians, and some endure to this day, while others have disappeared. Pittacus of Mitylenê, one of the Seven Wise Men, as they are called, sailed against Phrynon the general¹ and for a time carried on the war, but with poor management and ill consequences. It was at this time that the poet Alcaeus says that he himself, being sorely pressed in a certain battle, threw away his arms and fled. He addresses his story to a certain herald, whom he had bidden to report to the people at home that "Alcaeus is safe, but his arms have been hung up as an offering to Ares by the Attic army in the temple of Athena Glaukopis."² But later, on being challenged to single combat by Phrynon, he took up his fishing-tackle, ran to meet him, entangled him in his fishing net, and stabbed and slew him with trident and dagger. But since the war still went on, Periander was chosen by both sides as arbiter and ended it.

39. Demetrius says that Timaeus falsifies when he informs us that Periander fortified Achilleium against the Athenians with stones from Ilium, to help the army of Pittacus; for this place, he says, was indeed fortified by the Mitylenaeans against Sigeium, though not with such stones as those, nor yet by Periander.

¹ The Athenian general.

² Only this fragment (Bergk 32) of Alcaeus' poem, addressed to Melanippus (see Herodotus 5. 95), is preserved. But the text has been so badly mutilated by the copyists that none of the conjectural restorations can with certainty be adopted; and hence the translator can give only the general sense of the passage. However, the whole reference to Alcaeus appears to be merely a note that has crept into the text from the margin (see critical note).

Περιάνδρου. πῶς γὰρ ἂν αἰρεθῆναι διαιτητὴν
τὸν προσπολεμοῦντα; Ἀχιλλεῖον δ' ἐστὶν ὁ
τόπος, ἐν ᾧ τὸ Ἀχιλλέως μνῆμα, κατοικία μικρά.
κατέσκαπται δὲ καὶ τὸ Σίγειον ὑπὸ τῶν Ἰλιέων
ἁπειθοῦν.¹ ὑπ' ἐκείνοις γὰρ ἦν ὕστερον ἢ
παρὰ πᾶσα ἢ μέχρι Δαρδάνου, καὶ νῦν ὑπ'
ἐκείνοις ἐστὶ. τὸ δὲ παλαιὸν ὑπὸ τοῖς Αἰολεῦσιν
ἦν τὰ πλεῖστα, ὥστε Ἐφορος οὐκ ὀκνεῖ πᾶσαν
τὴν ἀπὸ Ἀβύδου μέχρι Κύμης καλεῖν Αἰολίδα.
Θουκυδίδης δέ φησιν ἀφαιρεθῆναι τὴν Τροίαν
ὑπὸ Ἀθηναίων τοὺς Μιτυληναίους ἐν τῷ
Πελοποννησιακῷ πολέμῳ τῷ Παχηγίῳ.

40. Λέγουσι δ' οἱ νῦν Ἰλιεῖς καὶ τοῦτο, ὥς οὐδὲ τελέως ἠφάνισθαι συνέβαινεν² τὴν πόλιν κατὰ τὴν ἄλωσιν ὑπὸ τῶν Ἀχαιῶν, οὐδ' ἐξελείφθη³ οὐδέποτε. αἱ γοῦν Λοκρίδες παρθένοι, μικρὸν ὕστερον ἀρξάμεναι, ἐπέμποντο κατ' ἔτος. καὶ ταῦτα δ' οὐχ Ὀμηρικά· οὔτε γὰρ τῆς Κασάνδρας φθορὰν οἶδεν Ὀμηρος, ἀλλ' ὅτι μὲν παρθένος ἦν ὑπ' ἐκείνουν τὸν χρόνον λέγει·

πέφνε γὰρ Ὀθρυονῆα, Καβησόθεν ἔνδον ἔοντα,
ὃς ῥα νέον πτολέμοιο μετὰ κλέος εἴληλούθει.

¹ CDF*hirwa* read ἀπειθούντων instead of ἀπειθοῦν.

² *mz*, and Corais, read *συνέβη* instead of *συνέβαινον*.

³ ἐξελείφθη, Corais, for ἐξελήφθη CDF, ἐξηλήφθη *hi*, ἐξηλείφθη *moz.*

¹ See 13. 1. 4.

² *i.e.* the campaign of Paches, the Athonian general, who in 427 B.C. captured Mitylenê (see Thucydides 3. 18-49).

³ To appease the wrath of Athena, caused after the Trojan War by the sacrilege of Aias the Locrian in her temple (he

For how could the opponent of the Athenians have been chosen as arbiter? Achilleium is the place where stands the monument of Achilles and is only a small settlement. Sigeium, also, has been rased to the ground by the Ilians, because of its disobedience; for the whole of the coast as far as Dardanus was later subject to the Ilians and is now subject to them. In ancient times the most of it was subject to the Aeolians, so that Ephorus does not hesitate to apply the name Aeolis to the whole of the coast from Abydus to Cymê.¹ Thucydides says that Troy was taken away from the Mitylenaeans by the Athenians in the Pachetian part² of the Peloponnesian War.

40. The present Ilians further tell us that the city was, in fact, not completely wiped out at its capture by the Achaeans and that it was never even deserted. At any rate the Locrian maidens, beginning a little later, were sent every year.³ But this too is non-Homeric, for Homer knows not of the violation of Cassandra, but he says that she was a maiden at about that time, "for he⁴ slew Othryoneus, a sojourner in Troy from Cabesus, who had but recently come, following after the rumour of war,⁵ and he

dragged Cassandra away from the altar of the Palladium), the Locrians were instructed by an oracle from Delphi to send to her temple (as temple slaves) at Ilium two maidens every year for a thousand years. It appears that the servitude of the maidens lasted for only one year, each pair being released at the end of the year when the next pair arrived, but that upon their return home they were forced to remain unmarried (see Leaf, *Annual of the British School at Athens*, XXI, pp. 148-154).

⁴ Idomeneus, son of Minos and King of Crete; one of the bravest heroes of the war.

⁵ Or perhaps "in quest of war's renown" (Leaf).

ἥτεε δὲ Πριάμοιο θυγατρῶν εἶδος ἀρίστην,
Κασσάνδρην, ἀνάεδνον·

βίας δὲ οὐδὲ μέμνηται, οὐδ' ὅτι ἡ φθορὰ τοῦ
Αἴαντος ἐν τῇ ναυαγίᾳ κατὰ μῆνιν Ἀθηναῖς
συνέβη, ἣ κατὰ τοιαύτην αἰτίαν, ἀλλ' ἀπεχθα-
C 601 νόμενον μὲν τῇ Ἀθηνᾷ κατὰ τὸ κοινὸν εἶρηκεν
(ἀπάντων γὰρ εἰς τὸ ἱερὸν ἀσεβησάντων, ἅπασιν
ἐμήνιεν), ἀπολέσθαι δὲ ὑπὸ Ποσειδῶνος μεγα-
λορρημονήσαντα. τὰς δὲ Λοκρίδας πεμφθῆναι,
Περσῶν ἤδη κρατούντων, συνέβη.

41. Οὕτω μὲν δὴ λέγουσιν οἱ Ἰλιεῖς, "Ὅμηρος
δὲ ῥητῶς τὸν ἀφανισμόν τῆς πόλεως εἶρηκεν·

ἔσσεται ἡμαρ, ὅταν ποτ' ὀλώλῃ Ἰλιος ἱρή.

ἣ γὰρ¹ καὶ Πριάμοιο πόλιν διεπέρσαμεν αἰπήν
βουλῇ² καὶ μύθοισι.

πέρθετο δὲ Πριάμοιο πόλις δεκάτῳ ἐνιαυτῷ.

καὶ τὰ τοιαῦτα δὲ τοῦ αὐτοῦ τίθενται τεκμήρια,
οἷον, ὅτι τῆς Ἀθηναῖς τὸ ξόανον νῦν μὲν ἐστηκὸς
ὁράται, "Ὅμηρος δὲ καθήμενον ἐμφαίνει· πέπλον
γὰρ κελεύει

θεῖναι Ἀθηναίης ἐπὶ γούνασιν·

ὥς καί,

μή ποτε γούνασιν οἷσιν ἐφέζεσθαι φίλον υἷόν.

βέλτιον γὰρ οὕτως, ἣ ὥς τινες δέχονται ἀντὶ τοῦ

¹ αὐτὰρ ἐπεὶ, instead of ἣ γάρ, is the reading in the *Odyssey*.

² The MSS., except *moz*, which omit βουλῇ καὶ μύθοισι, have
εἶπερ before these words.

¹ *Iliad* 13. 363. Homer mentions Cassandra in only two
other places, *Iliad* 24. 699 and *Odyssey* 11. 422.

was asking Cassandra in marriage, the comeliest of the daughters of Priam, without gifts of wooing,"¹ and yet he does not so much as mention any violation of her or say that the destruction of Aias in the shipwreck took place because of the wrath of Athena or any such cause; instead, he speaks of Aias as "hated by Athena,"² in accordance with her general hatred (for since they one and all committed sacrilege against her temple, she was angry at them all), but says that he was destroyed by Poseidon because of his boastful speech.³ But the fact is that the Locrian maidens were first sent when the Persians were already in power.

41. So the Ilians tell us, but Homer expressly states that the city was wiped out: "The day shall come when sacred Ilios shall perish";⁴ and "surely we have utterly destroyed the steep city of Priam,"⁵ "by means of counsels and persuasiveness";⁶ "and in the tenth year the city of Priam was destroyed."⁷ And other such evidences of the same thing are set forth; for example, that the wooden image of Athena now to be seen stands upright, whereas Homer clearly indicates that it was sitting, for orders are given to "put" the robe "upon Athena's knees"⁸ (compare "that never should there sit upon his knees a dear child").⁹ For it is better to interpret it¹⁰ in this way than, as some do, to interpret it as

² *Odyssey* 4. 502.

³ *Odyssey* 4. 500 ff.

⁴ *Iliad* 6. 448.

⁵ *Odyssey* 3. 130.

⁶ This phrase is not found in the *Iliad* or *Odyssey*, but once before (1. 2. 4) Strabo has ascribed it to Homer (see critical note).

⁷ *Iliad* 12. 15.

⁸ *Iliad* 6. 92, 273.

⁹ *Iliad* 9. 455.

¹⁰ i.e. the Greek preposition *ἐπὶ*, which more naturally means "upon" rather than "beside."

παρὰ τοῖς γόνασι θεῖναι, παρατιθέντες τὸ

ἢ δ' ἦσται ἐπ' ἐσχάρῃ ἐν πυρὸς αὐγῇ

ἀντὶ τοῦ παρ' ἐσχάρῃ. τίς γὰρ ἂν νοηθεῖη πέπλου ἀνάθεσις παρὰ τοῖς γόνασι; καὶ οἱ τὴν προσφῶδιαν δὲ διαστρέφοντες, γουνάσιν, ὡς θυιάσιν, ὁποτέρως ἂν δέξωνται, ἀπεραντολογοῦσιν, εἴθ' ἵκετεύοντές τε φρένας.¹ πολλὰ δὲ τῶν ἀρχαίων τῆς Ἀθηνᾶς ξοῦνων καθήμενα δείκνυται, καθάπερ ἐν Φωκαίᾳ, Μασσαλίᾳ, Ῥώμῃ, Χίῳ, ἄλλαις πλείοσιν. ὁμολογοῦσι δὲ καὶ οἱ νεώτεροι τὸν ἀφανισμόν τῆς πόλεως, ὃν ἐστὶ καὶ Λυκοῦργος ὁ ῥήτωρ· μνησθεὶς γὰρ τῆς Ἰλίου πόλεως φησί· τίς οὐκ ἀκήκοεν, ὡς ἄπαξ ὑπὸ τῶν Ἑλλήνων κατεσκάφθη, ἀοίκητον οὔσαν;

42. Εἰκάζουσι δὲ τοὺς ὕστερον ἀνακτίσαι διανοουμένους οἰωνίσασθαι τὸν τόπον ἐκεῖνον, εἴτε διὰ τὰς συμφοράς, εἴτε καὶ καταρασαμένου τοῦ Ἀγαμέμνονος κατὰ παλαιὸν ἔθος (καθάπερ καὶ ὁ Κροῖσος ἐξελὼν τὴν Σιδηνήν, εἰς ἣν ὁ τύραννος κατέφυγε Γλαυκίας, ἀρὰς ἔθετο κατὰ τῶν τειχιούτων πάλιν τὸν τόπον), ἐκείνου μὲν οὖν ἀποστῆναι τοῦ χωρίου, ἕτερον δὲ τειχίσαι. πρῶτοι μὲν οὖν Ἀστυπαλαιοεῖς οἱ τὸ Ῥοίτειον κατασχόντες συνώκισαν πρὸς τῷ Σιμόεντι Πόλιον, ὃ νῦν καλεῖται Πόλισμα, οὐκ ἐν εὐερκεῖ

¹ The words εἴθ' ἵκετεύοντές τε φρένας are unintelligible. Meineke emends to εἴθ' ἵκετείας ἐρμηνεύοντες εἴτε φρένας; Leaf translates (with a question mark) "whether as suppliants or mind"! Jones conj. that the words ἐπὶ (or ἐν) τῇ τέφρᾳ ("in the ashes"), referring to ἐπ' ἐσχάρῃ, are hidden in τε φρένας.

meaning "to put the robe 'beside' her knees," comparing the words "and she sits upon the hearth in the light of the fire," which they take to mean "beside" the hearth. For how could one conceive of the dedication of a robe "beside" the knees? Moreover, others, changing the accent on γούνασιν,¹ accenting it γουνάσιν,² like θυνάσιν³ (in whichever of two ways they interpret it), talk on endlessly. . . .⁴ There are to be seen many of the ancient wooden images of Athena in a sitting posture, as, for example, in Phocaea, Massalia, Rome, Chios, and several other places. Also the more recent writers agree that the city was wiped out, among whom is the orator Lycurgus,⁵ who, in mentioning the city of the Ilians, says: "Who has not heard that once for all it was rased to the ground by the Greeks, and is uninhabited?"

42. It is surmised that those who later thought of refounding the city regarded that site as ill-omened, either on account of its misfortune or also because, in accordance with an ancient custom, a curse had been laid upon it by Agamemnon, just as Croesus, after he destroyed Sidenê, whither the tyrant Glaucias had fled for refuge, put a curse on any persons who should re-fortify the site; and that they therefore avoided that place and fortified another. Now the Astypalaeans who held possession of Rhoeteium were the first to settle Polium, now called Polisma, on the Simoeis River, but not on a

¹ "Knees."

² They obviously took γουνάσιν, if there ever was such a word, to mean "female suppliants."

³ "Maenada."

⁴ See critical note.

⁵ *Against Leocrates*, 62.

τόπω· διὸ κατεσπίασθη ταχέως. ἐπὶ δὲ τῶν
 Λυδῶν ἢ νῦν ἐκτίσθη κατοικία καὶ τὸ ἱερόν· οὐ
 μὴν πόλις γε ἦν, ἀλλὰ πολλοῖς χρόνοις ὕστερον,
 C 602 καὶ κατ' ὀλίγον, ὡς εἴρηται, τὴν αὕξησιν ἔσχεν.
 Ἑλλάνικος δὲ χαριζόμενος τοῖς Ἰλιεῦσιν, οἷος
 ἐκείνου θυμός,¹ συνηγορεῖ τὸ τὴν αὐτὴν εἶναι
 πόλιν τὴν νῦν τῇ τότε. τὴν δὲ χώραν, ἀφανισ-
 θείσης τῆς πόλεως, οἱ τὸ Σίγειον καὶ τὸ Ῥοίτειον
 ἔχοντες διενείμαντο καὶ τῶν ἄλλων ὡς ἕκαστοι
 τῶν πλησιοχώρων, ἀπέδωσαν δ' ἀνοικισθείσης.

43. Πολυπίδακον δὲ τὴν Ἰδην ἰδίως οἶονται
 λέγεσθαι διὰ τὸ πλῆθος τῶν ἐξ αὐτῆς ρεόντων
 ποταμῶν, καθ' ἃ μάλιστα ἡ Δαρδανικὴ ὑπόπé-
 πτωκεν αὐτῇ καὶ μέχρι Σκήψεως καὶ τὰ περὶ
 Ἰλίου. ἔμπειρος δ' ὢν τῶν τόπων, ὡς ἂν
 ἐπιχώριος ἀνὴρ, ὁ Δημήτριος τοτὲ μὲν οὕτως
 λέγει περὶ αὐτῶν· ἔστι γὰρ λόφος τις τῆς Ἰδης
 Κότυλος· ὑπέρκειται δ' οὗτος ἑκατὸν πού καὶ
 εἴκοσι σταδίοις Σκήψεως, ἐξ οὗ ὃ τε Σκάμανδρος
 ρεῖ καὶ ὁ Γράνικος καὶ Αἴσηπος, οἱ μὲν πρὸς ἄρκτον
 καὶ τὴν Προποντίδα, ἐκ πλειόνων πηγῶν συλλει-
 βόμενοι, ὁ δὲ Σκάμανδρος ἐπὶ δύσιν ἐκ μιᾶς
 πηγῆς· πᾶσαι δ' ἀλλήλαις πλησιάζουσιν, ἐν
 εἴκοσι σταδίων περιεχόμεναι διαστήματι· πλεῖσ-
 του δ' ἀφέστηκεν ἀπὸ τῆς ἀρχῆς τὸ τοῦ Αἰσήπου
 τέλος, σχεδόν τι καὶ πεντακοσίους σταδίους.
 παρέχει δὲ λόγον, πῶς² φησιν ὁ ποιητής·

¹ θυμός, Xylander, for μῦθος; so the later editors.

² πῶς, Corais, for ὡς; so the later editors.

well-protected site; and therefore it was soon demolished. It was in the time of the Lydians that the present settlement¹ was founded, as also the temple. It was not a city, however, and it was only after many ages, and gradually, as I have said,² that it increased. But Hellanicus, to gratify the Ilians, "such is the spirit of that man,"³ agrees with them that the present Ilium is the same as the ancient. When the city was wiped out, its territory was divided up between the inhabitants of Sigeium and Rhoeteium and several other neighbouring peoples, but the territory was given back when the place was refounded.

43. The epithet "many-fountained"⁴ is thought to be especially applied to Mt. Ida because of the great number of rivers that flow from it, particularly in those parts below it where lie the territory of Dardanus—even as far as Scepsis—and the region of Ilium. Demetrius, who as a native was acquainted with the topography of the country, says in one place as follows: There is a hill of Ida called Cotylus; and this hill lies about one hundred and twenty stadia above Scepsis; and from it flow the Scamander, the Granicus, and the Aesepus, the two latter flowing towards the north and the Propontis and constituting a collection of streams from several sources, while the Scamander flows towards the west from only one source; and all the sources lie close together, being comprised within a distance of twenty stadia; but the end of the Aesepus stands farthest away from its beginning, approximately five hundred stadia. But it is a matter of argument what the poet means when he says: "And they came to the two

² A quotation from *Iliad* 15. 94.

⁴ Cf. 13. 1. 5.

κρουνὸν δ' ἴκανον καλιρρόω, ἔνθα δὲ πηγαί
δοιαὶ ἀναΐσσουνσι Σκαμάνδρου δινήεντος·
ἡ μὲν γάρ θ' ὕδατι λιαρῶ ῥέει,
ὃ ἐστὶ θερμῷ· ἐπιφέρει δέ·

ἀμφὶ δὲ καπνὸς
γίγνεται ἐξ αὐτῆς, ὥσει πυρός.
ἡ δ' ἑτέρη θέρεϊ προρέει εἰκυῖα χαλάζῃ
ἢ χιόνι ψυχρῇ.

οὔτε γὰρ θερμὰ νῦν ἐν τῷ τόπῳ εὐρίσκεται, οὔθ' ἡ
τοῦ Σκαμάνδρου πηγὴ ἐνταῦθα, ἀλλ' ἐν τῷ ὄρει·
καὶ μία, ἀλλ' οὐ δύο. τὰ μὲν οὖν θερμὰ ἐκλε-
λεῖφθαι εἰκός, τὸ δὲ ψυχρὸν κατὰ διάδοσιν¹
ὑπεκρέον ἐκ τοῦ Σκαμάνδρου κατὰ τοῦτ' ἀνατέλ-
λειν τὸ χωρίον, ἢ καὶ διὰ τὸ πλησίον εἶναι τοῦ
Σκαμάνδρου καὶ τοῦτο τὸ ὕδωρ λέγεσθαι τοῦ
Σκαμάνδρου πηγῇ· οὕτω γὰρ λέγονται πλείους
πηγαὶ τοῦ αὐτοῦ ποταμοῦ.

44. Συμπίπτει δ' εἰς αὐτὸν ὁ "Ανδιρος ἀπὸ τῆς
Καρησηνῆς, ὀρεινῆς τινὸς πολλαῖς κώμαις συνοι-
κουμένης καὶ γεωργουμένης καλῶς, παρακειμένης
τῇ Δαρδανικῇ μέχρι τῶν περὶ Ζέλειαν καὶ
Πιτύειαν² τόπων. ὠνομάσθαι δὲ τὴν χώραν
φασὶν ἀπὸ τοῦ Καρήσου ποταμοῦ, ὃν ὠνόμακεν ὁ
ποιητής·

Ῥῆσός θ' Ἐπτάπορος τε Κάρησός τε Ῥοδίος τε.
τὴν δὲ πόλιν κατεσπάσθαι τὴν ὁμώνυμον τῷ
ποταμῷ. πάλιν δ' οὗτός φησιν· ὁ μὲν Ῥῆσος
ποταμὸς νῦν καλεῖται Ῥοείτης, εἰ μὴ ἄρα ὁ εἰς
τὸν Γράνικον ἐμβάλλων Ῥῆσός ἐστιν. Ἐπτά-

¹ For διάδοσιν (all MSS. and Eustathius), Corais, Meineke
86

fair-flowing streams, where well up the two springs of eddying Scamander; for the one flows with soft water"¹ (that is, with "hot water"), and the poet adds, "and round about a smoke arises from it as if from a blazing fire, whereas the other even in summer flows forth cold as hail or chill snow." But, in the first place, no hot waters are now to be found at the site,² and, secondly, the source of the Scamander is not to be found there, but in the mountain; and it has only one source, not two. It is reasonable to suppose, therefore, that the hot spring has given out, and that the cold one is evacuated from the Scamander through an underground passage and rises to the surface here, or else that because of the nearness of the Scamander this water is called a source of the Scamander; for people are wont to ascribe several sources to one and the same river in this way.

44. The Scamander is joined by the Andirus, which flows from Caresenê, a mountainous country settled with many villages and beautifully cultivated; it extends alongside Dardania as far as the regions of Zeleia and Pityeia. It is said that the country was named after the Caresus River, which is named by the poet, "Rhesus, Heptaporus, Caresus, and Rhodius,"³ and that the city of the same name as the river was torn down. Again, Demetrius says as follows: "The Rhesus River is now called Rhoeites, unless it be that the river which empties into the Granicus is the Rhesus. The Heptaporus,

¹ *Iliad* 22. 147.

² *i.e.* of Troy.

³ *Iliad* 12. 20.

and Leaf, from conj. of Xylander, read *διδύσιν*; but the emendation is unnecessary.

² *Πιτυεῖαν*, Xylander, for *Πιτυίαν*; so the later editors.

C 603 πορος δέ, ὃν καὶ Πολύπορον λέγουσιν, ἐπτάκις διαβαινόμενος ἐκ τῶν περὶ τὴν Καλὴν Πεύκην χωρίων ἐπὶ Μελαινὰς κώμην ἰοῦσι καὶ τὸ Ἀσκληπίειον, ἵδρυμα Λυσιμάχου. περὶ δὲ τῆς Καλῆς Πεύκης Ἀτταλος ὁ πρῶτος βασιλεύσας οὕτως γράφει· τὴν μὲν περίμετρον εἶναί φησι ποδῶν τεττάρων καὶ εἴκοσι, τὸ δὲ ὕψος ἀπὸ μὲν ῥίζης ἀνιέναι¹ ἐπὶ ἐξήκοντα καὶ ἐπτά πόδας, εἴτ' εἰς τρία σχιζομένην ἴσον ἀλλήλων διέχοντα, εἴτα πάλιν συναγομένην εἰς μίαν κορυφήν, ἀποτελοῦσαν τὸ² πᾶν ὕψος δυεῖν πλέθρων καὶ πεντεκαίδεκα πηχῶν· Ἀδραμυττίου δὲ διέχει πρὸς ἄρκτον ἑκατὸν καὶ ὀγδοήκοντα σταδίους. Κάρησος δ' ἀπὸ Μαλοῦντος ῥεῖ, τόπου τινὸς κειμένου μεταξὺ Παλαισκήψεως καὶ Ἀχαιίου τῆς Τενεδίων περαίας· ἐμβάλλει δὲ εἰς τὸν Αἴσηπον. Ῥοδῖος δὲ ἀπὸ Κλεανδρίας καὶ Γόρδου, ἃ διέχει τῆς Καλῆς Πεύκης ἐξήκοντα σταδίους· ἐμβάλλει δ' εἰς τὸν Αἴνιον.³

45. Τοῦ δ' αὐλῶνος τοῦ περὶ τὸν Αἴσηπον ἐν ἀριστερᾷ τῆς ῥύσεως αὐτοῦ πρῶτόν ἐστι Πολίχνα, τειχῆρες χωρίον, εἴθ' ἡ Παλαίσκηψις, εἴτ' Ἀλαζόνιον, τοῦτ' ἤδη πεπλασμένον πρὸς τὴν τῶν Ἀλιζώνων ὑπόθεσιν, περὶ ὧν εἰρήκαμεν· εἴτα Κάρησος ἐρήμη καὶ ἡ Καρησηνὴ καὶ ὁμώνυμος ποταμός, ποιῶν καὶ αὐτὸς αὐλῶνα ἀξιόλογον, ἐλάττω δὲ τοῦ περὶ τὸν Αἴσηπον. τὰ δ' ἐξῆς ἤδη τὰ τῆς Ζελείας ἐστὶ πεδία καὶ ὀροπέδια καλῶς

¹ ἀνιέναι, Meineke and Leaf, following *i*, for ἐάν Dyl, ἐάν C, ἕως μοz.

² Instead of τὸ, CDFhi read τότε.

³ For Αἴνιον Kramer conj. Αἴσηπον.

also called Polyporus, is crossed seven times by one travelling from the region of the Beautiful Pine to the village called Melaenae and the Asclepieium that was founded by Lysimachus. Concerning the Beautiful Pine, King Attalus the First writes as follows: "Its circumference is twenty-four feet; and its trunk rises to a height of sixty-seven feet from the root and then splits into three forks equidistant from one another, and then contracts again into one head, thus completing a total height of two plethra and fifteen cubits."¹ It is one hundred and eighty stadia distant from Adramyttium, to the north of it. The Caresus flows from Malus, a place situated between Palaescepsis and the Achaeium, the part of the mainland that belongs to the Tenedians;² and it empties into the Aesepus. The Rhodius flows from Cleandria and Gordus, which are sixty stadia distant from the Beautiful Pine; and it empties into the Aenius.³

45. In the dale of the Aesepus, on the left of the stream, one comes first to Polichna, a place enclosed by walls; and then to Palaescepsis; and then to Alizonium (this last name having been fabricated⁴ to support the hypothesis about the Halizones, whom I have already discussed);⁵ and then to Caresus, which is deserted, and Caresenê, and the river of the same name,⁶ which also forms a notable dale, though smaller than that of the Aesepus; and next follow the plains and plateaux of Zeleia,

¹ About 225 feet.

² See end of § 32.

³ "Aenius" appears to be an error for "Aesepus," as suggested by Kramer. See Leaf, p. 207.

⁴ *i.e.* by Demetrius.

⁵ 12. 3. 20-27.

⁶ The Caresus, of course.

γεωργούμενα· ἐν δεξιᾷ δὲ τοῦ Αἰσήπου μεταξὺ Πολίχνας τε καὶ Παλαισκήφews ἡ Νέα¹ Κώμη καὶ Ἀργυρία,² καὶ τοῦτο πάλιν πλάσμα³ πρὸς τὴν αὐτὴν ὑπόθεσιν, ὅπως σωθεῖη τὸ

ὅθεν ἀργύρου ἐστὶ γενέθλη.

ἡ οὖν Ἀλύβη ποῦ, ἡ Ἀλόπη ἡ ὅπως βούλονται παρονομάζειν; ἐχρῆν γὰρ καὶ τοῦτο πλάσαι παρατριψαμένους τὸ μέτωπον καὶ μὴ χωλὸν εἶναι καὶ ἔτοιμον πρὸς ἔλεγχον ἅπαξ ἤδη ἀποτετολμηκότας. ταῦτα μὲν οὖν ἐνστασιν ἔχει τοιαύτην, τᾶλλα δὲ ὑπολαμβάνομεν, ἡ τὰ γε πλείστα, δεῖν προσέχειν⁴ ὡς ἀνδρὶ ἐμπείρῳ καὶ ἐντοπίῳ, φροντίσαντί τε τοσοῦτον περὶ τούτων, ὥστε τριάκοντα βίβλους συγγράφαι στίχων ἐξήγησιν μικρῶ πλειόνων ἐξήκοντα, τοῦ καταλόγου τῶν Τρώων. φησὶ δ' οὖν τὴν Παλαισκηψιν τῆς μὲν Αἰνέας⁵ διέχειν πεντήκοντα σταδίους, τοῦ δὲ ποταμοῦ τοῦ Αἰσήπου τριάκοντα, ἀπὸ δὲ τῆς Παλαισκήφews ταύτης διατεῖναι τὴν ὁμωνυμίαν καὶ εἰς ἄλλους πλείους τόπους. ἐπ' αὐτὴν δὲ ἐπὶ τὴν παραλίαν, ὅθεν περ ἀπελίπομεν.

C 604 46. Ἔστι δὲ⁶ μετὰ τὴν Σιγείαδα ἄκραν καὶ τὸ Ἀχίλλειον ἡ Τενεδίων περαία, τὸ Ἀχαῖιον, καὶ

¹ Νέα appears to be an error for Αἰνέα, and Leaf so reads. This appears to be the same village mentioned in the same paragraph below (Αἰνέας) and in 12. 3. 23 (Ἐνέαν Κώμην).

² Ἀργυρία, Corais, for ἀργυρεῖα *scz*, ἀργύρια other MSS.

³ After πλάσμα, F adds τάγματα ἀργύρια, CDhι τάγματα τὰ ἀργύρια, τακτέον τὰ ἀργυρεῖα, *x* τακτέον.

⁴ Professor Capps rightly suspects that αὐτῷ, or Δημοτρίῳ, has fallen out of the MSS. before προσέχειν.

⁵ Instead of Αἰνέας, CFh read Αἰνέας, *x* Νέας; Meineke reads Νέας.

which are beautifully cultivated. On the right of the Aesepus, between Polichna and Palaescepsis, one comes to Nea¹ Comê and Argyria,² and this again is a name fabricated to support the same hypothesis, in order to save the words, "where is the birthplace of silver."³ Now where is Alybê, or Alopê, or however they wish to alter the spelling of the name?⁴ For having once made their bold venture, they should have rubbed their faces⁵ and fabricated this name too, instead of leaving it lame and readily subject to detection. Now these things are open to objections of this kind, but, in the case of the others, or at least most of them, I take it for granted that we must give heed to him⁶ as a man who was acquainted with the region and a native of it, who gave enough thought to this subject to write thirty books of commentary on a little more than sixty lines of Homer, that is, on the *Catalogue of the Trojans*.⁷ He says, at any rate, that Palaescepsis is fifty stadia distant from Aenea and thirty from the Aesepus River, and that from this Palaescepsis⁸ the same name was extended to several other sites. But I shall return to the coast at the point where I left off.

46. After the Sigeian Promontory and the Achilleium one comes to the Achaeium, the part of the

¹ Leaf emends "Nea" ("New") to "Aenea" (see critical note).

² Silvertown.

³ *Iliad* 2. 856.

⁴ See 12. 3. 21.

⁵ *i.e.* to make them red and thus conceal their blushes of shame.

⁶ *i.e.* Demetrius of Scepsis.

⁷ *Iliad* 2. 816-877.

⁸ *Old Scepsis*.

αὐτὴ ἡ Τένεδος, οὐ πλείους τῶν τετταράκοντα σταδίων διέχουσα τῆς ἠπείρου· ἔχει δὲ τὴν περίμετρον ὅσον ὀγδοήκοντα σταδίων καὶ πόλιν Αἰολίδα καὶ λιμένας δύο καὶ ἱερὸν τοῦ Σμινθέως Ἀπόλλωνος, καθάπερ καὶ ὁ ποιητὴς μαρτυρεῖ·

Τενέδοιό τε ἱφί ἀνάσσεις,

Σμινθεῦ.

περίκειται δ' αὐτῇ νησία πλείω, καὶ δὴ καὶ δύο, ἃ καλοῦσι Καλύδνας, κειμένας κατὰ τὸν ἐπὶ Λεκτὸν πλοῦν· καὶ αὐτὴν δὲ τὴν Τένεδον Κάλυδνάν τινες εἶπον, ἄλλοι δὲ Λεύκοφρυν.¹ μυθεύουσι δ' ἐν αὐτῇ τὰ περὶ τὸν Τέννην, ἀφ' οὗ καὶ τοῦνομα τῇ νήσῳ, καὶ τὰ περὶ τὸν Κύκνον, Θράκα τὸ γένος, πατέρα δ', ὥς τινες, τοῦ Τέννου, βασιλέα δὲ Κολωνῶν.

47. Ἦν δὲ τῷ Ἀχαίῳ συνεχῆς ἢ τε Λάρισα καὶ Κολωναί, τῆς² Τενεδίων περαιᾶς οὔσαι πρότερον, καὶ ἡ νῦν Χρύσα, ἐφ' ὕψους τινὸς πετρώδους ὑπὲρ τῆς θαλάττης ἰδρυμένη, καὶ ἡ Ἀμαξιτὸς ἡ τῷ Λεκτῷ ὑποκειμένη συνεχῆς· νῦν δ' ἡ Ἀλεξάνδρεια συνεχῆς ἐστὶ τῷ Ἀχαίῳ· τὰ δὲ πολίσματα ἐκεῖνα συνφικισμένα τυγχάνει, καθάπερ καὶ ἄλλα πλείω τῶν φρουρίων, εἰς τὴν Ἀλεξάνδρειαν, ὧν καὶ Κεβρήνη καὶ Νεανδρία ἐστὶ, καὶ τὴν χώραν ἔχουσιν ἐκεῖνοι· ὁ δὲ τόπος, ἐν ᾧ νῦν κεῖται ἡ Ἀλεξάνδρεια, Σιγία ἐκαλεῖτο.

48. Ἐν δὲ τῇ Χρύσῃ ταύτῃ καὶ τὸ τοῦ

¹ After Λεύκοφρυν, *moz* add εἰσὶ δὲ καὶ ἕτερα νησία περὶ αὐτήν.

² After τῆς there is a lacuna in DFl of about ten letters followed by δίας οὔσαι κτλ. Corais writes Τενεδίας; but

mainland that belongs to the Tenedians;¹ and to Tenedos itself, which is not more than forty stadia distant from the mainland. It is about eighty stadia in circumference, and has an Aeolian city and two harbours and a temple of Sminthian Apollo, as the poet testifies: "And dost rule mightily over Tenedos, O Sminthian."² Round it lie several small islands, in particular two, which are called the Calydnæ and are situated on the voyage to Lectum. And some give the name Calydnæ to Tenedos itself, while others call it Leucophrys. In it is laid the scene of the myth of Tennes,³ after whom the island was named, as also that of Cygnus, a Thracian by birth and, according to some, father of Tennes and king of Colonæ.⁴

47. Both Larisa and Colonæ used to be adjacent to the Achæium, formerly being on the part of the mainland that belonged to the Tenedians; and then one comes to the present Chrysa, which was founded on a rocky height above the sea, and to Hamaxitus, which lies below Lectum and adjacent to it. At the present time Alexandreia is adjacent to the Achæium; and those other towns, like several others of the strongholds, have been incorporated with Alexandreia, among them Cebrenê and Neandria; and Alexandreia holds their territory. But the site on which Alexandreia now lies used to be called Sigia.

48. In this Chrysa is also the temple of Sminthian

¹ See end of § 32.

² *Iliad* 1. 38.

³ For this myth, see Pausanias 10. 14. 1.

⁴ On the myth of Cygnus, see Leaf, p. 219.

Kramer, Meineke, and Leaf write *Τενεδίων περπας*, the convincing conjecture of Groskurd.

Σμινθέως Ἀπόλλωνός ἐστιν ἱερὸν καὶ τὸ σύμβολον τὸ τὴν ἐτυμότητα τοῦ ὀνόματος σῶζον, ὁ μῦς, ὑπόκειται τῷ ποδὶ τοῦ ξοάνου. Σκόπα δ' ἐστὶν ἔργα¹ τοῦ Παρίου· συνοικιοῦσι δὲ καὶ τὴν ἱστορίαν εἶτε μῦθον τούτῳ τῷ τόπῳ τὴν περὶ τῶν μυῶν. τοῖς γὰρ ἐκ τῆς Κρήτης ἀφυγμένοις Τεύκροις (οὓς πρῶτος παρέδωκε Καλλίνος ὁ τῆς ἐλεγείας ποιητής, ἠκολούθησαν δὲ πολλοί) χρῆσμός ἦν, αὐτόθι ποιήσασθαι τὴν μονήν, ὅπου ἂν οἱ γηγενεῖς αὐτοῖς ἐπιθῶνται· συμβῆναι δὲ τοῦτ' αὐτοῖς φασὶ περὶ Ἀμαξιτόν· νύκτωρ γὰρ πολὺ πλῆθος ἀρουραίων μυῶν ἐξαυθῆσαν διαφαγεῖν ὅσα σκύτινα τῶν τε ὀπλων καὶ τῶν χρηστηρίων· τοὺς δὲ αὐτόθι μέναι· τούτους δὲ καὶ τὴν Ἰδὴν ἀπὸ τῆς ἐν Κρήτῃ προσονομάσαι.² Ἡρακλείδης δ' ὁ Ποντικός πληθύνοντάς φησι τοὺς μύας περὶ τὸ ἱερὸν νομισθῆναί τε ἱεροὺς καὶ τὸ ξοάνον οὕτω κατασκευασθῆναι βεβηκὸς ἐπὶ τῷ μυῖ. ἄλλοι δ' ἐκ τῆς Ἀττικῆς ἀφίχθαι τινὰ Τεύκρόν φασιν ἐκ δήμου Τρώων, ὃς νῦν οἱ Εὐπετεῶνες³ λέγεται, Τεύκρους δὲ μηδένας ἐλθεῖν ἐκ τῆς Κρήτης. τῆς δὲ πρὸς τοὺς Ἀττικοὺς ἐπιπλοκῆς τῶν Τρώων τιθέασι σημεῖον καὶ τὸ παρ' ἀμφοτέροις Ἐριχθόνιον τινὰ γενέσθαι τῶν ἀρχηγέων.⁴ λέγουσι μὲν οὖν οὕτως οἱ νεώτεροι, τοῖς δ' Ὀμήρου μᾶλλον C 605 ἔπεισι συμφωνεῖ τὰ ἐν τῷ Θήβης πεδίῳ καὶ τῇ αὐτόθι Χρῦση ἰδρυμένη ποτὲ δεικνύμενα ἔχνη,

¹ Instead of ἔργα, Eustathius reads ἔργον; so Leaf.

² Instead of προσονομάσαι, *moz* and Eustathius read παρονομάσαι; the editors before Kramér, κατονομάσαι.

³ οἱ Εὐπετεῶνες, Meineke, for ὀεπετεῶν; ὁ Εὐπετεών, Tzschucke and Corais.

Apollo; and the symbol which preserves the etymology of the name,¹ I mean the mouse, lies beneath the foot of his image. These are the works of Scopas of Paros; and also the history, or myth, about the mice is associated with this place: When the Teucrians arrived from Crete (Callinus the elegiac poet was the first to hand down an account of these people, and many have followed him), they had an oracle which bade them to "stay on the spot where the earth-born should attack them"; and, he says, the attack took place round Hamaxitus, for by night a great multitude of field-mice swarmed out of the ground and ate up all the leather in their arms and equipment; and the Teucrians remained there; and it was they who gave its name to Mt. Ida, naming it after the mountain in Crete. Heracleides of Pontus says that the mice which swarmed round the temple were regarded as sacred, and that for this reason the image was designed with its foot upon the mouse. Others say that a certain Teucer came from the deme of Troes, now called Xypeteones, in Attica, but that no Teucrians came from Crete. As a further sign of the close relationship of the Trojans with the people of Attica they record the fact that Erichthonius was one of the original founders in both tribes. Now this is the account of the more recent writers; but more in agreement with Homer are the traces to be seen in the plain of Thebê and in the Chrysa which was once founded there, which I shall soon

¹ Sminthian means "Mouse-god."

⁴ Instead of τῶν ἀρχηγῶν μοιζ read ἀρχηγέτην.

περὶ ὧν αὐτίκα ἐροῦμεν. πολλαχοῦ δ' ἐστὶ τὸ τοῦ Σμινθέως ὄνομα· καὶ γὰρ περὶ αὐτὴν τὴν Ἀμαξιτὸν χωρὶς τοῦ κατὰ τὸ ἱερὸν Σμινθίου δύο τόποι καλοῦνται Σμίνθια· καὶ ἄλλοι δ' ἐν τῇ πλησίον Λαρισαίᾳ· καὶ ἐν τῇ Παριανῇ δ' ἐστὶ χωρίον τὰ Σμίνθια καλούμενον καὶ ἐν Ῥόδῳ καὶ ἐν Λίνδῳ καὶ ἄλλοθι δὲ πολλαχοῦ.¹ καλοῦσι δὲ νῦν τὸ ἱερὸν Σμίνθιον. χωρὶς γοῦν καὶ τὸ Ἀλήσιον² πεδίου οὐ μέγα ἐντὸς³ τοῦ Λεκτοῦ καὶ τὸ Τραγασαῖον ἀλοπήγιον αὐτόματον τοῖς ἐτησίαις πηγνύμενον πρὸς Ἀμαξιτᾶ. ἐπὶ δὲ τῷ Λεκτῷ βωμὸς τῶν δώδεκα θεῶν δείκνυται, καλοῦσι δ' Ἀγαμέμνονος Ἰδρυμα· ἐν ἐπόψει δὲ τῷ Ἰλίῳ ἐστὶ τὰ χωρία ταῦτα, ὡς ἐν διακοσίοις σταδίοις ἢ μικρῷ πλείοσιν· ὡς δ' αὐτως καὶ τὰ περὶ Ἀβυδον ἐκ θατέρου μέρους, μικρὸν δ' ὅμως ἐγγυτέρω ἢ Ἀβυδος.

49. Κάμφαντι δὲ τὸ Λεκτὸν ἐλλογιμώταται πόλεις τῶν Αἰολέων καὶ ὁ Ἀδραμυττηνὸς κόλπος ἐκδέχεται, ἐν ᾧ τοὺς πλείους τῶν Λελέγων κατοικίζων ὁ ποιητὴς φαίνεται καὶ τοὺς Κίλικας, διττοὺς ὄντας. ἐνταῦθα δὲ καὶ ὁ τῶν Μιτυληναίων ἐστὶν αἰγιαλός, κώμας τινὰς ἔχων τῶν⁴ κατὰ τὴν ἡπειρον τῶν Μιτυληναίων. τὸν δὲ αὐτὸν κόλπον καὶ Ἰδαῖον λέγουσιν· ἢ γὰρ ἀπὸ τοῦ Λεκτοῦ ῥάχης, ἀνατείνουσα πρὸς τὴν Ἰδην, ὑπέρκειται τῶν πρώτων τοῦ κόλπου μερῶν· ἐν οἷς πρῶτον τοὺς Λέλεγας ἰδρυμένους ὁ ποιητὴς πεποίηκεν.

¹ Leaf omits the words καλοῦσι . . . γοῦν, and indicates a lacuna.

² Ἀλήσιον E and the editors, Ἀλίσιον DCFHx, Ἀλύσιον μοx.

³ ἐντὸς, Tyrwhitt, for ἐν τοῖς; so the later editors.

⁴ τῶν, before κατὰ, hi, Corais and Leaf omit.

discuss. The name of Smintheus is used in many places, for in the neighbourhood of Hamaxitus itself, apart from the Sminthium at the temple, there are two places called Sminthia; and there are others in the neighbouring territory of Larisa. And also in the territory of Parium there is a place called Sminthia, as also in Rhodes and in Lindus and in many other places. And they now call the temple Sminthium. Apart, at any rate,¹ lie both the Halesian Plain, of no great size, and inland from Lectum, and the Tragasaean salt-pan near Hamaxitus, where salt is naturally caused to congeal by the Etesian winds. On Lectum is to be seen an altar of the twelve gods, said to have been founded by Agamemnon. These places are all in sight of Ilium, at a distance of about two hundred stadia or a little more; and the same is the case with the places round Abydus on the other side, although Abydus is a little closer.

49. On doubling Lectum one comes next to the most notable cities of the Aeolians, and to the Gulf of Adramyttium, on which the poet obviously places the majority of the Leleges, as also the Cilicians, who were twofold.² Here too is the shore-land of the Mitylenaeans, with certain villages³ belonging to the Mitylenaeans who live on the mainland. The same gulf is also called the Idaean Gulf, for the ridge which extends from Lectum to Mt. Ida lies above the first part of the gulf, where the poet represents the Leleges as first settled.⁴

¹ The Greek for these four words seems to be corrupt.

² See 13. 1. 7, 60.

³ Coryphantis and Heracleia are named in § 51.

⁴ *Iliad* 10. 429.

50. Εἴρηται δὲ περὶ αὐτῶν καὶ πρότερον· καὶ νῦν δὲ προσληπτέον, ὅτι Πήδασόν τινα λέγει πόλιν αὐτῶν ὑπὸ Ἀλτη τεταγμένην.¹

Ἀλτεω, ὃς Λελέγεσσι φιλοπτολέμοισιν ἀνάσσει,

Πήδασον αἰπήεσαν ἔχων ἐπὶ Σατνιόεντι.
καὶ νῦν ὁ τόπος δείκνυται τῆς πόλεως ἔρημος. γράφουσι δὲ τινες οὐκ εὔ ὑπὸ Σατνιόεντι, ὥς ὑπὸ ὄρει Σατνιόεντι κειμένης τῆς πόλεως· οὐδὲν δ' ἐστὶν ὄρος ἐνταῦθα Σατνιόεις πρασαγορευόμενον, ἀλλὰ ποταμός, ἐφ' ᾧ ἴδρυται ἡ πόλις· νῦν δ' ἐστὶν ἐρήμη. ὀνομάζει δὲ τὸν ποταμὸν ὁ ποιητής·

Σάτνιον γὰρ² οὔτασε δουρὶ

Οἰνοπίδην,³ ὃν ἄρα νύμφη τέκε Νηὶς ἀμύμων

Οἰνοπι⁴ βουκολέοντι παρ' ὄχθαις Σατνιόεντος·

καὶ πάλιν·

C 606 ναῖε δὲ Σατνιόεντος ἐϋρρείταιο παρ' ὄχθαις
Πήδασον αἰπεινήν.

Σατνιόεντα δ' ὕστερον εἶπον, οἱ δὲ Σαφνιόεντα. ἔστι δὲ χεῖμαρρος μέγας· ἄξιον δὲ μνήμης πεποίηκεν ὀνομάζων ὁ ποιητής αὐτόν. οὗτοι δ' οἱ τόποι συνεχεῖς εἰσὶ τῇ Δαρδανίᾳ καὶ τῇ Σκηψίᾳ, ὥσπερ ἄλλη τις Δαρδανία, ταπεινοτέρα δέ.

51. Ἀσσίων δ' ἐστὶ νῦν καὶ Γαργαρέων τὰ⁵ ἕως τῆς κατὰ Λέσβον θαλάττης περιεχόμενα τῇ τε

¹ Instead of τεταγμένην, CDhix read τεταγμένων.

² γάρ, after Σάτνιον, omitted by other editors.

³ Instead of Οἰνοπίδην, the editors before Kramer, following the MSS. of *Iliad* 14. 443, read Ἦνοπίδην.

50. But I have already discussed these matters.¹ I must now add that Homer speaks of a Pedasus, a city of the Leleges, as subject to lord Altes: "Of Altes, who is lord over the war-loving Leleges, who hold steep Pedasus on the Satnioeis."² And the site of the place, now deserted, is still to be seen. Some write, though wrongly, "at the foot of Satnioeis,"³ as though the city lay at the foot of a mountain called Satnioeis; but there is no mountain here called Satnioeis, but only a river of that name, on which the city is situated; but the city is now deserted. The poet names the river, for, according to him, "he wounded Satnius with a thrust of his spear, even the son of Oenops, whom a peerless Naiad nymph bore unto Oenops, as he tended his herds by the banks of the Satnioeis";⁴ and again: "And he dwelt by the banks of the fair-flowing Satnioeis in steep Pedasus."⁵ And in later times it was called Satnioeis, though some called it Saphnioeis. It is only a large winter torrent, but the naming of it by the poet has made it worthy of mention. These places are continuous with Dardania and Scepsia, and are, as it were, a second Dardania, but it is lower-lying.

51. To the Assians and the Gargarians now belong all the parts as far as the sea off Lesbos that are sur-

¹ 13. 1. 7.

² *Iliad* 21. 86.

³ *i.e.* ὑπὸ for ἐπὶ in the Homeric passage quoted.

⁴ *Iliad* 14. 443.

⁵ *Iliad* 6. 34.

⁴ Instead of Οἰνοπι, CDF and the editors before Kramer, following *Iliad* 14. 444, read Ὑνοπι.

⁵ Leaf inserts τὰ before ἔως.

Ἀντανδρία καὶ τῇ Κεβρηνίων καὶ Νεανδριέων καὶ Ἀμαξιτέων. τῆς μὲν γὰρ Ἀμαξιτοῦ Νεανδριεῖς ὑπέρκεινται, καὶ αὐτοὶ ὄντες ἐντὸς Λεκτοῦ, μεσογειότεροι δὲ¹ καὶ πλησιαίτεροι τῷ Ἰλίῳ· διέχουσι γὰρ ἑκατὸν καὶ τριάκοντα σταδίου. τούτων δὲ καθύπερθε Κεβρήνιοι, τούτων δὲ Δαρδάνιοι μέχρι Παλαισκήψεως καὶ αὐτῆς τῆς Σκήψεως. τὴν δὲ Ἀντανδρον Ἀλκαῖος μὲν καλεῖ Λελέγων πόλιν·

πρῶτα² μὲν Ἀντανδρος Λελέγων πόλιν.

ὁ δὲ Σκήψιος ἐν ταῖς παρακειμέναις τίθησιν, ὥστ' ἐκπίπτει ἂν εἰς τὴν τῶν Κιλίκων· οὗτοι γὰρ εἰσι συνεχεῖς τοῖς Λέλεξι, μᾶλλον πως τὸ νότιον πλευρὸν τῆς Ἰδῆς ἀφορίζοντες· ταπεινοὶ δ' ὅμως καὶ οὗτοι καὶ³ τῇ παραλίᾳ συνάπτοντες μᾶλλον τῇ κατὰ Ἀδραμύττιον. μετὰ γὰρ τὸ Λεκτὸν τὸ Πολυμήδιόν ἐστι χωρίον τι ἐν τετταράκοντα σταδίοις, εἴτ' ἐν ὀγδοήκοντα Ἄσσοις,⁴ μικρὸν ὑπὲρ τῆς θαλάττης, εἴτ' ἐν ἑκατὸν καὶ τετταράκοντα

¹ δέ, Corais, for τε.

² For πρῶτα, Leaf, as his translation (p. 253) shows, must have intended to read πρῶτα (πρώτη).

³ οἱ, before τῇ, Corais rejects; so Kramer, Meineke, and Leaf.

⁴ Ἄσσοις, Tzschucke, from conj. of Mannert, for ἄλσος; so the later editors.

¹ *Frag.* 65 (Bergk). Leaf translates: "Antandros, first city of the Leleges" (see critical note).

² Leaf translates: "But Demetrios puts it in the district adjacent (to the Leleges), so that it would fall within the territory of the Kilikes"; and in his commentary (p. 255) he says: "As the words stand, Strabo says that 'Demetrios places Antandros (not at Antandros but) in the neighbourhood of Antandros.' That is nonsense however we look at

rounded by the territory of Antandrus and that of the Cebrenians and Neandrians and Hamaxitans; for the Antandrians are situated above Hamaxitus, like it being situated inside Lectum, though farther inland and nearer to Ilium, for they are one hundred and thirty stadia distant from Ilium. Higher up than these are the Cebrenians, and still higher up than the latter are the Dardanians, who extend as far as Palaescepsis and Scepsis itself. Antandrus is called by Alcaeus "city of the Leleges": "First, Antandrus, city of the Leleges";¹ but it is placed by the Scepsian among the cities adjacent to their territory,² so that it would fall within the territory of the Cilicians; for the territory of the Cilicians is continuous with that of the Leleges, the former, rather than the latter, marking off the southern flank of Mt. Ida. But still the territory of the Cilicians also lies low and, rather than that of the Leleges, joins the part of the coast that is near Adramyttium.³ For after Lectum one comes to a place called Polymedium, at a distance of forty stadia; then, at a distance of eighty,⁴ to Assus, slightly above the sea; and then, at a distance of one hundred and

it." Yet the Greek cannot mean that Demetrius transfers Antandrus, "a fixed point," to "the adjacent district," as Leaf interprets, but that he includes it among the cities (ταῖς παρακειμέναις) which he enumerates as Cilician.

³ The interpretation of the Greek for this last sentence is somewhat doubtful. Cf. translation and commentary of Leaf (pp. 254-255), who regards the text as corrupt.

⁴ i.e. eighty stadia from Polymedium, not from Lectum, as thought by Thatcher Clark (*American Journal of Archaeology*, 4. 291 ff., quoted by Leaf). His interpretation, neither accepted nor definitely rejected by Leaf (p. 257), is not in accordance with Strabo's manner of enumerating distances, a fact apparently overlooked by both scholars.

Γάργαρα· κείται δὲ τὰ Γάργαρα ἐπ' ἄκρας ποιούσης τὸν ἰδίως Ἀδραμυττηνὸν καλούμενον κόλπον, λέγεται γὰρ καὶ πᾶσα ἡ ἀπὸ Λεκτοῦ μέχρι Κανῶν παραλία τῷ αὐτῷ τούτῳ ὀνόματι, ἐν ᾧ καὶ ὁ Ἑλαϊτικὸς περιλαμβάνεται· ἰδίως μέντοι τοῦτόν φασιν Ἀδραμυττηνόν, τὸν κλειόμενον ὑπὸ ταύτης τε τῆς ἄκρας, ἐφ' ἣ τὰ Γάργαρα, καὶ τῆς Πυρρᾶς ἄκρας προσαγορευομένης, ἐφ' ἣ καὶ Ἀφροδίσιον ἵδρυται. πλάτος δὲ τοῦ στόματός ἐστιν ἀπὸ τῆς ἄκρας ἐπὶ τὴν ἄκραν διάρμα ἑκατὸν καὶ εἴκοσι σταδίων. ἐντὸς δὲ ἡ τε Ἀντανδρός ἐστιν, ὑπερ- κείμενον ἔχουσα ὄρος, ὃ καλοῦσιν Ἀλεξάνδρειαν, ὅπου τὰς θεὰς κριθῆναί φασιν ὑπὸ τοῦ Πάριδος, καὶ ὁ Ἀσπανεύς, τὸ ὑλοτόμιον τῆς Ἰδαίας ὕλης· ἐνταῦθα γὰρ διατίθενται κατάγοντες τοῖς δεο- μένοις. εἴτ' Ἀστυρα, κώμη καὶ ἄλσος τῆς Ἀστυρηνῆς Ἀρτέμιδος ἁγίου. πλησίον δ' εὐθύς τὸ Ἀδραμύττιον, Ἀθηναίων ἄποικος πόλις, ἔχουσα καὶ λιμένα καὶ ναύσταθμον· ἔξω δὲ τοῦ C 607 κόλπου καὶ τῆς Πυρρᾶς ἄκρας ἡ τε Κισθήνη ἐστὶ πόλις ἔρημος, ἔχουσα λιμένα. ὑπὲρ αὐτῆς ἐν τῇ μεσογαίᾳ τό τε τοῦ χαλκοῦ μέταλλον καὶ Περπερηνή¹ καὶ Τράριον καὶ ἄλλαι τοιαῦται κατοικίαι. ἐν δὲ τῇ παραλίᾳ τῇ ἐφεξῆς αἱ τῶν Μιτυληναίων κῶμαι Κορυφαντίς τε καὶ Ἡράκλεια, καὶ μετὰ ταῦτα Ἀττεα, εἴτ' Ἀταρνεὺς καὶ Πιτάνη καὶ αἱ τοῦ Καῖκου ἐκβολαί· ταῦτα δ' ἤδη τοῦ Ἑλαϊτῶν κόλπου· καὶ ἐστὶν ἐν τῇ

¹ Περπερηνή, Meineke, from conj. of Kramer, for Περπερήνα.

¹ See preceding foot-note.

twenty,¹ to Gargara, which lies on a promontory² that forms the Adramyttene Gulf, in the special sense of that term; for the whole of the coast from Lectum to Canae is also called by this same name, in which is also included the Elaïtic Gulf. In the special sense of the term, however, only that part of it is called Adramyttene which is enclosed by that promontory on which Gargara lies and the promontory called Pyrrha, on which the Aphrodisium³ is situated. The breadth of the mouth across from promontory to promontory is a distance of one hundred and twenty stadia. Inside is Antandrus, above which lies a mountain called Alexandraia, where the Judgment of Paris is said to have taken place, as also Aspaneus, the market for the timber from Mt. Ida; for here people bring it down and sell it to those who want it. And then comes Astyra, a village with a precinct sacred to the Astyrene Artemis. And quite near Astyra is Adramyttium, a city colonised by the Athenians, which has both a harbour and a naval station. Outside the gulf and the promontory called Pyrrha lies Cisthenê, a deserted city with a harbour. Above it, in the interior, lie the copper mine and Perperenê and Trarium and other settlements like these two. On the next stretch of coast one comes to the villages of the Mitylenaeans, I mean Coryphantis and Heraclia; and after these places to Attea, and then to Atarneus and Pitanê and the outlets of the Caïcus River; and here we have already reached the Elaïtic Gulf. On the far side of the river lie

² So Clark; or "on a height," as Leaf translates (see his note).

³ Temple of Aphrodite.

περαία ἢ Ἑλαία¹ καὶ ὁ λοιπὸς μέχρι Κανῶν κόλπος. λέγωμεν δὲ ἀναλαμβάνοντες περὶ τῶν καθ' ἕκαστα πάλιν, εἴ τι παραλέλειπται μνήμης ἄξιον, καὶ πρῶτον περὶ τῆς Σκῆψεως.

52. Ἔστι δ' ἡ μὲν Παλαίσκηψις ἐπάνω Κεβρῆνος κατὰ τὸ μετεωρότατον τῆς Ἰδης ἐγγὺς Πολίχνης· ἐκαλεῖτο δὲ τότε Σκῆψις, εἴτ' ἄλλως, εἴτ' ἀπὸ τοῦ περισκεπτον εἶναι τὸν τόπον, εἰ δεῖ τὰ παρὰ τοῖς βαρβύροις ἐν τῷ τότε ὀνόματα ταῖς Ἑλληνικαῖς ἐτυμολογεῖσθαι φωναῖς· ὕστερον δὲ κατωτέρω σταδίοις² ἐξήκοντα εἰς τὴν νῦν Σκῆψιν μετωκίσθησαν ὑπὸ Σκαμανδρίου τε τοῦ Ἑκτορος καὶ Ἀσκανίου τοῦ Αἰνείου παιδός· καὶ δύο γένη ταῦτα βασιλεῦσαι πολὺν χρόνον ἐν τῇ Σκῆψει λέγεται· μετὰ ταῦτα δ' εἰς ὀλιγαρχίαν μετέστησαν, εἴτα Μιλήσιοι³ συνεπολιτεύθησαν αὐτοῖς⁴ καὶ δημοκρατικῶς ᾤκουν· οἱ δ' ἀπὸ τοῦ γένους οὐδὲν ἦττον ἐκαλοῦντο βασιλεῖς, ἔχοντές τινας τιμάς· εἴτ' εἰς τὴν Ἀλεξάνδρειαν συνεπόλισε τοὺς Σκηψίους Ἀντίγονος, εἴτ' ἀπέλυσε Λυσίμαχος καὶ ἐπανήλθον εἰς τὴν οἰκίαν.

53. Οἶεται δ' ὁ Σκῆψιος καὶ βασιλείον τοῦ Αἰνείου γεγονέναι τὴν Σκῆψιν, μέσσην οὖσαν τῆς τε ὑπὸ τῷ Αἰνείᾳ καὶ Λυρνησοῦ, εἰς ἣν φυγεῖν εἴρηται διωκόμενος ὑπὸ τοῦ Ἀχιλλέως· φησὶ γοῦν ὁ Ἀχιλλεύς·

¹ Ἑλαία, Tzschucke, from conj. of Casaubon, for Μελαία O'Frazz, Μελέα D, Μελέα h, Μελέα i.

² After σταδίοις, Leaf inserts διακοσίοις καὶ (i.e. σταδίοισις) instead of σταδίοισις).

³ Μιλήσιοι, Corais, following Ald., for Μιλησίους.

⁴ For αὐτοῖς, mox and Corais read αὐτοί.

Elaea and the rest of the gulf as far as Canae. But let me go back and again discuss in detail the several places, if anything worthy of mention has been passed over; and first of all, Scepsis.

52. Palaescepsis lies above Cebren near the highest part of Mt. Ida, near Polichna; and it was then called Scepsis (whether for another reason or from the fact that the place is visible all round, if it is right to derive from Greek words names then used by barbarians),¹ but later the inhabitants were removed sixty stadia² lower down to the present Scepsis by Scamandrius the son of Hector and Ascanius the son of Aeneias; and their two families are said to have held the kingship over Scepsis for a long time. After this they changed to an oligarchy, and then Milesians settled with them as fellow-citizens;³ and they began to live under a democracy. But the heirs of the royal family none the less continued to be called kings and retained certain prerogatives. Then the Scepsians were incorporated into Alexandria by Antigonos; and then they were released by Lysimachus and went back to their home-land.

53. Demetrius thinks that Scepsis was also the royal residence of Aeneias, since it lies midway between the territory subject to Aeneias and Lyrnessus, to which latter he fled, according to Homer's statement, when he was being pursued by Achilles. At

¹ The Greek word "scepsis" means "a viewing," "an inspection."

² Leaf emends to "two hundred and sixty stadia" (see critical note).

³ See 14. 1. 6.

ἥ οὐ μέμνη, ὅτε πέρ σε βοῶν ἄπο μῦνον
 ἔοντα

σεῦα κατ' Ἰδαίων ὀρέων ταχέεσσι πόδεσσι,
 κεῖθεν δ' ἐς Λυρνησσὸν ὑπέκφυγες· αὐτὰρ ἐγὼ
 τήν

πέρσα, μεθορμηθείς.

οὐχ ὁμολογεῖ δὲ τῷ περὶ τῶν ἀρχηγετῶν τῆς
 Σκήψεως λόγῳ τῷ λεχθέντι νῦν τὰ περὶ τοῦ
 Αἰνείου θρυλούμενα. περιγενέσθαι γὰρ δὴ τοῦτόν
 φασιν ἐκ τοῦ πολέμου διὰ τὴν πρὸς Πριάμον
 δυσμένειαν·

αἰὲ γὰρ Πριάμῳ ἐπεμήνιε δίῳ,
 οὐνεκ' ἄρ' ἐσθλὸν ἔοντα μετ' ἀνδράσιν οὗ τι
 τίσκε·

τοὺς δὲ συνάρχοντας Ἀντηνορίδας καὶ αὐτὸν τὸν
 Ἀντήνορα διὰ τὴν Μενελάου παρ' αὐτῷ ξενίαν.
 C 608 Σοφοκλῆς γοῦν ἐν τῇ ἀλώσει τοῦ Ἰλίου παρδαλέαν
 φησὶ πρὸ τῆς θύρας τοῦ Ἀντήνορος προτεθῆναι
 σύμβολον τοῦ ἀπόρθητον ἐαθῆναι τὴν οἰκίαν.
 τὸν μὲν οὖν Ἀντήνορα καὶ τοὺς παῖδας μετὰ τῶν
 περιγενομένων¹ Ἑνετῶν εἰς τὴν Θράκην περι-
 σωθῆναι,² κάκειθεν διαπεσεῖν εἰς τὴν λεγομένην
 κατὰ τὸν Ἀδρίαν Ἑνετικὴν· τὸν δὲ Αἰνείαν μετ'
 Ἀγχίσου τοῦ πατρὸς καὶ τοῦ παιδὸς Ἀσκανίου
 λαὸν ἀθροίσαντα πλεῦσαι, καὶ οἱ μὲν οἰκῆσαι
 περὶ τὸν Μακεδονικὸν Ὀλυμπόν φασιν, οἱ δὲ
 περὶ Μαντίνειαν τῆς Ἀρκαδίας κτίσαι Καπύας,
 ἀπὸ Κάπυος θέμενον τοῦνομα τῷ πολίσματι, οἱ
 δ' εἰς Αἶγεςταν κατὰραι τῆς Σικελίας σὺν Ἐλύ-

¹ περιγενομένων, Eustathius and the editors, for παραγενο-
 106

any rate, Achilles says: "Dost thou not remember how from the kine, when thou wast all alone, I made thee run down the Idaean mountains with swift feet? And thence thou didst escape to Lyrnessus, but I rushed in pursuit of thee and sacked it."¹ However, the oft-repeated stories of Aencias are not in agreement with the account which I have just given of the founders of Scepsis. For according to these stories he survived the war because of his enmity to Priam: "For always he was wroth against goodly Priam, because, although he was brave amid warriors, Priam would not honour him at all";² and his fellow-rulers, the sons of Antenor and Antenor himself, survived because of the hospitality shown Menelaüs at Antenor's house. At any rate, Sophocles³ says that at the capture of Troy a leopard's skin was put before the doors of Antenor as a sign that his house was to be left unpillaged; and Antenor and his children safely escaped to Thrace with the survivors of the Heneti, and from there got across to the Adriatic Heneticê,⁴ as it is called, whereas Aeneias collected a host of followers and set sail with his father Anchises and his son Ascanius; and some say that he took up his abode near the Macedonian Olympus, others that he founded Capyae near Mantinea in Arcadia, deriving the name he gave the settlement from Capys, and others say that he landed at Aegesta in Sicily with

¹ *Iliad* 20. 188.

² *Iliad* 13. 460.

³ *Frag.* 10 (Nauck).

⁴ As distinguished from that in Paphlagonia (see 5. 1. 4).

μένων Διὶ, λεγόμενων τωκ, . . . νομένων C; word omitted by *nos*.

² For περισωθῆναι Corais reads περαιωθῆναι.

μῶ¹ Τρωὶ καὶ Ἐρυκα καὶ Διλύβαιοι κατασχεῖν,
καὶ ποταμοὺς περὶ Αἶγεσταν προσαγορεύσαι Σκά-
μανδρον καὶ Σιμόνεντα· ἔνθεν δ' εἰς τὴν Λατίνην
ἐλθόντα μεῖναι κατὰ τι λόγιον τὸ κελεῖον μένειν,
ὅπου ἂν τὴν τράπεζαν καταφάγῃ· συμβῆναι δὲ
τῆς Λατίνης² περὶ τὸ Λαουίνιον τοῦτο, ἄρτου
μεγάλου τεθέντος ἀντὶ τραπέζης κατὰ ἀπορίαν³
καὶ ἅμα ἀναλωθέντος τοῖς ἐπ' αὐτῷ κρέασιν.
Ὅμηρος μέντοι συνηγορεῖν οὐδετέροις ἔοικεν, οὐδὲ
τοῖς περὶ τῶν ἀρχηγετῶν τῆς Σκῆψεως λεχθεῖσιν·
ἐμφαίνει γὰρ μεμενηκότα τὸν Αἰνείαν ἐν τῇ
Τροίᾳ καὶ διαδεδεγμένον τὴν ἀρχὴν καὶ παρα-
δεδωκότα παισὶ παίδων τὴν διαδοχὴν αὐτῆς,
ἡφανισμένου τοῦ τῶν Πριαμιδῶν γένους·

ἤδη γὰρ Πριάμου γενεὴν ἤχθηρε Κρονίων·
νῦν δὲ δὴ Αἰνείας βίη Τρῶεσσιν ἀνάξει
καὶ παίδων παῖδες, τοὶ κεν μετόπισθε γέ-
νωνται.

οὕτω δ' οὐδ' ἡ τοῦ Σκαμανδρίου διαδοχὴ σώζοιτ'
ἂν. πολὺ δὲ μᾶλλον τοῖς ἑτέροις διαφωνεῖ τοῖς
μέχρι καὶ Ἰταλίας αὐτοῦ τὴν πλάνην λέγουσι
καὶ αὐτόθι ποιοῦσι τὴν καταστροφὴν τοῦ βίου.
τινὲς δὲ γράφουσιν

Αἰνείας γένος πάντεσσιν ἀνάξει,
καὶ παῖδες παίδων,
τοὺς Ῥωμαίους λέγοντες.

54. Ἐκ δὲ τῆς Σκῆψεως οἱ τε Σωκρατικοὶ

¹ Ἐλύμφ F, Ἐλύμφ other MSS.

² Instead of τῆς Λατίνης, D(pr. man.) ἰνῶ have τοῖς Λατίνοις,
μοι ἐν τῇ Λατίνῃ.

Elymus the Trojan and took possession of Eryx and Lilybaeum, and gave the names Scamander and Simoeis to rivers near Aegesta, and that thence he went into the Latin country and made it his abode, in accordance with an oracle which bade him abide where he should eat up his table, and that this took place in the Latin country in the neighbourhood of Lavinium, where a large loaf of bread was put down for a table, for want of a better table, and eaten up along with the meats upon it. Homer, however, appears not to be in agreement with either of the two stories, nor yet with the above account of the founders of Scepsis; for he clearly indicates that Aeneias remained in Troy and succeeded to the empire and bequeathed the succession thereto to his sons' sons, the family of the Priamidae having been wiped out: "For already the race of Priam was hated by the son of Cronus; and now verily the mighty Aeneias will rule over the Trojans, and his sons' sons that are hereafter to be born."¹ And in this case one cannot even save from rejection the succession of Scamandrius.² And Homer is in far greater disagreement with those who speak of Aeneias as having wandered even as far as Italy and make him die there. Some write, "the family of Aeneias will rule over all,"³ and his sons' sons," meaning the Romans.

54. From Scepsis came the Socratic philosophers

¹ *Iliad* 20. 306.

² The son of Hector, who, along with Ascanius, was said to have been king of Scepsis (§ 52).

³ i.e. they emend "Trojans" (Τρώεσσιν) to "all" (πάντες) in the Homeric passage.

⁴ ἀπορίαν, Casaubon, for ἀπειρίαν; so the later editors.

γεγόνασιν Ἐραστος καὶ Κορίσκος καὶ ὁ τοῦ Κορίσκου υἱὸς Νηλεὺς, ἀνὴρ καὶ Ἀριστοτέλους ἠκροαμένος καὶ Θεοφράστου, διαδεδεγμένος δὲ τὴν βιβλιοθήκην τοῦ Θεοφράστου, ἐν ᾗ ἦν καὶ ἡ τοῦ Ἀριστοτέλους· ὁ γοῦν Ἀριστοτέλης τὴν ἑαυτοῦ Θεοφράστῳ παρέδωκεν, ὥπερ καὶ τὴν σχολὴν ἀπέλιπε, πρῶτος, ὧν ἴσμεν, συναγαγὼν βιβλία καὶ διδάξας τοὺς ἐν Αἰγύπτῳ βασιλέας C 109 βιβλιοθήκης σύνταξιν. Θεόφραστος δὲ Νηλεῖ παρέδωκεν· ὁ δ' εἰς Σκίηνιν κομίσας τοῖς μετ' αὐτὸν παρέδωκεν, ἰδιώταις ἀνθρώποις, οἳ κατὰ κλειστα εἶχον τὰ βιβλία, οὐδ' ἐπιμελῶς κείμενα· ἐπειδὴ δὲ ἦσθοντο τὴν σπουδὴν τῶν Ἀτταλικῶν βασιλέων, ὑφ' οἷς ἦν ἡ πόλις, ζητούντων βιβλία εἰς τὴν κατασκευὴν τῆς ἐν Περγάμῳ βιβλιοθήκης, κατὰ γῆς ἔκρυψαν ἐν διώρυγί τινι· ὑπὸ δὲ νοτίας καὶ σιγῶν κακωθέντα ὧς ποτε ἀπέδοντο οἱ ἀπὸ τοῦ γένους Ἀπελλικῶντι τῷ Τηίῳ πολλῶν ἀργυρίων· τὰ τε Ἀριστοτέλους καὶ τὰ τοῦ Θεοφράστου βιβλία· ἦν δὲ ὁ Ἀπελλικῶν φιλόβιβλος μᾶλλον ἢ φιλόσοφος· διὸ καὶ ζητῶν ἐπανόρθωσιν τῶν διαβρωμάτων εἰς ἀντίγραφα καινὰ μετήνεγκε τὴν γραφὴν, ἀναπληρῶν οὐκ εὖ, καὶ ἐξέδωκεν ἀμαρτάνων πλήρη τὰ βιβλία, συνέβη δὲ τοῖς ἐκ τῶν περιπάτων τοῖς μὲν πάλαι τοῖς μετὰ Θεόφραστον οὐκ ἔχουσιν ὅλως τὰ βιβλία πλὴν ὀλίγων, καὶ μάλιστα τῶν ἐξωτερικῶν, μηδὲν ἔχειν φιλοσοφεῖν πραγματικῶς, ἀλλὰ θέσεις ληκυθίζειν· τοῖς δ' ὕστερον, ἀφ' οὗ τὰ βιβλία ταῦτα προῆλθεν, ἄμεινον μὲν

¹ Strabo refers to Eumenes II, who reigned 197-159 B.C.

Erastus and Coriscus and Neleus the son of Coriscus, this last a man who not only was a pupil of Aristotle and Theophrastus, but also inherited the library of Theophrastus, which included that of Aristotle. At any rate, Aristotle bequeathed his own library to Theophrastus, to whom he also left his school; and he is the first man, so far as I know, to have collected books and to have taught the kings in Egypt how to arrange a library. Theophrastus bequeathed it to Neleus; and Neleus took it to Scepsis and bequeathed it to his heirs, ordinary people, who kept the books locked up and not even carefully stored. But when they heard how zealously the Attalic kings¹ to whom the city was subject were searching for books to build up the library in Pergamum, they hid their books underground in a kind of trench. But much later, when the books had been damaged by moisture and moths, their descendants sold them to Apellicon² of Teos for a large sum of money, both the books of Aristotle and those of Theophrastus. But Apellicon was a bibliophile rather than a philosopher; and therefore, seeking a restoration of the parts that had been eaten through, he made new copies of the text, filling up the gaps incorrectly, and published the books full of errors. The result was that the earlier school of Peripatetics who came after Theophrastus had no books at all, with the exception of only a few, mostly exoteric works, and were therefore able to philosophise about nothing in a practical way, but only to talk bombast about commonplace propositions, whereas the later school, from the time the books in question appeared, though better able

² Died about 84 B.C.

ἐκείνων φιλοσοφεῖν καὶ ἀριστοτελίζειν, ἀναγκάζεσθαι μέντοι τὰ πολλὰ εἰκότα λέγειν διὰ τὸ πλῆθος τῶν ἀμαρτιῶν. πολὺ δὲ εἰς τοῦτο καὶ ἡ Ῥώμη προσελάβετο· εὐθὺς γὰρ μετὰ τὴν Ἀπελλικῶντος τελευτὴν Σύλλας ἦρε τὴν Ἀπελλικῶντος βιβλιοθήκην ὃ τὰς Ἀθήνας ἐλὼν, δεῦρο δὲ κομισθεῖσαν Τυραννίων τε ὁ γραμματικὸς διεχειρίσατο φιλαριστοτέλης ὢν, θεραπεύσας τὸν ἐπὶ τῆς βιβλιοθήκης, καὶ βιβλιοπῶλαί τινες γραφεῦσι φαύλοις χρώμενοι καὶ οὐκ ἀντιβάλλοντες, ὅπερ καὶ ἐπὶ τῶν ἄλλων συμβαίνει τῶν εἰς πρᾶσιν γραφομένων βιβλίων καὶ ἐνθάδε καὶ ἐν Ἀλεξανδρείᾳ. περὶ μὲν οὖν τούτων ἀπόχρη.

55. Ἐκ δὲ τῆς Σκήψεως καὶ ὁ Δημήτριος ἐστίν, οὗ μεμνήμεθα πολλάκις, ὁ τὸν Τρωικὸν διάκοσμον ἐξηγησάμενος γραμματικὸς, κατὰ τὸν αὐτὸν χρόνον γεγωνὼς Κράτητι καὶ Ἀριστάρχῳ καὶ μετὰ τοῦτο Μητρόδωρος, ἀνὴρ ἐκ τοῦ φιλοσόφου μεταβεβληκὼς ἐπὶ τὸν πολιτικὸν βίον καὶ ῥητορεύων τὸ πλεόν ἐν τοῖς συγγράμμασιν· ἐχρήσατο δὲ φράσεώς τινι χαρακτῆρι καινῷ καὶ κατεπλήξατο¹ πολλούς· διὰ δὲ τὴν δόξαν ἐν Χαλκηδόνι γάμου λαμπροῦ πένης ὢν ἔτυχε καὶ ἐχρημάτιζε Χαλκηδόνιος· Μιθριδάτην δὲ θεραπεύσας τὸν Εὐπάτορα συναπῆρεν εἰς τὸν Πόντον ἐκείνῳ μετὰ τῆς γυναικὸς καὶ ἐτιμύθη C 610 διαφερόντως, ταχθεὶς ἐπὶ τῆς δικαιοδοσίας, ἀφ' ² ἧς οὐκ ἦν τῷ κριθέντι ἀναβολὴ³ τῆς δίκης ἐπὶ τὸν βασιλέα. οὐ μέντοι διηντύχησεν, ἀλλ'

¹ Instead of κατεπλήξατο, F reads κατεπλήξαντο, μοῖα κατέπληξε (so Corais, who inserts τοὺς before πολλούς).

to philosophise and Aristotelise, were forced to call most of their statements probabilities, because of the large number of errors.¹ Rome also contributed much to this; for, immediately after the death of Apellicon, Sulla, who had captured Athens, carried off Apellicon's library to Rome, where Tyrannion the grammarian, who was fond of Aristotle, got it in his hands by paying court to the librarian, as did also certain booksellers who used bad copyists and would not collate the texts—a thing that also takes place in the case of the other books that are copied for selling, both here² and at Alexandria. However, this is enough about these men.

55. From Scepsis came also Demetrius, whom I often mention, the grammarian who wrote a commentary on *The Marshalling of the Trojan Forces*, and was born at about the same time as Crates and Aristarchus; and later, Metrodorus, a man who changed from his pursuit of philosophy to political life, and taught rhetoric, for the most part, in his written works; and he used a brand-new style and dazzled many. On account of his reputation he succeeded, though a poor man, in marrying brilliantly in Chalcedon; and he passed for a Chalcedonian. And having paid court to Mithridates Eupator, he with his wife sailed away with him to Pontus; and he was treated with exceptional honour, being appointed to the judgeship from which there was no appeal to the king. However, his good fortune did

¹ i.e. errors in the available texts of Aristotle.

² i.e. at Rome.

² ἀφ', Casaubon, for ἐφ'; so the later editors.

² ἀναβολή, Casaubon, for βουλή; so the later editors.

ἐμπεσὼν εἰς ἔχθραν ἀδικωτέρων ἀνθρώπων ἀπέστη τοῦ βασιλέως κατὰ τὴν πρὸς Τυγράνην τὸν Ἀρμένιον πρεσβείαν· ὁ δ' ἄκουτα ἀνέπεμψεν αὐτὸν τῷ Εὐπάτορι, φεύγοντι ἤδη τὴν προγονικὴν, κατὰ δὲ τὴν ὁδὸν κατέστρεψε τὸν βίον εἴθ' ὑπὸ τοῦ βασιλέως, εἴθ' ὑπὸ νόσον· λέγεται γὰρ ἀμφοτέρα. περὶ μὲν τῶν Σκηψίων ταῦτα.

56. Μετὰ δὲ Σκῆψιν Ἀνδείρα¹ καὶ Πιονίαι καὶ ἡ Γαργαρίς. ἔστι δὲ λίθος περὶ τὰ Ἀνδείρα, ὃς καίόμενος σίδηρος γίνεται· εἴτα μετὰ γῆς τινὸς καμινευθεὶς ἀποστάζει ψευδάργυρον, ἢ προσλαβοῦσα χαλκὸν τὸ καλούμενον γίνεται κρᾶμα, ὃ τινες ὀρείχαλκον καλοῦσι· γίνεται δὲ ψευδάργυρος καὶ περὶ τὸν Τμῶλον. ταῦτα δ' ἔστι τὰ χωρία, ἃ οἱ Δέλεγες κατεῖχον· ὥς δ' αὐτως καὶ τὰ περὶ Ἄσσον.

57. Ἔστι δὲ ἡ Ἄσσος ἐρυμνὴ καὶ εὐτειχὴς, ἀπὸ θαλάττης καὶ τοῦ λιμένος ὀρθίαν καὶ μακρὰν ἀνάβασιν ἔχουσα· ὥστ' ἐπ' αὐτῆς οἰκείως εἰρῆσθαι δοκεῖ τὸ τοῦ Στρατονίκου τοῦ κιθαριστοῦ.

Ἄσσον ἴθ', ὥς κεν θᾶσσον ὀλέθρου πείραθ' ἵκηαι.

ὁ δὲ λιμὴν χώματι κατεσκεύασται μεγάλῳ. ἐντεῦθεν ἦν Κλεάνθης, ὁ στωικὸς φιλόσοφος ὁ διαδεξάμενος τὴν Ζήνωνος τοῦ Κιτιέως σχολήν, καταλιπὼν δὲ Χρυσίππῳ τῷ Σολεῖ· ἐνταῦθα δὲ καὶ Ἀριστοτέλης διέτριψε διὰ τὴν πρὸς Ἑρμείαν τὸν τύραννον κηδείαν. ἦν δὲ Ἑρμείας εὐνοῦχος, τραπεζίτου τινὸς οἰκέτης· γενόμενος δ' Ἀθήνησιν

¹ Instead of Ἀνδείρα, DEhí and Epit. read Ἀνδρα.

not continue, but he incurred the enmity of men less just than himself and revolted from the king when he was on the embassy to Tigranes the Armenian.¹ And Tigranes sent him back against his will to Eupator, who was already in flight from his ancestral realm; but Metrodorus died on the way, whether by order of the king² or from disease; for both accounts are given of his death. So much for the Scepsians.

56. After Scepsis come Andeira and Pioniae and the territory of Gargara. There is a stone in the neighbourhood of Andeira which, when burned, becomes iron, and then, when heated in a furnace with a certain earth, distils mock-silver;³ and this, with the addition of copper, makes the "mixture," as it is called, which by some is called "mountain-copper."⁴ These are the places which the Leleges occupied; and the same is true of the places in the neighbourhood of Assus.

57. Assus is by nature strong and well-fortified; and the ascent to it from the sea and the harbour is very steep and long, so that the statement of Stratonicus the citharist in regard to it seems appropriate: "Go to Assus, in order that thou mayest more quickly come to the doom of death."⁵ The harbour is formed by a great mole. From Assus came Cleanthes, the Stoic philosopher who succeeded Zeno of Citium as head of the school and left it to Chrysippus of Soli. Here too Aristotle tarried, because of his relationship by marriage with the tyrant Hermeias. Hermeias was a eunuch, the slave of a certain banker;⁶ and on his arrival at Athens he

¹ For the story see Plutarch, *Lucullus* 22. ² Tigranes.

³ i.e. zinc.

⁴ The Latin term is *orichalcum*.

⁵ A precise quotation of *Iliad* 6. 143 except that Homer's ἀσσον ("nearer") is changed to Ἀσσον ("to Assus").

⁶ Eubulus.

ἠκροάσατο καὶ Πλάτωνος καὶ Ἀριστοτέλους· ἐπανελθὼν δὲ τῷ δεσπότη συνετυράννησε, πρῶτον ἐπιθεμένῳ τοῖς περὶ Ἀταρνεά καὶ Ἄσσον χωρίοις· ἔπειτα διεδέξατο ἐκείνον, καὶ μετεπέμψατο τὸν τε Ἀριστοτέλην καὶ Ξενοκράτην καὶ ἐπεμελήθη αὐτῶν· τῷ δ' Ἀριστοτέλει καὶ θυγατέρα ἀδελφοῦ συνώκισε. Μένμων δ' ὁ Ῥόδιος ὑπηρετῶν τότε τοῖς Πέρσαις καὶ στρατηγῶν, προσποιησάμενος φιλίαν καλεῖ πρὸς ἑαυτὸν ξενίας τε ἅμα¹ καὶ πραγμάτων προσποιητῶν χάριν, συλλαβὼν δ' ἀνέπεμψεν ὡς τὸν βασιλέα, καὶ κεῖ κρεμασθεὶς ἀπώλετο· οἱ φιλόσοφοι δ' ἐσώθησαν, φεύγοντες τὰ χωρία, ἃ οἱ Πέρσαι κατέσχον.

58. Φησὶ δὲ Μυρσίλος Μηθυμναίων κτίσμα εἶναι τὴν Ἄσσον, Ἑλλάνικός τε καὶ Αἰολίδα φησὶν, ὥσπερ² καὶ τὰ Γάργαρα καὶ ἡ Λαμπωνία Αἰολέων. Ἀσσίῳ γάρ ἐστι κτίσμα τὰ Γάργαρα, C 611 οὐκ εὖ συνοικούμενα· ἐποίκουσ γὰρ οἱ βασιλεῖς εἰσήγαγον ἐκ Μιλητουπόλεως, ἐρημώσαντες ἐκείνην, ὥστε ἡμιβαρβάρους γενέσθαι φησὶ Δημήτριος αὐτοὺς ὁ Σκῆψιος ἀντὶ Αἰολέων. καθ' Ὅμηρον μέντοι ταῦτα πάντα ἦν Λελέγων, οὓς τινες μὲν Κᾶρας ἀποφαίνουσιν, Ὅμηρος δὲ χωρίζει.

πρὸς μὲν ἀλὸς Κᾶρες καὶ Παίονες ἀγκυλότοξοι καὶ Λέλεγες καὶ Καύκωνες.

ἕτεροι μὲν τοίνυν τῶν Καρῶν ὑπῆρξαν· ὧκουν δὲ

¹ Instead of ἅμα, most read ὀνόματι.

² ὥσπερ, Meineke, for ὥς τε; others omit τε.

¹ The historian of Methymna, who appears to have

became a pupil of both Plato and Aristotle. On his return he shared the tyranny with his master, who had already laid hold of the districts of Atarneus and Assus; and then Hermeias succeeded him and sent for both Aristotle and Xenocrates and took care of them; and he also married his brother's daughter to Aristotle. Memnon of Rhodes, who was at that time serving the Persians as general, made a pretence of friendship for Hermeias, and then invited him to come for a visit, both in the name of hospitality and at the same time for pretended business reasons; but he arrested him and sent him up to the king, where he was put to death by hanging. But the philosophers safely escaped by flight from the districts above-mentioned, which were seized by the Persians.

58. Myrsilus¹ says that Assus was founded by the Methymnaeans; and Hellanicus too calls it an Aeolian city, just as also Gargara and Lamponia belonged to the Aeolians. For Gargara was founded by the Assians; but it was not well peopled, for the kings brought into it colonists from Miletropolis when they devastated that city, so that instead of Aeolians, according to Demetrius of Scepsis, the inhabitants of Gargara became semi-barbarians. According to Homer, however, all these places belonged to the Leleges, who by some are represented to be Carians, although by Homer they are mentioned apart: "Towards the sea are the Carians and the Paconians of the curved bow and the Leleges and the Cauconians."² They were therefore a different people from the Carians; and they lived between

flourished about 300 B.C.; only fragments of his works remain.

² *Iliad* 10. 428.

μεταξὺ τῶν ὑπὸ τῷ Αἰνεΐᾳ καὶ τῶν καλουμένων
ὑπὸ τοῦ ποιητοῦ Κίλικων ἐκπορθηθέντες δὲ ὑπὸ
τοῦ Ἀχιλλέως μετέστησαν εἰς τὴν Καρίαν, καὶ
κατέσχον τὰ περὶ τὴν νῦν Ἀλικαρνασὸν¹ χωρία.

59. Ἡ μὲντοι νῦν ἐκλειφθεῖσα ὑπ' αὐτῶν πόλις
Πήδασος οὐκέτ' ἐστίν. ἐν δὲ τῇ μεσογαίᾳ τῶν
Ἀλικαρνασέων² τὰ Πήδασα ὑπ' αὐτῶν ὀνο-
μασθέντα ἦν πόλις, καὶ ἡ νῦν χώρα Πηδασίς
λέγεται. φασὶ δ' ἐν αὐτῇ καὶ ὀκτὼ πόλεις
ῥοκίσθαι ὑπὸ τῶν Λελέγων πρότερον εὐανδρη-
σάντων, ὥστε καὶ τῆς Καρίας κατασχεῖν τῆς
μέχρι Μύνδου καὶ Βαργυλίων, καὶ τῆς Πισιδίας
ἀποτεμέσθαι πολλήν. ὕστερον δ' ἅμα τοῖς Καρσί
στρατευόμενοι κατεμερίσθησαν εἰς ὅλην τὴν
Ἑλλάδα καὶ ἠφανίσθη τὸ γένος, τῶν δ' ὀκτὼ
πόλεων τὰς ἑξ Μαύσωλος εἰς μίαν τὴν Ἀλι-
καρνασὸν³ συνήγαγεν, ὡς Καλλισθένης ἱστορεῖ.
Συνάγγελα⁴ δὲ καὶ Μύνδον διεφύλαξε. τοῖς δὲ
Πηδασεῦσι τούτοις φησὶν Ἡρόδοτος ὅτε μέλλοι
τι ἀνεπιτήδειον⁵ ἔσεσθαι καὶ τοῖς περιοίκοις, τὴν
ἰέρειαν τῆς Ἀθηνᾶς πώγωνα ἴσχειν⁶ τρεῖς δὲ
συμβῆναι τοῦτο αὐτοῖς. Πήδασον⁷ δὲ καὶ ἐν τῇ
νῦν Στρατονικέῳ πολίχνιον ἐστίν. ἐν ὅλῃ δὲ

¹ Ἀλικαρνασόν, D^hacc, Ἀλικαρνασόν other MSS.

² Ἀλικαρνασέων OF; Ἀλικαρνασέων other MSS.

³ Ἀλικαρνασόν, all MSS., but see two preceding notes;
also see 8. 6. 14 (where all MSS. have Ἀλικαρνασόν) and
14. 2. 16.

⁴ Συνάγγελα, Kramer, for συναγάλα CDx, σὺν ἀγάλαι ἡτοιμα,
συναγγελας F (Συνάγγελα Tzschucke and Corais, from conj. of
Casaubon); so Müller-Dübner, Meineke, and Leaf.

⁵ ἀνεπιτήδειον, Xylander, for ἐπιτήδειον; so the later
editors.

⁶ ἴσχειν, Corais, for σχεῖν; so the later editors,

the people subject to Aeneias and the people whom the poet called Cilicians, but when they were pillaged by Achilles they migrated to Caria and took possession of the district round the present Halicarnassus.¹

59. However, the city Pedasus, now abandoned by them, is no longer in existence; but in the inland territory of the Halicarnassians there used to be a city Pedasa, so named by them; and the present territory is called Pedasis. It is said that as many as eight cities were settled in this territory by the Leleges, who in earlier times were so numerous that they not only took possession of that part of Caria which extends to Myndus and Bargylia, but also cut off for themselves a large portion of Pisidia. But later, when they went out on expeditions with the Carians, they became distributed throughout the whole of Greece, and the tribe disappeared. Of the eight cities, Mausolus² united six into one city, Halicarnassus, as Callisthenes tells us, but kept Syangela and Myndus as they were. These are the Pedasians of whom Herodotus³ says that when any misfortune was about to come upon them and their neighbours, the priestess of Athena would grow a beard; and that this happened to them three times. And there is also a small town called Pedasum in the present territory of Stratoniceia. And throughout the whole of Caria

¹ Cf. 7. 7. 2. On the variant spellings of "Halicarnas(s)us" see critical note.

² King of Caria 377-353 B.C. The first "Mausoleum" was so named after him.

³ 1. 175, S. 104.

⁷ Instead of Πήδαρον, *now* have Πήδαρος (see Stephanus, s.v. Πήδαρος).

Καρία καὶ ἐν Μιλήτῳ¹ Λελέγων τάφοι καὶ ἐρύματα καὶ ἔχνη κατοικιῶν δείκνυνται.

60. Μετὰ δὲ τοὺς Λέλεγας τὴν ἐξῆς παραλίαν ᾠκουν Κίλικες καθ' Ὁμηρον, ἣν νῦν ἔχουσιν Ἀδραμυττηνοὶ τε καὶ Ἀταρνεῖται καὶ Πιταναῖοι μέχρι τῆς ἐκβολῆς τοῦ Καΐκου. διήρηντο δ' εἰς δύο δυναστείας οἱ Κίλικες, καθάπερ εἵπομεν, τὴν τε ὑπὸ τῷ Ἡετίωνι καὶ τὴν ὑπὸ Μύνητι.

61. Τοῦ μὲν οὖν Ἡετίωνος λέγει πόλιν Θήβην· ᾠχόμεθ' ἐς Θήβην ἱερὴν πόλιν Ἡετίωνος.

τούτου δὲ καὶ τὴν Χρύσαν τὴν ἔχουσιν² τὸ ἱερὸν τοῦ Σμινθέως Ἀπόλλωνος ἐμφαίνει, εἴπερ ἢ Χρυσῆς ἐκ τῆς Θήβης ἐάλω·

C 612 ᾠχόμεθα γάρ, φησὶν, ἐς Θήβην,
τὴν δὲ διεπράθομέν τε καὶ ἡγομεν ἐνθάδε πάντα,
καὶ τὰ μὲν εὖ δάσσαντο μετὰ σφίσιν,
ἐκ δ' ἔλον Ἀτρεΐδῃ Χρυσήϊδα.

τοῦ δὲ Μύνητος τὴν Λυρνησσὸν ἐπειδὴ

Λυρνησσὸν διαπορθήσας καὶ τείχεα Θήβης
τόν τε Μύνητα καὶ τὸν Ἐπίστροφον ἀνεῖλεν
Ἀχιλλεύς· ὥστε, ὅταν φῇ ἢ Βρισηΐς,

οὐδέ μ' ἔασκες, ὅτ' ἀνδρ' ἐμὸν ὠκύς Ἀχιλλεύς
ἔκτεινεν, πέρσεν δὲ πόλιν θείοιο Μύνητος,

οὐ τὴν Θήβην λέγοι ἄν (αὕτη γὰρ Ἡετίωνος),
ἀλλὰ τὴν Λυρνησσὸν· ἀμφότεραι δ' ἦσαν ἐν τῷ
κληθέντι μετὰ ταῦτα Θήβης πεδίῳ, ὃ διὰ τὴν
ἀρετὴν περιμάχητον γενέσθαι φασὶ Μυσοῖς μὲν

¹ ἐν Μιλήτῳ, omitted by Dñi.

and in Miletus are to be seen tombs, fortifications, and traces of settlements of the Leleges.

60. After the Leleges, on the next stretch of coast, lived the Cilicians, according to Homer; I mean the stretch of coast now held by the Adramytteni and Atarneitae and Pitanaei, as far as the outlet of the Caicus. The Cilicians, as I have said,¹ were divided into two dynasties,² one subject to Eëtion and one to Mynes.

61. Now Homer calls Thebê the city of Eëtion: "We went into Thebê, the sacred city of Eëtion";³ and he clearly indicates that also Chrysa, which had the temple of Sminthian Apollo, belonged to Eëtion, if it be true that Chryseis was taken captive at Thebê, for he says, "We went into Thebê, and laid it waste and brought hither all the spoil. And this they divided aright among themselves, but they chose out Chryseis for the son of Atreus";⁴ and that Lyrnessus belonged to Mynes, since Achilles "laid waste Lyrnessus and the walls of Thebê"⁵ and slew both Mynes and Epistrophus; so that when Briseis says, "thou wouldst not even let me,"⁶ when swift Achilles slew my husband and sacked the city of divine Mynes,"⁷ Homer cannot mean Thebê (for this belonged to Eëtion), but Lyrnessus. Both were situated in what was afterwards called the Plain of Thebê, which, on account of its fertility, is said to have been an object of contention between the

¹ 13. 1. 7, 49.

² *Iliad* 1. 366.

³ *Iliad* 2. 691.

⁴ *Iliad* 19. 295.

⁵ But cf. 13. 1. 70.

⁶ *Iliad* 1. 366 ff.

⁷ *sc.* "weep."

² τὴν ἔχουσαν, added from *moz.*

καὶ Λυδοῖς τὸ ¹ πρότερον, τοῖς δ' Ἑλλησιν ὕστερον τοῖς ἐποικήσασιν ἐκ τῆς Αἰολίδος καὶ τῆς Λέσβου. ἔχουσι δὲ νῦν Ἀδραμυττηνοὶ τὸ πλεόν. ἐνταῦθα γὰρ καὶ ἡ Θήβη καὶ ἡ Λυρνησσός, ἐρυμνὸν χωρίον· ἔρημοι δ' ἀμφότεραι· διέχουσι δὲ Ἀδραμυττίου σταδίους ἢ μὲν ἐξήκοντα, ἢ δὲ ὀγδοήκοντα καὶ ὀκτὼ ἐπὶ θάτερα.²

62. Ἐν δὲ τῇ Ἀδραμυττηνῇ ἐστὶ καὶ ἡ Χρῦσα καὶ ἡ Κίλλα· πλησίον οὖν τῆς Θήβης ἔτι ³ νῦν Κίλλα τις τόπος λέγεται,⁴ ἐν ᾧ Κιλλαίου ⁵ Ἀπόλλωνός ἐστιν ἱερόν· παραρρεῖ δ' αὐτῷ ἐξ Ἰδης φερόμενος ὁ Κίλλαιος ⁶ ποταμός· ταῦτα δ' ἐστὶ κατὰ τὴν Ἀντανδρίαν· καὶ τὸ ἐν Λέσβῳ δὲ Κίλλαιον ⁷ ἀπὸ ταύτης τῆς Κίλλης ὠνόμασται· ἔστι δὲ καὶ Κίλλαιον ὄρος μεταξὺ Γαργάρων καὶ Ἀντάνδρου. φησὶ δὲ Δάης ὁ Κολωναεὺς ἐν Κολωναῖς ἰδρυθῆναι πρῶτον ὑπὸ τῶν ἐκ τῆς Ἑλλάδος πλευσάντων Αἰολέων τὸ τοῦ Κιλλαίου Ἀπόλλωνος ἱερόν· καὶ ἐν Χρύσῃ δὲ λέγουσι Κίλλαιον Ἀπόλλωνα ἰδρῦσθαι, ἄδηλον, εἴτε τὸν αὐτὸν τῷ Σμινθεῖ, εἴθ' ἕτερον.

63. Ἡ δὲ Χρῦσα ἐπὶ θαλάττῃ πολίχνιον ἦν ἔχον λιμένα, πλησίον δὲ ὑπέρεκειται ἡ Θήβη· ἐνταῦθα δ' ἦν καὶ τὸ ἱερόν τοῦ Σμινθέως Ἀπόλ-

¹ τό, before πρότερον, Meineke, for τοῖς. Corais omits the τοῖς, and so Leaf.

² Leaf omits the words καὶ ὀκτὼ ἐπὶ θάτερα (see his critical note on text, p. 36).

³ ἔτι, Meineke, for ἔστι.

⁴ Instead of λέγεται, *moz* read λεγόμενος.

⁵ Κιλλαίου, Casaubon and later editors, for Κιλλεός C, Κιλλέους Dhrw, Κιλλεός F, Κιλλέου *moz*.

⁶ Κίλλαιος, Kramer and later editors, for Κιλλεός F, Κίλλεος other MSS.

Mysians and Lydians in earlier times, and later between the Greeks who colonised it from Aeolis and Lesbos. But the greater part of it is now held by the Adramytteni, for here lie both Thebê and Lyrnessus, the latter a natural stronghold; but both places are deserted. From Adramyttium the former is distant sixty stadia and the latter eighty-eight, in opposite directions.¹

62. In the territory of Adramyttium lie also Chrysa and Cilla. At any rate there is still to-day a place near Thebê called Cilla, where is a temple of the Cillaeon Apollo; and the Cillaeus River, which runs from Mt. Ida, flows past it. These places lie near the territory of Antandrus. The Cillaeum in Lesbos is named after this Cilla; and there is also a Mt. Cillaeum between Gargara and Antandrus. Daëd of Colonaë says that the temple of the Cillaeon Apollo was first founded in Colonaë by the Aeolians who sailed from Greece; it is also said that a temple of Cillaeon Apollo was established at Chrysa, though it is not clear whether he is the same as the Sminthian Apollo or distinct from him.

63. Chrysa was a small town on the sea, with a harbour; and near by, above it, lies Thebê. Here too was the temple of the Sminthian Apollo; and

¹ The site of Thebê has been definitely identified with that of the modern Edremid (see Leaf, p. 322). But that of Lyrnessus is uncertain. Leaf (p. 308), regarding the text as corrupt, reads merely "eighty" instead of "eighty-eight," and omits "in opposite directions" (see critical note).

² Κίλλαιον, Tzschucke and later editors, for Κίλλεον; and so in the three subsequent instances the MSS. have ε instead of αι.

λωνος καὶ ἡ Χρυσῆς· ἡρήμωται δὲ νῦν τὸ χωρίον
τελέως· εἰς δὲ τὴν νῦν Χρῦσαν τὴν κατὰ Ἀμαξιτὸν
μεθίδρυται τὸ ἱερόν τῶν Κιλικίων τῶν μὲν εἰς τὴν
Παμφυλίαν ἐκπεσόντων, τῶν δὲ εἰς Ἀμαξιτόν.
οἱ δ' ἀπειρότεροι τῶν παλαιῶν ἱστοριῶν ἐνταῦθα
τὸν Χρῦσιν καὶ τὴν Χρυσήδα γεγονέναι φασὶ
καὶ τὸν Ὅμηρον τούτου τοῦ τόπου μεμνήσθαι.
ἀλλ' οὔτε λιμὴν ἐστὶν ἐνταῦθα, ἐκεῖνος δὲ φησιν·

οἱ δ' ὅτε δὴ λιμένος πολυβενθέος ἐντὸς ἴκοντο,

οὗτ' ἐπὶ θαλάττῃ τὸ ἱερόν ἐστιν, ἐκεῖνος δ' ἐπὶ
θαλάττῃ ποιεῖ τὸ ἱερόν·

ἐκ δὲ Χρυσῆς νηὸς βῆ ποντοπόροιο·

C 613 τὴν μὲν ἔπειτ' ἐπὶ βωμὸν ἄγων πολύμητις
Ὀδυσσεὺς

πατρὶ φίλῳ ἐν χερσὶ τίθει·

οὐδὲ Θήβης πλησίον, ἐκεῖνος δὲ πλησίον· ἐκείθεν
γούν ἀλοῦσαν λέγει τὴν Χρυσήδα. ἀλλ' οὐδὲ
Κίλλα τόπος οὐδεὶς ἐν τῇ Ἀλεξανδρέων χώρα
δείκνυται, οὐδὲ Κιλλαίου Ἀπόλλωνος ἱερόν· ὁ
ποιητὴς δὲ συζεύγνυσιν·

ὃς Χρῦσιν ἀμφιβέβηκας

Κίλλαν τε ζαθέην·

ἐν δὲ τῇ Θήβης πεδίῳ δείκνυται πλησίον· ὃ τε
πλοῦς ἀπὸ μὲν τῆς Κιλικίου Χρύσης ἐπὶ τὸ
ναύσταθμον ἑπτακοσίων πον σταδίων ἐστὶν
ἡμερήσιός πως, ὅσον φαίνεται πλεύσας ὁ Ὀδυσ-
σεύς. ἐκβὰς γὰρ εὐθύς¹ παρίστησι τὴν θυσίαν
τῷ θεῷ καὶ τῆς ἐσπέρας ἐπιλαβούσης μένει
αὐτόθι, πρῶι δὲ ἀποπλεῖ· ἀπὸ δὲ Ἀμαξιτοῦ τὸ

here lived Chryseis. But the place is now utterly deserted; and the temple was transferred to the present Chrysa near Hamaxitus when the Cilicians were driven out, partly to Pamphylia¹ and partly to Hamaxitus. Those who are less acquainted with ancient history say that it was at this Chrysa that Chryses and Chryseis lived, and that Homer mentions this place; but, in the first place, there is no harbour here, and yet Homer says, "And when they had now arrived inside the deep harbour";² and, secondly, the temple is not on the sea, though Homer makes it on the sea, "and out from the seafaring ship stepped Chryseis. Her then did Odysseus of many wiles lead to the altar, and place in the arms of her dear father";³ neither is it near Thebê, though Homer makes it near; at any rate, he speaks of Chryseis as having been taken captive there. Again, neither is there any place called Cilla to be seen in the territory of the Alexandreians, nor any temple of Cillæan Apollo; but the poet couples the two, "who dost stand over Chrysa and sacred Cilla."⁴ But it is to be seen near by in the Plain of Thebê. And the voyage from the Cilician Chrysa to the Naval Station is about seven hundred stadia, approximately a day's voyage, such a distance, obviously, as that sailed by Odysseus;⁵ for immediately upon disembarking he offered the sacrifice to the god, and since evening overtook him he remained on the spot and sailed away the next morning. But the distance from Hamaxitus is scarcely a third of that above

¹ Cf. 14. 4. 1.² *Iliad* 1. 432.³ *Iliad* 1. 438.⁴ *Iliad* 1. 37.⁵ See *Iliad* 1. 430 ff.¹ εὐθὺς πρ., εὐθὺ other MSS.

τρίτον μόλις τοῦ λεχθέντος διαστήματός ἐστιν, ὥστε παρῇν τῷ Ὀδυσσεῖ αὐθημερόν ἀναπλεῖν ἐπὶ τὸ ναύσταθμον τελέσαντι τὴν θυσίαν. ἔστι δὲ καὶ Κίλλου μνῆμα περὶ τὸ ἱερόν τοῦ Κιλλαίου Ἀπόλλωνος, χῶμα μέγα· ἡνίοχον δὲ τοῦτον Πέλοπος φασιν ἡγησάμενον τῶν τόπων, ἀφ' οὗ ἴσως ἡ Κιλικία ἢ ἔμπαλιν.

64. Τὰ οὖν περὶ τοὺς Τεύκρους καὶ τοὺς μύας, ἀφ' ὧν ὁ Σμινθεύς, ἐπειδὴ σμίνθοι¹ οἱ μύες, δεῦρο μετενεκτέον. παραμυθοῦνται δὲ τὴν ἀπὸ μικρῶν ἐπὶ κλησιν τοιούτοις τισί· καὶ γὰρ ἀπὸ τῶν παρνόπων, οὓς οἱ Οἰταῖοι² κόρνοπας λέγουσι, Κορνοπίωνα³ τιμᾶσθαι παρ' ἐκείνοις Ἡρακλέα ἀπαλλαγῆς ἀκρίδων χάριν· Ἰποκτόνον δὲ παρ' Ἐρυθραίοις τοῖς τὸν Μίμαντα⁴ οἰκοῦσιν, ὅτι φθαρτικὸς τῶν ἀμπελοφάγων ἰπῶν· καὶ δὴ παρ' ἐκείνοις μόνοις τῶν Ἐρυθραίων τὸ θηρίον τοῦτο μὴ γίνεσθαι.⁵ Ῥόδιοι δὲ Ἐρυθρίβιον Ἀπόλλωνος ἔχουσιν ἐν τῇ χώρᾳ ἱερόν, τὴν ἐρυσίβην καλοῦντες ἐρυθρίβην· παρ' Αἰολεῦσι δὲ τοῖς ἐν Ἀσίᾳ μείς τις⁶ καλεῖται Πορνοπίων, οὕτω τοὺς πάρνοπας καλούντων Βοιωτῶν, καὶ θυσία συντελεῖται Πορνοπίωνι Ἀπόλλωνι.

65. Μυσία μὲν οὖν ἐστὶν ἡ περὶ τὸ Ἀδραμύντιον, ἣν δέ ποτε ὑπὸ Λυδοῖς, καὶ νῦν Πύλαι Λύδαι καλοῦνται ἐν Ἀδραμυντίῳ, Λυδῶν, ὧς

¹ σμίνθοι, Meineke, for σμίνθοιοι.

² Οἰταῖοι E, Ὅτιοι other MSS.

³ E inserts *τινα* before *τιμᾶσθαι*.

⁴ Μίμαντα, Cornis, for Μελιοῦντα (see 14. l. 33); so the later editors.

⁵ γίνεσθαι, *πιος* and *Corais* and *Meineke*, for *γενέσθαι*.

⁶ *μνείς τις* EF, *μὲς τις* D^{morez}, *μύων τις* *h⁴*, *μιστὶς* O.

mentioned, so that Odysseus could have completed the sacrifice and sailed back to the Naval Station on the same day. There is also a tomb of Cillus in the neighbourhood of the temple of the Cillaean Apollo, a great barrow. He is said to have been the charioteer of Pelops and to have ruled over this region; and perhaps it was after him that Cilicia was named, or vice versa.

64. Now the story of the Teucrians and the mice—whence the epithet “Sminthian,”¹ since “sminthi” means “mice”—must be transferred to this place. And writers excuse this giving of epithets from small creatures by such examples as the following: It is from locusts,² they say, which the Oetaeans call “cornopes,” that Heracles is worshipped among the Oetaeans as “Cornopion,” for ridding them of locusts; and he is worshipped among the Erythraeans who live in Mimas as “Ipoctonus,”³ because he is the destroyer of the vine-eating *ips*;⁴ and in fact, they add, these are the only Erythraeans in whose country this creature is not to be found. And the Rhodians, who call *erysibê*⁵ “erythibê,” have a temple of Apollo “Erythibius” in their country; and among the Aeolians in Asia a certain month is called Pornopion, since the Boeotians so call the locusts, and a sacrifice is offered to Apollo Pornopion.

65. Now the territory round Adramyttium is Mysian, though it was once subject to the Lydians; and to-day there is a gate in Adramyttium which is called the Lydian Gate because, as they say, the

¹ i.e. the “Sminthian” Apollo (*Iliad* 1. 39).

² “Parnopes.”

⁴ A kind of *cynips*.

³ “Ips-slayer.”

⁵ “Mildew.”

φασι, τὴν πόλιν ἐκτικόντων. Μυσίας δὲ Ἀστυρα
τὴν πλησίον κώμην φασίν. ἦν δὲ πολίχνη ποτέ,
ἐν ἣ τὸ τῆς Ἀστυρηνῆς Ἀρτέμιδος ἱερὸν ἐν ἄλσει,
προστατούμενον μετὰ ἀγιστείας ὑπ' Ἀντανδρίων,
οἷς μᾶλλον γειννῶ· διέχει δὲ τῆς παλαιᾶς Χρύσης
εἴκοσι σταδίους, καὶ αὐτῆς ἐν ἄλσει τὸ ἱερὸν
ἐχούσης. αὐτοῦ δὲ καὶ ὁ Ἀχίλλειος χάραξ· ἐν
C 614 δὲ τῇ μεσογαίᾳ ἀπὸ πεντήκοντα σταδίων ἐστὶν
ἡ Θήβη ἔρημος,¹ ἣν φησιν ὁ ποιητὴς ὑπὸ Πλάκῳ
ὕλησση· οὔτε δὲ Πλάκος ἡ Πλάξ ἐκεῖ τι λέγεται,
οὔθ' ὕλη ὑπέρεκειται, καίτοι πρὸς τῇ Ἰδῇ. Ἀστυ-
ρων δ' ἡ Θήβη διέχει εἰς ἑβδομήκοντα σταδίους,
Ἀνδείρων² δὲ ἐξήκοντα. πάντα δὲ ταῦτά ἐστι
τὰ ὀνόματα τόπων ἐρήμων ἢ φαύλως οἰκουμένων
ἢ ποταμῶν χειμάρρων· τεθρύληται δὲ διὰ τὰς
παλαιὰς ἱστορίας.

66. Πόλεις δ' εἰσὶν ἀξιόλογοι Ἀσσος τε καὶ
Ἀδραμύττιον. ἠτύχησε δὲ τὸ Ἀδραμύττιον ἐν
τῷ Μιθριδατικῷ πολέμῳ· τὴν γὰρ βουλὴν ἀπέ-
σφαξε τῶν πολιτῶν Διόδωρος στρατηγός, χαριζό-
μενος τῷ βασιλεῖ, προσποιούμενος δ' ἅμα τῶν τε
ἐξ Ἀκαδημίας φιλοσόφων εἶναι καὶ δίκας λέγειν
καὶ σοφιστεῦειν τὰ ῥητορικά· καὶ δὴ καὶ συνα-
πῆρεν εἰς τὸν Πόντον τῷ βασιλεῖ καταλυθέντος
δὲ τοῦ βασιλέως, ἔτισε δίκας τοῖς ἀδικηθεῖσιν·
ἐγκλημάτων γὰρ ἐπενεχθέντων ἅμα πολλῶν,
ἀπεκαρτέρησεν αἰσχροῦς, οὐ φέρων τὴν δυσφη-
μίαν, ἐν τῇ ἡμετέρᾳ πόλει. ἀνὴρ δὲ Ἀδραμυτ-

¹ ἔρημος, ποζ omit.

² For Ἀνδείρων, DEi read Ἀνδήρων, in D corrected to Ἀνδίων.

city was founded by Lydians. And they say that the neighbouring village Astyra belongs to Mysia. It was once a small town, where, in a sacred precinct, was the temple of the Astyrene Artemis, which was superintended, along with holy rites, by the Antandrians, who were its nearer neighbours. It is twenty stadia distant from the ancient Chrysa, which also had its temple in a sacred precinct. Here too was the Palisade of Achilles. And in the interior, fifty stadia away, is Thebê, now deserted, which the poet speaks of as "beneath wooded Placus";¹ but, in the first place, the name "Placus" or "Plax" is not found there at all, and, secondly, no wooded place lies above it, though it is near Mt. Ida. Thebê is as much as seventy stadia distant from Astyra and sixty from Andeira. But all these are names of deserted or scantily peopled places, or of winter torrents; and they are often mentioned only because of their ancient history.

66. Both Assus and Adramyttium are notable cities. But misfortune befell Adramyttium in the Mithridatic War, for the members of the city council were slaughtered, to please the king, by Diodorus² the general, who pretended at the same time to be a philosopher of the Academy, a dispenser of justice, and a teacher of rhetoric. And indeed he also joined the king on his journey to Pontus; but when the king was overthrown he paid the penalty for his misdeeds; for many charges were brought against him, all at the same time, and, being unable to bear the ignominy, he shamefully starved himself to death, in my own city. Another inhabitant of Adramyttium

¹ *Iliad* 6. 396.

² This Diodorus is otherwise unknown.

τηνὸς ῥήτωρ ἐπιφανὴς γεγένηται Ξενοκλῆς, τοῦ μὲν Ἀσιανοῦ χαρακτήρος, ἀγωνιστῆς δέ, εἴ τις ἄλλος, καὶ εἰρηκῶς ὑπὲρ τῆς Ἀσίας ἐπὶ τῆς συγκλήτου, καθ' ὃν καιρὸν αἰτίαν εἶχε Μιθριδατισμοῦ.

67. Πρὸς δὲ τοῖς Ἀστύροις λίμνη καλεῖται Σάπρα βαραθρώδης, εἰς ῥαχιώδη τῆς θαλάττης αἰγιαλὸν τὸ ἔκρηγμα ἔχουσα. ὑπὸ δὲ τοῖς Ἀνδεύροις ἱερόν ἐστι Μητρὸς θεῶν Ἀνδειρηνῆς ἁγίον καὶ ἄντρον ὑπόνομον μέχρι Παλαιᾶς. ἐστὶ δ' ἡ Παλαιὰ κατοικία τις οὕτω καλουμένη, διέχουσα τῶν Ἀνδεύρων ἑκατὸν καὶ τριάκοντα σταδίους· ἔδειξε δὲ τὴν ὑπόνομον χίμαρος ἐμπεσὼν εἰς τὸ στόμα καὶ ἀνευρεθεὶς τῇ ὑστεραίᾳ κατὰ Ἀνδείρα¹ ὑπὸ τοῦ ποιμένος κατὰ τύχην ἐπὶ θυσίαν ἦκοντος. Ἀταρνεὺς δ' ἐστὶ τὸ τοῦ Ἑρμεῖου² τυραννεῖον, εἰτα Πιτάνη, πόλις Αἰολικῇ, δύο ἔχουσα λιμένας, καὶ ὁ παραρρέων αὐτὴν ποταμὸς Εὐηνος, ἐξ οὗ τὸ ὕδραγωγεῖον πεποιήται τοῖς Ἀδραμυττηνοῖς. ἐκ δὲ τῆς Πιτάνης ἐστὶν Ἀρκεσίλαος, ὁ ἐκ τῆς Ἀκαδημίας, Ζήνωνος τοῦ Κιτιέως συσχολαστῆς παρὰ Πολέμωνι. καλεῖται δὲ καὶ ἐν τῇ Πιτάνῃ τις τόπος ἐπὶ θαλάττῃ Ἀταρνεὺς ὑπὸ τῇ Πιτάνῃ, κατὰ τὴν καλουμένην νῆσον Ἐλεοῦσαν.³ φασὶ δ' ἐν τῇ Πιτάνῃ τὰς πλίνθους ἐπιπολάζειν ἐν τοῖς ὕδασι, καθάπερ καὶ ἐν τῇ Τυρρηνίᾳ γῇ τις⁴ πέπονθε· κουφοτέρα γὰρ ἡ γῇ τοῦ ἐπισόγκου ὕδατός ἐστιν, ὥστ' ἐποχεῖσθαι.

¹ Instead of Ἀνδείρα, ODh read Ἀνδῖρα.

² Ἑρμεῖον F, Ἑρμῖου other MSS.

³ Ἐλεοῦσαν, Palmer, for ἔχουσαν; so later editors, except Meineke and Leaf, who read Ἐλαιοῦσαν.

was the famous orator Xenocles,¹ who belonged to the Asiatic school and was as able a debater as ever lived, having even made a speech on behalf of Asia before the Senate,² at the time when Asia was accused of Mithridatism.

67. Near Astyra is an abysmal lake called Sapra, which has an outbreak into a reefy seashore. Below Andeira is a temple sacred to the Andeirene Mother of the gods, and also a cave that runs underground as far as Palaea. Palaea is a settlement so named,³ at a distance of one hundred and thirty stadia from Andeira. The underground passage became known through the fact that a goat fell into the mouth of it and was found on the following day near Andeira by a shepherd who happened to have come to make sacrifice. Atarneus is the abode of the tyrant Hermeias; and then one comes to Pitanê, an Aeolic city, which has two harbours, and the Evenus River, which flows past it, whence the aqueduct has been built by the Adramytteni. From Pitanê came Arcesilaüs, of the Academy, a fellow-student with Zeno of Citium under Polemon. In Pitanê there is also a place on the sea called "Atarneus below Pitanê," opposite the island called Eleussa. It is said that in Pitanê bricks float on water, as is also the case with a certain earth⁴ in Tyrrhenia, for the earth is lighter than an equal bulk of water, so that it floats. And

¹ This Xenocles is otherwise unknown except for a reference to him by Cicero (*Brutus* 91).

² The Roman Senate.

i.e. "Old Settlement."

⁴ "Rotten-stone."

⁴ γῆ τις, Corais, for νησίς; so Leaf.

C 615 ἐν Ἰβηρίᾳ δέ φησιν ἰδεῖν Ποσειδώνιος ἕκ τινος
 γῆς ἀργιλώδους, ἥ τὰ ἀργυρώματα ἐκμάττεται,
 πλίνθους πηγνυμένας καὶ ἐπιπλεούσας. μετὰ δὲ
 τὴν Πιτάνην ὁ Κάϊκος εἰς τὸν Ἑλαίτην καλούμενον
 κόλπον ἐν τριάκοντα σταδίοις ἐκδίδωσιν. ἐν δὲ
 τῷ πέραν τοῦ Καΐκου, δώδεκα διέχουσα τοῦ
 ποταμοῦ σταδίους Ἑλαία πόλις Αἰολικὴ καὶ
 αὕτη Περγαμηνῶν ἐπίνειον, ἑκατὸν καὶ εἴκοσι
 σταδίους διέχουσα τοῦ Περγάμου.

68. Εἴτ' ἐν ἑκατὸν σταδίοις ἡ Κάνη, τὸ ἀνταῖρον
 ἀκρωτήριον τῷ Λεκτῷ καὶ ποιοῦν τὸν Ἀδραμυτ-
 τηνὸν κόλπον, οὗ μέρος καὶ ὁ Ἑλαϊτικὸς ἐστὶ.
 Κάναι δὲ πολίχνην Δοκρῶν τῶν ἐκ Κύνου κατὰ
 τὰ ἄκρα τῆς Λέσβου τὰ νοτιώτατα κείμενον ἐν
 τῇ Καναίᾳ· αὕτη δὲ μέχρι τῶν Ἀργινουσῶν
 διήκει καὶ τῆς ὑπερκειμένης ἄκρας, ἣν Αἰγά¹ τινες
 ὀνομάζουσιν ὁμωνύμως τῷ ζῳῷ· δεῖ δὲ μακρῶς
 τὴν δευτέραν συλλαβὴν ἐκφέρειν Αἰγάν,² ὥς
 Ἀκτὰν καὶ Ἀρχάν· οὕτω γὰρ καὶ τὸ ὄρος ὅλον
 ὠνομάζετο, ὃ νῦν Κάνην καὶ Κάνας λέγουσι.
 κύκλῳ δὲ περὶ τὸ ὄρος πρὸς νότον μὲν καὶ δύσιν
 ἢ θάλαττα, πρὸς ἑὼ δὲ τὸ Καΐκου πεδῖον ὑπό-
 κειται, πρὸς ἄρκτον δὲ ἡ Ἑλαίτις· αὐτὸ δὲ καθ'
 αὐτὸ ἰκανῶς συνέσταλται, προσνεύει δὲ ἐπὶ τὸ
 Αἰγαῖον πέλαγος, ὅθεν αὐτῷ καὶ τοῦνομα· ³ ὅστε-

¹ Instead of Αἶγα, D reads Αἰγᾶ, hoc Αἶγαν, Epit. Αἶγα, Meineke Αἰγάν.

² Αἰγάν· Ez; so Meineke and Leaf.

³ Leaf brackets the words ὅστερον . . . Κάναι.

¹ i.e. Αἶξ, "goat."

Poseidonius says that in Iberia he saw bricks moulded from a clay-like earth, with which silver is cleaned, and that they floated on water. After Pitane one comes to the Caïcus River, which empties at a distance of thirty stadia into the Elaïtic Gulf, as it is called. On the far side of the Caïcus, twelve stadia distant from the river, is Elaea, an Aeolic city, which also is a seaport of the Pergamenians, being one hundred and twenty stadia distant from Pergamum.

68. Then, at a distance of a hundred stadia, one comes to Cané, the promontory which rises opposite Lectum and forms the Adramyttene Gulf, of which the Elaïtic Gulf is a part. Canae is a small town of Locrians from Cynus, and lies in the Canaeon territory opposite the southernmost ends of Lesbos. This territory extends as far as the Arginussae Islands and the promontory above them, which some call Aega, making it the same as the word for the animal;¹ but the second syllable should be pronounced long, that is, "Aegā," like Actā and Archā, for Aega used to be the name of the whole of the mountain which is now called Cané or Canae. The mountain is surrounded on the south and west by the sea, and on the east by the plain of the Caïcus, which lies below it, and on the north by the territory of Elaea. This mountain forms a fairly compact mass off to itself, though it slopes towards the Aegean Sea, whence it got its name.² Later

² It is not clear in the Greek whether Strabo says that the Aegean Sea got its name from Aega or vice versa. Elsewhere (8. 7. 4) he speaks of "Aegae in Boeotia, from which it is probable that the Aegean Sea got its name."

ρον δὲ αὐτὸ τὸ ἀκρωτήριον Αἰγὰ¹ κεκληῖσθαι,²
ὥς Σαπφώ φησιν,³ τὸ δὲ λοιπὸν Κάνη καὶ
Κάναι.

69. Μεταξὺ δὲ Ἑλαίας τε καὶ Πιτάνης καὶ
Ἀταρνέως καὶ Περγάμου Τευθρανία ἐστί, διέ-
χουσα οὐδεμιᾶς αὐτῶν ὑπὲρ ἑβδομήκοντα σταδίου
ἐντὸς τοῦ Καΐκου, καὶ ὁ Τεύθρας Κιλικῶν καὶ
Μυσῶν ἱστόρηται βασιλεὺς. Εὐριπίδης δ' ὑπὸ
Ἀλέου⁴ φησί, τοῦ τῆς Αὔγης πατρός, εἰς λάρνακα
τὴν Αὔγην κατατεθεῖσαν ἅμα τῷ παιδί Τηλέφῳ
καταποντωθῆναι, φωράσαντος τὴν ἐξ Ἡρακλέους
φθοράν. Ἀθηναῖς δὲ προνοίᾳ τὴν λάρνακα περαιω-
θεῖσαν ἐκπεσεῖν εἰς τὸ στόμα τοῦ Καΐκου, τὸν δὲ
Τεύθραντα, ἀναλαβόντα τὰ σώματα, τῇ μὲν ὡς
γαμετῇ χρήσασθαι, τῷ δ' ὡς ἑαυτοῦ παιδί. τοῦτο
μὲν οὖν μῦθος, ἄλλην δὲ τινα δεῖ γεγονέναι συντυ-
χίαν, δι' ἣν ἡ τοῦ Ἀρκάδος θυγάτηρ τῷ Μυσῶν
βασιλεῖ συνηλθε καὶ ὁ ἐξ αὐτῆς διεδέξατο τὴν
ἐκείνου βασιλείαν. πεπίστευται δ' οὖν, ὅτι καὶ
ὁ Τεύθρας καὶ ὁ Τήλεφος ἐβασίλευσαν τῆς χώρας
τῆς περὶ τὴν Τευθρανίαν καὶ τὸν Κάϊκον, ὁ δὲ
ποιητῆς ἐπὶ τοσοῦτον μέμνηται μόνον τῆς ἱστορίας
ταύτης.

ἀλλ' οἶον τὸν Τηλεφίδην κατενῆρατο χαλκῷ
ἥρῳ Εὐρύπυλον, πολλοὶ δ' ἀμφ' αὐτὸν ἐταῖροι
Κήτειοι κτείνοντο γυναιῶν εἵνεκα δώρων.

C 616 αἰνιγμα τιθεὶς ἡμῖν μᾶλλον ἢ λέγων τι σαφές.

¹ Αἰγά, Meineke, for Αἰγα DE, Αἰγᾶ other MSS.

² For κεκληῖσθαι Müller-Dübner write ἐκλήθη.

³ φησιν, after Σαπφώ, *mox* insert; but Meineke, following conj. of Kramer, omits ὥς Σαπφώ.

the promontory itself was called Aega, as in Sappho,¹ but the rest was called Canê or Canae.

69. Between Blaea, Pitanê, Atarneus, and Pergamum lies Teuthrania, which is at no greater distance than seventy stadia from any of them and is this side the Caïcus River; and the story told is that Teuthras was king of the Cilicians and Mysians. Euripides² says that Augê, with her child Telephus, was put by Aleus, her father, into a chest and submerged in the sea when he had detected her ruin by Heracles, but that by the providence of Athena the chest was carried across the sea and cast ashore at the mouth of the Caïcus, and that Teuthras rescued the prisoners, and treated the mother as his wife and the child as his own son.³ Now this is the myth, but there must have been some other issue of fortune through which the daughter of the Arcadian consorted with the king of the Mysians and her son succeeded to his kingdom. It is believed, at any rate, that both Teuthras and Telephus reigned as kings over the country round Teuthrania and the Caïcus, though Homer goes only so far as to mention the story thus: "But, what a man was the son of Telephus, the hero Eurypylus, whom he slew with the bronze; and round him were slain many comrades, Ceteians, on account of a woman's gifts."⁴ The poet thus sets before us a puzzle instead of making a clear statement; for we neither know whom we should under-

¹ A fragment otherwise unknown (Bergk *Frag.* 131).

² *Frag.* 696 (Nauck). ³ Cf. 12.8.2, 4. ⁴ *Odyssey* 11.521.

⁴ Ἀλέου, Xylander, for Ἀλάνου F, Ἀλαίου other MSS.; so the later editors.

οὔτε γὰρ τοὺς Κητείους ἴσμεν, οὔστινας δέξασθαι δεῖ, οὔτε τὸ γυναιῶν εἵνεκα δώρων· ἀλλὰ καὶ οἱ γραμματικοὶ μυθάρια παραβάλλοντες εὐρεσιλογοῦσι μᾶλλον ἢ λύουσι τὰ ζητούμενα.

70. Ἐάσθω δὴ ταῦτα, ἐκεῖνο δ', ὅπερ ἐστὶ μᾶλλον ἐν φανερῷ, λαβόντες λέγωμεν, ὅτι ἐν τοῖς περὶ τὸν Κάϊκον τόποις φαίνεται βεβασιλευκῶς καθ' Ὁμηρον ὁ Εὐρύπυλος, ὥστ' ἴσως καὶ τῶν Κιλικίων τι μέρος ἦν ὑπ' αὐτῷ, καὶ οὐ δύο δυναστεῖαι μόνον, ἀλλὰ καὶ τρεῖς ὑπήρξαν ἐν αὐτοῖς. τῷ δὲ λόγῳ τούτῳ συνηγορεῖ τὸ ἐν τῇ Ἐλαίτιδι χειμαρρῶδες ποτάμιον δείκνυσθαι Κήτειον· ἐμπίπτει δ' οὗτος εἰς ἄλλον ὅμοιον, εἴτ' ἄλλον, καταστρέφουσι δὲ εἰς τὸν Κάϊκον· ὁ δὲ Κάϊκος οὐκ ἀπὸ τῆς Ἰδης ρεῖ, καθάπερ εἴρηκε Βακχυλίδης, οὐδ' ὀρθῶς¹ Εὐριπίδης τὸν Μαρσύαν φησὶ

τὰς διωνομασμένας
ναίειν Κελαινὰς ἐσχάτοις Ἰδης τόποις·

πολὺ γὰρ τῆς Ἰδης ἄπωθεν αἱ Κελαιναί, πολὺ δὲ καὶ αἱ τοῦ Κάϊκου πηγαί· δείκνυνται γὰρ ἐν πεδίῳ. Τήμνον² δ' ἐστὶν ὄρος, ὃ διορίζει τοῦτό τε καὶ τὸ καλούμενον Ἀπίας πεδίον, ὃ ὑπέρεκειται ἐν τῇ μεσογαίᾳ τοῦ Θήβης πεδίου· ρεῖ δ' ἐκ τοῦ Τήμνου³ ποταμὸς Μύσιος, ἐμβάλλων εἰς τὸν Κάϊκον ὑπὸ ταῖς πηγαῖς αὐτοῦ, ἀφ' οὗ δέχονται

¹ οὐδ' ὀρθῶς, Jones, for οὐχ ὥς F, οὐθ' other MSS.; οὐτ' ὀρθῶς conj. Meineke; Groskurd conj. οὐτ' ἀληθῶς. Kramer would omit the negative before ὥς.

² Τήμνον, Xylander, for Τήκνον.

³ τοῦ Τήμνου, Xylander, for τοῦ Τήκνου Dindorf, τῶν Τήκνων Orelli.

stand the poet to mean by the "Ceteians" nor what he means by "on account of the gifts of a woman";¹ but the grammarians too throw in petty myths, more to show their inventiveness than to solve questions.

70. However, let us dismiss these; and let us, taking that which is more obvious, say that, according to Homer, Eurypylos clearly reigned in the region of the Caïcus, so that perhaps a part of the Cilicians were subject to him, in which case there were three dynasties among them and not merely two.² This statement is supported by the fact that there is to be seen in the territory of Elaea a torrential stream called the Ceteius; this empties into another like it, and this again into another, and they all end in the Caïcus. But the Caïcus does not flow from Ida, as Bacchylides³ states; neither is Euripides⁴ correct in saying that Marsyas "dwells in widely-famed Celaenae, in the farthest region of Ida"; for Celaenae is very far from Ida, and the sources of the Caïcus are also very far, for they are to be seen in a plain. Temnus is a mountain which forms the boundary between this plain and the Plain of Apia, as it is called, which lies in the interior above the Plain of Thebê. From Temnus flows a river called Mysius, which empties into the Caïcus below its sources; and it was from this fact, as some interpret

¹ On the variant myths of Augê and Telephus see Eustathius (note on *Od.*, l.c.); also Leaf's note and references (p. 340).

² Cf. 13. 1. 7, 67.

³ A fragment otherwise unknown (Bergk 66).

⁴ *Frag.* 1085 (Nauck).

τινες εἰπεῖν Αἰσχύλον κατὰ τὴν εἰσβολὴν τοῦ ἐν Μυρμιδόσι προλόγου·

ἰὼ Κάϊκε Μύσιαί τ' ἐπιρροαί.

ἐγγὺς δὲ τῶν πηγῶν κώμη Γέργιθ¹ ἐστίν, εἰς ἣν μετόκισεν Ἀτταλος τοὺς ἐν τῇ Τρωάδι, τὸ χωρίον ἐξελὼν.

II

1. Ἐπεὶ² δὲ τῇ παραλίᾳ τῇ ἀπὸ Λεκτοῦ μέχρι Κανῶν ἀντιπαρατέταται νῆσος ἡ Λέσβος, λόγου ἀξία πλείστου (περίκειται δὲ αὐτῇ καὶ νησία, τὰ μὲν ἔξωθεν, τὰ δὲ καὶ ἐν τῷ³ μεταξὺ αὐτῆς τε καὶ τῆς ἠπείρου), καιρὸς ἤδη περὶ τούτων εἰπεῖν· καὶ γὰρ ταῦτά ἐστιν Αἰολικά, σχεδὸν δέ τι καὶ μητρόπολις ἡ Λέσβος ὑπάρχει τῶν Αἰολικῶν πόλεων. ἀρκτέον δ' ἀφ' ὧν περ καὶ τὴν παραλίαν ἐπήλθομεν τὴν κατ' αὐτήν.

2. Ἀπὸ Λεκτοῦ τοίνυν ἐπὶ Ἀσσον πλέουσιν ἀρχὴ τῆς Λεσβίας ἐστὶ κατὰ Σίγριον τὸ πρὸς ἄρκτον αὐτῆς ἄκρον. ἐνταῦθα δέ που καὶ Μήθυμνα πόλις Λεσβίων ἐστίν ἀπὸ ἐξήκοντα σταδίων τῆς ἐκ Πολυμηδίου πρὸς τὴν Ἀσσον παραλίας. οὔσης δὲ τῆς περιμέτρου σταδίων χιλίων ἑκατόν, ἣν ἡ σύμπασα ἐκπληροῖ νῆσος, τὰ καθέκαστα οὕτως ἔχει· ἀπὸ Μηθύμνης εἰς Μαλίαν τὸ νοτιώτατον ἄκρον ἐν δεξιᾷ ἔχουσι

¹ Γ'ργιθα, Corais, for Γέργιθα.

² ἐπεὶ οὐ; ἐπὶ other MSS.

³ τῷ, Corais, for τῇ.

the passage, that Aeschylus¹ said at the opening of the prologue to the *Myrmidons*, "Oh! thou Caicus and ye Mysian in-flows." Near the sources is a village called Gergitha, to which Attalus transferred the Gergithians of the Troad when he had destroyed their place.

II

1. Since Lesbos, an island worthy of a full account, lies alongside and opposite the coast which extends from Lectum to Canae, and also has small islands lying round it, some outside it and some between it and the mainland, it is now time to describe these; for these are Aeolian, and I might almost say that Lesbos is the metropolis of the Aeolian cities. But I must begin at the point whence I began to traverse the coast that lies opposite the island.

2. Now as one sails from Lectum to Assus, the Lesbian country begins at Sigrium, its promontory on the north.² In this general neighbourhood is also Methymna, a city of the Lesbians, sixty stadia distant from the coast that stretches from Polymedium to Assus. But while the perimeter which is filled out by the island as a whole is eleven hundred stadia, the several distances are as follows: From Methymna to Malia, the southernmost³ promontory to one keeping the island on the right, I

¹ *Frag.* 143 (Nauck).

² But Sigrium was the westernmost promontory of the island.

³ More accurately, "southwesternmost."

C 617 τὴν νῆσον, καθ' ἧς αἱ Κάναι μάλιστα ἀντίκεινται τῇ νήσῳ καὶ συναπαρτίζουσι, στάδιοι εἰσι τριακόσιοι τετταράκοντα· ἐντεῦθεν δ' ἐπὶ Σίγγριον, ὅπερ ἐστὶ τῆς νήσου τὸ μῆκος, πεντακόσιοι ἐξήκοντα· εἴτ' ἐπὶ τὴν Μήθυμναν¹ διακόσιοι δέκα. Μιτυλήνη δὲ κεῖται μεταξύ Μηθύμνης καὶ τῆς Μαλίας ἡ μεγίστη πόλις, διέχουσα τῆς Μαλίας ἐβδομήκοντα σταδίους, τῶν δὲ Κανῶν ἑκατὸν εἴκοσιν, ὅσους καὶ τῶν Ἀργινουσῶν, αἱ τρεῖς μὲν εἰσιν οὐ μεγάλαι νῆσοι, πλησιάζουσι δὲ τῇ ἡπείρῳ, παρακείμεναι² ταῖς Κάναις. ἐν δὲ τῷ μεταξύ Μιτυλήνης καὶ τῆς Μηθύμνης κατὰ κώμην τῆς Μηθυμναίας, καλουμένην Λῆγειρον, στενωπάτῃ ἐστὶν ἡ νήσος, ὑπέρβασιν ἔχουσα εἰς τὸν Πυρραίων Εὐριπον σταδίων εἴκοσιν. ἴδρυται δ' ἡ Πύρρα ἐν τῷ ἐσπερίῳ πλευρῷ τῆς Λέσβου, διέχουσα τῆς Μαλίας ἑκατόν. ἔχει δ' ἡ Μιτυλήνη λιμένας δύο, ὧν ὁ νότιος κλειστός τριηρικὸς³ ναυσὶ πεντήκοντα, ὁ δὲ βόρειος μέγας καὶ βαθύς, χώματι σκεπαζόμενος· πρόκειται δ' ἀμφοῖν νησίον, μέρος τῆς πόλεως ἔχον αὐτόθι συνοικούμενον· κατεσκευάσται δὲ τοῖς πᾶσι καλῶς.

3. Ἄνδρας δ' ἔσχεν ἐνδόξους, τὸ παλαιὸν μὲν Πιττακόν, ἓνα τῶν ἐπτὰ σοφῶν, καὶ τὸν ποιητὴν Ἀλκαῖον καὶ τὸν ἀδελφὸν Ἀντιμενίδαν, ὃν φησιν Ἀλκαῖος Βαβυλωνίοις συμμαχοῦντα τελέσαι

¹ Μήθυμναν, Kramer, for Μηθυμναίαν.

² δέ, after παρακείμεναι, omitted by *moz* and ejected by Corais and later editors.

³ τριηρικὸς, Meineke, for τριήρικαι. Wesseling conj.

mean at the point where Canae lies most directly opposite the island and precisely corresponds with it, the distance is three hundred and forty stadia; thence to Sigrium, which is the length of the island, five hundred and sixty; and then to Methymna, two hundred and ten.¹ Mitylene, the largest city, lies between Methymna and Malia, being seventy stadia distant from Malia, one hundred and twenty from Canae, and the same distance from the Arginussae, which are three small islands lying near the mainland alongside Canae. In the interval between Mitylene and Methymna, in the neighbourhood of a village called Aegeirus in the Methymnaean territory, the island is narrowest, with a passage of only twenty stadia over to the Euripus of the Pyrrhaeans. Pyrrha is situated on the western side of Lesbos at a distance of one hundred stadia from Malia. Mitylene has two harbours, of which the southern can be closed and holds only fifty triremes, but the northern is large and deep, and is sheltered by a mole. Off both lies a small island, which contains a part of the city that is settled there. And the city is well equipped with everything.

3. Mitylene has produced famous men: in early times, Pittacus, one of the Seven Wise Men; and the poet Alcaeus, and his brother Antimenidas, who, according to Alcaeus, won a great struggle when fighting on the side of the Babylonians, and rescued

¹ The total, 1110, being ten more than the round number given above.

τριηρικὸς καὶ ναύσταθμον, the complete phrase found in 14. 2. 15.

μέγαν ἄθλον καὶ ἐκ πόνων αὐτοὺς ῥύσασθαι,
κτείναντα

ἄνδρα μαχαίταν, βασιλῆιον¹
παλαστὰν² (ὥς φησι) ἀπολείποντα³ μόνον
μίαν⁴
παχέων ἀπὸ πέμπων.⁵

συνήκμασε δὲ τούτοις καὶ ἡ Σαπφώ, θαυμαστόν
τι χρῆμα· οὐ γὰρ ἴσμεν ἐν τῷ τοσούτῳ χρόνῳ τῷ
μνημονευομένῳ φανείσαν τινα γυναῖκα ἐνάμιλλον,
οὐδὲ κατὰ μικρόν, ἐκείνη ποιήσεως χάριν. ἐτυ-
ραννήθη δὲ ἡ πόλις κατὰ τοὺς χρόνους τούτους
ὑπὸ πλειόνων διὰ τὰς διχαστασίας, καὶ τὰ
στασιωτικὰ καλούμενα τοῦ Ἀλκαίου ποιήματα
περὶ τούτων ἐστίν· ἐν δὲ τοῖς τυράννοις καὶ ὁ
Πιττακὸς ἐγένετο. Ἀλκαῖος μὲν οὖν ὁμοίως
ἐλοιδορεῖτο καὶ τούτῳ καὶ τοῖς ἄλλοις, Μυρσίλῳ
καὶ Μελάγχρῳ⁶ καὶ τοῖς Κλεανακτίδαις καὶ
ἄλλοις τισίν, οὐδ' αὐτὸς καθαρεύων τῶν τοιούτων
νεωτερισμῶν. Πιττακὸς δ' εἰς μὲν τὴν τῶν δυνα-
στεϊῶν κατάλυσιν ἐχρήσατο τῇ μοναρχίᾳ καὶ
αὐτός, καταλύσας δὲ ἀπέδωκε τὴν αὐτονομίαν τῇ
πόλει. ὕστερον δ' ἐγένετο χρόνοις πολλοῖς
Διοφάνης ὁ ῥήτωρ· καθ' ἡμᾶς δὲ Ποτάμων καὶ
Λεσβοκλῆς καὶ Κριναγόρας καὶ ὁ συγγραφεὺς
Θεοφάνης. οὗτος δὲ καὶ πολιτικὸς ἀνὴρ ὑπῆρξε
καὶ Πομπηίῳ τῷ Μάγνῳ κατέστη φίλος, μάλιστα
διὰ τὴν ἀρετὴν αὐτήν, καὶ πάσας συγκατώρθωσεν

¹ βασιλῆιον, O. Müller (quoted by Bergk, who prefers βασιληῖον), for βασιλῆων.

² παλαστὰν DFH and Kramer (παλάσταν Meineke); παλαί-
σταν other MSS.

them from their toils by killing "a warrior, the royal wrestler" (as he says), "who was but one short of five cubits in height."¹ And along with these flourished also Sappho, a marvellous woman; for in all the time of which we have record I do not know of the appearance of any woman who could rival Sappho, even in a slight degree, in the matter of poetry. The city was in those times ruled over by several tyrants because of the dissensions among the inhabitants; and these dissensions are the subject of the Stasiotic² poems, as they are called, of Alcaeus. And also Pittacus³ was one of the tyrants. Now Alcaeus would rail alike at both Pittacus and the rest, Myrsilus and Melanchrus and the Cleanaetidae and certain others, though even he himself was not innocent of revolutionary attempts; but even Pittacus himself used monarchy for the overthrow of the oligarchs, and then, after overthrowing them, restored to the city its independence. Diophanes the rhetorician was born much later; but Potamon, Lesbocles, Crinagoras, and Theophanes the historian in my time. Theophanes was also a statesman; and he became a friend to Pompey the Great, mostly through his very ability, and helped him to succeed in all his achievements;

¹ *Frag.* 33 (Bergk).

² Seditious.

³ Reigned 589-579 B.C.

³ ἀπολείποντα, Müller, for ἀπολιπόντα; so Kramer and Meineke.

⁴ μίαν, Müller, for ἀνίαν; so Kramer and Meineke.

⁵ ἀπὸ πέμπτων (ἀποπέμπτων F), Müller, for ἀποπέμπτων; so Kramer and Meineke.

⁶ Μελάγχρου, Groskurd and other editors, for Μελάνδρου F, Μεγαλογύρου other MSS.

C 618 αὐτῷ τὰς πράξεις· ἀφ' ὧν τὴν τε πατρίδα ἐκόσμησε τὰ μὲν δι' ἐκείνου, τὰ δὲ δι' ἑαυτοῦ, καὶ ἑαυτὸν πάντων τῶν Ἑλλήνων ἐπιφανέστατον ἀνέδειξεν· υἱὸν τε ἀπέλιπε Μάρκον Πομπήιον, ὃν τῆς Ἀσίας ἐπίτροπον κατέστησέ ποτε Καῖσαρ ὁ Σεβαστός, καὶ νῦν ἐν τοῖς πρώτοις ἐξετάζεται τῶν Τιβερίου φίλων. Ἀθηναῖοι δ' ἐκινδύνευσαν μὲν ἀνηκέστῳ ψόγῳ περιπεσεῖν, ψηφισάμενοι Μιτυληναίους ἡβηδὸν ἀποσφαγῆναι, μετέγνωσαν δέ, καὶ ἔφθη μὲν θᾶπτον ἡμέρα τὸ ψήφισμα ἀφυγμένον ὥς τοὺς στρατηγούς πρὶν ἢ πράξαι τὸ προσταχθέν.

4. Ἡ δὲ Πύρρα κατέστραπται, τὸ δὲ προάσκειον οἰκεῖται καὶ ἔχει λιμένα, ὅθεν εἰς Μιτυλήνην ὑπέρβασις σταδίων ὀγδοήκοντα. εἴτ' Ἐρεσσός ἐστι μετὰ τὴν Πύρραν Ἰδρυται δ' ἐπὶ λόφου καθήκει τε ἐπὶ θάλατταν· εἴτ' ἐπὶ τὸ Σίγριον ἐντεῦθεν στάδιοι εἰκοσιοκτώ· ἐξ Ἐρεσσοῦ δ' ἦσαν Θεόφραστός τε καὶ Φανίας, οἱ ἐκ τῶν περιπάτων φιλόσοφοι, Ἀριστοτέλους γνώριμοι. Τύρταμος δ' ἐκαλεῖτο ἔμπροσθεν ὁ Θεόφραστος, μετωνόμασε δ' αὐτὸν Ἀριστοτέλης Θεόφραστον, ἅμα μὲν φεύγων τὴν τοῦ προτέρου ὀνόματος κακοφωνίαν, ἅμα δὲ τὸν τῆς φράσεως αὐτοῦ ζῆλον ἐπισημαινόμενος· ἅπαντας μὲν γὰρ λογίους ἐποίησε τοὺς μαθητὰς Ἀριστοτέλης, λογιώτατον δὲ Θεόφραστον. Ἀντισσα δ' ἐφεξῆς ἐστὶ τῷ Σιγρίῳ πόλις, ἔχουσα λιμένα· ἔπειτα Μήθυμνα, ἐντεῦθεν δ' ἦν Ἀρίων ὁ ἐπὶ τῷ δελφῖνι μυθευόμενος ὑπὸ τῶν περὶ Ἡρόδοτον εἰς Ταΐναρον σωθῆναι, καταποντωθεὶς ὑπὸ τῶν ληστῶν· οὗτος μὲν οὖν κιθαρωδός. καὶ Τέρπανδρον δὲ τῆς αὐτῆς

whence he not only adorned his native land, partly through Pompey and partly through himself, but also rendered himself the most illustrious of all the Greeks. He left a son, Marcus Pompey, whom Augustus Caesar once set up as Procurator of Asia, and who is now counted among the first of the friends of Tiberius. The Athenians were in danger of suffering an irreparable disgrace when they voted that all Mitylenaeans from youth upwards should be slain, but they changed their minds and their counter-decree reached the generals only one day before the order was to be executed.

4. Pyrrha has been rased to the ground, but its suburb is inhabited and has a harbour, whence there is a passage of eighty stadia over hills to Mitylene. Then, after Pyrrha, one comes to Eressus; it is situated on a hill and extends down to the sea. Then to Sigrium, twenty-eight stadia from Eressus. Both Theophrastus and Phanias, the peripatetic philosophers, disciples of Aristotle, were from Eressus. Theophrastus was at first called Tyrtamus, but Aristotle changed his name to Theophrastus, at the same time avoiding the cacophony of his former name and signifying the fervour of his speech; for Aristotle made all his pupils eloquent, but Theophrastus most eloquent of all. Antissa, a city with a harbour, comes next in order after Sigrium. And then Methymna, whence came Arion, who, according to a myth told by Herodotus and his followers, safely escaped on a dolphin to Taenarum after being thrown into the sea by the pirates. Now Arion played, and sang to, the cithara; and Terpander,

μουσικῆς τεχνίτην γεγονέναι φασὶ καὶ τῆς αὐτῆς νήσου, τὸν πρῶτον ἀντὶ τῆς τετραχόρδου λύρας ἑπταχόρδῳ χρησάμενον· καθάπερ καὶ ἐν τοῖς ἀναφερομένοις ἔπεσιν εἰς αὐτὸν λέγεται·

σοὶ δ' ἡμεῖς τετράγηρυν ἀποστρέψαντες αἰοιδῆν,
ἑπτατόνῳ φόρμιγγι νέους κελαδήσομεν ὕμνους.

καὶ Ἑλλάνικος δὲ Λέσβιος συγγραφεὺς καὶ Καλλίας ὁ τὴν Σαπφῶ καὶ τὸν Ἀλκαῖον ἐξηγησάμενος.

5. Κατὰ δὲ τὸν πορθμὸν τὸν μεταξὺ τῆς Ἀσίας καὶ τῆς Λέσβου νησία ἐστὶ περὶ εἴκοσιν, ὡς δὲ Τιμοσθένης φησί, τετταράκοντα· καλοῦνται δ' Ἑκατόννησοι συνθέτως, ὡς Πελοπόννησος, κατὰ ἔθος τι τοῦ Ν γράμματος πλεονάζοντος ἐν τοῖς τοιούτοις, ὡς Μυόννησος καὶ Προκόννησος λέγεται καὶ Ἀλόννησος, ὥστε Ἑκατόννησοί εἰσιν, οἷον Ἀπολλωνόννησοι, Ἐκατος γὰρ ὁ Ἀπόλλων· παρὰ πᾶσαν γὰρ δὴ τὴν παραλίαν ταύτην ὁ Ἀπόλλων ἐκτετίμηται μέχρι Τενέδου, Σμινθεὺς ἢ Κιλλαῖος καλούμενος ἢ Γρυνεὺς ἢ τινα ἄλλην ἐπωνυμίαν ἔχων. πλησίον δὲ τούτων ἐστὶ καὶ ἡ Πορδοσελήνη,¹ πόλιν ὁμώνυμον ἔχουσα C 619 ἐν αὐτῇ· καὶ πρὸ τῆς πόλεως ταύτης ἄλλη νήσος² μείζων αὐτῆς ὁμώνυμος, ἔρημος, ἱερὸν ἅγιον ἔχουσα Ἀπόλλωνος.

6. Τὰς δὲ δυσφημίας τῶν ὀνομάτων φεύγοντές³ τινες ἐνταῦθα μὲν Ποροσελήνην δεῖν λέγειν φασί, τὸ δ' Ἀσπόρδηνον ὄρος τὸ περὶ Πέργαμον, τραχὺ

¹ Instead of Πορδοσελήνη, Dindorf read Παρδοσελήνη.

² πόλις (πόλις F) after νήσος, Jones ejects, following conj. of Kramer and C. Müller.

also, is said to have been an artist in the same music and to have been born in the same island, having been the first person to use the seven-stringed instead of the four-stringed lyre, as we are told in the verses attributed to him: "For thee I, having dismissed four-toned song, shall sing new hymns to the tune of a seven-stringed cithara."¹ Also Hellanicus the historian, and Callias, who interpreted Sappho and Alcaeus, were Lesbians.

5. In the strait between Asia and Lesbos there are about twenty small islands, but according to Timosthenes, forty. They are called Hecatonnesi, a compound name like Peloponnesus, the second letter *n* being customarily redundant in such compounds, as in the names Myonnesus, Proconnesus, and Halonnesus; and consequently we have Hecatonnesi, which means Apollonnesi, for Apollo is called Hecatus; for along the whole of this coast, as far as Tenedos, Apollo is highly honoured, being called Sminthian or Cillaeian or Grynian or by some other appellation. Near these islands is Pordoselenê, which contains a city of the same name, and also, in front of this city, another island, larger and of the same name, which is uninhabited and has a temple sacred to Apollo.

6. Some writers, to avoid the indecency of the names, say that in this place we should read "Pordoselenê," and that we should call Aspendenum, the rocky and barren mountain round Pergamum, "Aspendenum," and the temple of the Mother of the

¹ *Frag.* 5 (Bergk).

² *φεύγοντες*, Corais, for *φυγόντες*; so the later editors.

STRABO

καὶ λυπρὸν οὖν, Ἀσπόρηνον,¹ καὶ τὸ ἱερὸν τὸ
ἐνταῦθα τῆς Μητρὸς τῶν θεῶν Ἀσπορηνῆς.² τί οὖν
φῆσομεν τὴν Πόρδαλιν καὶ τὸν Σαπέρδην καὶ τὸν
Περδίκκαν καὶ τὸ Σιμωνίδου

σὺν πορδακοῖσιν ἐκπεσόντες εἴμασιν³

ἀντὶ τοῦ διαβρόχοις, καὶ ἐν τῇ ἀρχαίᾳ που
κωμωδία

πορδακὸν τὸ χωρίον,

τὸ λίμναζον; διέχει δ' ἡ Λέσβος τὸ ἴσον ἀπὸ
τῆς Τενέδου καὶ Λήμνου καὶ Χίου σχεδὸν τι τῶν
πεντακοσίων ἐνδοτέρω σταδίων.

III

1. Τοιαύτης δὲ τῆς πρὸς τοὺς Τρῶας οἰκειό-
τητος ὑπαρχούσης τοῖς τε Λέλεξι καὶ τοῖς Κίλιξι,
ζητοῦσιν αἰτίαν, δι' ἣν οὐ συγκαταλέγονται καὶ
οὗτοι ἐν τῷ καταλόγῳ. εἰκὸς δὲ διὰ τὴν τῶν
ἡγεμόνων διαφθορὰν καὶ τὴν τῶν πόλεων
ἐκπόρθησιν ὀλίγους ὑπολειφθέντας τοὺς Κίλικας
ὑπὸ τῷ Ἑκτορι τάττεσθαι· ὃ τε γὰρ Ἡετίων
καὶ οἱ παῖδες αὐτοῦ λέγονται πρὸ τοῦ καταλόγου
διαφθαρῆναι·

ἦτοι μὲν πατέρ' ἀμὸν⁴ ἀπέκτανε διὸς Ἀχιλ-
λεὺς,

ἐκ δὲ πόλιν πέρσεν Κιλικῶν,

Θήβην ὑψίπυλον.

¹ Instead of Ἀσπόρηνον, F reads Ἀσπρόκνον, oz Ἀσπόρινον.

² Ἀσπορινῆς oz.

gods there the temple of the "Asporene" mother.¹ What, then, shall we say of Pordalis and Saperdes and Perdiccas, and of the phrase of Simonides, "banished, 'pordacian' clothes and all," instead of "wet" clothes, and, somewhere in the early comedy, "the place is 'pordacian,'" that is, the place that is "marshy"? Lesbos is equidistant from Tenedos and Lemnos and Chios, one might say rather less than five hundred stadia.

III

1. Since the Leleges and the Cilicians were so closely related to the Trojans, people inquire for the reason why they are not included with the Trojans in the *Catalogue*. But it is reasonable to suppose that because of the loss of their leaders and the sacking of their cities the few Cilicians that were left were placed under the command of Hector, for both Eëtion and his sons are said to have been slain before the *Catalogue*:² "Verily my father was slain by the goodly Achilles, who utterly sacked the city of Cilicians, Thebê of the lofty gates.

¹ *i.e.* they avoid "pord," which, as also "perd," is the stem of an indecent Greek word.

² *i.e.* before the marshalling of the troops as described in the *Catalogue*.

³ ἐλμασιν, Tyrwhitt, for ἱμασιν; so the later editors.

⁴ ἄμὸν, Xylander, for ἐμὸν; so the later editors.

οἳ δέ μοι ἑπτὰ κασίγνητοι ἔσαν ἐν μεγαροισιν,
οἳ μὲν πάντες ἰὼ κίου ἡματι Ἄϊδος εἴσω·
πάντας γὰρ κατέπεφνε ποδάρκης διὸς Ἀχιλ-
λεύς.

ὥς δ' αὐτως καὶ οἱ ὑπὸ Μύνητι τοὺς τε ἡγεμόνας
ἀποβεβλήκασι καὶ τὴν πόλιν·

καδ' δὲ Μύνητ' ἔβαλε καὶ Ἐπίστροφον,
πέρσεν δὲ πόλιν θείοιο Μύνητος.

τοὺς δὲ Λέλεγας τοῖς μὲν ἀγῶσι παρόντας ποιεῖ,
ὅταν οὕτω λέγῃ·

πρὸς μὲν ἄλός Κᾶρες καὶ Παῖονες ἀγκυλότοξοι
καὶ Λέλεγες καὶ Καύκωνες·

καὶ πάλιν·

Σάτνιον οὕτασε δουρὶ
Οἰνοπίδην, ὃν ἄρα νύμφη τέκε Νηὶς ἀμύμων
Οἶνοπι βουκολέοντι παρ' ὄχθας Σατνιόεντος.

οὐ γὰρ οὕτως ἐξελελοίπεσαν τελέως, ὥστε μὴ
καὶ καθ' αὐτοὺς ἔχειν τι σύστημα, ἅτε τοῦ
βασιλέως αὐτῶν ἔτι περιόντος,

Ἄλτεω, ὃς Λελέγεσσι φιλοπτολέμοισιν ἀνάσσει,
καὶ τῆς πόλεως οὐ τελέως ἠφανισμένης· ἐπιφέρει
γὰρ

Πήδασον αἰπήεσαν ἔχων ἐπὶ ¹ Σατνιόεντι.

C 620 ἐν μέντοι τῷ καταλόγῳ παραλέλοιπεν αὐτοὺς,
οὐχ ἱκανὸν ἡγούμενος τὸ σύστημα, ὥστ' ἐν
καταλόγῳ τάττεσθαι, ἣ καὶ ² ὑπὸ τῷ Ἑκτορι καὶ
τούτους συγκαταλέγων, οὕτως ὄντας οἰκείους.
ὁ γὰρ Λυκάων φησὶν, ἀδελφὸς ὢν Ἑκτορος·

And the seven brothers of mine in our halls, all these on the same day¹ went inside the home of Hades, for all were slain by swift-footed, goodly Achilles."² And so, in the same way, those subject to Mynes lost both their leaders and their city: "And he laid low Mynes and Epistrophus, and sacked the city of godlike Mynes."³ But he makes the Leleges present at the battles when he says as follows: "Towards the sea are situated the Carians and the Paeonians, with curved bows, and the Leleges and Caucones."⁴ And again, "he pierced with his spear Satnius, son of Oenops, whom a noble Naiad nymph bore to Oenops, as he tended his herds beside the banks of the Satnioeis";⁵ for they had not so completely disappeared that they did not have a separate organisation of their own, since their king still survived, "of Altes, who is lord over the war-loving Leleges,"⁶ and since their city had not been utterly wiped out, for the poet adds, "who holds steep Pedasus on the Satnioeis."⁷ However, the poet has omitted them in the *Catalogue*, not considering their organisation sufficient to have a place in it, or else including them under the command of Hector because they were so closely related;

¹ i.e. with Eëtion.² *Iliad* 6. 414.³ *Iliad* 2. 692, 19. 296.⁴ *Iliad* 10. 428.⁵ *Iliad* 14. 443.⁶ *Iliad* 21. 86.⁷ *Iliad* 21. 87.¹ ἐπὶ, Corais, for ὑπὸ.² καί, before ὑπὸ, omitted by C.

μινυνθάδιον δέ με μήτηρ
 γείνατο Λαοθόη, θυγάτηρ Ἀλταο γέροντος,
 Ἀλτεω, ὃς Λελέγεσσι φιλοπτολέμοισιν ἀνάσσει.

ταῦτα μὲν οὖν τοιαύτην τινα ἔχει τὴν εἰκοτολογίαν.

2. Εἰκοτολογεῖν δ' ἐστί, καὶ εἴ τις τὸν ἀκριβῆ ζητεῖ κατὰ τὸν ποιητὴν ὅρον, μέχρι τίνος οἱ Κίλικες διέτεινον καὶ οἱ Πελασγοὶ καὶ ἔτι οἱ μεταξὺ τούτων Κήτειοι λεγόμενοι οἱ ὑπὸ τῷ Εὐρυπύλῳ. περὶ μὲν οὖν τῶν Κιλικῶν καὶ τῶν ὑπ' Εὐρυπύλῳ τὰ ἐνόντα εἴρηται, καὶ διότι ἐπὶ ¹ τὰ περὶ τὸν Κάϊκον μάλιστα περατοῦνται. τοὺς δὲ Πελασγοὺς εὐλογον τούτοις ἐφεξῆς τιθέναι ἔκ τε τῶν ὑφ' Ὀμήρου λεγομένων καὶ ἐκ τῆς ἄλλης ἱστορίας. ὁ μὲν γὰρ οὕτω φησίν·

Ἰππόθοος δ' ἄγε φύλα Πελασγῶν ἐγγχεσι-
 μῶρων,

τῶν, οὗ Λάρισαν ἐριβώλακα ναιετάασκον
 τῶν ἥρχ' Ἰππόθοός τε Πύλαιός τ' ὄζος Ἀρης,
 νῆε δ' ὡς Λήθιοιο Πελασγοῦ Τευταμίδαο.

ἐξ ὧν πληθὺς τε ἐμφαίνει ἀξιόλογον τὸ τῶν Πελασγῶν (οὐ γὰρ φύλον, ἀλλὰ φύλα ἔφη) καὶ τὴν οἴκησιν ἐν Λαρίσῃ φράζει. πολλαὶ μὲν οὖν αἱ Λάρισαι, δεῖ δὲ τῶν ἐγγύς τινα δέξασθαι, μάλιστα δ' ἂν τὴν περὶ Κύμην ὑπολάβοι τις ὀρθῶς· τριῶν γὰρ οὐσῶν, ἥ μὲν καθ' Ἀμαξιτὸν ἐν ὄψει τελέως ἐστὶ τῷ Ἰλίῳ, καὶ ἐγγὺς σφόδρα ἐν διακοσίοις πον σταδίοις, ὥστ' οὐκ ἂν λέγοιτο

¹ ἐπὶ, Meineke inserts.

for Lycaon, who was a brother of Hector, says, "to a short span of life my mother, daughter of the old man Altes, bore me—Altes who is lord over the war-loving Leleges."¹ Such, then, are the probabilities in this matter.

2. And it is also a matter of reasoning from probabilities if one inquires as to the exact bounds to which the poet means that the Cilicians extended, and the Pelasgians, and also the Ceteians, as they are called, under the command of Eurypylus, who lived between those two peoples. Now as for the Cilicians and the peoples under the command of Eurypylus, all has been said about them that can be said, and that their country is in a general way bounded by the region of the Caicus River. As for the Pelasgians, it is reasonable, both from the words of Homer and from history in general, to place them next in order after these peoples; for Homer says as follows: "And Hippothoüs led the tribes of the Pelasgians that rage with the spear, them that dwelt in fertile Larisa; these were ruled by Hippothoüs and Pylæus, scion of Ares, the two sons of Pelasgian Lethus, son of Teutamus."² By these words he clearly indicates that the number of Pelasgians was considerable, for he says "tribes," not "tribe;" and he also specifies their abode as "in Larisa." Now there are many Larisas, but we must interpret him as meaning one of those that were near; and best of all one might rightly assume the one in the neighbourhood of Cymê; for of the three Larisas the one near Hamaxitus was in plain sight of Ilium and very near it, within a distance of two hundred stadia, and therefore it could not be said with plausibility that

¹ *Iliad* 21. 84.

² *Iliad* 2. 840.

πιθανῶς ὁ Ἰππόθοος πεσεῖν ἐν τῷ ὑπὲρ Πα-
τρόκλου ἀγῶνι

τῇλ' ἀπὸ Λαρίσης,

ταύτης γε, ἀλλὰ μάλλον τῆς περὶ Κύμην· χίλιοι
γάρ που στάδιοι μεταξύ· τρίτη δ' ἐστὶ Λάρισα,
κώμη τῆς Ἐφεσίας ἐν τῷ Καῦστρίῳ πεδίῳ, ἣν
φασι πόλιν ὑπάρχει πρότερον, ἔχουσαν καὶ ἱερὸν
Ἀπόλλωνος Λαρισηνοῦ, πλησιάζουσιν τῷ Ἰμῳ
μᾶλλον ἢ τῇ Ἐφέσῳ· ταύτης γὰρ ἑκατὸν καὶ
ὀγδοῖκοντα διέχει σταδίους, ὥστε ὑπὸ τοῖς
Μήσοις ἂν τις τάττοι ταύτην. Ἐφέσιοι δ'
αὐξηθέντες ὕστερον πολλὴν τῆς τῶν Μηόνων,
οὓς νῦν Λυδοὺς φάμεν, ἀπετέμοντο, ὥστ' οὐδ'
αὕτη ἂν ἢ τῶν Πελασγῶν Λάρισα εἴη, ἀλλ'
ἐκείνη μάλλον. καὶ γὰρ τῆς μὲν ἐν τῇ Καῦστριανῇ
Λαρίσῃ οὐδὲν ἔχομεν τεκμήριον ἰσχυρόν, ὡς ἦν
ἤδη τότε· οὐδὲ γὰρ τῆς Ἐφέσου· τῆς δὲ περὶ τὴν
C 621 Κύμην μαρτύριόν ἐστι πᾶσα ἡ Αἰολικὴ ἱστορία,
μικρὸν ὕστερον τῶν Τρωικῶν γενομένη.

3. Φασὶ γὰρ τοὺς ἐκ τοῦ Φρικίου¹ τοῦ ὑπὲρ
Θερμοπυλῶν Δοκρικοῦ ὄρους ὀρμηθέντας κατὰραι
μὲν εἰς τὸν τόπον, ὅπου νῦν ἡ Κύμη ἐστὶ,
καταλαβόντας δὲ τοὺς Πελασγοὺς κεκακωμένους
ὑπὸ τοῦ Τρωικοῦ πολέμου, κατέχοντας δ' ὅμως
ἔτι τὴν Λάρισαν διέχουσιν τῆς Κύμης ὅσον
ἑβδομήκοντα σταδίους, ἐπιτειχίσαι αὐτοῖς τὸ νῦν
ἔτι λεγόμενον Νέον τεῖχος ἀπὸ τριάκοντα σταδίων
τῆς Λαρίσης, ἐλόντας² δὲ κτίσαι τὴν Κύμην καὶ
τοὺς περιγενομένους ἀνθρώπους ἐκεῖσε ἀνοικίσαι·

¹ ἐκ τοῦ Φρικίου, Tyrwhitt, for ἐν τῷ Φρικίῳ; so the later editors.

Hippochoüs fell in the fight over Patroclus "far away from" this "Larisa," but rather from the Larisa near Cymê, for the distance between the two is about a thousand stadia. The third Larisa is a village in the territory of Ephesus in the Cayster Plain; it is said to have been a city in earlier times, containing a temple of Larisæan Apollo and being situated closer to Mt. Tmolus than to Ephesus. It is one hundred and eighty stadia distant from Ephesus, and might therefore be placed under the Maconians. But the Ephesians, having grown in power, later cut off for themselves much of the territory of the Maconians, whom we now call Lydians, so that this could not be the Larisa of the Pelasgians either, but rather the one near Cymê. In fact we have no strong evidence that the Larisa in the Cayster Plain was already in existence at that time, for we have no such evidence as to Ephesus either; but all Aeolian history, which arose but shortly after the Trojan times, bears testimony to the existence of the Larisa near Cymê.

3. For it is said that the people who set out from Phricium, the Locrian mountain above Thermopylae, put in at the place where Cymê now is, and finding the Pelasgians in bad plight because of the Trojan War, though still in possession of Larisa, which was about seventy stadia distant from Cymê, built on their frontier what is still to-day called Neon Teichos,¹ thirty stadia from Larisa, and that, having captured Larisa, they founded Cymê and settled there the survivors. And Cymê is called Cymê

¹ "New wall."

² ἐλόντας, Corais, Kramer, and Meineke, for ἐλθόντας; ἀνελθόντας Groskurd.

ἀπὸ δὲ τοῦ Λοκρικοῦ ὄρους τὴν τε Κύμην Φρικωνίδα καλοῦσιν, ὁμοίως δὲ καὶ τὴν Λίρισαν ἐρήμη δ' ἐστὶ νῦν. ὅτι δ' οἱ Πελασγοὶ μέγα ἦν ἔθνος, καὶ ἐκ τῆς ἄλλης ἱστορίας οὕτως ἐκμαρτυρεῖσθαι¹ φασί· Μενεκράτης γοῦν ὁ Ἐλαίτης ἐν τοῖς περὶ κτίσεων φησὶ τὴν παραλίαν τὴν νῦν Ἰωνικὴν πᾶσαν, ἀπὸ Μυκάλης ἀρξαμένην, ὑπὸ Πελασγῶν οἰκεῖσθαι πρότερον καὶ τὰς πλησίον νήσους. Λέσβιοι δ' ὑπὸ Πυλαίῳ τετάχθαι λέγουσι σφᾶς, τῷ ὑπὸ τοῦ ποιητοῦ λεγομένῳ τῶν Πελασγῶν ἄρχοντι, ἀφ' οὗ καὶ τὸ παρ' αὐτοῖς ὄρος ἔτι Πύλαιον καλεῖσθαι. καὶ Χίῳι δὲ οἰκιστὰς ἐαυτῶν Πελασγούς φασί τοὺς ἐκ τῆς Θετταλίας. πολὺπλανον δὲ καὶ ταχὺ τὸ ἔθνος πρὸς ἀπαναστάσεις,² ἠϋξήθη τε ἐπὶ πολὺ καὶ ἀθρόαν ἔλαβε τὴν ἑκλείψιν, καὶ μάλιστα κατὰ τὴν τῶν Αἰολέων καὶ τῶν Ἰόνων περαίωσιν εἰς τὴν Ἀσίαν.

4. Ἴδιον δέ τι τοῖς Λαρισαίοις συνέβη τοῖς τε Καῦστριανοῖς³ καὶ τοῖς Φρικωνεῦσι καὶ τρίτοις τοῖς ἐν Θετταλίᾳ· ἅπαντες γὰρ ποταμόχωστον τὴν χώραν ἔσχον, οἱ μὲν ὑπὸ τοῦ Καῦστρου, οἱ δ' ὑπὸ τοῦ Ἑρμου, οἱ δ' ὑπὸ τοῦ Πηνειοῦ. ἐν δὲ τῇ Φρικωνίδι Λαρίσῃ τετιμῆσθαι λέγεται Πίαςος, ὃν φασιν ἄρχοντα Πελασγῶν ἐρασθῆναι τῆς θυγατρὸς Λαρίσης, βιασάμενον δ' αὐτὴν τίσαι τῆς ὕβρεως δίκην· ἐγκύψαντα γὰρ εἰς πίθον οἴνου καταμαθοῦσαν τῶν σκελῶν λαβομένην ἐξᾶραι καὶ καθεῖναι αὐτὸν εἰς τὸν πίθον. τὰ μὲν οὖν ἀρχαῖα τοιαῦτα.

¹ Dhl read τοῦτο ἐκμαρτυρεῖσθαι.

² ἀπαναστάσεις, Corais, for ἐπαναστάσεις.

Phriconis after the Locrian mountain; and likewise Larisa is called Larisa Phriconis; but Larisa is now deserted. That the Pelasgians were a great tribe is said also to be the testimony of history in general: Menecrates of Elaea, at any rate, in his work *On the Founding of Cities*, says that the whole of what is now the Ionian coast, beginning at Mycalê, as also the neighbouring islands, were in earlier times inhabited by Pelasgians. But the Lesbians say that their people were placed under the command of Pylaeus, the man whom the poet calls the ruler of the Pelasgians,¹ and that it is from him that the mountain in their country is still called Pylaeus. The Chians, also, say that the Pelasgians from Thessaly were their founders. But the Pelasgian race, ever wandering and quick to migrate, greatly increased and then rapidly disappeared, particularly at the time of the migration of the Aeolians and Ionians to Asia.

4. A peculiar thing happened in the case of the Larisaeans, I mean the Caystrian and the Phryconian Larisaeans and, third, those in Thessaly: they all held land that was deposited by rivers, by the Cayster and by the Hermus and by the Pencius. It is at the Phryconian Larisa that Piasus is said to have been honoured, who, they say, was ruler of the Pelasgians and fell in love with his daughter Larisa, and, having violated her, paid the penalty for the outrage; for, observing him leaning over a cask of wine, they say, she seized him by the legs, raised him, and plunged him into the cask. Such are the ancient accounts.

¹ *Iliad* 2. 842.

² Instead of Καύστριανούς, ΟΙΕκίνοσ read Καύστρηνοίς, Ψα Καύστρηνοίς.

5. Ταῖς δὲ νῦν Αἰολικαῖς πόλεσιν ἔτι καὶ τὰς Αἰγὰς¹ προσληπτέον καὶ τὴν Τῆμνον, ὅθεν ἦν Ἑρμαγόρας ὁ τὰς ῥητορικὰς τέχνας συγγράψας· ἰδρυνταὶ δ' αἱ πόλεις αὗται κατὰ τὴν ὀρεινὴν τὴν ὑπερκειμένην τῆς τε Κυμαίας καὶ τῆς Φωκαέων καὶ Σμυρναίων γῆς, παρ' ἣν ὁ Ἑρμος ρεῖ. οὐκ ἄπωθεν δὲ τούτων τῶν πόλεων οὐδ' ἡ Μαγνησία ἐστὶν ἡ ὑπὸ Σιπύλῳ, ἐλευθέρα πόλις ὑπὸ Ῥωμαίων κεκριμένη. καὶ ταύτην δ' ἐκίκωσαν οἱ νεωστὶ γενόμενοι σεισμοί. εἰς δὲ C 622 τὰναντία τὰ ἐπὶ τὸν Κάϊκον νεύοντα ἀπὸ Λαρίσης μὲν διαβάντι τὸν Ἑρμον εἰς Κύμην ἐβδομήκοντα στάδιοι, ἐντεῦθεν δ' εἰς Μύριναν τετταράκοντα στάδιοι, τὸ δ' ἴσον ἐντεῦθεν εἰς Γρύνιον, κακείθεν εἰς Ἑλαίαν· ὥς δ' Ἀρτεμίδωρος, ἀπὸ τῆς Κύμης εἰσὶν Ἀδαι, εἴτ' ἄκρα μετὰ τετταράκοντα σταδίους, ἣν καλοῦσιν Ὑδραν, ἡ ποιοῦσα τὸν κόλπον τὸν Ἑλαϊτικὸν πρὸς τὴν ἀπεναντίον ἄκραν Ἀρματοῦντα. τοῦ μὲν οὖν στόματος τὸ πλάτος περὶ ὀγδοήκοντα σταδίους ἐστίν, ἐγκολπίζοντι δὲ Μύρινα ἐν ἐξήκοντα σταδίοις, Αἰολὶς πόλις ἔχουσα λιμένα, εἴτ' Ἀχαιῶν λιμὴν, ὅπου οἱ βωμοὶ τῶν δώδεκα θεῶν, εἴτα πολίχνην Γρύνιον καὶ ἱερὸν Ἀπόλλωνος καὶ μαντεῖον ἀρχαῖον καὶ νεὸς πολυτελὲς λίθου λευκοῦ, στάδιοι δ' ἐπ' αὐτὴν τετταράκοντα· εἴθ' ἐβδομήκοντα εἰς Ἑλαίαν, λιμένα ἔχουσιν καὶ ναύσταθμον τῶν Ἀτταλικῶν βασιλέων, Μενεσθέως κτίσμα καὶ τῶν σὺν αὐτῷ Ἀθηναίων τῶν συστρατευσάντων ἐπὶ Ἴλιον. τὰ δ' ἐξῆς εἴρηται τὰ περὶ Πιτάνην καὶ Ἀταρνέα καὶ τὰλλα τὰ ταύτῃ.

5. To the present Aeolian cities we must add Aegae, and also Temnus, the birthplace of Herma-goras, who wrote *The Art of Rhetoric*. These cities are situated in the mountainous country that lies above the territory of Cymê and that of the Phocians and that of the Smyrnaeans, along which flows the Hermus. Neither is Magnesia, which is situated below Mt. Sipylus and has been adjudged a free city by the Romans, far from these cities. This city too has been damaged by the recent earthquakes. To the opposite parts, which incline towards the Caïcus, from Larisa across the Hermus to Cymê, the distance is seventy stadia; thence to Myrina, forty stadia; thence to Grynium, the same; and from there to Elaea. But, according to Artemidorus, one goes from Cymê to Adae, and then, forty stadia distant, to a promontory called Hydra, which with the opposite promontory Harmatus forms the Elastic Gulf. Now the width of the mouth of this gulf is about eighty stadia, but, including the sinuosities of the gulf, Myrina, an Aeolian city with a harbour, is at a distance of sixty stadia; and then one comes to the Harbour of the Achaeans, where are the altars of the twelve gods; and then to a town Grynium and an altar of Apollo and an ancient oracle and a costly shrine of white marble, to which the distance is forty stadia; and then seventy stadia to Elaea, with harbour and naval station belonging to the Attalic kings, which was founded by Menestheus and the Athenians who took the expedition with him to Ilium. I have already spoken of the places that come next, those about Pitane and Atarneus and the others in that region.

¹ *Abyûs Dâ.*

6. Μεγίστη δέ ἐστι τῶν Αἰολικῶν καὶ ἀρίστη Κύμη καὶ σχεδὸν μητρόπολις αὕτη τε καὶ ἡ Λέσβος τῶν ἄλλων πόλεων, περὶ τριάκοντά που τὸν ἀριθμὸν, ὧν ἐκλελοίπασιν οὐκ ὀλίγαι. σκώπεται δ' εἰς ἀναισθησίαν ἡ Κύμη κατὰ τοιαύτην τινά, ὥς φασιν ἔνιοι, δόξαν, ὅτι τριακοσίοις ἔτεσιν ὕστερον τῆς κτίσεως ἀπέδοντο τοῦ λιμένος τὰ τέλη, πρότερον δ' οὐκ ἐκαρπούτο τὴν πρόσδοτον ταύτην ὁ δῆμος· κατέσχευεν οὖν δόξα, ὡς ὀψὲ ἦσθημένων, ὅτι ἐπὶ θαλάττῃ πόλιν οἰκοῖεν. ἐστὶ δὲ καὶ ἄλλος λόγος, ὅτι δανεισάμενοι χρήματα δημοσίᾳ τὰς στοὰς ὑπέθεντο, εἴτ' οὐκ ἀποδιδόντες κατὰ τὴν ὠρισμένην ἡμέραν εἴργοντο τῶν περιπάτων· ὅτε μέντοι ὄμβρος εἶη, κατ' αἰδῶ τινὰ κηρύττειεν οἱ δανεισταί, κελεύοντες ὑπὸ τὰς στοὰς ὑπέρχεσθαι· τοῦ δὲ κήρυκος οὕτω φθειγγομένου "ὑπὸ τὰς στοὰς ὑπέλθετε," ἐκπεσεῖν λόγον, ὡς Κυμαίων οὐκ αἰσθανομένων, ὡς ἐν τοῖς ὄμβροις ὑπὸ τὰς στοὰς ὑπελθετέον, ἂν μὴ σημάνῃ τις αὐτοῖς διὰ κηρύγματος. ἀνὴρ δ' ἄξιος μνήμης ἐκ τῆσδε τῆς πόλεως ἀναντιλέκτως μὲν ἐστὶν Ἐφορος, τῶν Ἰσοκράτους γνωρίμων τοῦ ῥήτορος, ὁ τὴν ἱστορίαν συγγράψας καὶ τὰ περὶ τῶν εὐρημάτων· καὶ ἔτι πρότερος τούτου Ἡσίοδος ὁ ποιητής· αὐτὸς γὰρ εἶρηκεν, ὅτι ὁ πατὴρ αὐτοῦ Δῖος μετόκησεν εἰς Βοιωτούς, Κύμην Αἰολίδα προλιπών·

νάσσατο δ' ἄγχ' Ἐλικῶνος διῆυρῃ ἐνὶ κόμῃ.

"Ἀσκη, χεῖμα κακῇ, θέρει ἀργαλήν, οὐδέ ποτ' ἐσθλή.

Ο623 Ὅμηρος δ' οὐχ ὁμολογουμένως· πολλοὶ γὰρ

6. The largest and best of the Aeolian cities is Cymê; and this with Lesbos might be called the metropolis of the rest of the cities, about thirty in number, of which not a few have disappeared. Cymê is ridiculed for its stupidity, owing to the repute, as some say, that not until three hundred years after the founding of the city did they sell the tolls of the harbour, and that before this time the people did not reap this revenue. They got the reputation, therefore, of being a people who learned late that they were living in a city by the sea. There is also another report of them, that, having borrowed money in the name of the state, they pledged their porticoes as security, and then, failing to pay the money on the appointed day, were prohibited from walking in them; when it rained, however, their creditors, through a kind of shame, would bid them through a herald to go under the porticoes; so the herald would cry out the words, "Go under the porticoes," but the report went abroad that the Cymaeans did not understand that they were to go under the porticoes when it rained unless they were given notice by the herald. Ephorus, a man indisputably noteworthy, a disciple of Isocrates the orator, and the author of the *History* and of the work on *Inventions*, was from this city; and so was Hesiod the poet, still earlier than Ephorus, for Hesiod himself states that his father Dius left Aeolian Cymê and migrated to Boeotia: "And he settled near Helicon in a wretched village, Ascî, which is bad in winter, oppressive in summer, and pleasant at no time."¹ But it is not agreed that Homer was from Cymê, for

¹ *Works and Days*, 639-40 (quoted also in 9. 2. 25).

ἀμφισβητοῦσιν αὐτοῦ. τὸ δ' ὄνομα ἀπὸ Ἀμαζόνος τῇ πόλει τεθεῖσθαι, καθάπερ καὶ τῇ Μυρίνῃ ἀπὸ τῆς ἐν τῷ Τρωικῷ πεδίῳ κειμένης ὑπὸ τῇ Βατιείᾳ·

τὴν ἦτοι ἄνδρες Βατίειαν κυκλήσκουσιν,
ἀθάνατοι δέ τε σῆμα πολυσκάρθοιο Μυρίνης.

σκόπτεται δὲ καὶ ὁ Ἑφορος, διότι τῆς πατρίδος ἔργα οὐκ ἔχων φράζειν ἐν τῇ διαριθμήσει τῶν ἄλλων πράξεων, οὐ μὴν οὐδ' ¹ ἀμνημόνευτον αὐτὴν εἶναι θέλων, οὕτως ἐπιφωνεῖ· “Κατὰ δὲ τὸν αὐτὸν καιρὸν Κυμαῖοι τὰς ἡσυχίας ἦγον.” ἐπεὶ δὲ διεληλύθαμεν τὴν Τρωικὴν ἅμα καὶ τὴν Αἰολικὴν παραλίαν, ἐφεξῆς ἂν εἴη τὴν μεσόγαιαν ἐπιδραμεῖν μέχρι τοῦ Ταύρου, φυλάσσοντας τὴν αὐτὴν τῆς ἐφόδου τάξιν.

IV

1. Ἐχει δὲ τινα ἡγεμονίαν πρὸς τοὺς τόπους τούτους τὸ Πέργαμον, ἐπιφανὲς πόλις καὶ πολὺν συνευτυχήσασα χρόνον τοῖς Ἀτταλικοῖς βασιλεῦσι· καὶ δὴ καὶ ἐντεῦθεν ἀρκτέον τῆς ἐξῆς περιουσίας, καὶ πρῶτον περὶ τῶν βασιλέων, ὁπόθεν ὠρμήθησαν καὶ εἰς ἃ κατέστρεψαν, ἐν βραχείσι δηλωτέον. ἦν μὲν δὴ τὸ Πέργαμον Λυσιμάχου γαζοφυλάκιον τοῦ Ἀγαθοκλέους, ἐνὸς τῶν Ἀλεξάνδρου διαδόχων, αὐτὴν τὴν ἄκραν τοῦ ὄρους συνοικουμένην ἔχον· ἔστι δὲ στροβιλοειδὲς τὸ ὄρος εἰς ὀξείαν κορυφὴν ἀπολήγον. ἐπεπίστυτο δὲ τὴν φυλακὴν τοῦ ἐρύματος τούτου καὶ τῶν χρημάτων (ἦν δὲ τάλαντα ἑννακισχίλια)

many peoples lay claim to him. It is agreed, however, that the name of the city was derived from an Amazon, as was Myrina from the Amazon who lies in the Trojan plain below Baticia, "which verily men call Baticia, but the immortals the tomb of much-bounding Myrina."¹ Ephorus, too, is ridiculed because, though unable to tell of deeds of his native land in his enumeration of the other achievements in history, and yet unwilling that it should be unmentioned, he exclaims as follows: "At about the same time the Cymaeans were at peace."

Since I have traversed at the same time the Trojan and Aeolian coasts, it would be next in order to treat cursorily the interior as far as the Taurus, observing the same order of approach.

IV

1. A kind of hegemony is held over these places by Pergamum, which is a famous city and for a long time prospered along with the Attalic kings; indeed I must begin my next description here, and first I must show briefly the origin of the kings and the end to which they came. Now Pergamum was a treasure-hold of Lysimachus, the son of Agathocles, who was one of the successors of Alexander, and its people are settled on the very summit of the mountain; the mountain is cone-like and ends in a sharp peak. The custody of this stronghold and the treasure, which amounted to nine thousand talents,

¹ Also quoted in 12. 8. 6.

¹ All MSS. except If insert *av* after *ov8'*.

Φιλέταιρος, ἀνὴρ Τιανός,¹ θλιβίας ἐκ παιδός. συνέβη γὰρ ἔν τινι ταφῇ θέας οὔσης καὶ πολλῶν παρόντων, ἀποληφθεῖσαν ἐν τῷ ὄχλῳ τὴν κομίζουσαν τροφὸν τὸν Φιλέταιρον ἔτι νήπιον συνθλιβῆναι μέχρι τοσοῦδε, ὥστε πηρωθῆναι τὸν παῖδα. ἦν μὲν δὴ εὐνοῦχος, τραφεὶς δὲ καλῶς ἐφάνη τῆς πίστεως ταύτης ἄξιος. τέως μὲν οὖν εὐνους διέμεινε² τῷ Λυσιμάχῳ, διενεχθεὶς δὲ πρὸς Ἀρσινόην τὴν γυναῖκα αὐτοῦ διαβάλλουσαν αὐτὸν ἀπέστησε τὸ χωρίον καὶ πρὸς τοὺς καιροὺς ἐπολιτεύετο, ὁρῶν ἐπιτηδείους πρὸς νεωτερισμόν· ὃ τε γὰρ Λυσίμαχος κακοῖς οἰκείοις περιπεσὼν ἠναγκάσθη τὸν υἱὸν ἀνελεῖν Ἀγαθοκλέα, Σέλευκός τε ἐπελθὼν³ ὁ Νικάτωρ ἐκείνόν τε κατέλυσε καὶ αὐτὸς κατελύθη, δολοφονηθεὶς ὑπὸ Πτολεμαίου τοῦ Κεραυνοῦ. τοιούτων δὲ θορύβων ὄντων, διεγένετο μένων ἐπὶ τοῦ ἐρύματος ὁ εὐνοῦχος καὶ πολιτευόμενος δι' ⁴ ὑποσχέσεων καὶ τῆς ἄλλης θεραπείας αἰὲς πρὸς τὸν ἰσχύοντα καὶ ἐγγὺς παρόντα· διετέλεσε γοῦν ἔτη εἴκοσι κύριος ὢν τοῦ φρουρίου καὶ τῶν χρημάτων.

C 624 2. Ἦσαν δ' αὐτῷ δύο ἀδελφοί, πρεσβύτερος μὲν Εὐμένης, νεώτερος δ' Ἀτταλος· ἐκ μὲν οὖν τοῦ Εὐμένους ἐγένετο ὁμώνυμος τῷ πατρὶ Εὐμένης, ὅσπερ καὶ διεδέξατο τὸ Πέργαμον, καὶ ἦν ἤδη δυνάστης τῶν κύκλῳ χωρίων, ὥστε καὶ περὶ Σάρδεις ἐνίκησε μάχῃ συμβαλὼν Ἀντίοχον τὸν Σελεύκου· δύο δὲ καὶ εἴκοσιν ἄρξας ἔτη τελευτᾷ τὸν βίον. ἐκ δὲ Ἀττάλου καὶ Ἀν-

¹ Τιανός C, Τιανός x, Τιανεύς μοz.

² Instead of διέμεινε, CDzz and Corais read διέμενε.

³ ἐπανελθὼν μοz, instead of ἐπελθὼν.

was entrusted to Philetaerus of Tieium, who was a eunuch from boyhood; for it came to pass at a certain burial, when a spectacle was being given at which many people were present, that the nurse who was carrying Philetaerus, still an infant, was caught in the crowd and pressed so hard that the child was incapacitated. He was a eunuch, therefore, but he was well trained and proved worthy of this trust. Now for a time he continued loyal to Lysimachus, but he had differences with Arsinoë, the wife of Lysimachus, who slandered him, and so he caused Perganum to revolt, and governed it to suit the occasion, since he saw that it was ripe for a change; for Lysimachus, beset with domestic troubles, was forced to slay his son Agathocles, and Seleucus Nicator invaded his country and overthrew him, and then he himself was overthrown and treacherously murdered by Ptolemy Ceraunus. During these disorders the eunuch continued to be in charge of the fortress and to manage things through promises and courtesies in general, always catering to any man who was powerful or near at hand. At any rate, he continued lord of the stronghold and the treasure for twenty years.

2. He had two brothers, the elder of whom was Eumenes, the younger Attalus. Eumenes had a son of the same name, who succeeded to the rule of Perganum, and was by this time sovereign of the places round about, so that he even joined battle with Antiochus the son of Seleucus near Sardeis and conquered him. He died after a reign of twenty-two years.¹ Attalus, the son of Attalus and Antiochis,

¹ 263-241 B.C.

⁴ *μεθ' ἑω*, instead of *δε*.

τιοχίδος, τῆς Ἀχαιοῦ, γεγονώς Ἀτταλος διεδέξατο τὴν ἀρχήν, καὶ ἀνηγορεύθη βασιλεὺς πρῶτος, νικήσας Γαλάτας μάχῃ μεγάλη. οὗτος δὲ καὶ Ῥωμαίοις κατέστη φίλος καὶ συνεπολέμησε πρὸς Φίλιππον μετὰ τοῦ Ῥοδίων ναυτικοῦ· γηραιὸς δὲ ἐτελεύτα,¹ βασιλεύσας ἔτη τρία καὶ τετταράκοντα, κατέλιπε δὲ τέτταρας υἱοὺς ἐξ Ἀπολλωνίδος Κυζικηνῆς γυναικός, Εὐμένη, Ἀτταλον, Φιλέταιρον, Ἀθήναιον. οἱ μὲν οὖν νεώτεροι διέτελεσαν ἰδιῶται, τῶν δ' ἄλλων ὁ πρεσβύτερος Εὐμένης ἐβασίλευσε· συνεπολέμησε δὲ οὗτος Ῥωμαίοις πρὸς τε Ἀντίοχον τὸν μέγαν καὶ πρὸς Περσέα, καὶ ἔλαβε παρὰ τῶν Ῥωμαίων ἅπασαν τὴν ὑπ' Ἀντιόχῳ τὴν ἐντὸς τοῦ Ταύρου. πρότερον δ' ἦν τὰ περὶ Πέργαμον οὐ πολλὰ χωρία μέχρι τῆς θαλάττης τῆς κατὰ τὸν Ἐλαίτην κόλπον καὶ τὸν Ἀδραμυττηνόν. κατεσκεύασε δ' οὗτος τὴν πόλιν καὶ τὸ Νικηφόριον ἄλσει κατεφύτευσε, καὶ ἀναθήματα καὶ βιβλιοθήκας καὶ τὴν ἐπὶ τοσόνδε κατοικίαν τοῦ Περγάμου τὴν νῦν οὖσαν ἐκεῖνος προσεφίλοκάλησε· βασιλεύσας δὲ² ἔτη τετταράκοντα καὶ ἐννέα ἀπέλιπεν υἱὸν τὴν ἀρχὴν Ἀττάλῳ, γεγονότι ἐκ Στρατονίκης τῆς Ἀριαράθου θυγατρὸς τοῦ Καππαδόκων βασιλέως. ἐπίτροπον δὲ κατέστησε καὶ τοῦ παιδὸς νέου τελέως οὗτος καὶ τῆς ἀρχῆς τὸν ἀδελφὸν Ἀτταλον. ἐν δὲ καὶ εἴκοσιν ἔτη βασιλεύσας γέρων οὗτος τελευτᾷ, κατορθώσας πολλά·

¹ ἐτελεύτησε μοι, instead of ἐτελεύτα.

² δέ, before ἔτη, inserted by π; μοι have τε.

daughter of Achæus, succeeded to the throne and was the first to be proclaimed king, after conquering the Galatians in a great battle. Attalus not only became a friend of the Romans but also fought on their side against Philip along with the fleet of the Rhodians. He died in old age, having reigned as king forty-three years;¹ and he left four sons by Apollonis, a woman from Cyzicus, Eumenes, Attalus, Philetaerus, and Athenæus. Now the two younger sons remained private citizens, but Eumenes, the elder of the other two, reigned as king. Eumenes fought on the side of the Romans against Antiochus the Great and against Perseus, and he received from the Romans all the country this side the Taurus that had been subject to Antiochus. But before that time the territory of Pergamum did not include many places that extended as far as the sea at the Elætic and Adramyttene Gulfs. He built up the city and planted Nicephorium with a grove, and the other elder brother,² from love of splendour, added sacred buildings and libraries and raised the settlement of Pergamum to what it now is. After a reign of forty-nine years³ Eumenes left his empire to Attalus, his son by Stratonice, the daughter of Ariathres, king of the Cappadocians. He appointed his brother Attalus⁴ as guardian both of his son, who was extremely young, and of the empire. After a reign of twenty-one years,⁵ his brother died an old man, having won success in many undertakings; for

² Others make *ἑκείνος* refer to Eumenes, but the present translator must make it refer to Attalus, unless the text is corrupt.

³ But he died in 159 B.C. (see Pauly-Wissowa, s.v. "Eumenes," p. 1103), thus having reigned 197-159 B.C.

⁴ Attalus Philadelphus.

⁵ 159-138 B.C.

καὶ γὰρ Δημήτριον τὸν Σελεύκου συγκατέπολέ-
 μησεν Ἀλεξάνδρῳ τῷ Ἀντιόχου καὶ συνεμάχησε
 Ῥωμαίους ἐπὶ τὸν Ψευδοφίλιππον, ἐχειρώσατο
 δὲ καὶ Διήγγυλιν τὸν Καινῶν¹ βασιλέα στρα-
 τεύσας εἰς τὴν Θράκην, ἀνείλε δὲ καὶ Προυσίαν,
 ἐπισυστήσας αὐτῷ Νικομήδην τὸν υἱόν, κατέλιπε
 δὲ² τὴν ἀρχὴν τῷ ἐπιτροπευθέντι Ἀττάλῳ·
 βασιλεύσας δὲ οὗτος ἔτη πέντε καὶ κληθεὶς
 Φιλομήτωρ ἐτελεύτα νόσῳ τὸν βίον, κατέλιπε
 δὲ κληρονόμους Ῥωμαίους· οἱ δ' ἐπαρχίαν ἀπέ-
 δειξαν τὴν χώραν, Ἀσίαν προσαγορεύσαντες,
 ὁμώνυμον τῇ ἡπείρῳ. παραρρεῖ δ' ὁ Κάϊκος τὸ
 Πέργαμον, διὰ τοῦ Καϊκου πεδίου προσαγορευο-
 μένου σφόδρα εὐδαίμονα γῆν διεξιῶν, σχεδὸν δέ
 τι καὶ τὴν ἀρίστην τῆς Μυσίας.

- C 625 3. Ἄνδρες δ' ἐγένοντο ἐλλόγιμοι καθ' ἡμᾶς
 Περγαμηνοί, Μιθριδάτης τε Μηνοδότου υἱὸς καὶ
 Ἀδοβογίωνος, ὃς³ τοῦ τετραρχικοῦ τῶν Γαλατῶν
 γένους ἦν, ἦν⁴ καὶ⁵ παλλακεῦσαι τῷ βασιλεῖ
 Μιθριδάτῃ φασίν· ὅθεν καὶ τοῦνομα τῷ παιδὶ
 θέσθαι τοὺς ἐπιτηδεῖους, προσποιησμένους ἐκ
 τοῦ βασιλέως αὐτὸν γεγονέναι. οὗτος γοῦν
 Καίσαρι τῷ Θεῷ γενόμενος φίλος εἰς τοσόνδε
 προήλθε τιμῆς, ὥστε καὶ τετράρχης ἀπεδείχθη
 ἀπὸ⁶ τοῦ μητρώου γένους καὶ βασιλεὺς ἄλλων
 τε καὶ τοῦ Βοσπόρου· κατελύθη δ' ὑπὸ Ἀσάν-
 δρου⁷ τοῦ καὶ Φαρνάκην ἀνελόντος τὸν βασιλέα
 καὶ κατασχόντος τὸν Βόσπορον. οὗτός τε δὴ

¹ Καινῶν, Tzschucke, for ἐκείνων CDλήστοριαα, ἐκείνων F, καινόν Epit.; so the later editors.

² The MSS., except Fz, have καὶ after δέ.

³ Ἀδοβογίωνος, ὅς, the editors, for Ἀδοβογίων, ὅς.

example, he helped Alexander, the son of Antiochus, to defeat in war Demetrius, the son of Seleucus, and he fought on the side of the Romans against the Pseudo-Philip, and in an expedition against Thrace he defeated Diegylis the king of the Caeni, and he slew Prusias, having incited his son Nicomedes against him, and he left his empire, under a guardian, to Attalus. Attalus, surnamed Philometor, reigned five years,¹ died of disease, and left the Romans his heirs. The Romans proclaimed the country a province, calling it Asia, by the same name as the continent. The Caicus flows past Pergamum, through the Caicus Plain, as it is called, traversing land that is very fertile and about the best in Mysia.

3. Pergamenians have become famous in my time: Mithridates the son of Menodotus and of Adobogion. Menodotus was of the family of the tetrarchs of the Galatians, and Adobogion, it is said, was also the concubine of King Mithridates,² and for this reason her relatives gave to the child the name of Mithridates, pretending that he was the son of the king. At any rate, he became a friend to the deified Caesar and reached so great preferment with him that he was appointed tetrarch from his mother's family and king both of the Bosphorus and other territories. He was overthrown by Asander, who not only slew King Pharnaces but also took possession of the Bosphorus. Mithridates, then, has been

¹ 138-133 B.C.

² Mithridates the Great.

⁴ $\xi\nu$, inserted by the editors.

⁵ $\delta\nu$, before $\pi\alpha\lambda\lambda\alpha\kappa\epsilon\upsilon\sigma\alpha\iota$, ejected by the editors.

⁶ $\alpha\pi\acute{o}$, Casaubon inserts; so the later editors.

⁷ $\Lambda\sigma\delta\alpha\nu\delta\rho\omicron\nu$, Casaubon, for $\Lambda\nu\sigma\delta\alpha\nu\delta\rho\omicron\nu$; so the later editors.

ὀνόματος ἡξίωται μέγαλον, καὶ Ἀπολλόδωρος ὁ ῥήτωρ ὁ τὰς τέχνας συγγράψας καὶ τὴν Ἀπολλοδώρειον αἵρεσιν παραγαγών, ἥτις ποτ' ἐστὶ πολλὰ γὰρ ἐπεκράτει, μείζονα δὲ ἢ καθ' ἡμᾶς ἔχοντα τὴν κρίσιν, ὧν ἐστὶ καὶ ἡ Ἀπολλοδώρειος αἵρεσις καὶ ἡ Θεοδώρειος. μάλιστα δὲ ἐξήρε τὸν Ἀπολλόδωρον ἡ τοῦ Καίσαρος φιλία τοῦ Σεβαστοῦ, διδύσκαλον τῶν λόγων γενόμενον· μαθητὴν δ' ἔσχεν ἀξιόλογον Διονύσιον τὸν ἐπικληθέντα Ἀττικόν, πολίτην αὐτοῦ, καὶ γὰρ σοφιστὴς ἦν ἱκανὸς καὶ συγγραφεὺς καὶ λογογράφος.

4. Προϊόντι δ' ἀπὸ τοῦ πεδίου καὶ τῆς πόλεως ἐπὶ μὲν τὰ πρὸς ἑὼ μέρη πόλις ἐστὶν Ἀπολλωνία, μετεώροις ἐπικειμένη τόποις· ἐπὶ δὲ τὸν νότον ὀρεινὴ ῥάχις ἐστίν, ἣν ὑπερβᾶσι καὶ βαδίξουσιν ἐπὶ Σάρδεων πόλις ἐστὶν ἐν ἀριστερᾷ Θυάτειρα, κατοικία Μακεδόνων, ἣν Μυσῶν ἐσχάτην τινὲς φασιν. ἐν δεξιᾷ δ' Ἀπολλωνίς, διέχουσα Περγάμου τριακοσίους σταδίους, τοὺς δὲ ἴσους καὶ τῶν Σάρδεων, ἐπώνυμος δ' ἐστὶ τῆς Κυζικηνῆς Ἀπολλωνίδος· εἴτ' ἐκδέχεται τὸ Ἑρμοῦ πεδίον καὶ Σάρδεις· τὰ δὲ προσάρκτια τῷ Περγάμῳ τὰ πλείστα ὑπὸ Μυσῶν ἔχεται τὰ ἐν δεξιᾷ τῶν Ἀβαιετῶν¹ λεγομένων, οἷς συνάπτει ἡ Ἐπικτητος μέχρι Βιθυνίας.

5. Αἱ δὲ Σάρδεις πόλις ἐστὶ μεγάλη, νεωτέρα μὲν τῶν Τρωικῶν, ἀρχαία δ' ὅμως, ἄκραν ἔχουσα εὐερκὴ· βασιλείον δ' ὑπῆρξε τῶν Λυδῶν, οὓς ὁ

¹ Ἀβαιετῶν, Kramer, from conj. of Kiepert, for Ἀβλιτῶν E, Ἀβλιτῶν other MSS.

thought worthy of a great name, as has also Apollodorus the rhetorician, who wrote the work on *Rhetoric* and was the leader of the Apollodoreian sect, whatever in the world it is; for numerous philosophies were prevalent, but to pass judgment upon them is beyond my power, and among these are the sects of Apollodorus and Theodorus. But the friendship of Caesar Augustus has most of all exalted Apollodorus, who was his teacher in the art of speech. And Apollodorus had a notable pupil in Dionysius, surnamed Atticus, his fellow-citizen, for he was an able sophist and historian and speech-writer.

4. As one proceeds from the plain and the city towards the east, one comes to a city called Apollonia, which lies on an elevated site, and also, towards the south, to a mountain range, on crossing which, on the road to Sardeis, one comes to Thyateira, on the left-hand side, a settlement of the Macedonians, which by some is called the farthestmost city of the Mysians. On the right is Apollonis, which is three hundred stadia distant from Pergamum, and the same distance from Sardeis, and it is named after the Cyzicene Apollonis. Next one comes to the plain of Hermus and to Sardeis. The country to the north of Pergamum is held for the most part by the Mysians, I mean the country on the right of the Abaeitae, as they are called, on the borders of which is the Epictetus¹ as far as Bithynia.

5. Sardeis is a great city, and, though of later date than the Trojan times, is nevertheless old, and has a strong citadel. It was the royal city of the Lydians, whom the poet calls Meionians; and later

¹ Phrygia Epictetus (see 12. 3. 7, 12. 4. 1, and 12. 4. 5).

ποιητῆς καλεῖ Μήονας, οἱ δ' ὕστερον Μαίονας, οἱ μὲν τοὺς αὐτοὺς τοῖς Λυδοῖς, οἱ δ' ἑτέρους ἀποφαίνοντες, τοὺς δ' αὐτοὺς ἄμεινόν ἐστι λέγειν. ὑπέρκειται δὲ τῶν Σάρδεων ὁ Τρωῶλος, εὐδαιμον ὄρος, ἐν τῇ ἀκρωρεῖα σκοπὴν ἔχον, ἐξέδραν λευκοῦ λίθου, Περσῶν ἔργον, ἀφ' οὗ κατοπτεύεται τὰ κύκλῳ πεδία, καὶ μάλιστα τὸ Καῦστριανόν· περιοικοῦσι δὲ Λυδοὶ καὶ Μυσοὶ καὶ Μακεδόνες. ρεῖ δ' ὁ Πακτωλὸς ἀπὸ τοῦ Τρωῶλου, καταφέρων τὸ παλαιὸν ψῆγμα χρυσοῦ πολὺ, ἀφ' οὗ τὸν

Ο 626 Κροίσου λεγόμενον πλούτον καὶ τῶν προγόνων αὐτοῦ διονομασθῆναί φασι· νῦν δ' ἐκλέλοιπε τὸ ψῆγμα. καταφέρεται δ' ὁ Πακτωλὸς εἰς τὸν Ἑρμον, εἰς ὃν καὶ ὁ Ἕλλος ἐμβάλλει, Φρύγιος νυνὶ καλούμενος· συμπεσόντες δ' οἱ τρεῖς καὶ ἄλλοι ἀσημότεροι σὺν αὐτοῖς εἰς τὴν κατὰ Φωκαίαν ἐκδιδύασι θάλατταν, ὡς Ἡρόδοτός φησιν. ἄρχεται δ' ἐκ Μυσίας ὁ Ἑρμος, ἐξ ὄρους ἱεροῦ τῆς Δινδυμήνης, καὶ διὰ τῆς Κατακεκαυμένης εἰς τὴν Σαρδιανὴν φέρεται καὶ τὰ¹ συνεχῇ πεδία, ὡς εἴρηται, μέχρι τῆς θαλάττης. ὑπόκειται δὲ τῇ πόλει τό τε Σαρδιανὸν πεδίον καὶ τὸ τοῦ Κύρου² καὶ τὸ τοῦ Ἑρμου καὶ τὸ Καῖστριανόν, συνεχῇ τε ὄντα καὶ πάντων ἄριστα πεδίων. ἐν δὲ σταδίοις τετταράκοντα ἀπὸ τῆς πόλεως ἐστὶν ἡ Γυγαία μὲν ὑπὸ τοῦ ποιητοῦ λεγομένη, Κολόη δ' ὕστερον μετονομασθίσα, ὅπου τὸ ἱερὸν τῆς Κολοηνῆς Ἀρτέμιδος, μεγάλην ἀγιστείαν ἔχον. φασὶ δ'

¹ καὶ τὰ Εἰξ, κατὰ CFw, κατὰ τὰ Dhmss.

² Κύρου (see Κύρου πεδίον, 13. 4. 13), Tzschucke, for κόρου; Καῖκου, Corais.

writers call them Maconians, some identifying them with the Lydians and others representing them as different, but it is better to call them the same people. Above Sardeis is situated Mt. Tmolus, a blest mountain, with a look-out on its summit, an arcade of white marble, a work of the Persians, whence there is a view of the plains below all round, particularly the Caÿster Plain. And round it dwell Lydians and Mysians and Macedonians. The Pactolus River flows from Mt. Tmolus; in early times a large quantity of gold-dust was brought down in it, whence, it is said, arose the fame of the riches of Croesus and his forefathers. But the gold-dust has given out. The Pactolus runs down into the Hermus, into which also the Hyllus, now called the Phrygius, empties. These three, and other less significant rivers with them, meet and empty into the sea near Phocaea, as Herodotus says.¹ The Hermus rises in Mysia, in the sacred mountain Dindymenê, and flows through the Catacecaumene country into the territory of Sardeis and the contiguous plains, as I have already said,² to the sea. Below the city lie the plain of Sardeis and that of the Cyrus and that of the Hermus and that of the Caÿster, which are contiguous to one another and are the best of all plains. Within forty stadia from the city one comes to Gygaea,³ which is mentioned by the poet, the name of which was later changed to Coloë, where is the temple of Coloënian Artemis, which is characterised by great holiness. They say that at the festivals here the

¹ 1. 80.² Cf. 13. 1. 2.³ Lake Gygaea, *Iliad* 2. 865.

ἐνταῦθα χορεύειν τοὺς καλὰθους¹ κατὰ τὰς
 ἑορτάς, οὐκ οἶδ' ὅπως ποτὲ παραδοξολογούντες
 μᾶλλον ἢ ἀληθεύοντες.

6. Κειμένων δ' οὕτω πως τῶν ἐπῶν παρ'
 Ὀμήρῳ·

Μήοσιν αὖ Μέσθλης τε καὶ Ἀντιφός ἡγησά-
 σθην,
 υἱε Ταλαιμένεος,² τῷ Γυγαίῃ τέκε λίμνη,
 οἳ καὶ Μήονας ἤγον ὑπὸ Τμῶλῳ γεγαῶτας,
 προσγράφουσιν τινες τοῦτο τέταρτον ἔπος·

Τμῶλῳ ὑπὸ νιφόεντι, Ὕδης³ ἐν πίνονι δῆμῳ.
 οὐδεμία δ' εὐρίσκεται Ὕδῃ ἐν τοῖς Λυδοῖς. οἳ δὲ
 καὶ τὸν Τυχίον ἐνθένδε ποιοῦσιν, ὃν φησιν ὁ
 ποιητής·

σκυτοτόμων ὅχ' ἄριστος Ὕδῃ⁴ ἐνι,
 προστιθέασιν δὲ καί, διότι δρυμώδης ὁ τόπος καὶ
 κεραυνόβολος, καὶ ὅτι ἐνταῦθα οἱ Ἀριμοὶ καὶ
 γὰρ τῷ⁵

ἐν Ἀρίμοις, ὅθι φασὶ Τυφώος ἔμμεναι εὐνὰς
 ἐπεισφέρουσι

χώρῳ ἐνὶ δρυόεντι, Ὕδης ἐν πίνονι δῆμῳ.
 ἄλλοι δ' ἐν Κιλικίᾳ, τινὲς δ' ἐν Συρίᾳ πλάττουσι
 τὸν μῦθον τοῦτον, οἳ δ' ἐν Πιθηκούσσαις, οἳ καὶ
 τοὺς πιθήκους φασὶ παρὰ τοῖς Τυρρηνοῖς ἀρίμους
 καλεῖσθαι· οἳ δὲ τὰς Σάρδεις Ὕδην ὀνομάζουσιν,
 οἳ δὲ τὴν ἀκρόπολιν αὐτῆς. πιθανωτάτους δ' ὁ

¹ Instead of καλὰθους, rw read καθόλου; mæ, Ald., and
 Casaubon πιθήκους; Lobeck conj. πιθήκων and certain others
 καλὰμους.

baskets dance,¹ though I do not know why in the world they talk marvels rather than tell the truth.

6. The verses of Homer are about as follows: "Mnesthes and Antiphus, the two sons of Talae-
menes, whose mother was Lake Gygaea, who led
also the Meïonians, who were born at the foot
of Tmolus";² but some add the following fourth
verse: "At the foot of snowy Tmolus, in the fertile
land of Hydê." But there is no Hydê to be found
in the country of the Lydians. Some also put
Tychius there, of whom the poet says, "far the
best of workers in hide, who lived in Hydê."³
And they add that the place is woody and subject
to strokes of lightning, and that the Arimi live
there, for after Homer's verse, "in the land of
the Arimi where men say is the couch of
Typhon,"⁴ they insert the words, "in a wooded
place, in the fertile land of Hydê." But others lay
the scene of this myth in Cilicia, and some lay
it in Syria, and still others in the Pithecussae
Islands, who say that among the Tyrrhenians
"pitheci"⁵ are called "arimi." Some call Sardeis
Hydê, while others call its acropolis Hydê. But

¹ Thought to be the baskets carried on the heads of maidens at festivals.

² *Iliad* 2. 864.

³ *Iliad* 7. 221.

⁴ *Iliad* 2. 783.

⁵ i.e. monkeys.

² Ταλαιμένης, Corais, for Παλαιμένης *Dhrîw*, Πυλαιμένης *CEFXZ*.

³ "τῶς *Emoz*, "τλς *CDFHirwz*. Thus the MSS. vary in the following "τῶς.

⁴ Instead of "τῶς, *h*(by corr.)*orz* read "τλς.

⁵ τῶ *E* (so Meineke); οὔτως other MSS.

Σκήψιος ἡγείται τοὺς ἐν τῇ Κατακεκαυμένη τῆς Μυσίας τοὺς Ἀρίμους τιθέντας. Πίνδαρος δὲ συνοικειοῖ τοῖς ἐν τῇ Κιλικίᾳ τὰ ἐν Πιθηκούσσαις, ἅπερ ἐστὶ πρὸ τῆς Κυμαίας, καὶ τὰ ἐν Σικελίᾳ· καὶ γὰρ τῇ Αἴτνῃ φησὶν ὑποκεῖσθαι τὸν Τυφῶνα·

τόν ποτε

Κιλικίον θρέψεν πολυώνυμον ἄντρον· νῦν γε μὰν

C 627 ταί θ' ¹ ὑπὲρ Κύμας ἀλιερκές ὄχθαι
Σικελία τ' αὐτοῦ πιέζει στέρνα λαχναέντα.²

καὶ πάλιν·

κείνω μὲν Αἴτνα δεσμός ὑπερφίαλος
ἀμφίκειται.

καὶ πάλιν·

ἀλλ' οἷος ἄπλατον κεραίῳζε θεῶν
Τυφῶνα πεντηκοντακέφαλον³ ἀνάγκα Ζεὺς
πατῆρ
ἐν Ἀρίμοις ποτέ.

οἱ δὲ τοὺς Σύρους Ἀρίμους⁴ δέχονται, οὓς νῦν Ἀραμαίους λέγουσι, τοὺς δὲ Κίλικας τοὺς ἐν Τροίᾳ μεταναστάντας εἰς Συρίαν ἀνφοκισμένους, ἀποτεμεσθαι παρὰ τῶν Σύρων τὴν νῦν λεγομένην Κιλικίαν. Καλλισθένης δ' ἐγγὺς τοῦ Καλυκάδου καὶ τῆς Σαρπηδόνος ἄκρας παρ' αὐτὸ τὸ Κωρύκιον ἄντρον εἶναι τοὺς Ἀρίμους, ἀφ' ὧν τὰ ἐγγὺς ὄρη λέγεσθαι Ἄριμα.

7. Περὶκεῖται δὲ τῇ λίμνῃ τῇ Κολόῃ τὰ μνήματα τῶν βασιλέων. πρὸς δὲ ταῖς Σάρδεσιν ἐστὶ τὸ τοῦ Ἀλυσίου ἐπὶ κρηπίδος ὑψηλῆς

the Scepsian¹ thinks that those writers are most plausible who place the Arimi in the Catacecaumene country in Mysia. But Pindar associates the Pithecussae which lie off the Cymaeon territory, as also the territory in Sicily, with the territory in Cilicia, for he says that Typhon lies beneath Aetna: "Once he dwelt in a far-famed Cilician cavern; now, however, his shaggy breast is o'er-pressed by the sea-girt shores above Cymae and by Sicily."² And again, "round about him lies Aetna with her haughty fetters," and again, "but it was father Zeus that once amongst the Arimi, by necessity, alone of the gods, smote monstrous Typhon of the fifty heads."³ But some understand that the Syrians are Arimi, who are now called the Arimaecans, and that the Cilicians in Troy, forced to migrate, settled again in Syria and cut off for themselves from Syria what is now called Cilicia. Callisthenes says that the Arimi, after whom the neighbouring mountains are called Arima, are situated near Mt. Calycadnus and the promontory of Sarpedon near the Corycian cave itself.

7. Near Lake Coloë are the monuments of the kings. At Sardeis is the great mound, on a lofty base, of Alyattes, built, as Herodotus⁴ says, by the

¹ Demetrius of Scepsis.

² *Pythian Odes*, 1. 31.

³ *Frag.* 93 (Bergk).

⁴ 1. 93.

¹ Instead of μὲν ταῖς θ', CDFh have μαντευθ'.

² λαχράντα, the editors, for λαχρήντα.

³ For πεντηκοντακέφαλον, Bergk, following Hermann and Boeckh, reads ἑκατοντακέφαλον (see Pindar, *Pyth.* 8. 16 and *Ol.* 4. 7). Meineke emends to πεντηκοντακάρανον.

⁴ Ἀρίμους, Casaubon, for Ἀράμους.

χῶμα μέγα, ἐργασθέν, ὥς φησιν Ἡρόδοτος, ὑπὸ τοῦ πλήθους τῆς πόλεως, οὗ τὸ πλεῖστον ἔργον αἱ παιδίσκαι συνετέλεσαν· λέγει δ' ἐκεῖνος καὶ πορνεύεσθαι πάσας, τινὲς δὲ καὶ πόρνης μνήμα λέγουσι τὸν τάφον. χειροποίητον δὲ τὴν λίμνην ἔνιοι ἱστοροῦσι τὴν Κολοήν πρὸς τὰς ἐκδοχὰς τῶν πλημμυρίδων, αἱ συμβαίνουσι τῶν ποταμῶν πληρουμένων. Ὑπαιπα δὲ πόλις ἐστὶ καταβαίνουσιν ἀπὸ τοῦ Τμώλου πρὸς τὸ τοῦ Καῦστρου πεδίον.

8. Φησὶ δὲ Καλλισθένης ἀλῶναι τὰς Σάρδεις ὑπὸ Κιμμερίων πρῶτον, εἴθ' ὑπὸ Τρηρῶν καὶ Λυκίων, ὅπερ καὶ Καλλίνου δηλοῦν, τὸν τῆς ἐλεγείας ποιητὴν, ὕστατα δὲ τὴν ἐπὶ Κύρου καὶ Κροίσου γενέσθαι ἄλωσιν. λέγοντος δὲ τοῦ Καλλίνου τὴν ἔφοδον τῶν Κιμμερίων ἐπὶ τοὺς Ἑσιονῆας γεγονέναι, καθ' ἣν αἱ Σάρδεις ἐάλωσαν, εἰκάζουσιν οἱ περὶ τὸν Σκήψιον ἰαστὶ λέγεσθαι Ἑσιονεῖς τοὺς Ἀσιονεῖς· τάχα γὰρ ἡ Μηονία, φησὶν, Ἀσία ἐλέγετο, καθ' ἣ καὶ Ὀμηρος εἴρηκεν·

Ἀσίῳ ἐν λειμῶνι Καῦστρίου ἀμφὶ ῥέεθρα.

ἀναληφθεῖσα δ' ἀξιολόγως ὕστερον διὰ τὴν ἀρετὴν τῆς χώρας ἢ πόλις καὶ οὐδεμιᾶς λειπομένη τῶν ἀστυγειτόνων, νεωστὶ ὑπὸ σεισμῶν ἀπέβαλε πολλὰν τῆς κατοικίας. ἡ δὲ τοῦ Τιβερίου πρόνοια, τοῦ καθ' ἡμᾶς ἡγεμόνος, καὶ ταύτην καὶ τῶν ἄλλων συχνὰς ἀνέλαβε ταῖς εὐεργεσίαις, ὅσαι περὶ τὸν αὐτὸν καιρὸν ἐκοινώνησαν τοῦ αὐτοῦ πάθους.

9. Ἄνδρες δ' ἀξιόλογοι γεγονάσι τοῦ αὐτοῦ γένους Διόδωροι δύο οἱ ῥήτορες, ὧν ὁ πρεσβύτερος

common people of the city, most of the work on which was done by prostitutes; and he says that all women of that country prostituted themselves; and some call the tomb of Alyattes a monument of prostitution. Some report that Lake Coloë is an artificial lake, made to receive the overflows which take place when the rivers are full. Hypæpa is a city which one comes to on the descent from Mt. Tmolus to the Caÿster Plain.

8. Callisthenes says that Sardeis was captured first by the Cimmerians, and then by the Treres and the Lycians, as is set forth by Callinus the elegiac poet, and lastly in the time of Cyrus and Croesus. But when Callinus says that the incursion of the Cimmerians was against the Esioneis, at the time of which Sardeis was captured, the Scepsian¹ and his followers surmise that the Asioneis were by Callinus called the Esioneis, in the Ionic dialect; for perhaps Meïonia, he says, was called Asia, and accordingly Homer likewise says, "on the Asian mead about the streams of the Caÿster." The city was later restored in a notable way because of the fertility of its territory, and was inferior to none of its neighbours, though recently it has lost many of its buildings through earthquakes. However, the forethought of Tiberius, our present ruler, has, by his beneficence, restored not only this city but many others—I mean all the cities that shared in the same misfortune at about the same time.

9. Notable men of the same family were born at Sardeis: the two Diodoruses, the orators, of whom

¹ Again Demetrius of Scopsis.

ἐκαλεῖτο Ζωνᾶς, ἀνὴρ πολλοὺς ἀγῶνας ἡγωνισμένος ὑπὲρ τῆς Ἀσίας, κατὰ δὲ τὴν Μιθριδάτου τοῦ βασιλέως ἔφοδον αἰτίαν ἐσχηκώς, ὡς ἀφιστὰς παρ' αὐτοῦ¹ τὰς πόλεις, ἀπελύσατο τὰς διαβολὰς ἀπολογησάμενος· τοῦ δὲ νεωτέρου φίλου ἡμῖν γενομένου καὶ ἱστορικὰ συγγράμματά ἐστι καὶ μέλη καὶ ἄλλα ποιήματα, τὴν ἀρχαίαν γραφὴν ἐπιφαίνοντα ἱκανῶς. Ξάνθος δὲ ὁ παλαιὸς συγγραφεὺς Λυδὸς μὲν λέγεται, εἰ δὲ ἐκ Σύρδεων, οὐκ ἴσμεν.

10. Μετὰ δὲ Λυδούς εἰσιν οἱ Μυσοὶ καὶ πόλεις Φιλαδέλφεια σεισμῶν πλήρης. οὐ γὰρ διαλείπουσιν οἱ τοῖχοι διστώμενοι, καὶ ἄλλοτ' ἄλλο μέρος τῆς πόλεως κακοπαθοῦν· οἰκοῦσιν οὖν ὀλίγοι διὰ τοῦτο τὴν πόλιν, οἱ δὲ πολλοὶ καταβιοῦσιν ἐν τῇ χώρᾳ γεωργοῦντες, ἔχοντες εὐδαίμονα γῆν· ἀλλὰ καὶ τῶν ὀλίγων θαυμάζειν ἐστίν, ὅτι οὕτω φιλοχωροῦσιν, ἐπισφαλεῖς τὰς οἰκήσεις ἔχοντες· ἔτι δ' ἂν τις μᾶλλον θαυμάσειε τῶν κτισάντων αὐτήν.

11. Μετὰ δὲ ταῦτ' ἐστὶν ἡ Κατακεκαυμένη λεγόμενη χώρα μῆκος μὲν καὶ πεντακοσίων σταδίων, πλάτος δὲ τετρακοσίων, εἴτε Μυσίαν χρή καλεῖν, εἴτε Μηονίαν (λέγεται γὰρ ἀμφοτέρως), ἅπανα ἄδενδρος πλὴν ἀμπέλου τὸν Κατακεκαυμενίτην φερούσης οἶνον, οὐδενὸς τῶν ἐλλογίμων ἀρετῇ λειπόμενον. ἔστι δὲ ἡ ἐπιφάνεια τεφρώδης τῶν πεδίων, ἡ δ' ὄρεινὴ καὶ πετρώδης μέλαινα, ὡς ἂν

¹ παρ' αὐτοῦ, Xylander changes from a position between τὰς and πόλεις; so the later editors.

¹ i.e. "burnt" country, situated about the upper course

the elder was called Zonas, a man who many times pleaded the cause of Asia; and at the time of the attack of King Mithridates, he was accused of trying to cause the cities to revolt from him, but in his defence he acquitted himself of the slander. The younger Diodorus, who was a friend of mine, is the author, not only of historical treatises, but also of melic and other poems, which display full well the ancient style of writing. Xanthus, the ancient historian, is indeed called a Lydian, but whether or not he was from Sardeis I do not know.

10. After the Lydians come the Mysians; and the city Philadelphia, ever subject to earthquakes. Incessantly the walls of the houses are cracked, different parts of the city being thus affected at different times. For this reason but few people live in the city, and most of them spend their lives as farmers in the country, since they have a fertile soil. Yet one may be surprised at the few, that they are so fond of the place when their dwellings are so insecure; and one might marvel still more at those who founded the city.

11. After this region one comes to the Catacecaumene country,¹ as it is called, which has a length of five hundred stadia and a breadth of four hundred, whether it should be called Mysia or Meïonia (for both names are used); the whole of it is without trees except the vine that produces the Catacecaumenite wine, which in quality is inferior to none of the notable wines. The surface of the plains are covered with ashes, and the mountainous and rocky country

of the Hermus and its tributaries. Hamilton (*Researches*, II, p. 136), quoted by Tozer (*Selections*, p. 289), confirms Strabo's account.

ἐξ ἐπικαύσεως. εἰκάζουσι μὲν οὖν τινὲς ἐκ κεραυνοβολιῶν καὶ πρηστήρων συμβῆναι τοῦτο, καὶ οὐκ ὀκνοῦσι τὰ περὶ τὸν Τυφῶνα ἐνταῦθα μυθολογεῖν. Ξάνθος δὲ καὶ Ἀριμούν τινὰ λέγει τῶν τόπων τούτων βασιλέα. οὐκ εὐλογον δὲ ὑπὸ τοιούτων παθῶν τὴν τοσαύτην χώραν ἐμπρησθῆναι ἀθρώως, ἀλλὰ μᾶλλον ὑπὸ γηγενοῦς πυρός, ἐκλιπεῖν δὲ νῦν τὰς πηγάς· δείκνυνται δὲ καὶ βόθροι τρεῖς, οὓς φύσας καλοῦσιν, ὅσον τετταράκοντα ἀλλήλων διεστῶτες σταδίους· ὑπέρκεινται δὲ λόφοι τραχεῖς, οὓς εἰκὸς ἐκ τῶν ἀναφυσηθέντων σεσωρεῦσθαι μύδρων. τὸ δ' εὐάμπελον τὴν τοιαύτην ὑπάρχειν γῆν, λάβοι τις ἂν καὶ ἐκ τῆς Καταναίας¹ τῆς χωσθείσης τῇ σποδῷ καὶ νῦν ἀποδιδούσης οἶνον δαψιλῇ καὶ καλόν. ἀστειζόμενοι δὲ τινες, εἰκότως πυριγενῇ τὸν Διόνυσον λέγεσθαί φασιν, ἐκ τῶν τοιούτων χωρίων τεκμαιρόμενοι.

12. Τὰ δ' ἐξῆς ἐπὶ τὰ νότια μέρη τοῖς τόποις τούτοις ἐμπλοκάς ἔχει μέχρι πρὸς τὸν Ταῦρον, ὥστε καὶ τὰ Φρύγια καὶ τὰ Καρικὰ καὶ τὰ Λύδια καὶ ἔτι τὰ τῶν Μυσῶν δυσδιάκριτα εἶναι, παραπίπτοντα εἰς ἄλληλα· εἰς δὲ τὴν σύγχυσιν ταύτην οὐ μικρὰ συλλαμβάνει τὸ τοὺς Ῥωμαίους μὴ κατὰ φύλα διελεῖν αὐτούς, ἀλλὰ ἕτερον τρόπον διατάξαι τὰς διοικήσεις, ἐν αἷς τὰς ἀγοραίους ποιοῦνται καὶ τὰς δικαιοδοσίας. ὁ μὲν γε Τρωῖλος ἱκανῶς συνῆκται² καὶ περιγραφὴν ἔχει μετρίαν, ἐν αὐτοῖς ἀφοριζόμενος τοῖς Λυδίους μέρεσιν, ἡ δὲ

¹ Καταναίας, Xylander, for Κατανίας.

² συνῆκται E, συνήπται other MSS.

is black, as though from conflagration. Now some conjecture that this resulted from thunderbolts and from fiery subterranean outbursts, and they do not hesitate to lay there the scene of the mythical story of Typhon; and Xanthus adds that a certain Arimus was king of this region; but it is not reasonable to suppose that all that country was burnt all at once by reason of such disturbances, but rather by reason of an earth-born fire, the sources of which have now been exhausted. Three pits are to be seen there, which are called "bellows," and they are about forty stadia distant from each other. Above them lie rugged hills, which are reasonably supposed to have been heaped up by the hot masses blown forth from the earth. That such soil should be well adapted to the vine one might assume from the land of Catana, which was heaped with ashes and now produces excellent wine in great plenty. Some writers, judging from places like this, wittily remark that there is good reason for calling Dionysus "Pyrigenes." ¹

12. The parts situated next to this region towards the south as far as the Taurus are so inwoven with one another that the Phrygian and the Carian and the Lydian parts, as also those of the Mysians, since they merge into one another, are hard to distinguish. To this confusion no little has been contributed by the fact that the Romans did not divide them according to tribes, but in another way organised their jurisdictions, within which they hold their popular assemblies and their courts. Mt. Tmolus is a quite contracted mass of mountain and has only a moderate circumference, its limits lying within the territory of the Lydians themselves; but the Mesogis extends

Μεσωγίς¹ εἰς τὸ ἀντικείμενον μέρος διατείνει μέχρι Μυκάλης, ἀπὸ Κελαινῶν ἀρξάμενον, ὥς φησι Θεόπομπος· ὥστε τὰ μὲν αὐτοῦ Φρύγες κατέχουσι, τὰ πρὸς ταῖς Κελαιναῖς καὶ τῇ Ἀπαμείᾳ, C 629 τὰ δὲ Μυσοὶ καὶ Λυδοί, τὰ δὲ Κᾶρες καὶ Ἴωνες. οὕτω δὲ καὶ οἱ ποταμοί, καὶ μάλιστα ὁ Μαίανδρος, τὰ μὲν διορίζοντες τῶν ἐθνῶν, δι' ὧν δὲ μέσοι φερόμενοι, δύσληπτον ποιοῦσι τὰ κριβές· καὶ περὶ τῶν πεδίων δὲ τῶν ἐφ' ἑκάτερα τῆς τε ὀρεινῆς καὶ τῆς ποταμίας ὁ αὐτὸς λόγος. οὐδ' ἡμῖν ἴσως ἐπὶ τοσοῦτον φροντιστέον, ὥς ἀναγκαῖον³ χωρομετροῦσιν, ἀλλὰ τοσοῦτον μόνον ὑπογραπτέον,⁴ ὅσον καὶ οἱ πρὸ ἡμῶν παραδεδώκασι.

13. Τῷ δὲ Καῦστριανῷ πεδίῳ μεταξὺ πίπτουσι τῆς τε Μεσωγίδος⁵ καὶ τοῦ Ὑμῶλου, συνεχές ἐστι πρὸς ἑὼ τὸ Κιλιβιανὸν πεδίον, πολὺ τε καὶ συνοικούμενον εὖ καὶ χώραν ἔχον σπουδαίαν· εἴτα τὸ Ὑρκάνιον πεδίον, Περσῶν ἐπονομασάντων καὶ ἐποίκους ἀγαγόντων ἐκεῖθεν (ὁμοίως δὲ καὶ τὸ Κύρου πεδίον⁶ Πέρσαι κατωνόμασαν)· εἴτα τὸ Πελτινὸν πεδίον, ἥδη Φρύγιον, καὶ τὸ Κιλλάνιον καὶ τὸ Ταβηνόν, ἔχοντα⁷ πολίχνας μιξοφρυγίους, ἐχούσας τι καὶ Πισιδικόν, ἀφ' ὧν αὐτὰ κατωνομάσθη.

14. Ὑπερβάλλουσι δὲ τὴν Μεσωγίδα τὴν μεταξὺ Καρῶν τε καὶ τῆς Νυσαίδος, ἣ ἐστι χώρα

¹ Μεσωγίς, Palmer, μεσόγαιος F, μεσόγειος other MSS.

² οὐδ', Meineke, for οὐδ'.

³ ἀναγκαῖον, Kramer, for ἄρα κενῷ, all MSS. except F, which has ἀναγκαῖον κενῷ.

⁴ Instead of ὑπογραπτέον, Dñi have περιγραπτέον.

⁵ Μεσωγίδος, Casaubon, for μεσωγειώτιδος; so the later editors.

in the opposite direction as far as Mycalê, beginning at Celaenae, according to Theopompus. And therefore some parts of it are occupied by the Phrygians, I mean the parts near Celaenae and Apameia, and other parts by Mysians and Lydians, and other parts by Carians and Ionians. So, also, the rivers, particularly the Maeander, form the boundary between some of the tribes, but in cases where they flow through the middle of countries they make accurate distinction difficult. And the same is to be said of the plains that are situated on either side of the mountainous territory and of the river-land. Neither should I, perhaps, attend to such matters as closely as a surveyor must, but sketch them only so far as they have been transmitted by my predecessors.

13. Contiguous on the east to the Caÿster Plain, which lies between the Mesogis and the Tmolus, is the Cilbian Plain. It is extensive and well settled and has a fertile soil. Then comes the Hyrcanian Plain, a name given it by the Persians, who brought Hyrcanian colonists there (the Plain of Cyrus, likewise, was given its name by the Persians). Then come the Peltine Plain (we are now in Phrygian territory) and the Cillanian and the Tabene Plains, which have towns with a mixed population of Phrygians, these towns also containing a Pisidian element; and it is after these that the plains themselves were named.

14. When one crosses over the Mesogis, between the Carians and the territory of Nysa, which latter is

⁶ δ, after πεδίον, the editors reject.

⁷ ἔχοντα, Corais and Meineke, for ἐχοντας D^h, ἐχον τὰς other MSS.

κατὰ τὸ τοῦ Μαιάνδρου πέραν μέχρι τῆς Κιβυ-
 ράτιδος καὶ τῆς Καβαλίδος, πόλεις¹ εἰσὶ, πρὸς
 μὲν τῇ Μεσσηνίδι καταντικρὺ Λαοδικείας Ἱερά-
 πολις, ὅπου τὰ θερμὰ ὕδατα καὶ τὸ Πλουτώνιον,
 ἄμφω παραδοξολογίαν τινὰ ἔχοντα. τὸ μὲν γὰρ
 ὕδωρ οὕτω ῥαδίως εἰς πῶρον μεταβάλλει πηττό-
 μενον, ὥστ' ὀχετοὺς ἐπάγοντες φραγμοὺς ἀπεργά-
 ζονται μονολίθους, τὸ δὲ Πλουτώνιον ὑπ' ὀφρύι
 μικρᾷ τῆς ὑπερκειμένης ὀρεινῆς στομίον ἐστι
 σύμμετρον, ὅσον ἄνθρωπον δέξασθαι δυνάμενον,
 βεβᾶνται δ' ἐπὶ πολὺ· πρόκειται δὲ τούτου
 δρυφάκτωμα τετράγωνον, ὅσον ἡμιπλέθρου τὴν
 περίμετρον· τοῦτο δὲ πλήρὲς ἐστὶν ὀμιχλώδους
 παχείας ἀχλὺς, ὥστε μόγις τοῦδαφος καθορᾶν.
 τοῖς μὲν οὖν κύκλῳ πλησιάζουσι πρὸς τὸν δρύ-
 φακτον ἄλυσος ἐστὶν ὁ ἀήρ, καθαρεύων ἐκείνης
 τῆς ἀχλὺς ἐν ταῖς νηνεμίαις· συμμένει γὰρ ἐντὸς
 τοῦ περιβόλου· τῷ δ' εἰσω παρίοντι ζῶν θάνατος
 παραχρῆμα ἀπαντᾷ· ταῦροι γοῦν εἰσαχθέντες
 πίπτουσι καὶ ἐξέλκονται νεκροί, ἡμεῖς δὲ στρουθία
 ἐπέμψαμεν καὶ ἔπεσεν εὐθὺς ἐκπνεύσαντα· οἱ δ'
 ἀπόκοποι Γάλλοι παρίασιν ἀπαθεῖς, ὥστε καὶ
 μέχρι τοῦ στομίου πλησιάζειν καὶ ἐγκύπτειν καὶ
 καταδύνειν μέχρι ποσοῦ συνέχοντας ὥς ἐπὶ τὸ
 πολὺ τὸ πνεῦμα (ἐωρῶμεν γὰρ ἐκ τῆς ὀψεως
 ὥς ἂν πνιγώδους τινὸς πάθους ἔμφασιν), εἴτε

¹ δ', after πόλεις, omitted by x and the later editors.

¹ On the "Plutonia," see Vol. II, p. 442, footnote 1.

² "The road overlooks many green spots, once vineyards and gardens, separated by partitions of the same material"

a country on the far side of the Maeander extending to Cibyratis and Cabalis, one comes to certain cities. First, near the Mesogis, opposite Laodiceia, to Hierapolis, where are the hot springs and the Plutonium,¹ both of which have something marvellous about them; for the water of the springs so easily congeals and changes into stone that people conduct streams of it through ditches and thus make stone fences² consisting of single stones, while the Plutonium, below a small brow of the mountainous country that lies above it, is an opening of only moderate size, large enough to admit a man, but it reaches a considerable depth, and it is enclosed by a quadrilateral handrail, about half a plethrum in circumference, and this space is full of a vapour so misty and dense that one can scarcely see the ground. Now to those who approach the handrail anywhere round the enclosure the air is harmless, since the outside is free from that vapour in calm weather, for the vapour then stays inside the enclosure, but any animal that passes inside meets instant death. At any rate, bulls that are led into it fall and are dragged out dead; and I threw in sparrows and they immediately breathed their last and fell. But the Galli,³ who are eunuchs, pass inside with such impunity that they even approach the opening, bend over it, and descend into it to a certain depth, though they hold their breath as much as they can (for I could see in their countenances an indication of a kind of suffocating attack, as it were),—whether this immunity belongs

(Chandler, *Travels in Asia Minor*, I. p. 288), quoted by Tozer (*op. cit.*, p. 290).

³ Priests of Cybelê.

πάντων οὕτω πεπηρωμένων τοῦτο, εἴτε μόνον τῶν περὶ τὸ ἱερόν, καὶ εἴτε θεία προνοία, καθάπερ ἐπὶ τῶν ἐνθουσιασμῶν εἰκός, εἴτε ἀντιδότοις τισὶ δυνάμεσι τούτου¹ συμβαίνοντος. τὸ δὲ τῆς ἀπολιθώσεως καὶ ἐπὶ τῶν ἐν Λαοδικεῖα ποταμῶν φασὶ συμβαίνειν, καίπερ ὄντων ποτίμων. ἔστι δὲ καὶ πρὸς βαφὴν ἐρίων θαυμαστῶς σύμμετρον τὸ κατὰ τὴν Ἱεράπολιν ὕδωρ, ὥστε τὰ ἐκ τῶν ῥιζῶν βαπτόμενα ἐνάμιλλα εἶναι τοῖς² ἐκ τῆς κόκκου καὶ τοῖς ἀλουργέσιν· οὕτω δ' ἔστιν ἄφθονον τὸ πλῆθος τοῦ ὕδατος, ὥστε ἡ πόλις μεστή τῶν αὐτομάτων βαλανείων ἐστί.

15. Μετὰ δὲ τὴν Ἱεράπολιν τὰ πέραν τοῦ Μαιάνδρου, τὰ μὲν³ περὶ Λαοδίκειαν καὶ Ἀφροδισιάδα καὶ τὰ μέχρι Καρούρων εἴρηται. τὰ δ' ἐξῆς ἐστὶ τὰ μὲν πρὸς δύσιν, ἡ τῶν Ἀντιοχέων πόλις τῶν ἐπὶ Μαιάνδρῳ, τῆς Καρίας ἡδὴ· τὰ δὲ πρὸς νότον ἡ Κίβυρά ἐστιν ἡ μεγάλη καὶ ἡ Σίνδα καὶ ἡ Καβαλὶς⁴ μέχρι τοῦ Ταύρου καὶ τῆς Λυκίας. ἡ μὲν οὖν Ἀντιόχεια μετρία πόλις ἐστὶν ἐπ' αὐτῷ κειμένη τῷ Μαιάνδρῳ κατὰ τὸ πρὸς τῇ Φρυγίᾳ μέρος, ἐπέξευκται δὲ γέφυρα· χώραν δ' ἔχει πολλὴν ἐφ' ἐκάτερα τοῦ ποταμοῦ, πᾶσαν εὐδαίμονα, πλείστην δὲ φέρει τὴν καλουμένην Ἀντιοχικὴν ἰσχάδα, τὴν δὲ αὐτὴν καὶ τρίφυλλον ὀνομάζουσιν· εὐσειστος δὲ καὶ οὗτός ἐστιν ὁ τόπος. σοφιστῆς δὲ παρὰ τούτοις ἔνδοξος γεγένη-

¹ Instead of τούτου, Dñi and Corais read οὕτω.

² τοῖς Fix, τὰς other MSS.

³ After μὲν, E and Meineke read οὖν.

⁴ Καβαλὶς, the editors, for Καβαλαῖς, all MSS. except Dñ, which read Καβαλαῖς.

to all who are maimed in this way or only to those round the temple, or whether it is because of divine providence, as would be likely in the case of divine obsessions, or whether it is the result of certain physical powers that are antidotes against the vapour. The changing of water into stone is said also to be the case with the rivers in Laodiceia, although their water is potable. The water at Hierapolis is remarkably adapted also to the dyeing of wool, so that wool dyed with the roots¹ rivals that dyed with the coccus² or with the marine purple.³ And the supply of water is so abundant that the city is full of natural baths.

15. After Hierapolis one comes to the parts on the far side of the Maeander; I have already described⁴ those round Laodiceia and Aphrodisias and those extending as far as Carura. The next thereafter are the parts towards the west, I mean the city of the Antiocheians on the Maeander, where one finds himself already in Caria, and also the parts towards the south, I mean Greater Cibyra and Sinda and Cabalis, extending as far as the Taurus and Lycia. Now Antiocheia is a city of moderate size, and is situated on the Maeander itself in the region that lies near Phrygia, and there is a bridge over the river. Antiocheia has considerable territory on each side of the river, which is everywhere fertile, and it produces in greatest quantities the "Antiocheian" dried fig, as it is called, though they also name the same fig "three-leaved." This region, too, is much subject to earthquakes. Among these people

¹ Madder-root.

² Kermes-berries.

³ Using this particular water, of course.

⁴ 12. 8. 13, 16, 17.

ται Διοτρέφης, οὗ διήκουσεν Ἵβρέας, ὁ καθ' ἡμᾶς γενόμενος μέγιστος ῥήτωρ.

16. Σολύμους δ' εἶναι φασὶ τοὺς Καβαλεῖς.¹ τῆς γοῦν Τερμησσέων² ἄκρας ὁ ὑπερκείμενος λόφος καλεῖται Σόλυμος, καὶ αὐτοὶ δὲ οἱ Τερμησσεῖς³ Σόλυμοι καλοῦνται. πλησίον δ' ἐστὶ καὶ ὁ Βελλεροφόντου χάραξ καὶ ὁ Πεισάνδρου τάφος τοῦ υἱοῦ, πεσόντος ἐν τῇ πρὸς Σολύμους μάχῃ. ταῦτα δὲ καὶ τοῖς⁴ ὑπὸ τοῦ ποιητοῦ λεγομένοις ὁμολογεῖται· περὶ μὲν γὰρ τοῦ Βελλεροφόντου φησὶν οὕτως·

δεύτερον αὖ Σολύμοισι μαχέσσατο κυδαλίμοισι·
περὶ δὲ τοῦ παιδὸς αὐτοῦ·

C 631 Πείσανδρον⁵ δὲ οἱ υἱὸν Ἄρης ἄτος πολέμοιο
μαρνάμενον Σολύμοισι κατέκτανεν.

ἡ δὲ Τερμησσός ἐστι Πισιδικὴ πόλις ἡ μάλιστα καὶ ἔγγιστα ὑπερκειμένη τῆς Κιβύρας.

17. Λέγονται δὲ ἀπόγονοι Λυδῶν οἱ Κιβυράται τῶν κατασχόντων τὴν Καβαλίδαν,⁶ ὕστερον δὲ Πισιδῶν τῶν ὁμόρων οἰκισάντων⁷ καὶ μετακτισάντων εἰς ἕτερον τόπον εὐερέεστατον ἐν κύκλῳ σταδίων περὶ ἑκατόν. ἠϋξήθη δὲ διὰ τὴν εὐνομίαν, καὶ αἱ κῶμαι παρεξέτειναν ἀπὸ Πισιδίας καὶ τῆς ὁμόρου Μιλυάδος⁸ ἕως Λυκίας καὶ τῆς Ῥοδίων

¹ Καβαλεῖς x, Καβαλλεῖς other MSS.

² Τερμησσέων, Corais, for Τερμησέως CDF¹moxx, Τελμήσσεως rw, Τελμισσέων E.

³ Instead of Τερμησσεῖς, CDF¹hx read Τελμησεῖς, rw Τελμησσεῖς, Eί Τελμισεῖς.

⁴ δὲ καὶ τοῖς, Corais, for δ' ἐκάστοις CDF¹hίrw, δ' ἐκάστοις τοῖς x, δ' ἕκαστα τοῖς, δὲ τοῖς nww.

arose a famous sophist, Diotrephes, whose complete course was taken by Hybreas, who became the greatest orator of my time.

16. The Cabaleis are said to be the Solymi; at any rate, the hill that lies above the fortress of the Termessians is called Solymus, and the Termessians themselves are called Solymi. Near by is the Palisade of Bellerophon, and also the tomb of his son Peisander, who fell in the battle against the Solymi. This account agrees also with the words of the poet, for he says of Bellerophon, "next he fought with the glorious Solymi,"¹ and of his son, "and Peisander² his son was slain by Ares, insatiate of war, when he was fighting with the Solymi."³ Termessus is a Pisidian city, which lies directly above Cibra and very near it.

17. It is said that the Cibratae are descendants of the Lydians who took possession of Cabalis, and later of the neighbouring Pisidians, who settled there and transferred the city to another site, a site very strongly fortified and about one hundred stadia in circuit. It grew strong through its good laws; and its villages extended alongside it from Pisidia and the neighbouring Milyas as far as Lycia and the Peraea⁴ of the Rhodians. Three bordering

¹ *Iliad* 6. 184.

² The Homeric text reads "Isander" (see 12. 8. 5).

³ *Iliad* 6. 203.

⁴ Mainland territory.

⁵ Instead of Πείσανδρον, E reads Πίσανδρον. The Homeric text has "Isander".

⁶ Καβαλλίδα, the editors, for Καβαλλίδα.

⁷ D^Fhorz read οκησάντων.

⁸ Μιλυδοι, Tzschucke, for Μυλιδος.

περαίας· προσγενομένων δὲ τριῶν πόλεων ὁμόρων, Βουβῶνος,¹ Βαλβούρων, Οἰνοάνδων,² τετράπολις τὸ σύστημα ἐκλήθη, μίαν ἐκάστης ψῆφον ἔχουσης, δύο δὲ τῆς Κιβύρας· ἔστελλε γὰρ αὕτη πεζῶν μὲν τρεῖς μυριάδας, ἱππέας δὲ δισχιλίους· ἐτυραννεῖτο δ' αἰεὶ, σωφρόνως δ' ὁμως· ἐπὶ Μοαγέτου δ' ἡ τυραννὶς τέλος ἔσχε, καταλύσαντος αὐτὴν Μουρηναῖ καὶ Λυκίοις προσορίσαντος τὰ Βάλβουρα καὶ τὴν Βουβῶνα· οὐδὲν δ' ἦττον ἐν ταῖς μεγίσταις ἐξετάζεται διοικήσεσι τῆς Ἀσίας ἢ Κιβυρατικῇ. τέτταρσι δὲ γλώτταις ἐχρῶντο οἱ Κιβυράται, τῇ Πισιδικῇ, τῇ Σολύμῳ, τῇ Ἑλληνίδι, τῇ Λυδῶν· τῆς Λυδῶν³ δὲ οὐδ' ἵχνος ἐστὶν ἐν Λυδίᾳ. ἴδιον δ' ἐστὶν ἐν Κιβύρα τὸ τὸν σίδηρον τορεῦσθαι ῥαδίως. Μιλύα⁴ δ' ἐστὶν ἢ ἀπὸ τῶν κατὰ Τερμησσὸν στενῶν καὶ τῆς εἰς τὸ ἐντὸς τοῦ Ταύρου ὑπερθέσεως δι' αὐτῶν ἐπὶ Ἰσινδα παρατείνουσα ὁρεινὴ μέχρι Σαγαλασσοῦ καὶ τῆς Ἀπαμέων χώρας.

¹ Βουβῶνος, Tzschucke, for Βουβούρων C, Βουβάνων other MSS.

² Οἰνοάνδων, Tzschucke, for Οἰνοάνδρου.

³ τῆς Λυδῶν, Müller-Dübner insert; νῦν ἰ, ταύτης certain editors.

cities were added to it, Bubon, Balbura, and Oenoanda, and the union was called Tetrapolis, each of the three having one vote, but Cibyra two; for Cibyra could send forth thirty thousand foot-soldiers and two thousand horse. It was always ruled by tyrants; but still they ruled it with moderation. However, the tyranny ended in the time of Moagetes, when Murena overthrew it and included Balbura and Bubon within the territory of the Lycians. But none the less the jurisdiction of Cibyra is rated among the greatest in Asia. The Cibyratae used four languages, the Pisidian, that of the Solymi, Greek, and that of the Lydians;¹ but there is not even a trace of the language of the Lydians in Lydia. The easy embossing of iron is a peculiar thing at Cibyra. Milya is the mountain-range extending from the narrows at Termessus and from the pass that leads over through them to the region inside the Taurus towards Isinda, as far as Sagalassus and the country of the Apameians.

¹ See A. H. Sayce, *Anatolian Studies presented to Sir William Mitchell Ramsay*, p. 396.

² Instead of Μιλία, DE read Μυλία, or Μιλία.



BOOK XIV

ΙΔ'

I

C 632 1. Λοιπὸν δ' ἐστὶν εἰπεῖν περὶ Ἰώνων καὶ Καρῶν καὶ τῆς ἔξω τοῦ Ταύρου παραλίας, ἣν ἔχουσι Λύκιοί τε καὶ Πάμφυλοι¹ καὶ Κίλικες· οὕτω γὰρ ἂν ἔχοι τέλος ἡ πᾶσα τῆς χερρονήσου περιήγησις, ἥς ἰσθμὸν ἔφαμεν τὴν ὑπέρβασιν τὴν ἐκ τῆς Ποντικῆς θαλάττης ἐπὶ τὴν Ἰσικὴν.

2. Ἔστι δὲ τῆς Ἰωνίας ὁ μὲν περίπλους ὁ παρὰ γῆν σταδίων που τρισχιλίων τετρακοσίων τριάκοντα διὰ τοὺς κόλπους καὶ διὰ τὸ χερρονησίζειν ἐπὶ πλεῖον τὴν χώραν, τὸ δ' ἐπ' εὐθείας μῆκος οὐ πολὺ. αὐτὸ οὖν τὸ ἐξ Ἐφέσου μέχρι Σμύρνης ὁδὸς μὲν ἐστὶν ἐπ' εὐθείας τριακόσιοι εἴκοσι στάδιοι· εἰς γὰρ Μητρόπολιν ἑκατὸν καὶ εἴκοσι στάδιοι, οἱ λοιποὶ δὲ εἰς Σμύρναν, περίπλους δὲ μικρὸν ἀπολείπων τῶν δισχιλίων καὶ διακοσίων. ἐστὶ δ' οὖν ἀπὸ τοῦ Ποσειδίου τοῦ Μιλησίων καὶ τῶν Καρικῶν ὄρων² μέχρι Φωκαίας καὶ τοῦ Ἑρμου τὸ πέρας τῆς Ἰωνικῆς παραλίας.

3. Ταύτης δὲ φησι Φερεκύδης Μίλητον μὲν καὶ Μυοῦντα καὶ τὰ περὶ Μυκάλην καὶ Ἐφεσον

¹ Πάμφυλοι DF; Παμφύλιοι other MSS.

² ὄρων, Groskurd, for ὄρων; so the later editors.

¹ For map of Asia Minor, see Vol. V (at end).

BOOK XIV

I

1.¹ It remains for me to speak of the Ionians and the Carians and the seaboard outside the Taurus, which last is occupied by Lycians, Pamphylians, and Cilicians; for in this way I can finish my entire description of the peninsula, the isthmus of which, as I was saying,² is the road which leads over from the Pontic Sea to the Issic Sea.

2. The coasting voyage round Ionia is about three thousand four hundred and thirty stadia, this distance being so great because of the gulfs and the fact that the country forms a peninsula of unusual extent; but the distance in a straight line across the isthmus is not great. For instance, merely the distance from Ephesus to Smyrna is a journey, in a straight line, of three hundred and twenty stadia, for the distance to Metropolis is one hundred and twenty stadia and the remainder to Smyrna, whereas the coasting voyage is but slightly short of two thousand two hundred. Be that as it may, the bounds of the Ionian coast extend from the Poseidium of the Milesians, and from the Carian frontiers, as far as Phocaea and the Hermus River, which latter is the limit of the Ionian seaboard.

3. Pherecydes says concerning this seaboard that Miletus and Myus and the parts round Mycalê and

² 12. 1. 3.

Κᾶρας ἔχειν πρότερον, τὴν δ' ἐξῆς παραλίαν
 μέχρι Φωκαίας καὶ Χίου καὶ Σάμου,¹ ἧς Ἀγκαῖος
 ἦρχε, Δέλεγας· ἐκβληθῆναι δ' ἀμφοτέρους ὑπὸ
 τῶν Ἰώνων, καὶ εἰς τὰ λοιπὰ μέρη τῆς Καρίας
 ἐκπεσεῖν. ἄρξαι δέ φησιν Ἀνδροκλον τῆς τῶν
 Ἰώνων ἀποικίας, ὕστερον τῆς Αἰολικῆς, υἱὸν
 γνήσιον Κόδρου τοῦ Ἀθηνῶν βασιλέως, γενέσθαι
 C 633 δὲ τοῦτον Ἐφέσου κτίστην· διόπερ τὸ βασιλείου
 τῶν Ἰώνων ἐκεῖ συστήναί φασι· καὶ ἔτι νῦν οἱ
 ἐκ τοῦ γένους ὀνομάζονται βασιλεῖς, ἔχοντές τινας
 τιμὰς, προεδρίαν τε ἐν ἀγῶσι καὶ πορφύραν ἐπί-
 σσημον τοῦ βασιλικοῦ γένους, σκίπωνα ἀντὶ σκῆπ-
 τρου, καὶ τὰ ἱερὰ τῆς Ἐλευσινίας Δήμητρος. καὶ
 Μίλητον δ' ἐκτίσεν Νηλεὺς ἐκ Πύλου τὸ γένος
 ὦν· οἳ τε Μεσσήνιοι καὶ οἱ Πύλιοι συγγενείαν
 τινα προσποιοῦνται, καθ' ἣν καὶ Μεσσήνιον τὸν
 Νέστορα οἱ νεώτεροί φασι ποιηταί, καὶ τοῖς περὶ
 Μελανθον τὸν Κόδρου πατέρα πολλοὺς καὶ τῶν
 Πυλίων συνεξᾶραί φασιν εἰς τὰς Ἀθήνας· τοῦτον
 δὴ πάντα τὸν λαὸν μετὰ τῶν Ἰώνων κοινῇ στεῖλαι
 τὴν ἀποικίαν. τοῦ δὲ Νηλέως ἐπὶ τῷ Ποσειδίῳ
 βωμὸς ἱδρυμα δέικνυται. Κυδρῆλος δὲ νόθος
 υἱὸς Κόδρου Μυῦντα κτίζει· Ἀνδρόπομπος δὲ
 Λέβεδον, καταλαβόμενος τόπον τινὰ Ἀρτιν-
 Κολοφῶνα δ' Ἀνδραίμων² Πύλιος, ὥς φησι καὶ
 Μίμνερμος ἐν Ναννοῦ· Πιρήνην δ' Αἴπυτος ὁ
 Νηλέως, εἴθ' ὕστερον Φιλώτας ἐκ Θηβῶν λαὸν
 ἀγαγών· Τέω δὲ Ἀθάμας μὲν πρότερον, διόπερ
 Ἀθαμαντίδα καλεῖ αὐτὴν Ἀνακρέων, κατὰ δὲ

¹ For Χίου and Σάμου Kramer conj. Χίου and Σάμου.

² Ἀνδρεμῶν C^Fszcz.

³ A fragment (Bergk 10) otherwise unknown.

Ephesus were in earlier times occupied by Carians, and that the coast next thereafter, as far as Phocaea and Chios and Samos, which were ruled by Ancaeus, was occupied by Leleges, but that both were driven out by the Ionians and took refuge in the remaining parts of Caria. He says that Androclus, legitimate son of Codrus the king of Athens, was the leader of the Ionian colonisation, which was later than the Aeolian, and that he became the founder of Ephesus; and for this reason, it is said, the royal seat of the Ionians was established there. And still now the descendants of his family are called kings; and they have certain honours, I mean the privilege of front seats at the games and of wearing purple robes as insignia of royal descent, and staff instead of sceptre, and of the superintendence of the sacrifices in honour of the Eleusinian Demeter. Miletus was founded by Neleus, a Pylian by birth. The Messenians and the Pylians pretend a kind of kinship with one another, according to which the more recent poets call Nestor a Messenian; and they say that many of the Pylians accompanied Melanthus, father of Codrus, and his followers to Athens, and that, accordingly, all this people sent forth the colonising expedition in common with the Ionians. There is an altar, erected by Neleus, to be seen on the Poseidium. Myus was founded by Cydrelus, bastard son of Codrus; Lebedus by Andropompus, who seized a place called Artis; Colophon by Andraemon a Pylian, according to Mimnermus in his *Nanno*; ¹ Priênê by Aepytus the son of Neleus, and then later by Philotas, who brought a colony from Thebes; Teos, at first by Athamas, for which reason it is by Anacreon called Athamantis, and at

τὴν Ἰωνικὴν ἀποικίαν Ναυκλος υἱὸς Κόδρου νόθος, καὶ μετὰ τοῦτον Ἀποικος¹ καὶ Δάμασος Ἀθηναῖοι καὶ Γέρης² ἐκ Βοιωτῶν. Ἐρυθρὰς δὲ Κυνῶπος, καὶ οὗτος υἱὸς Κόδρου νόθος. Φωκαῖαν δ' οἱ μετὰ Φιλογένους Ἀθηναῖοι. Κλαζομενὰς δὲ Πάραλος. Χίον δὲ Ἐγέρτιος, σύμμικτον ἐπαγόμενος πλῆθος. Σάμον δὲ Τεμβρίων,³ εἴθ' ὕστερον Προκλῆς.⁴

4. Αὗται μὲν δώδεκα Ἰωνικαὶ πόλεις, προσελήφθη δὲ χρόνοις ὕστερον καὶ Σμύρνα, εἰς τὸ Ἰωνικὸν ἐναγαγόντων Ἐφεσίων. ἦσαν γὰρ αὐτοῖς σύνοικοι τὸ παλαιόν, ἥνικα καὶ Σμύρνα ἐκαλεῖτο ἢ Ἐφεσος. καὶ Καλλίνος που οὕτως ὠνόμακεν αὐτήν, Σμυρναίους τοὺς Ἐφεσίους καλῶν ἐν τῷ πρὸς τὸν Δία λόγῳ.

Σμυρναίους δ' ἐλέησον
καὶ πάλιν

μῆσαι δ' εἴκοτέ τοι μηρία καλὰ βοῶν
Σμυρναῖοι κατέκηαν.⁵

Σμύρνα δ' ἦν Ἀμαζῶν ἡ κατασχοῦσα τὴν Ἐφεσον, ἀφ' ἧς τοῦνομα καὶ τοῖς ἀνθρώποις καὶ τῇ πόλει, ὥς καὶ ἀπὸ Σισύρβης Σισυρβίται τινες τῶν Ἐφεσίων ἐλέγοντο. καὶ τόπος δέ τις τῆς Ἐφέσου Σμύρνα ἐκαλεῖτο, ὥς δηλοῖ Ἰππῶνας.

ᾧκει δ' ὀπισθε τῆς πόλεως ἐν Σμύρῃ
μεταξὺ Τρηχείης τε καὶ Λεπρῆς ἀκτῆς.

ἐκαλεῖτο γὰρ Λεπρὴ μὲν ἀκτὴ ὁ Πριῶν ὁ ὑπερκείμενος τῆς νῦν πόλεως, ἔχων μέρος τοῦ τείχους αὐτῆς. τὰ γοῦν ὀπισθεν τοῦ Πριῶνος κτήματα

¹ Ἀποικος, Tzachucke, for Πολικης F, Πόικης α, Πολικης other MSS.

the time of the Ionian colonisation by Naucelus, bastard son of Codrus, and after him by Apoeucus and Damasus, who were Athenians, and Geres, a Boeotian; Erythrae by Cnopus, he too a bastard son of Codrus; Phocaea by the Athenians under Philogenes; Clazomenae by Paralus; Chios by Egertius, who brought with him a mixed crowd; Samos by Tembrion, and then later by Procles.

4. These are the twelve Ionian cities,¹ but at a later time Smyrna was added, being induced by the Ephesians to join the Ionian League; for the Ephesians were fellow-inhabitants of the Smyrnaeans in ancient times, when Ephesus was also called Smyrna. And Callinus somewhere so names it, when he calls the Ephesians Smyrnaeans in the prayer to Zeus, "and pity the Smyrnaeans"; and again, "remember, if ever the Smyrnaeans burnt up beautiful thighs of oxen in sacrifice to thee."² Smyrna was an Amazon who took possession of Ephesus; and hence the name both of the inhabitants and of the city, just as certain of the Ephesians were called Sisyrbitae after Sisyrbê. Also a certain place belonging to Ephesus was called Smyrna, as Hipponax plainly indicates: "He lived behind the city in Smyrna between Tracheia and Lepra Actê";³ for the name Lepra Actê was given to Mt. Prion, which lies above the present city and has on it a part of the city's wall. At any rate, the possessions behind Prion

¹ S. 7. 1. ² *Frag.* 2 (Bergk). ³ *Frag.* 44 (Bergk).

² Γέρης, the editors, for γὰρ ἦν.

³ Τρυβρίων, the editors, for Τημεβρίων.

⁴ Instead of Προκλήτ, *most* read Πατροκλήτ (cp. *Etym. Mag.* s.v.).

⁵ Σμυρναῖοι κατέκταν, Jones inserts, from conj. of Corais.

Q 634 ἔτι νυνὶ λέγεται ἐν τῇ Ὀπισθολεπρία· Τραχεῖα δ' ἐκαλεῖτο ἢ περὶ τὸν Κορησσὸν παρώρειος. ἢ δὲ πόλις ἦν τὸ παλαιὸν περὶ τὸ Ἀθηναίων τὸ νῦν ἔξω τῆς πόλεως ὅν κατὰ τὴν καλουμένην Ὑπέλαιον, ὥστε ἡ Σμύρνα ἦν κατὰ τὸ νῦν γυμνάσιον ὅπισθεν μὲν τῆς νῦν¹ πόλεως, μεταξὺ δὲ Τρηχείης τε καὶ Λεπρῆς² ἀκτῆς. ἀπελθόντες δὲ παρὰ τῶν Ἐφεσίων οἱ Σμυρναῖοι στρατεύουσιν ἐπὶ τὸν τόπον, ἐν ᾧ νῦν ἐστὶν ἡ Σμύρνα, Δελέγων κατεχόντων· ἐκβαλόντες δ' αὐτοὺς ἐκτίσαν τὴν παλαιὰν Σμύρναν, διέχουσιν τῆς νῦν περὶ εἴκοσι σταδίους. ὕστερον δὲ ὑπὸ Αἰολέων ἐκπεσόντες κατέφυγον εἰς Κολοφῶνα, καὶ μετὰ τῶν ἐνθένδε ἐπιόντες τὴν σφετέραν ἀπέλαβον· καθάπερ καὶ Μίμνερμος ἐν τῇ Ναννοῖ φράζει, μνησθεὶς τῆς Σμύρνης, ὅτι περιμάχητος αἶ·

ἡμεῖς αἰπὺ³ Πύλου⁴ Νηλήιον ἄστνυ λιπόντες
ἱμερτήν Ἀσίην νηυσὶν ἀφικόμεθα.

ἐς δ' ἐρατὴν⁵ Κολοφῶνα βίην ὑπέροπλον
ἔχοντες

ἐξόμεθ' ἀργαλέης ὕβριος ἡγεμόνες.

κεῖθεν δ' Ἀστήεντος⁶ ἀπορνύμενοι ποταμοῖο
θεῶν βουλῇ Σμύρναν εἵλομεν⁷ Αἰολίδα.

ταῦτα μὲν περὶ τούτων· ἐφοδευτέον δὲ πάλιν τὰ
καθ' ἕκαστα, τὴν ἀρχὴν ἀπὸ τῶν ἡγεμονικωτέρων

¹ Instead of νῦν, F reads ποτε; whence Kramer conj. ποτε and Meineke reads τότε.

² Λεπρῆς, the editors, for Λεπρίης.

³ Instead of αἰπύ, F reads ἐπεί; τε, after αἰπύ, the editors since Hopper omit, except Meineke, who writes ἡμεῖς δηῶτε for αἰπύ τε.

⁴ Πύλου Bergk, for Πύλον, which latter Meineke retains.

are still now referred to as in the "opistholeprian" territory,¹ and the country alongside the mountain round Coressus was called "Tracheia."² The city was in ancient times round the Athenaeum, which is now outside the city near the Hypelaëus,³ as it is called; so that Smyrna was near the present gymnasium, behind the present city, but between Tracheia and Lepra Actê. On departing from the Ephesians, the Smyrnacans marched to the place where Smyrna now is, which was in the possession of the Leleges, and, having driven them out, they founded the ancient Smyrna, which is about twenty stadia distant from the present Smyrna. But later, being driven out by the Aeolians, they fled for refuge to Colophon, and then with the Colophonians returned to their own land and took it back, as Mimnermus tells us in his *Nanno*, after recalling that Smyrna was always an object of contention: "After we left Pylus, the steep city of Neleus, we came by ship to lovely Asia, and with our overweening might settled in beloved Colophon, taking the initiative in grievous insolence. And from there, setting out from the Astêcis River, by the will of the gods we took Aeolian Smyrna."⁴ So much, then, on this subject. But I must again go over the several parts in detail,

¹ i.e. in the territory "behind Lepra."

² i.e. "Rugged" country.

³ A fountain.

⁴ *Frag.* 9 (Bergk).

⁵ ἐρατήν, Wytttenbach, for ἔρα τήν; so the editors.

⁶ δ' Ἀσθήεντος is doubtful (see C. Müller, *Ind. Var. Lect.* p. 1028); C¹For read διασθήεντος; the editors before Kramer, δ' Ἀστυέντος.

⁷ ἔλθομεν, Clavier, for εἰδομεν; so the editors.

τόπων ποιησαμένους, ἐφ'¹ ὥνπερ καὶ πρῶτον αἱ κτίσεις ἐγένοντο, λέγω δὲ τῶν περὶ Μίλητον καὶ Ἐφεσον· αὗται γὰρ ἄρισται πόλεις καὶ ἐνδοξόταται.

5. Μετὰ δὲ τὸ Ποσειδίου τὸ Μιλησίων ἐξῆς ἐστὶ τὸ μαντεῖον τοῦ Διδυμέως Ἀπόλλωνος τὸ ἐν Βραγχίδαις, ἀναβάντι ὅσον ὀκτωκαίδεκα σταδίους· ἐνεπρήσθη δ' ὑπὸ Ξέρξου, καθάπερ καὶ τὰ ἄλλα ἱερὰ πλὴν τοῦ ἐν Ἐφέσῳ· οἱ δὲ Βραγχίδαι τοὺς θησαυροὺς τοῦ θεοῦ παραδόντες τῷ Πέρσῃ φεύγουσι συναπῆραν, τοῦ μὴ τίσαι δίκας τῆς ἱεροσυλίας καὶ τῆς προδοσίας. ὕστερον δ' οἱ Μιλήσιοι μέγιστον νεὼν τῶν πάντων κατεσκεύασαν, διέμεινε δὲ χωρὶς ὀροφῆς διὰ τὸ μέγεθος· κώμης γοῦν κατοικίαν ὁ τοῦ σηκοῦ περίβολος δέδεκται καὶ ἄλλος ἐντὸς τε καὶ ἐκτὸς πολυτελής· ἄλλοι δὲ σηκοὶ τὸ μαντεῖον καὶ τὰ ἱερὰ συνέχουσιν· ἐνταῦθα δὲ μυθεύεται τὰ περὶ τὸν Βράγχον καὶ τὸν ἔρωτα τοῦ Ἀπόλλωνος· κεκόσμηται δ' ἀναθήμασι τῶν ἀρχαίων τεχνῶν πολυτελέστατα· ἐντεῦθεν δ' ἐπὶ τὴν πόλιν οὐ πολλὴ ὁδὸς ἐστίν, οὐδὲ πλοῦς.

6. Φησὶ δ' Ἐφορος τὸ πρῶτον κτίσμα εἶναι Κρητικόν, ὑπὲρ τῆς θαλάττης τετειχισμένον, ὅπου νῦν ἡ πάλαι Μίλητός ἐστι, Σαρπηδόνος ἐκ Μιλήτου τῆς Κρητικῆς ἀγαγόντος οἰκήτορας καὶ
C 635 θεμένου τοῦνομα τῇ πόλει τῆς ἐκεῖ πόλεως ἐπώνυμον, κατεχόντων πρότερον Λελέγων τὸν τόπον· τοὺς δὲ περὶ Νηλέα ὕστερον τὴν νῦν τειχίσαι πόλιν. ἔχει δὲ τέτταρας λιμένας ἡ νῦν, ὧν ἓνα καὶ στόλφ' ἱκανόν. πολλὰ δὲ τῆς πόλεως ἔργα

¹ ἐφ', Corais, for ἀφ'.

beginning with the principal places, those where the foundings first took place, I mean those round Miletus and Ephesus; for these are the best and most famous cities.

5. Next after the Poseidion of the Milesians, eighteen stadia inland, is the oracle of Apollo Didymeus among the Branchidae.¹ It was set on fire by Xerxes, as were also the other temples, except that at Ephesus. The Branchidae gave over the treasures of the god to the Persian king, and accompanied him in his flight in order to escape punishment for the robbing and the betrayal of the temple. But later the Milesians erected the largest temple in the world, though on account of its size it remained without a roof. At any rate, the circuit of the sacred enclosure holds a village settlement; and there is a magnificent sacred grove both inside and outside the enclosure; and other sacred enclosures contain the oracle and the shrines. Here is laid the scene of the myth of Branchus and the love of Apollo. The temple is adorned with costliest offerings consisting of early works of art. Thence to the city is no long journey, by land or by sea.

6. Ephorus says: Miletus was first founded and fortified above the sea by the Cretans, where the Miletus of olden times is now situated, being settled by Sarpedon, who brought colonists from the Cretan Miletus and named the city after that Miletus, the place formerly being in the possession of the Leleges; but later Neleus and his followers fortified the present city. The present city has four harbours, one of which is large enough for a fleet. Many are

¹ i.e. at Didyma. On this temple see Herod. 1. 46, 5. 36, 6. 19.

ταύτης, μέγιστον δὲ τὸ πλῆθος τῶν ἀποικιῶν.¹ ὁ τε γὰρ Εὐξείνιος πόντος ὑπὸ τούτων συνώκισται πᾶς καὶ ἡ Προποντὶς καὶ ἄλλοι πλείους τόποι. Ἀναξιμένης γοῦν ὁ Λαμψακηνὸς οὕτω φησίν, ὅτι καὶ Ἰκαρον τὴν νῆσον καὶ Λέρον Μιλήσιοι συνώκισαν καὶ περὶ Ἑλλήσποντον ἐν μὲν τῇ Χερρονήσῳ Λίμνας, ἐν δὲ τῇ Ἀσίᾳ Ἀβυδον, Ἀρισβαν, Παισόν· ἐν δὲ τῇ Κυζικηνῶν νήσῳ Ἀρτάκην, Κύζικον· ἐν δὲ τῇ μεσογαίᾳ τῆς Τρωάδος Σκῆψιν· ἡμεῖς δ' ἐν τοῖς καθ' ἕκαστα λέγομεν καὶ τὰς ἄλλας τὰς ὑπὸ τούτου παραλελειμμένας. Οὐλίον δ' Ἀπόλλωνα καλοῦσιν τινα καὶ Μιλήσιοι καὶ Δήλιοι, οἷον ὑγιαστικὸν καὶ παιωνικόν· τὸ γὰρ οὐλεῖν ὑγιαίνειν, ἀφ' οὗ καὶ τὸ οὐλή. καὶ τὸ

οὐλέ τε καὶ μέγα² χαίρε·

ἰατρικὸς γὰρ ὁ Ἀπόλλων· καὶ ἡ Ἀρτεμις ἀπὸ τοῦ ἀρτεμέας ποιεῖν· καὶ ὁ Ἥλιος δὲ καὶ ἡ Σελήνη συνοικεῖονται τούτοις, ὅτι τῆς περὶ τοὺς ἀέρας εὐκρασίας αἵτιοι· καὶ τὰ λοιμικὰ δὲ πάθη καὶ τοὺς αὐτομάτους θανάτους τούτοις ἀνάπτουσι τοῖς θεοῖς.

7. Ἄνδρες δ' ἄξιοι μνήμης ἐγένοντο ἐν τῇ Μιλήτῳ Θαλῆς τε, εἰς τῶν ἐπτὰ σοφῶν, ὁ πρῶτος φυσιολογίας ἄρξας ἐν τοῖς Ἑλλησι καὶ μαθηματικῆς, καὶ ὁ τούτου μαθητὴς Ἀναξίμανδρος καὶ ὁ τούτου πάλιν Ἀναξιμένης, ἔτι δ' Ἐκαταῖος ὁ τὴν ἱστορίαν συντάξας, καθ' ἡμᾶς δὲ Αἰσχίνης

¹ ἀποικιῶν, *x* and the editors, instead of ἀποίκων.

² The Homeric text has μάλα instead of μέγα.

¹ *i.e.* a "healed wound"; also a "scar."

² *i.e.* "safe and sound." ³ The Sun-god.

the achievements of this city, but the greatest is the number of its colonisations; for the Euxine Pontus has been colonised everywhere by these people, as also the Propontis and several other regions. At any rate, Anaximenes of Lampsacus says that the Milesians colonised the islands Icaros and Leros; and, near the Hellespont, Limnae in the Chersonesus, as also Abydus and Arisba and Paesus in Asia; and Artacé and Cyzicus in the island of the Cyziceni; and Scepsis in the interior of the Troad. I, however, in my detailed description speak of the other cities, which have been omitted by him. Both Milesians and Delians invoke an Apollo "Ulius," that is, as god of "health and healing," for the verb "ulein" means "to be healthy"; whence the noun "ulé"¹ and the salutation, "Both health and great joy to thee"; for Apollo is the god of healing. And Artemis has her name from the fact that she makes people "Artemeas."² And both Helios³ and Selené⁴ are closely associated with these, since they are the causes of the temperature of the air. And both pestilential diseases and sudden deaths are imputed to these gods.

7. Notable men were born at Miletus: Thales, one of the Seven Wise Men, the first to begin the science of natural philosophy⁵ and mathematics among the Greeks, and his pupil Anaximander, and again the pupil of the latter, Anaximenes, and also Hecataeus, the author of the *History*, and, in my time, Aeschines the orator, who remained in exile

¹ The Moon-goddess.

² Literally "physiology," which again shows the perversion of Greek scientific names in English (cf. Vol. I, p. 27, footnote 2).

ὁ ῥήτωρ, ὃς ἐν φυγῇ διετελέεσε, παρρησιασάμενος
 πέρα τοῦ μετρίου πρὸς Πομπήιον Μάγνον. ἡτύ-
 χησε δ' ἡ πόλις, ἀποκλείσασα Ἀλέξανδρον καὶ
 βία ληφθεῖσα, καθάπερ καὶ Ἀλικαρνασός· ἔτι δὲ
 πρότερον ὑπὸ Περσῶν· καὶ φησί γε Καλλισθένης,
 ὑπ' Ἀθηναίων χιλίαις δραχμαῖς ζημιωθῆναι Φρύ-
 νιχον τὸν τραγικόν, διότι δρᾶμα ἐποίησε Μιλήτου
 ἄλωσιν ὑπὸ Δαρείου. προκειται δ' ἡ Λάδη νῆσος
 πλησίον καὶ τὰ¹ περὶ τὰς Τραγαίας νησία,
 ὑφόρμους ἔχοντα λησταῖς.

8. Ἐξῆς δ' ἐστὶν ὁ Λατμικός² κόλπος, ἐν ᾧ
 Ἡράκλεια ἢ ὑπὸ Λάτμῳ λεγομένη, πολίχνην
 ὑφορμον ἔχον· ἐκαλεῖτο δὲ πρότερον Λάτμος
 ὁμωνύμως τῷ ὑπερκειμένῳ ὄρει, ὅπερ Ἑκαταῖος
 μὲν ἐμφαίνει τὸ αὐτὸ εἶναι νομίζων τῷ ὑπὸ τοῦ
 ποιητοῦ Φθειρῶν ὄρει λεγομένῳ (ὑπὲρ γὰρ τῆς
 Λάτμου φησί τὸ Φθειρῶν ὄρος κείσθαι), τινὲς
 C 636 δὲ τὸ Γρίον φασίν, ὥς ἂν παράλληλον τῷ
 Λάτμῳ ἀνῆκον ἀπὸ τῆς Μιλησίας πρὸς ἕω διὰ
 τῆς Καρίας μέχρι Εὐρώμου καὶ Χαλκητόρων·
 ὑπέρεται δὲ ταύτης ἐν ὕψει.³ μικρὸν δ' ἄπωθεν
 διαβάντι ποταμίσκον πρὸς τῷ Λάτμῳ δείκνυται
 τάφος Ἐνδυμίωνος ἐν τινι σπηλαίῳ· εἴτα ἀφ'
 Ἡρακλείας ἐπὶ Πύρραν πολίχνην πλοῦς ἑκατόν
 πον σταδίων.

9. Μικρὸν δὲ πλέον τὸ ἀπὸ Μιλήτου εἰς
 Ἡράκλειαν ἐγκολπίζοντι, εὐθυπλοία δ' εἰς Πύρ-

¹ τὰ, omitted by MSS. except E.

² Λατμικός, Xylander, for Λητομηκός F, Λατομμικός s, Λατομικός other MSS.

³ For ὕψει Groskurd conj. ὕψει, and Meineke so reads.

to the end, since he spoke freely, beyond moderation, before Pompey the Great. But the city was unfortunate, since it shut its gates against Alexander and was taken by force, as was also the case with Halicarnassus; and also, before that time, it was taken by the Persians. And Callisthenes says that Phrynichus the tragic poet was fined a thousand drachmas by the Athenians because he wrote a play entitled *The Capture of Miletus by Dareius*. The island Ladê lies close in front of Miletus, as do also the isles in the neighbourhood of the Tragacæ, which afford anchorage for pirates.

8. Next comes the Latmian Gulf, on which is situated "Heracleia below Latmus," as it is called, a small town that has an anchoring-place. It was at first called Latmus, the same name as the mountain that lies above it, which Hecataeus indicates, in his opinion, to be the same as that which by the poet is called "the mountain of the Phtheires"¹ (for he says that the mountain of the Phtheires lies above Latmus), though some say that it is Mt. Grium, which is approximately parallel to Latmus and extends inland from Milesia towards the east through Caria to Euromus and Chalcetores.² This mountain lies above Heracleia, and at a high elevation.³ At a slight distance away from it, after one has crossed a little river near Latmus, there is to be seen the sepulchre of Endymion, in a cave. Then from Heracleia to Pyrrha, a small town, there is a voyage of about one hundred stadia.

9. But the voyage from Miletus to Heracleia, including the sinuosities of the gulfs, is a little more

¹ *Iliad* 2. 868.

² See 14. 2. 22.

³ Or rather, perhaps, "and in sight of it" (see critical note).

ραν ἐκ Μιλήτου τριάκοντα· τοσαύτην ἔχει μακροπορίαν ὁ παρά γῆν πλοῦς. ἀνάγκη δ' ἐπὶ τῶν ἐνδόξων τόπων ὑπομένειν τὸ περισκελές τῆς τοιαύτης γεωγραφίας.

10. Ἐκ δὲ Πύρρας ἐπὶ τὴν ἐκβολὴν τοῦ Μαιάνδρου πεντήκοντα· τεναγώδης δ' ὁ τόπος καὶ ἐλώδης· ἀναπλεύσαντι δ' ὑπηρετικοῖς σκάφεσι τριάκοντα σταδίους πόλις Μυοῦς, μία τῶν Ἰάδων τῶν δώδεκα, ἣ νῦν δι' ὀλιγανδρίαν Μιλησίοις συμπεπόλισται. ταύτην ὄψον λέγεται Θεμιστοκλεῖ δοῦναι Ξέρξης, ἄρτον δὲ Μαγνησίαν, οἶνον δὲ Λάμφακον.

11. Ἐνθεν ἐν σταδίοις τέτταρσι κώμη Καρικὴ Θυμβρία, παρ' ἣν Ἄορνόν ἐστι σπήλαιον ἱερόν, Χαρώνιον λεγόμενον ὀλεθρίους ἔχον ἀποφοράς. ὑπέρκειται δὲ Μαγνησία ἢ πρὸς Μαιάνδρῳ, Μαγνήτων ἀποικία τῶν ἐν Θετταλίᾳ καὶ Κρητῶν, περὶ ἧς αὐτίκα ἐροῦμεν.

12. Μετὰ δὲ τὰς ἐκβολὰς τοῦ Μαιάνδρου ὁ κατὰ Πριήνην ἐστὶν αἰγιαλός, ὑπὲρ αὐτοῦ δ' ἡ Πριήνη καὶ Μυκάλῃ τὸ ὄρος, εὐθῆρον καὶ εὐδενδρον. ἐπείκειται δὲ τῇ Σαμία καὶ ποιεῖ πρὸς αὐτὴν ἐπέκεινα τῆς Τρωγιλίου καλουμένης ἄκρας ὅσον ἐπταστάδιον πορθμόν. λέγεται δ' ὑπὸ τινων ἡ Πριήνη Κάδμη, ἐπειδὴ Φιλώτας ὁ ἐπικτίσας αὐτὴν Βοιώτιος ὑπῆρχεν· ἐκ Πριήνης δ' ἦν Βίας, εἰς τῶν ἐπτὰ σοφῶν, περὶ οὗ φησιν οὕτως Ἰππώναξ·

καὶ δικάσασθαι Βίαντος τοῦ Πριηνέως κρέσσων.

than one hundred stadia, though that from Miletus to Pyrrha, in a straight course, is only thirty—so much longer is the journey along the coast. But in the case of famous places my reader must needs endure the dry part of such geography as this.

10. The voyage from Pyrrha to the outlet of the Maeander River is fifty stadia, a place which consists of shallows and marshes; and, going inland in row-boats thirty stadia, one comes to the city Myus, one of the twelve Ionian cities, which, on account of its sparse population, has now been incorporated into Miletus. Xerxes is said to have given this city to Themistocles to supply him with fish, Magnesia to supply him with bread, and Lampsacus with wine.

11. Thence, within four stadia, one comes to a village, the Carian Thymbria, near which is Aornum, a sacred cave, which is called Charonium, since it emits deadly vapours. Above it lies Magnesia on the Maeander, a colony of the Magnesians of Thessaly and the Cretans, of which I shall soon speak.¹

12. After the outlets of the Maeander comes the shore of Priênê, above which lies Priênê, and also the mountain Mycalê, which is well supplied with wild animals and with trees. This mountain lies above the Samian territory² and forms with it, on the far side of the promontory called Trogilian, a strait about seven stadia in width. Priênê is by some writers called Cadmê, since Philotas, who founded it, was a Boeotian. Bias, one of the Seven Wise Men, was a native of Priênê, of whom Hipponax says "stronger in the pleading of his cases than Bias of Priênê."³

¹ §§ 39-40 following.

² *frag.* 79 (Bergk).

³ The isle of Samos.

13. Τῆς δὲ Τρωγιλίου πρόκειται νησίον ὁμώνυμον· ἐντεῦθεν δὲ τὸ ἐγγυτάτω διάρμά ἐστιν ἐπὶ Σούνιον σταδίων χιλίων ἑξακοσίων, κατ' ἀρχὰς μὲν Σάμον ἐν δεξιᾷ ἔχοντι καὶ Ἰκαρίαν καὶ Κορσίας,¹ τοὺς δὲ Μελαντίους² σκοπέλους ἐξ εὐωνύμων, τὸ λοιπὸν δὲ διὰ μέσων τῶν Κυκλάδων νήσων. καὶ αὕτη δ' ἡ Τρωγίλιος ἄκρα πρόπους τις τῆς Μυκάλης ἐστί. τῇ Μυκάλῃ δ' ὄρος ἄλλο πρόσκειται τῆς Ἐφεσίας Πακτύης· καὶ ἡ Μεσωγίς δὲ εἰς αὐτὴν καταστρέφει.

14. Ἀπὸ δὲ τῆς Τρωγιλίου στάδιοι τετταράκοντα εἰς τὴν Σάμον· βλέπει δὲ πρὸς νότον καὶ αὕτη καὶ ὁ λιμὴν, ἔχων ναύσταθμον. ἐστὶ C 637 δ' αὐτῆς ἐν ἐπιπέδῳ τὸ πλεόν, ὑπὸ τῆς θαλάττης κλυζόμενον, μέρος δέ τι καὶ εἰς τὸ ὄρος ἀνέχει τὸ ὑπερκείμενον. ἐν δεξιᾷ μὲν οὖν προσπλέουσι πρὸς τὴν πόλιν ἐστὶ τὸ Ποσειδίου, ἄκρα ἡ ποιούσα πρὸς τὴν Μυκάλην τὸν ἑπταστάδιον πορθμόν, ἔχει δὲ νεῶν Ποσειδῶνος· πρόκειται δ' αὐτοῦ νησίδιον ἢ Ναρθηκίς· ἐπ' ἀριστερᾷ δὲ τὸ προάστειον τὸ πρὸς τῷ Ἡραίῳ καὶ ὁ Ἰμβρασος ποταμὸς καὶ τὸ Ἡραῖον, ἀρχαῖον ἱερὸν καὶ νεῶς μέγας, ὃς νῦν πινακοθήκη ἐστί· χωρὶς δὲ τοῦ πλήθους τῶν ἐνταῦθα κειμένων πινάκων ἄλλαι πινακοθήκαι καὶ ναῖσκοι τινές εἰσι πλήρεις τῶν ἀρχαίων τεχνῶν· τό τε ὕπαιθρον ὁμοίως μεστὸν ἀνδριάντων ἐστὶ τῶν ἀρίστων· ὧν τρία Μύρωνος ἔργα κολοσσικὰ ἰδρυμένα ἐπὶ μιᾷς βάσεως, ἃ

¹ Κορσίας F; Tzschucke emends to Κορασσίας.

² Μελαντίους, Tzschucke, from conj. of Voss, for Μελανθίους; so the later editors.

13. Off the Trogilian promontory lies an isle of the same name. Thence the nearest passage across to Sunium is one thousand six hundred stadia; on the voyage one has at first Samos and Icaria and Corsia on the right, and the Melantian rocks on the left; and the remainder of the voyage is through the midst of the Cyclades islands. The Trogilian promontory itself is a kind of spur of Mt. Mycalê. Close to Mycalê lies another mountain, in the Ephesian territory, I mean Mt. Pactyes, in which the Mesogis terminates.

14. The distance from the Trogilian promontory to Samos¹ is forty stadia. Samos faces the south, both it and its harbour, which latter has a naval station. The greater part of it is on level ground, being washed by the sea, but a part of it reaches up into the mountain that lies above it. Now on the right, as one sails towards the city, is the Poseidium, a promontory which with Mt. Mycalê forms the seven-stadia strait; and it has a temple of Poseidon; and in front of it lies an isle called Narthecis; and on the left is the suburb near the Heraeum, and also the Imbrusus River, and the Heraeum, which consists of an ancient temple and a great shrine, which latter is now a repository of tablets.² Apart from the number of the tablets placed there, there are other repositories of votive tablets and some small chapels full of ancient works of art. And the temple, which is open to the sky, is likewise full of most excellent statues. Of these, three of colossal size, the work of Myron, stood upon one base; Antony

¹ *i.e.* the city Samos.

² Whether maps or paintings, or both, the translator does not know.

ἦρε μὲν Ἀντώνιος, ἀνέθηκε δὲ πάλιν ὁ Σεβαστὸς Καῖσαρ εἰς τὴν αὐτὴν βάσιν τὰ δύο, τὴν Ἀθηναίων καὶ τὸν Ἡρακλέα, τὸν δὲ Δία εἰς τὸ Καπετώλιον μετήνεγκε, κατασκευάσας αὐτῷ ναῖσκον.

15. Περίπλους δ' ἐστὶ τῆς Σαμίων νήσου σταδίων ἑξακοσίων. ἐκαλεῖτο δὲ Παρθενία πρότερον οἰκούντων Καρῶν, εἶτα Ἀνθεμοῦς,¹ εἶτα Μελάμφυλλος,² εἶτα Σάμος, εἴτ' ἀπὸ τινος ἐπιχωρίου ἡρώος, εἴτ' ἐξ Ἰθάκης καὶ Κεφαλληνίας ἀποικήσαντος.³ καλεῖται μὲν οὖν καὶ ἄκρα τις Ἀμπελος βλέπουσά πῶς πρὸς τὸ τῆς Ἰκαρίας Δρέπανον, ἀλλὰ καὶ τὸ ὄρος ἅπαν, ὃ ποιεῖ τὴν ὅλην νῆσον ὀρεινὴν, ὁμωνύμως λέγεται· ἔστι δ' οὐκ εὐοῖνος, καίπερ εὐοῖνουσῶν τῶν κύκλῳ νήσων, καὶ τῆς ἡπείρου σχεδόν τι τῆς προσεχοῦς πάσης τοὺς ἀρίστους ἐκφερούσης οἴνους, οἶον Χίου καὶ Λέσβου καὶ Κῶ.⁴ καὶ μὴν καὶ ὁ Ἐφέσιος καὶ Μητροπολίτης ἀγαθοί, ἥ τε Μεσσηνία καὶ ὁ Τμῶλος καὶ ἡ Κατακεκαυμένη καὶ Κνίδος καὶ Σμύρνα καὶ ἄλλοι ἀσημότεροι τόποι διαφόρως χρηστοῖ νοῦσιν ἢ πρὸς ἀπόλαυσιν ἢ πρὸς διαίτας ἱατρικάς. περὶ μὲν οὖν⁵ οἴνους οὐ πάνυ εὐτυχεῖ Σάμος, τὰ δ' ἄλλα εὐδαίμων, ὥς δῆλον ἐκ τε τοῦ περιμάχητον γενέσθαι καὶ ἐκ τοῦ τοὺς ἐπαινοῦντας μὴ ὀκνεῖν ἐφαρμόττειν αὐτῇ τὴν λέγουσαν παροιμίαν, ὅτι φέρει καὶ ὀρνίθων γάλα, καθάπερ

¹ For Ἀνθεμοῦς, Corais, following Eustathius (note on Dionys. 533), reads Ἀνθεμῖς. By some writers the name is spelled Ἀνθεμοῦσα.

² Μελάμφυλλος, Meineke, for Μελάμφυλος.

³ ἀποικήσαντος F, ἀποικίσαντος other MSS.

⁴ οἶον . . . Κῶ, Meineke ejects.

took these statues away,¹ but Augustus Caesar restored two of them, those of Athena and Heracles, to the same base, although he transferred the Zeus to the Capitolium, having erected there a small chapel for that statue.

15. The voyage round the island of the Samians is six hundred stadia. In earlier times, when it was inhabited by Carians, it was called Parthenia, then Anthemus, then Melamphyllus, and then Samos, whether after some native hero or after someone who colonised it from Ithaca and Cephallenia.² Now in Samos there is a promontory approximately facing Drepanum in Icaria which is called Ampelus, but the entire mountain which makes the whole of the island mountainous is called by the same name. The island does not produce good wine, although good wine is produced by the islands all round, and although most of the whole of the adjacent mainland produces the best of wines, for example, Chios and Lesbos and Cos. And indeed the Ephesian and Metropolitan wines are good; and Mt. Mesogis and Mt. Tmolus and the Catacecaumene country and Cnidos and Smyrna and other less significant places produce exceptionally good wine, whether for enjoyment or medicinal purposes. Now Samos is not altogether fortunate in regard to wines, but in all other respects it is a blest country, as is clear from the fact that it became an object of contention in war, and also from the fact that those who praise it do not hesitate to apply to it the proverb, that "it

¹ See 13. 1. 30.

² See 10. 2. 17.

³ *οἶνον*, before *οἶνους*, Meineke inserts.

που καὶ Μένανδρος ἔφη.¹ τοῦτο δὲ καὶ τῶν τυραννίδων αἴτιον αὐτῇ κατέστη, καὶ τῆς πρὸς Ἀθηναίους ἔχθρας.

C 638 16. Αἱ μὲν οὖν τυραννίδες ἤκμασαν κατὰ Πολυκράτη μάλιστα καὶ τὸν ἀδελφὸν αὐτοῦ Συλοσῶντα· ἦν δ' ὁ μὲν καὶ τύχῃ καὶ δυνάμει λαμπρός, ὥστε καὶ θαλαττοκρατῆσαι· τῆς δ' εὐτυχίας αὐτοῦ σημεῖον τιθέασιν, ὅτι ῥίψαντος εἰς τὴν θάλατταν ἐπίτηδες τὸν δακτύλιον λίθου καὶ γλύμματος πολυτελοῦς, ἀνῆνεγκε μικρὸν ὕστερον τῶν ἀλιέων τις τὸν καταπιόντα ἰχθύν αὐτόν· ἀνατμηθέντος δ' εὐρέθη ὁ δακτύλιος· πυθόμενον δὲ τοῦτο τὸν Αἰγυπτίων βασιλέα φασὶ μαντικῶς πως ἀποφθέγξασθαι, ὡς ἐν βραχεῖ καταστρέψει τὸν βίον εἰς οὐκ εὐτυχές τέλος ὁ τοσοῦτον ἐξηρμένος ταῖς εὐπραγίαις· καὶ δὴ καὶ συμβῆναι τοῦτο· ληφθέντα γὰρ ἐξ ἀπάτης ὑπὸ τοῦ σατράπου τῶν Περσῶν κρεμασθῆναι. τούτῳ συνεβίωσεν Ἀνακρέων ὁ μελοποιός· καὶ δὴ καὶ πᾶσα ἡ ποιήσις πλήρης ἐστὶ τῆς περὶ αὐτοῦ μνήμης. ἐπὶ τούτου δὲ καὶ Πυθαγόραν ἱστοροῦσιν ἰδόντα φυομένην τὴν τυραννίδα ἐκλιπεῖν τὴν πόλιν καὶ ἀπελθεῖν εἰς Αἴγυπτον καὶ Βαβυλῶνα φιλομαθείας χάριν· ἐπανιόντα δ' ἐκεῖθεν, ὁρῶντα ἔτι συμμένουσαν τὴν τυραννίδα, πλεύσαντα εἰς Ἰταλίαν ἐκεῖ διατελέσαι τὸν βίον. περὶ Πολυκράτους μὲν ταῦτα.

17. Συλοσῶν δ' ἀπελείφθη μὲν ἰδιώτης ὑπὸ τοῦ ἀδελφοῦ, Δαρείῳ δὲ τῷ Ὑστάσπεω χαρισάμενος

¹ καθάπερ . . . ἔφη, Meineke ejects.

produces even birds' milk," as Menander somewhere says. This was also the cause of the establishment of the tyrannies there, and of their enmity against the Athenians.

16. Now the tyrannies reached their greatest height in the time of Polycrates and his brother Syloson. Polycrates was such a brilliant man, both in his good fortune and in his natural ability, that he gained supremacy over the sea; and it is set down,¹ as a sign of his good fortune, that he purposely flung into the sea his ring, a ring of very costly stone and engraving, and that a little later one of the fishermen brought him the very fish that swallowed it; and that when the fish was cut open the ring was found; and that on learning this the king of the Egyptians, it is said, declared in a kind of prophetic way that any man who had been exalted so highly in welfare would shortly come to no happy end of life; and indeed this is what happened, for he was captured by treachery by the satrap of the Persians and hanged. Anacreon the melic poet lived in companionship with Polycrates; and indeed the whole of his poetry is full of his praises. It was in his time, as we are told, that Pythagoras, seeing that the tyranny was growing in power, left the city and went off to Egypt and Babylon, to satisfy his fondness for learning; but when he came back and saw that the tyranny still endured, he set sail for Italy and lived there to the end of his life. So much for Polycrates.

17. Syloson was left a private citizen by his brother, but to gratify Darcus, the son of Hystas-

¹ See Herodotus, 3. 40-43, and 120, 125.

ἐσθῆτα, ἧς ἐπεθύμησεν ἐκείνος φοροῦντα ἰδών, οὐπω δ' ἐβασίλευε τότε, βασιλεύσαντος ἀντέλαβε δῶρον τὴν τυραννίδα. πικρῶς δ' ἥρξεν, ὥστε καὶ ἐλειπάνδρησεν ἡ πόλις· κακείθεν ἐκπεσεῖν συνέβη τὴν παροιμίαν·

ἔκητι Συλοσῶντος εὐρυχωρίη.

18. Ἀθηναῖοι δὲ πρότερον μὲν πέμψαντες στρατηγὸν Περικλέα καὶ σὺν αὐτῷ Σοφοκλέα τὸν ποιητὴν πολιορκία κακῶς διέθηκαν ἀπειθοῦντας τοὺς Σαμίους, ὕστερον δὲ καὶ κληρούχους ἔπεμψαν δισχιλίους ἐξ ἑαυτῶν, ὧν ἦν καὶ Νεοκλῆς, ὁ Ἐπικούρου τοῦ φιλοσόφου πατήρ, γραμματοδιδάσκαλος, ὥς φασι· καὶ δὴ καὶ τραφήναι φασιν ἐνθάδε καὶ ἐν Τέφῳ, καὶ ἐφηβεῦσαι Ἀθήνησι· γενέσθαι δ' αὐτῷ συνέφηβον Μένανδρον τὸν κωμικόν· Σάμιος δ' ἦν καὶ Κρεώφυλος, ὃν φασι δεξάμενον ξενία ποτὲ Ὅμηρον, λαβεῖν δῶρον τὴν ἐπιγραφὴν τοῦ ποιήματος, ὃ καλοῦσιν Οἰχαλίας ἄλωσιν. Καλλίμαχος δὲ τοῦναντίον ἐμφαίνει δι' ἐπιγράμματός τινος, ὡς ἐκείνου μὲν ποιήσαντος, λεγομένου δ' Ὅμηρου διὰ τὴν λεγομένην ξενίαν·

τοῦ Σαμίου πόνος εἰμί, δόμῳ ποτὲ θεῖον
"Ὅμηρον

δεξαμένον· κλείω¹ δ' Εὐρυτον, ὅσ' ἔπαθεν,
καὶ ξανθὴν Ἰόλειαν· Ὅμηρειον δὲ καλεῦμαι
γράμμα· Κρεωφύλῳ, Ζεῦ φίλε, τοῦτο μέγα.

Ο 639 τινὲς δὲ διδάσκαλον Ὅμηρου τοῦτόν φασιν, οἱ δ' οὐ τοῦτον, ἀλλ' Ἀριστέαν τὸν Προκοννήσιον.

¹ κλείω, Meineke, for καίω; κλαίω Tzschucke.

pes, he gave him a robe which Dareius desired when he saw him wearing it; and Dareius at that time was not yet king, but when Dareius became king, Syloson received as a return-gift the tyranny of Samos. But he ruled so harshly that the city became depopulated; and thence arose the proverb, "by the will of Syloson there is plenty of room."

18. The Athenians at first sent Pericles as general and with him Sophocles the poet, who by a siege put the disobedient Samians in bad plight; but later they sent two thousand allottees from their own people, among whom was Neocles, the father of Epicurus the philosopher, a schoolmaster as they call him. And indeed it is said that Epicurus grew up here and in Teos, and that he became an ephēbus¹ at Athens, and that Menander the comic poet became an ephēbus at the same time. Creophylus, also, was a Samian, who, it is said, once entertained Homer and received as a gift from him the inscription of the poem called *The Capture of Oechalia*. But Callimachus clearly indicates the contrary in an epigram of his, meaning that Creophylus composed the poem, but that it was ascribed to Homer because of the story of the hospitality shown him: "I am the toil of the Samian, who once entertained in his house the divine Homer. I bemoan Eurytus, for all that he suffered, and golden-haired Ioleia. I am called Homer's writing. For Creophylus, dear Zeus, this is a great achievement." Some call Creophylus Homer's teacher, while others say that it was not Creophylus, but Aristēas the Proconnesian, who was his teacher.

¹ i.e. at eighteen years of age underwent a "scrutiny" and was registered as an Athenian citizen.

19. Παράκειται δὲ τῇ Σάμῳ νῆσος Ἰκαρία, ἀφ' ἧς τὸ Ἰκάριον πέλαγος. αὕτη δ' ἐπώνυμός ἐστιν Ἰκάρου, παιδὸς τοῦ Δαιδύλου, ὃν φασὶ τῷ πατρὶ κοινωνήσαντα τῆς φυγῆς, ἡνίκα ἀμφότεροι πτερωθέντες ἀπῆραν ἐκ Κρήτης, πεσεῖν ἐνθάδε, μὴ κρατήσαντα τοῦ δρόμου· μετεωρισθέντι γὰρ πρὸς τὸν ἥλιον ἐπὶ πλεον περιρρυῆναι τὰ πτερά, τακέντος τοῦ κηροῦ. τριακοσίων δ' ἐστὶ τὴν περίμετρον σταδίων ἡ νῆσος ἅπασα καὶ ἀλίμενος, πλὴν ὑφόρων, ὧν ὁ κάλλιστος Ἰστοὶ λέγονται· ἄκρα δ' ἐστὶν ἀνατείνουσα πρὸς ζέφυρον. ἔστι δὲ καὶ Ἀρτέμιδος ἱερὸν, καλούμενον Ταυροπόλιον, ἐν τῇ νήσῳ καὶ πολισμάτιον Οἰνότη, καὶ ἄλλο Δράκανον, ὁμώνυμον τῇ ἄκρᾳ, ἐφ' ἣ ἰδρύται, πρόσορμον ἔχον· ἡ δὲ ἄκρα διέχει τῆς Σαμίων ἄκρας, τῆς Κανθαρίου καλουμένης, ὀγδοήκοντα σταδίους, ὅπερ ἐστὶν ἐλάχιστον διάστημα τὸ μεταξύ. νυνὶ μέντοι λειπανδροῦσαν Σάμιοι νέμονται τὰ πολλὰ βοσκημάτων χάριν.

20. Μετὰ δὲ τὸν Σάμιον πορθμὸν τὸν πρὸς Μυκάλῃ πλέουσιν εἰς Ἐφεσον ἐν δεξιᾷ ἐστὶν ἡ Ἐφεσίων παραλία· μέρος δέ τι ἔχουσιν αὐτῆς καὶ οἱ Σάμιοι. πρῶτον δ' ἐστὶν ἐν τῇ παραλίᾳ τὸ Πανιώνιον, τρισὶ σταδίοις ὑπερκείμενον τῆς θαλάττης, ὅπου τὰ Πανιώνια, κοινὴ πανηγυρις τῶν Ἰώνων, συντελεῖται τῷ Ἑλικωνίῳ Ποσειδῶνι καὶ θυσία· ἱερῶνται δὲ Πριηνεῖς· εἰρήται δὲ περὶ αὐτῶν ἐν τοῖς Πελοποννησιακοῖς. εἴτα Νεάπολις, ἡ πρότερον μὲν ἦν Ἐφεσίων, νῦν δὲ

¹ i.e. the wax which joined the wings to his body.

19. Alongside Samos lies the island Icaria, whence was derived the name of the Icarian Sea. This island is named after Icarus the son of Daedalus, who, it is said, having joined his father in flight, both being furnished with wings, flew away from Crete and fell here, having lost control of their course; for, they add, on rising too close to the sun, his wings slipped off, since the wax¹ melted. The whole island is three hundred stadia in perimeter; it has no harbours, but only places of anchorage, the best of which is called Histi.² It has a promontory which extends towards the west. There is also on the island a temple of Artemis, called Tauropolium; and a small town Oenoë; and another small town Dracanum, bearing the same name as the promontory on which it is situated and having near by a place of anchorage. The promontory is eighty stadia distant from the promontory of the Samians called Cantharius, which is the shortest distance between the two. At the present time, however, it has but few inhabitants left, and is used by Samians mostly for the grazing of cattle.

20. After the Samian strait, near Mt. Mycalê, as one sails to Ephesus, one comes, on the right, to the seaboard of the Ephesians; and a part of this seaboard is held by the Samians. First on the seaboard is the Panionium, lying three stadia above the sea where the Pan-Ionia, a common festival of the Ionians, are held, and where sacrifices are performed in honour of the Heliconian Poseidon; and Prienians serve as priests at this sacrifice, but I have spoken of them in my account of the Peloponnesus.³ Then comes Neapolis, which in earlier times belonged to

² *i.e.* Masts.

³ 8. 7. 2.

Σαμίῳ, διαλλαξαμένων πρὸς τὸ Μαραθήσιον,
 τὸ ἐγγυτέρω πρὸς τὸ ἀπωτέρω· εἴτα Πύγελα
 πολίχμιον, ἱερὸν ἔχον Ἀρτέμιδος Μουνυχίας,
 ἴδρυμα Ἀγαμέμνονος, οἰκούμενον ὑπὸ μέρους τῶν
 ἐκείνου λαῶν· πυγαλγέας¹ γάρ τινάς φασι² καὶ
 γενέσθαι καὶ κληθῆναι, κάμνοντας δ' ὑπὸ τοῦ
 πάθους καταμεῖναι, καὶ τυχεῖν οἰκείου τοῦδε
 τοῦ ὀνόματος τὸν τόπον. εἴτα λιμὴν Πάνορμος
 καλούμενος, ἔχων ἱερὸν τῆς Ἐφεσσίας Ἀρτέμιδος·
 εἶθ' ἡ πόλις. ἐν δὲ τῇ αὐτῇ παραλίᾳ μικρὸν
 ὑπὲρ τῆς θαλάττης ἐστὶ καὶ ἡ Ὀρτυγία, δια-
 πρεπὲς ἄλλος παντοδαπῆς ὕλης, κυπαρίττου
 δὲ τῆς πλείστης. διαρρεῖ δὲ ὁ Κέγχριος
 ποταμός, οὗ φασὶ νίψασθαι τὴν Λητὼ μετὰ
 τὰς ὠδῖνας. ἐνταῦθα γὰρ μυθεύουσι τὴν λοχείαν
 καὶ τὴν τροφὸν τὴν Ὀρτυγίαν καὶ τὸ ἄδυτον,
 ἐν ᾧ ἡ λοχεία, καὶ τὴν πλησίον ἐλαίαν,
 ἣ πρῶτον ἐπαναπαύσασθαι φασὶ τὴν θεὸν
 C 640 ἀπολυθεῖσαν τῶν ὠδίνων. ὑπέρεκειται δὲ τοῦ
 ἄλλους ὄρος ὁ Σολμισσός, ὅπου στάντας φασὶ
 τοὺς Κουρήτας τῷ ψόφῳ τῶν ὅπλων ἐκπλήξαι
 τὴν Ἥραν ζηλοτύπως ἐφεδρεύουσιν, καὶ λαθεῖν
 συμπράξαντας τὴν λοχείαν τῇ Λητοί. ὄντων δ'
 ἐν τῷ τόπῳ πλειόνων ναῶν, τῶν μὲν ἀρχαίων,
 τῶν δ' ὕστερον γενομένων, ἐν μὲν τοῖς ἀρχαίοις
 ἀρχαῖά ἐστι ξόανα, ἐν δὲ τοῖς ὕστερον Σκόπα
 ἔργα·³ ἡ μὲν Λητὼ σκῆπτρον ἔχουσα, ἡ δ'
 Ὀρτυγία παρέστηκεν ἐκατέρα τῇ χειρὶ παιδίον

¹ πυγαλγέας, Corais, for πυγαλλίας Corz., πυγαλίας other MSS.; πυγαλγίας Meineke.

² φασι, Jones inserts.

³ Instead of Σκόπα ἔργα, F has σκολιά σκόπ' ἔργα; other MSS. σκολιά ἔργα, except v which has Σκόπα in the margin.

the Ephesians, but now belongs to the Samians, who gave in exchange for it Marathesium, the more distant for the nearer place. Then comes Pygela, a small town, with a temple of Artemis Munychia, founded by Agamemnon and inhabited by a part of his troops; for it is said that some of his soldiers became afflicted with a disease of the buttocks¹ and were called "diseased-buttocks," and that, being afflicted with this disease, they stayed there, and that the place thus received this appropriate name. Then comes the harbour called Panormus, with a temple of the Ephesian Artemis; and then the city Ephesus. On the same coast, slightly above the sea, is also Ortygia, which is a magnificent grove of all kinds of trees, of the cypress most of all. It is traversed by the Cenchrius River, where Leto is said to have bathed herself after her travail.² For here is the mythical scene of the birth, and of the nurse Ortygia, and of the holy place where the birth took place, and of the olive tree near by, where the goddess is said first to have taken a rest after she was relieved from her travail. Above the grove lies Mt. Solmissus, where, it is said, the Curetes stationed themselves, and with the din of their arms frightened Hera out of her wits when she was jealously spying on Leto, and when they helped Leto to conceal from Hera the birth of her children. There are several temples in the place, some ancient and others built in later times; and in the ancient temples are many ancient wooden images, but in those of later times there are works of Scopas; for example, Leto holding a sceptre and Ortygia standing beside her with a

¹ In Greek, with "pygalgia."

² Referring, of course, to the birth of Apollo and Artemis.

ἔχουσα. πανήγυρις δ' ἐνταῦθα συντελεῖται κατ' ἔτος, ἔθει δέ τινη οἱ νέοι φιλοκαλοῦσι, μάλιστα περὶ τὰς ἐνταῦθα εὐωχίας λαμπρυνόμενοι· τότε δὲ καὶ τῶν Κουρήτων ἀρχεῖον συνάγει συμπόσια, καὶ τινὰς μυστικὰς θυσίας ἐπιτελεῖ.

21. Τὴν δὲ πόλιν ᾧκου μὲν Κᾶρές τε καὶ Λέλεγες, ἐκβαλὼν δ' ὁ Ἄνδροκλος τοὺς πλείστους ᾧκισεν ἐκ τῶν συνελθόντων αὐτῷ περὶ τὸ Ἀθήναιον καὶ τὴν Ὑπέλαιον, προσπεριλαβὼν καὶ τῆς περὶ τὸν Κορησσὸν παρωρείας. μέχρι μὲν δὴ τῶν κατὰ Κροῖσον οὕτως ᾧκεῖτο, ὕστερον δ' ἀπὸ τῆς παρωρείου καταβάντες, περὶ τὸ νῦν ἱερὸν ᾧκησαν μέχρι Ἀλεξάνδρου. Λυσίμαχος δὲ τὴν νῦν πόλιν τειχίσας, ἀηδὼς τῶν ἀνθρώπων μεθισταμένων, τηρήσας καταρράκτην ὄμβρον συνήργησε καὶ αὐτὸς καὶ τοὺς ῥινοῦχους ἐνέφραξεν, ὥστε κατακλύσαι τὴν πόλιν· οἱ δὲ μετέστησαν ἄσμενοι. ἐκύλεσε δ' Ἀρσινόη ἀπὸ τῆς γυναικὸς τὴν πόλιν, ἐπεκράτησε μέντοι τὸ ἀρχαῖον ὄνομα. ἦν δὲ γερουσία καταγραφομένη, τούτοις δὲ συνήεσαν οἱ ἐπὶ κλητοὶ καλούμενοι καὶ διόκου πάντα.

22. Τὸν δὲ νεὼν τῆς Ἀρτέμιδος πρῶτος¹ μὲν Χερσίφρων ἡρχιτεκτόνησεν, εἴτ' ἄλλος² ἐποίησε μεῖζω· ὥς δὲ τοῦτον Ἡρόστρατός τις ἐνέπρησεν, ἄλλον ἀμείνω κατεσκεύασαν συνενέγκαντες τὸν τῶν γυναικῶν κόσμον καὶ τὰς ἰδίας οὐσίας, διαθέμενοι δὲ καὶ τοὺς προτέρους κίονας· τούτων δὲ μαρτύριά ἐστι τὰ γενηθέντα τότε ψηφίσματα,

¹ πρῶτον F.

² ἄλλος, Xylander, for ἄλλον.

¹ Men specially summoned, privy-councillors.

child in each arm. A general festival is held there annually; and by a certain custom the youths vie for honour, particularly in the splendour of their banquets there. At that time, also, a special college of the Curetes holds symposiums and performs certain mystic sacrifices.

21. The city of Ephesus was inhabited both by Carians and by Leleges, but Androclus drove them out and settled the most of those who had come with him round the Athenaeum and the Hypelaeus, though he also included a part of the country situated on the slopes of Mt. Coressus. Now Ephesus was thus inhabited until the time of Croesus, but later the people came down from the mountain-side and abode round the present temple until the time of Alexander. Lysimachus built a wall round the present city, but the people were not agreeably disposed to change their abodes to it; and therefore he waited for a downpour of rain and himself took advantage of it and blocked the sewers so as to inundate the city; and the inhabitants were then glad to make the change. He named the city after his wife Arsinoë; the old name, however, prevailed. There was a senate, which was conscripted; and with these were associated the Epicleti,¹ as they were called, who administered all the affairs of the city.

22. As for the temple of Artemis, its first architect was Chersiphron; and then another man made it larger. But when it was set on fire by a certain Herostratus, the citizens erected another and better one, having collected the ornaments of the women and their own individual belongings, and having sold also the pillars of the former temple. Testimony is borne to these facts by the decrees that were made

ἄπερ ἀγνοοῦντά φησιν ὁ Ἀρτεμίδωρος τὸν
 Ταυρομενίτην Τίμαιον, καὶ ἄλλως βάσκανον
 ὄντα καὶ συκοφάντην (διὸ καὶ Ἐπιτίμαιον¹
 κληθῆναι), λέγειν, ὥς ἐκ τῶν Περσικῶν παρα-
 καταθηκῶν ἐποίησαντο τοῦ ἱεροῦ τὴν ἐπισκευήν·
 οὔτε δὲ ὑπάρξαι παρακαταθήκας τότε, εἴ τε
 ὑπῆρξαν, συνεμπεπρήσθαι ἂν² τῷ ναῷ· μετὰ δὲ
 τὴν ἔμπρησιν τῆς ὀροφῆς ἠφανισμένης, ἐν
 ὑπαίθρῳ τῷ σηκῷ τίνα ἂν ἐβελῆσαι παρακατα-
 θήκην κειμένην ἔχειν; Ἀλέξανδρον δὲ τοῖς
 O 641 Ἐφεσίοις ὑποσχέσθαι τὰ γεγονότα καὶ τὰ μέλ-
 λοντα ἀναλώματα, ἐφ' ᾧ τε τὴν ἐπιγραφὴν
 αὐτὸν ἔχειν, τοὺς δὲ μὴ ἐβελῆσαι, πολὺ μᾶλλον
 οὐκ ἂν ἐβελήσαντας ἐξ ἱεροσυλίας καὶ ἀποστε-
 ρήσεως φιλοδοξεῖν· ἐπαινεῖ τε τὸν εἰπόντα τῶν
 Ἐφεσίων πρὸς τὸν βασιλέα, ὥς οὐ πρόποι θεῶ
 θεοῖς ἀναθήματα κατασκευάζειν.

23. Μετὰ δὲ τὴν τοῦ νεῶ συντέλειαν, ὃν φησιν
 εἶναι Χειροκράτους³ ἔργον (τοῦ δ' αὐτοῦ καὶ τὴν
 Ἀλεξανδρείας κτίσιν· τὸν δ' αὐτὸν ὑποσχέσθαι
 Ἀλεξάνδρῳ τὸν Ἀθῶ διασκευάσειν εἰς αὐτόν,
 ὥσανεὶ ἐκ πρόχου τινὸς εἰς φιάλῃν καταχέοντα
 σπονδὴν, ποιήσοντα πόλεις δύο, τὴν μὲν ἐκ
 δεξιῶν τοῦ ὄρους, τὴν δ' ἐν ἀριστερᾷ, ἀπὸ δὲ
 τῆς ἐτέρας εἰς τὴν ἐτέραν ῥέοντα ποταμόν).

¹ Ἐπιτίμαιον, F; ἐπιτίμιον other MSS.

² ἂν, Jones inserts.

³ Instead of Χειροκράτους, w has Δεινοκράτους, which is apparently correct; and so read Corais and Meineke.

¹ Calumniator.

at that time. Artemidorus says: Timaeus of Tauro-menium, being ignorant of these decrees and being anyway an envious and slanderous fellow (for which reason he was also called Epitimaeus),¹ says that they exacted means for the restoration of the temple from the treasures deposited in their care by the Persians; but there were no treasures on deposit in their care at that time, and, even if there had been, they would have been burned along with the temple; and after the fire, when the roof was destroyed, who could have wished to keep deposits of treasure lying in a sacred enclosure that was open to the sky? Now Alexander, Artemidorus adds, promised the Ephesians to pay all expenses, both past and future, on condition that he should have the credit therefor on the inscription, but they were unwilling, just as they would have been far more unwilling to acquire glory by sacrilege and a spoliation of the temple.² And Artemidorus praises the Ephesian who said to the king³ that it was inappropriate for a god to dedicate offerings to gods.

23. After the completion of the temple, which, he says, was the work of Cheiocrates⁴ (the same man who built Alexandria and the same man who proposed to Alexander to fashion Mt. Athos into his likeness, representing him as pouring a libation from a kind of ewer into a broad bowl, and to make two cities, one on the right of the mountain and the other on the left, and a river flowing from one to

¹ Referring, of course, to the charge that they took the Persian treasures.

² Alexander.

⁴ Apparently an error for "Deinocrates," a Macedonian architect (cf. Vitruvius 1. 1. 4).

μετὰ δ' οὖν τὸν νεὼν τὸ τῶν ἄλλων ἀναθημάτων
 πλῆθος εὐρέσθαι τῇ ἐκτιμήσει τῶν δημιουργῶν,
 τὸν δὲ δὴ βωμὸν εἶναι τῶν Πραξιτέλους ἔργων
 ἅπαντα σχεδόν τι πληρῇ. ἡμῖν δ' ἐδείκνυτο καὶ
 τῶν Θράσωνός τινα, οὐπερ καὶ τὸ Ἑκατήσιόν
 ἐστὶ καὶ ἡ κηρίνη¹ Πηνελόπη καὶ ἡ πρεσβῦτις
 ἡ Εὐρύκλεια. ἱερέας δ' εὐνούχους εἶχον, οὓς
 ἐκάλουν Μεγαβύζους, καὶ ἀλλαχόθεν μετιόντες
 αἰετίνους ἀξιόους τῆς τοιαύτης προστασίας, καὶ
 ἦγον ἐν τιμῇ μεγάλη· συνιεῖσθαι δὲ τούτοις
 ἐχρῆν παρθένους. νυνὶ δὲ τὰ μὲν φυλάττεται
 τῶν νομίμων, τὰ δ' ἥττον, ἄσυλον δὲ μένει τὸ
 ἱερὸν καὶ νῦν καὶ πρότερον· τῆς δ' ἄσυλλας τοὺς
 ὄρους ἀλλαγῆναι συνέβη πολλάκις, Ἀλεξάνδρου
 μὲν ἐπὶ στάδιον ἐκτείναντος, Μιθριδάτου δὲ
 τόξευμα ἀφέντος ἀπὸ τῆς γωνίας τοῦ κεράμου
 καὶ δόξαντος ὑπερβαλέσθαι μικρὰ τὸ στάδιον,
 Ἀντωνίου δὲ διπλασιάσαντος τοῦτο² καὶ συμ-
 περιλαβόντος τῇ ἄσυλλᾳ μέρος τι τῆς πόλεως·
 ἐφάνη δὲ τοῦτο βλαβερόν καὶ ἐπὶ τοῖς κακούρ-
 γοις ποιοῦν τὴν πόλιν, ὥστ' ἠκύρωσεν ὁ Σεβαστὸς
 Καῖσαρ.

24. Ἐχει δ' ἡ πόλις καὶ νεώρια καὶ λιμένα·
 βραχύστομον δ' ἐποίησαν οἱ ἀρχιτέκτονες, συν-
 εξαπατηθέντες τῷ κελεύσαντι βασιλεῖ. οὗτος δ'
 ἦν Ἀτταλὸς ὁ Φιλάδελφος· οἰκθελὺς γὰρ οὗτος

¹ κηρίνη F (and Meineke); κρήνη other MSS.

² διπλασιάσαντος τοῦτο CF, πλησιάσαντας τοῦτο other MSS.

¹ Artemidorus means, of course, that the local artists were actuated by piety and patriotism.

the other)—after the completion of the temple, he says, the great number of dedications in general were secured by means of the high honour they paid their artists,¹ but the whole of the altar was filled, one might say, with the works of Praxiteles. They showed me also some of the works of Thrason, who made the chapel of Hecatê, the waxen image of Penelopê, and the old woman Eurycleia. They had eunuchs as priests, whom they called Megabyzi. And they were always in quest of persons from other places who were worthy of this preferment, and they held them in great honour. And it was obligatory for maidens to serve as colleagues with them in their priestly office. But though at the present some of their usages are being preserved, yet others are not; but the temple remains a place of refuge, the same as in earlier times, although the limits of the refuge have often been changed; for example, when Alexander extended them for a stadium, and when Mithridates shot an arrow from the corner of the roof and thought it went a little farther than a stadium, and when Antony doubled this distance and included within the refuge a part of the city. But this extension of the refuge proved harmful, and put the city in the power of criminals; and it was therefore nullified by Augustus Caesar.

24. The city has both an arsenal and a harbour. The mouth of the harbour was made narrower by the engineers,² but they, along with the king who ordered it, were deceived as to the result, I mean Attalus Philadelphus; for he thought that the

¹ Literally, "architects."

βαθὺν τὸν εἴσπλουν ὀλκάσι μεγάλαις ἔσεσθαι καὶ αὐτὸν τὸν λιμένα, τεναγώδη ὄντα πρότερον διὰ τὰς ἐκ τοῦ Καύστρου προσχώσεις,¹ ἐὰν παραβληθῇ χῶμα τῷ στόματι, πλατεῖ τελέως ὄντι, ἐκέλευσε γενέσθαι τὸ χῶμα. συνέβη δὲ τοῦναντίον· ἐντὸς γὰρ ἡ χοῦς εἰργομένη τεναγίζειν μᾶλλον ἐποίησε τὸν λιμένα σύμπαντα μέχρι τοῦ στόματος· πρότερον δ' ἱκανῶς αἱ πλημμυρίδες καὶ ἡ παλίρροια τοῦ πελάγους ἀφήρει τὴν χοῦν καὶ ἀνέσπα πρὸς τὸ ἐκτός. ὁ μὲν οὖν λιμὴν τοιοῦτος· ἡ δὲ πόλις τῇ πρὸς τὰ ἄλλα εὐκαιρία τῶν τόπων αὐξεται καθ' ἐκάστην ἡμέραν, ἐμπόριον οὔσα μέγιστον τῶν κατὰ τὴν Ἀσίαν τὴν

C 642 ἐντὸς τοῦ Ταύρου.

25. Ἄνδρες δ' ἀξιόλογοι γεγονάσιν ἐν αὐτῇ τῶν μὲν παλαιῶν Ἡράκλειτός τε ὁ σκοτεινὸς καλούμενος καὶ Ἑρμόδωρος, περὶ οὗ ὁ αὐτὸς οὗτός φησιν· Ἄξιον Ἐφεσίοις ἡβηδὸν ἀπάγξασθαι, οἵτινες Ἑρμόδωρον ἄνδρα ἐωντῶν ὀνήιστον ἐξέβαλον, φάντες, Ἡμέων μηδεὶς ὀνήιστος ἔστω, εἰ δὲ μή, ἄλλῃ τε καὶ μετ' ἄλλων δοκεῖ δ' οὗτος ὁ ἀνὴρ νόμους τινὰς Ῥωμαίοις συγγράφαι. καὶ Ἰππῶναξ δ' ἐστὶν ὁ ποιητὴς ἐξ Ἐφέσου καὶ Παρράσιος ὁ ζωγράφος καὶ Ἀπελλῆς, τῶν δὲ νεωτέρων Ἀλέξανδρος ῥήτωρ ὁ Λύχνος προσαγορευθεὶς, ὃς καὶ ἐπολιτεύσατο καὶ συνέγραψεν ἱστορίαν καὶ ἔπη κατέλιπεν, ἐν οἷς τὰ τε οὐράνια διατίθεται καὶ τὰς ἡπείρους γεωγραφεῖ, καθ' ἐκάστην ἐκδοὺς ποιήμα.²

26. Μετὰ δὲ τὴν ἐκβολὴν τοῦ Καύστρου

¹ προσχώσεις Eto, προχώσεις other MSS. and Meineke.

entrance would be deep enough for large merchant vessels—as also the harbour itself, which formerly had shallow places because of the silt deposited by the Cayster River—if a mole were thrown up at the mouth, which was very wide, and therefore ordered that the mole should be built. But the result was the opposite, for the silt, thus hemmed in, made the whole of the harbour, as far as the mouth, more shallow. Before this time the ebb and flow of the tides would carry away the silt and draw it to the sea outside. Such, then, is the harbour; and the city, because of its advantageous situation in other respects, grows daily, and is the largest emporium in Asia this side the Taurus.

25. Notable men have been born in this city: in ancient times, Heracleitus the Obscure, as he is called; and Hermodorus, concerning whom Heracleitus himself says: "It were right for the Ephesians from youth upwards to be hanged, who banished their most useful man, saying: 'Let no man of us be most useful; otherwise, let him be elsewhere and with other people.'" Hermodorus is reputed to have written certain laws for the Romans. And Hipponax the poet was from Ephesus; and so were Parrhasius the painter and Apelles, and more recently Alexander the orator, surnamed Lychnus,¹ who was a statesman, and wrote history, and left behind him poems in which he describes the position of the heavenly bodies and gives a geographic description of the continents, each forming the subject of a poem.

26. After the outlet of the Cayster River comes

¹ i.e. Lamp.

² *ποίημα* F, *ποιήματα* other MSS.

λίμνη ἐστὶν ἐκ τοῦ πελάγους ἀναχεομένη, καλεῖται δὲ Σελινουσία, καὶ ἐφεξῆς ἄλλη σύρρους αὐτῇ, μεγάλας ἔχουσαι προσόδους· ἃς οἱ βασιλεῖς μὲν, ἱερὰς οὔσας, ἀφείλοντο τὴν θεόν, Ῥωμαῖοι δ' ἀπέδωκαν· πάλιν δ' οἱ δημοσιῶναι βιασάμενοι περιέστησαν εἰς ἑαυτοὺς τὰ τέλη, πρεσβεύσας δὲ ὁ Ἀρτεμίδωρος, ὥς φησι, τὰς τε λίμνας ἀπέλαβε τῇ θεῷ, καὶ τὴν Ἡρακλεῶτιν ἀφισταμένην ἐξενίκησε, κριθεὶς ἐν Ῥώμῃ· ἀντὶ δὲ τούτων εἰκόνα χρυσὴν ἀνέστησεν ἡ πόλις ἐν τῷ ἱερῷ. τῆς δὲ λίμνης ἐν τῷ κοιλοτάτῳ βασιλέως ἐστὶν ἱερόν· φασὶ δ' Ἀγαμέμνονος ἴδρυμα.

27. Εἵτα τὸ Γαλλήσιον ὄρος καὶ ἡ Κολοφών, πόλις Ἰωνικὴ, καὶ τὸ πρὸ αὐτῆς ἄλσος τοῦ Κλαρίου Ἀπόλλωνος, ἐν ᾧ καὶ μαντεῖον ἦν ποτὲ παλαιόν. λέγεται δὲ Κάλχας ὁ μάντις μετ' Ἀμφιλόχου τοῦ Ἀμφιαράου κατὰ τὴν ἐκ Τροίας ἐπάνοδον πεζῇ δεῦρο ἀφικέσθαι, περιτυχὼν δ' ἑαυτοῦ κρείττονι μάντει κατὰ τὴν Κλάρων, Μόψῳ τῷ Μαντοῦς τῆς Τειρεσίου θυγατρὸς, διὰ λύπην ἀποθανεῖν. Ἡσίοδος μὲν οὖν οὕτω πως διασκευάζει τὸν μῦθον· προτείνει γάρ τι τοιοῦτο τῷ Μόψῳ τὸν Κάλχαντα·

θαυμά μ' ἔχει κατὰ θυμόν, ὅσους ἐρινειὸς
ὀλύνθους¹

οὗτος ἔχει, μικρὸς περ ἐών· εἵποισ ἂν ἀριθμόν·
τὸν δ' ἀποκρίνασθαι·

μύριοι εἰσιν ἀριθμόν, ἀτὰρ μέτρον γε μέδιμνος·

¹ ὅσους ἐρινειὸς ὀλύνθους, Tzschucke and later editors, for ἐρινεὶς ὅσους ὀλύνθους.

a lake that runs inland from the sea, called Selinusia; and next comes another lake that is confluent with it, both affording great revenues. Of these revenues, though sacred, the kings deprived the goddess, but the Romans gave them back; and again the tax-gatherers forcibly converted the tolls to their own use; but when Artemidorus was sent on an embassy, as he says, he got the lakes back for the goddess, and he also won the decision over Heracleotis, which was in revolt,¹ his case being decided at Rome; and in return for this the city erected in the temple a golden image of him. In the innermost recess of the lake there is a temple of a king, which is said to have been built by Agamemnon.

27. Then one comes to the mountain Gallesius, and to Colophon, an Ionian city, and to the sacred precinct of Apollo Clarius, where there was once an ancient oracle. The story is told that Calchas the prophet, with Amphiloehus the son of Amphiaraus, went there on foot on his return from Troy, and that having met near Clarus a prophet superior to himself, Mopsus, the son of Manto, the daughter of Teiresias, he died of grief. Now Hesiod² revises the myth as follows, making Calchas propound to Mopsus this question: "I am amazed in my heart at all these figs on this wild fig tree, small though it is; can you tell me the number?" And he makes Mopsus reply: "They are ten thousand in number, and their measure is a medimnus;³ but there is one

¹ *i.e.* from Ephesus.

² *Frag.* 160 (Rzach).

³ About a bushel and a half.

εἰς δὲ περισσεύει, τὸν ἐπενθέμεν¹ οὐ κε δύναιο.
ὥς φάτο· καὶ σφιν ἀριθμὸς ἐτήτυμος εἶδετο
μέτρον.

καὶ τότε δὴ Κάλχανθ' ὕπνος θανάτοιο κάλυψε.

- C 643 Φερεκύδης δὲ φησιν ὅν προβαλεῖν ἔγκυον τὸν
Κάλχαντα, πόσους ἔχει χοίρους, τὸν δ' εἰπεῖν,
ὅτι τρεῖς, ὧν ἓνα θῆλυν· ἀληθεύσαντος δ', ἀπο-
θανεῖν ὑπὸ λύπης. οἱ δὲ τὸν μὲν Κάλχαντα
προβαλεῖν τὴν ὅν φασί, τὸν δὲ τὸν ἐρινεόν, καὶ
τὸν μὲν εἰπεῖν τάληθές, τὸν δὲ μή, ἀποθανεῖν
δὲ ὑπὸ λύπης καὶ κατὰ τι λόγιον. λέγει δ'
αὐτὸ Σοφοκλῆς ἐν Ἑλένης ἀπαιτήσῃ, ὡς εἰμαρ-
μένον εἶη ἀποθανεῖν, ὅταν κρείττονι ἑαυτοῦ
μάντει περιτύχῃ· οὗτος δὲ καὶ εἰς Κιλικίαν
μεταφέρει τὴν ἔριν καὶ τὸν θάνατον τοῦ Κάλ-
χαντος. τὰ μὲν παλαιὰ τοιαῦτα.

28. Ἐκτῆσαντο δὲ ποτε καὶ ναυτικὴν ἀξιό-
λογον δύναμιν Κολοφώνιοι καὶ ἱππικὴν, ἐν ᾗ
τοσοῦτον διέφερον τῶν ἄλλων, ὥσθ', ὅπου ποτὲ
ἐν τοῖς δυσκαταλύτοις πολέμοις τὸ ἱππικὸν τῶν
Κολοφωνίων ἐπικουρήσειε, λύεσθαι τὸν πόλεμον
ἀφ' οὗ καὶ τὴν παροιμίαν ἐκδοθῆναι τὴν λέ-
γουσαν, τὸν Κολοφῶνα ἐπέθηκεν, ὅταν τέλος
ἐπιτεθῇ βέβαιον τῷ πράγματι. ἄνδρες δ' ἐγέ-
νοντο Κολοφώνιοι τῶν μνημονευομένων Μίμνε-
ρος, αὐλητὴς ἅμα καὶ ποιητὴς ἐλεγείας, καὶ
Ξενοφάνης ὁ φυσικός, ὁ τοὺς σίλλους ποιήσας
διὰ ποιημάτων· λέγει δὲ Πίνδαρος καὶ Πολύ-
μναστόν τινα τῶν περὶ τὴν μουσικὴν ἐλλογίμων·

¹ ἐπενθέμεν, Spohn, for ἐπελθέμεν; so the later editors.

over, which you cannot put in the measure."¹ "Thus he spake," Hesiod adds, "and the number the measure could hold proved true. And then the eyes of Calchas were closed by the sleep of death." But Pherecydes says that the question propounded by Calchas was in regard to a pregnant sow, how many pigs she carried, and that Mopsus said, "three, one of which is a female," and that when Mopsus proved to have spoken the truth, Calchas died of grief. Some say that Calchas propounded the question in regard to the sow, but that Mopsus propounded the question in regard to the wild fig tree, and that the latter spoke the truth but that the former did not, and died of grief, and in accordance with a certain oracle. Sophocles tells the oracle in his *Reclaiming of Helen*, that Calchas was destined to die when he met a prophet superior to himself, but he transfers the scene of the rivalry and of the death of Calchas to Cilicia. Such are the ancient stories.

28. The Colophonians once possessed notable naval and cavalry forces, in which latter they were so far superior to the others that wherever in wars that were hard to bring to an end, the cavalry of the Colophonians served as ally, the war came to an end; whence arose the proverb, "he put Colophon to it," which is quoted when a sure end is put to any affair. Native Colophonians, among those of whom we have record, were: Mimnermus, who was both a flute-player and elegiac poet; Xenophanes, the natural philosopher, who composed the "Silli"² in verse; and Pindar³ speaks also of a certain

¹ *i.e.* the measure would hold only 999 of these figs. .

² Satires, or lampoons, attacking Homer and Hesiod.

³ *Frag.* 188 (Bergk).

φθέγμα μὲν πάγκοινον ἔγνωκας Πολυμνάστου
Κολοφωνίου ἀνδρός·

καὶ "Ομηρον δέ τινες ἐντεῦθεν εἶναί φασιν.
εὐθυπλοία μὲν οὖν ἑβδομήκοντα στάδιοι εἰσιν
ἐξ Ἐφέσου, ἐγκολπίζοντι δὲ ἑκατὸν καὶ εἴκοσι.

29. Μετὰ δὲ Κολοφῶνα ὄρος Κοράκιον καὶ
νησίον ἱερὸν Ἀρτέμιδος, εἰς ὃ διαινηχομένας
τίκτειν τὰς ἐλάφους πεπιστεύκασιν. εἴτα Λέ-
βεδος, διέχουσα Κολοφῶνος ἑκατὸν καὶ εἴκοσι·
ἐνταῦθα τῶν περὶ τὸν Διόνυσον τεχνιτῶν ἢ
σύνδοδος καὶ κατοικία τῶν ἐν Ἰωνίᾳ μέχρι
Ἑλλησπόντου, ἐν ᾗ πανήγυρις τε καὶ ἀγῶνες
κατ' ἔτος συντελοῦνται τῷ Διονύσῳ. ἐν Τέῳ
δὲ ὥκουν πρότερον τῇ ἐφεξῆς πόλει τῶν Ἰώνων·
ἐμπεσοῦσής δὲ στάσεως, εἰς Ἐφεσον κατέφυγον.
Ἀττάλου δ' εἰς Μυόννησον αὐτοὺς καταστήσαντος
μεταξὺ Τέῳ καὶ Λεβέδου, πρεσβεύονται Τήιοι
δεόμενοι Ῥωμαίων, μὴ περιδεῖν ἐπιτειχιζομένην
σφίσι τὴν Μυόννησον, οἱ δὲ μετέστησαν εἰς
Λέβεδον, δεξαμένων τῶν Λεβεδίων ἀσμένως διὰ
τὴν κατέχουσαν αὐτοὺς ὀλιγανδρίαν. καὶ Τέως
δὲ Λεβέδου διέχει ἑκατὸν εἴκοσι, μεταξὺ δὲ
νῆσος Ἀσπῖς, οἱ δ' Ἀρκόννησον καλοῦσι· καὶ
ἡ Μυόννησος δὲ ἐφ' ὕψους χερρονησίζοντος
κατοικεῖται.

C 644 30. Καὶ ἡ Τέως δὲ ἐπὶ χερρονήσῳ ἱδρυται,
λιμένα ἔχουσα· ἐνθένδ' ἐστὶν Ἀνακρέων ὁ
μελοποιός, ἐφ' οὗ Τήιοι, τὴν πόλιν ἐκλιπόντες,
εἰς Ἀβδηρα ἀπώκησαν, Θρακίαν πόλιν, οὗ
φέρουντες τὴν τῶν Περσῶν ὕβριν, ἀφ' οὗ καὶ
τοῦτ' εἴρηται·

Polymnastus as one of the famous musicians: "Thou knowest the voice, common to all, of Polymnastus the Colophonian." And some say that Homer was from there. On a straight voyage it is seventy stadia from Ephesus, but if one includes the sinuosities of the gulfs it is one hundred and twenty.

29. After Colophon one comes to the mountain Coracius and to an isle sacred to Artemis, whither deer, it has been believed, swim across and give birth to their young. Then comes Lebedus, which is one hundred and twenty stadia distant from Colophon. This is the meeting-place and settlement of all the Dionysiac artists in Ionia as far as the Hellespont; and this is the place where both games and a general festal assembly are held every year in honour of Dionysus. They formerly lived in Teos, the city of the Ionians that comes next after Colophon, but when the sedition broke out they fled for refuge to Ephesus. And when Attalus settled them in Myonnesus between Teos and Lebedus the Tëians sent an embassy to beg of the Romans not to permit Myonnesus to be fortified against them; and they migrated to Lebedus, whose inhabitants gladly received them because of the dearth of population by which they were then afflicted. Teos, also, is one hundred and twenty stadia distant from Lebedus; and in the intervening distance there is an island Aspis, by some called Arconnesus. And Myonnesus is settled on a height that forms a peninsula.

30. Teos also is situated on a peninsula; and it has a harbour. Anacreon the melic poet was from Teos; in whose time the Tëians abandoned their city and migrated to Abdera, a Thracian city, being unable to bear the insolence of the Persians; and

Ἀβδηρα, καλὴ Τηίων ἀποικία.

πάλιν δ' ἐπανήλθον τινες αὐτῶν χρόνῳ ὕστερον· εἴρηται δὲ καὶ περὶ Ἀπελλικῶντος, ὅτι Τήιος ἦν κακεῖνος· γέγονε δὲ καὶ συγγραφεὺς Ἐκαταῖος ἐκ τῆς αὐτῆς πόλεως. ἔστι καὶ ἄλλος λιμὴν ὁ πρόσβορρος ἀπὸ τριάκοντα σταδίων τῆς πόλεως, Γερραῖδαι.

31. Εἴτα Χαλκιδεῖς καὶ¹ ὁ τῆς Χερρονήσου ἰσθμὸς τῆς Τηίων καὶ Ἐρυθραίων· ἐντὸς μὲν οὖν τοῦ ἰσθμοῦ οἰκοῦσιν οὗτοι, ἐπ' αὐτῷ δὲ τῷ ἰσθμῷ Τήιοι καὶ Κλαζομένιοι· τὸ μὲν γὰρ νότιον τοῦ ἰσθμοῦ πλευρὸν ἔχουσι Τήιοι, τοὺς Χαλκιδέας, τὸ δὲ πρόσβορρον Κλαζομένιοι, καθ' ὃ συνάπτουσι τῇ Ἐρυθραίᾳ. κεῖται δ' Ὑπόκρημνος ὁ τόπος ἐπὶ τῇ ἀρχῇ τοῦ ἰσθμοῦ, ἐντὸς μὲν ἀπολαμβάνων τὴν Ἐρυθραίαν, ἐκτὸς² δὲ τὴν τῶν Κλαζομενίων. ὑπέρεκειται δὲ τῶν Χαλκιδέων ἄλσος καθιερωμένον Ἀλεξάνδρῳ τῷ Φιλίππου, καὶ ἀγὼν ὑπὸ³ τοῦ κοινοῦ τῶν Ἰώνων Ἀλεξάνδρεια καταγγέλλεται, συντελούμενος ἐνταῦθα. ἡ δ' ὑπέρβασις τοῦ ἰσθμοῦ τοῦ ἀπὸ τοῦ Ἀλεξανδρείου καὶ τῶν Χαλκιδέων μέχρι τοῦ Ὑποκρήμνου πεντήκοντά εἰσι στάδιοι, ὁ δὲ περίπλους πλείους ἢ χίλιοι. κατὰ μέσον δέ που τὸν περίπλου αἱ Ἐρυθραί, πόλις Ἰωνικὴ, λιμένα ἔχουσα, καὶ νησίδας προκειμένας τέτταρας Ἰππους καλουμένας.

32. Πρὶν δ' ἐλθεῖν ἐπὶ τὰς Ἐρυθράς, πρῶτον μὲν Ἐραι πολίχνην ἔστι Τηίων· εἴτα Κώρυκος,

¹ καί, the editors insert.

² ἐκτός E, ἐντός other MSS.

³ ὑπό, Corais, for ἀπό.

hence the verse in reference to Abdera. "Abdera, beautiful colony of the Tēians." But some of them returned again in later times. As I have already said,¹ Apellicon also was a Tēian; and Hecataeus the historian was from the same city. And there is also another harbour to the north, thirty stadia distant from the city, called Gerrhaeidae.

31. Then one comes to Chalcideis, and to the isthmus of the Chersonesus, belonging to the Tēians and Erythraeans. Now the latter people live this side the isthmus, but the Tēians and Clazomenians live on the isthmus itself; for the southern side of the isthmus, I mean the Chalcideis, is occupied by Tēians, but the northern by Clazomenians, where their territory joins the Erythraean. At the beginning of the isthmus lies the place called Hypocremnus, which lies between the Erythraean territory this side the isthmus and that of the Clazomenians on the other side. Above the Chalcideis is situated a sacred precinct consecrated to Alexander the son of Philip; and games, called the Alexandreia, are proclaimed by the general assembly of the Ionians and are celebrated there. The passage across the isthmus from the sacred precinct of Alexander and from the Chalcideis to Hypocremnus is fifty stadia, but the voyage round by sea is more than one thousand. Somewhere about the middle of the circuit is Erythrae, an Ionian city, which has a harbour, and also four isles lying off it, called Hippi.²

32. Before coming to Erythrae, one comes first to a small town Erae belonging to the Tēians; and then

¹ 13. 1. 54.

² i.e. Horses.

ὄρος ὑψηλόν, καὶ λιμὴν ὑπ' αὐτῷ Κασύστης καὶ ἄλλος Ἐρυθρᾶς λιμὴν καλούμενος καὶ ἐφεξῆς πλείους ἕτεροι. φασὶ δὲ τὸν παράπλουν τοῦ Κωρύκου πάντα ληστήριον ὑπάρχει τῶν Κωρυκαίων καλουμένων, εὐρομένων τρόπον καινὸν τῆς ἐπιβουλῆς τῶν πλοῖζομένων· κατεσπαρμένους γὰρ ἐν τοῖς λιμέσι τοῖς καθορμιζομένοις ἐμπόροις προσφοιτᾶν καὶ ὠτακουστέιν, τί φέροιεν καὶ ποῦ πλέοιεν, εἰτα συνελθόντας ἀναχθεῖσι τοῖς ἀνθρώποις ἐπιτίθεσθαι καὶ καθαρπάζειν· ἀφ' οὗ δὴ πάντα τὸν πολυπράγμονα καὶ κατακούειν ἐπιχειροῦντα τῶν λάθρα καὶ ἐν ἀπορρήτῳ διαλεγόμενων Κωρυκαῖον καλούμεν, καὶ ἐν παροιμίᾳ φημέν·

τοῦ δ' ἄρ' ¹ ὁ Κωρυκαῖος ἠκροάζετο,

ὅταν δοκῇ τις πράττειν δι' ἀπορρήτων ἢ λαλεῖν, μὴ λανθάνῃ δὲ διὰ τοὺς κατασκοποῦντας καὶ φιλοπευστοῦντας τὰ μὴ προσήκοντα.

33. Μετὰ δὲ Κώρυκον Ἀλόννησος νησίον· C 645 εἰτα τὸ Ἀργεννον, ἄκρα τῆς Ἐρυθραίας πλησιάζουσα μάλιστα τῷ Χίῳ Ποσειδίῳ, ποιοῦντι πορθμὸν ὅσον ἐξήκοντα σταδίων. μετὰ δὲ τῶν Ἐρυθρῶν καὶ τοῦ Ὑποκρήμνου Μίμας ἐστὶν ὄρος ὑψηλόν, εὐθηνον, πολὺ δένδρον· εἰτα κόμη Κυβελία καὶ ἄκρα Μέλαινα καλουμένη, μύλων ἔχουσα λατόμιον.

34. Ἐκ δ' Ἐρυθρῶν Σίβυλλά ἐστίν, ἔνθους καὶ μαντικὴ γυνὴ τῶν ἀρχαίων τις· κατ' Ἀλέξανδρον δὲ ἄλλη ἦν τὸν αὐτὸν τρόπον μαντικῇ,

¹ ἄρ', Jones, from conj. of Professor Capps, for ἄρ'.

to Corycus, a high mountain, and to a harbour at the foot of it, Casystes, and to another harbour called Erythras, and to several others in order thereafter. The waters along the coast of Mt. Corycus, they say, were everywhere the haunt of pirates, the Corycaean, as they are called, who had found a new way of attacking vessels; for, they say, the Corycaean would scatter themselves among the harbours, follow up the merchants whose vessels lay at anchor in them, and overhear what cargoes they had aboard and whither they were bound, and then come together and attack the merchants after they had put to sea and plunder their vessels; and hence it is that we call every person who is a busybody and tries to overhear private and secret conversations a Corycaean; and that we say in a proverb: "Well then, the Corycaean was listening to this," when one thinks that he is doing or saying something in secret, but fails to keep it hidden because of persons who spy on him and are eager to learn what does not concern them.

33. After Mt. Corycus one comes to Halonnesos, a small island. Then to Argennum, a promontory of the Erythraean territory; it is very close to the Poseidium of the Chians, which latter forms a strait about sixty stadia in width. Between Erythrae and Hypocremnus lies Mimas, a lofty mountain, which is well supplied with game and well wooded. Then one comes to a village Cybelia, and to a promontory Melaena, as it is called, which has a millstone quarry.

34. Erythrae was the native city of Sibylla, a woman who was divinely inspired and had the gift of prophecy, one of the ancients. And in the time of Alexander there was another woman who likewise

καλουμένην Ἀθηναίς, ἐκ τῆς αὐτῆς πόλεως· καὶ καθ' ἡμᾶς Ἡρακλείδης Ἡροφίλειος¹ ἰατρός, συσχολαστῆς Ἀπολλωνίου τοῦ Μυῆς.

35. Ἡ δὲ Χίος τὸν μὲν περίπλουν ἐστὶ σταδίων ἐννακοσίων παρὰ γῆν φερομένῳ, πόλιν δ' ἔχει εὐλίμενον καὶ ναύσταθμον ναυσὶν ὀγδοήκοντα. ἐν δὲ τῷ περίπλῳ δεξιᾷν τὴν νῆσον ἔχοντι ἀπὸ τῆς πόλεως πρῶτον μὲν ἐστὶ τὸ Ποσειδίου, εἴτα Φάναι, λιμὴν βαθύς, καὶ νεῶς Ἀπόλλωνος καὶ ἄλσος φοινίκων· εἴτα Νότιον, ὕφορμος αἰγιαλός· εἴτα Λαίους, καὶ οὗτος ὕφορμος αἰγιαλός, ὅθεν εἰς τὴν πόλιν ἐξήκοντα σταδίων ἰσθμός· περίπλους δὲ τριακοσίων ἐξήκοντα, ὃν ἐπήλθομεν. εἴτα Μέλαινα ἄκρα, καθ' ἣν τὰ Ψύρα, νῆσος ἀπὸ πεντήκοντα σταδίων τῆς ἄκρας, ὑψηλή, πόλιν ὁμώνυμον ἔχουσα· κύκλος δὲ τῆς νήσου τετταράκοντα στάδιοι. εἴθ' ἡ Ἀριουσία χώρα τραχεῖα καὶ ἀλίμενος, σταδίων ὅσον τριάκοντα,² οἶνον ἄριστον φέρουσα τῶν Ἑλληνικῶν. εἴτα τὸ Πελιναῖον ὄρος ὑψηλότατον τῶν ἐν τῇ νήσῳ. ἔχει δ' ἡ νῆσος καὶ λατόμιον μαρμάρου λίθου. ἄνδρες δὲ Χῖοι γεγόνασιν ἐλλόγιμοι Ἴων τε ὁ τραγικός καὶ Θεόπομπος ὁ συγγραφεὺς καὶ Θεόκριτος ὁ σοφιστής· οὗτοι δὲ καὶ ἀντεπολιτεύσαντο ἀλλήλοις. ἀμφισβητοῦσι δὲ καὶ Ὀμήρου Χῖοι, μαρτύριον μέγα³ τοὺς Ὀμηρίδας καλουμένους ἀπὸ τοῦ ἐκείνου γένους προχειριζόμενοι, ὧν καὶ Πίνδαρος μέμνηται·

¹ Ἡροφίλειος, Tzschucke, for Ἡρόμιλος.

² τριάκοντα, Kramer, following Stephanus, for τριακοσίων; so Meineke.

³ μέγα, Meineke, for μετά; μὲν ποτὲ, κατὰ w; word omitted in R.

had the gift of prophecy; she was called Athenais, and was a native of the same city. And, in my time, Heracleides the Herophileian physician, fellow-pupil of Apollonius Mys,¹ was born there.

35. As for Chios, the voyage round it along the coast is nine hundred stadia; and it has a city with a good port and with a naval station for eighty ships. On making the voyage round it from the city, with the island on the right, one comes first to the Poseidium. Then to Phanae, a deep harbour, and to a temple of Apollo and a grove of palm trees. Then to Notium, a shore suited to the anchoring of vessels. Then to Laius, this too a shore suited to the anchoring of vessels; whence to the city there is an isthmus of sixty stadia, but the voyage round, which I have just now described, is three hundred and sixty stadia. Then to Melaena, a promontory, opposite to which lies Psyra, an island fifty stadia distant from the promontory, lofty, and having a city of the same name. The circuit of the island is forty stadia. Then one comes to Ariusia, a rugged and harbourless country, about thirty stadia in extent, which produces the best of the Grecian wines. Then to Pelinaeus, the highest mountain in the island. And the island also has a marble quarry. Famous natives of Chios are: Ion the tragic poet, and Theopompus the historian, and Theocritus the sophist. The two latter were political opponents of one another. The Chians also claim Homer, setting forth as strong testimony that the men called Homeridae were descendants of Homer's family; these are mentioned by Pindar:²

¹ Mus, i.e. Mouse.

² *Nemean Odes* 2. 1.

ὅθεν περ καὶ Ὀμηρίδαι
 ῥαπτῶν ἐπέων τὰ πόλλ' αἰοιοί.

ἐκέκτηντο δὲ καὶ ναυτικόν ποτε Χίοι, καὶ
 ἀνθήπτοντο τῆς κατὰ θάλατταν ἀρχῆς καὶ
 ἐλευθερίας. ἐκ Χίου δ' ἐς Λέσβον νότῳ τετρα-
 κόσιοί που στάδιοι.

36. Ἐκ δὲ τοῦ Ὑποκρήμνου¹ Χύτριόν ἐστι
 τόπος, ὅπου πρότερον ἴδρυντο Κλαζομεναί· εἴθ'
 ἡ νῦν πόλις, νησία ἔχουσα προκείμενα ὀκτὼ
 γεωργούμενα. Κλαζομένιος δ' ἦν ἀνὴρ ἐπιφανὴς
 Ἀναξαγόρας ὁ φυσικὸς, Ἀναξιμένους ὁμιλητὴς
 τοῦ Μιλησίου· διήκουσαν δὲ τούτου Ἀρχέλαος
 ὁ φυσικὸς καὶ Εὐριπίδης ὁ ποιητής. εἴθ' ἱερὸν
 Ἀπόλλωνος καὶ θερμὰ ὕδατα καὶ ὁ Σμυρναίων
 κόλπος καὶ ἡ πόλις.

C 646 37. Ἐξῆς δὲ ἄλλος κόλπος, ἐν ᾧ ἡ παλαιὰ
 Σμύρνα ἀπὸ εἴκοσι σταδίων τῆς νῦν. Λυδῶν δὲ
 κατασπασάντων τὴν Σμύρναν, περὶ τετρακόσια
 ἔτη διετέλεσεν οἰκουμένη κωμηδόν· εἴτα ἀνήγειρεν
 αὐτὴν Ἀντίγονος, καὶ μετὰ ταῦτα Λυσίμαχος,
 καὶ νῦν ἐστὶ καλλίστη τῶν πασῶν, μέρος μὲν
 τι ἔχουσα ἐπ' ὄρει τετειχισμένον, τὸ δὲ πλεόν
 ἐν πεδίῳ πρὸς τῷ λιμένι καὶ πρὸς τῷ Μητρῷ
 καὶ πρὸς γυμνασίῳ. ἔστι δ' ἡ ῥυμοτομία
 διάφορος ἐπ' εὐθειῶν εἰς δύναμιν καὶ αἱ ὁδοὶ
 λιθόστρωτοι στοαὶ τε μεγάλαι τετράγωνοι, ἐπί-
 πεδοί τε καὶ ὑπερώοι· ἔστι δὲ καὶ βιβλιοθήκη
 καὶ τὸ Ὀμήρειον, στοὰ τετράγωνος, ἔχουσα νεῶν
 Ὀμήρου καὶ ξόανον· μεταποιοῦνται γὰρ καὶ οὗτοι

¹ Ὑποκρήμνου F, Ἀποκρήμνου other MSS.; but cp. Ὑποκρήμνου
 in 14. 1. 33.

"Whence also the Homeridae, singers of deftly woven lays, most often" The Chians at one time possessed also a fleet, and attained to liberty and to maritime empire. The distance from Chios to Lesbos, sailing southwards, is about four hundred stadia.

36. After Hypocremnus one comes to Chytrium, the site on which Clazomenae was situated in earlier times. Then to the present Clazomenae, with eight small islands lying off it that are under cultivation. Anaxagoras, the natural philosopher, an illustrious man and associate of Anaximenes the Milesian, was a Clazomenian. And Archelläus the natural philosopher and Euripides the poet took his entire course. Then to a temple of Apollo and to hot springs, and to the gulf and the city of the Smyrnaeans.

37. Next one comes to another gulf, on which is the old Smyrna, twenty stadia distant from the present Smyrna. After Smyrna had been rased by the Lydians, its inhabitants continued for about four hundred years to live in villages. Then they were reassembled into a city by Antigonos, and afterwards by Lysimachus, and their city is now the most beautiful of all; a part of it is on a mountain and walled, but the greater part of it is in the plain near the harbour and near the Metröum and near the gymnasium. The division into streets is exceptionally good, in straight lines as far as possible; and the streets are paved with stone; and there are large quadrangular porticoes, with both lower and upper stories. There is also a library; and the Homereium, a quadrangular portico containing a shrine and wooden statue¹ of Homer; for the

¹ The primary meaning of the Greek word here used for "statue," *zoanon*, is "a prehistoric statue carved of wood."

διαφερόντως τοῦ ποιητοῦ, καὶ δὴ καὶ νόμισμά τι χαλκοῦν παρ' αὐτοῖς Ὀμήρειον λέγεται. ῥεῖ δὲ πλησίον τοῦ τείχους ὁ Μέλης ποταμός. ἔστι δὲ πρὸς τῇ ἄλλῃ κατασκευῇ τῆς πόλεως καὶ λιμὴν κλειστός. ἐν δ' ἐλάττωμα τῶν ἀρχιτεκτόνων οὐ μικρόν, ὅτι τὰς ὁδοὺς στορνύντες,¹ ὑπορρύσεις οὐκ ἔδωκαν αὐταῖς, ἀλλ' ἐπιπολάζει τὰ σκύβαλα, καὶ μάλιστα ἐν τοῖς ὄμβροις ἐπαφιεμένων τῶν ἀποσκευῶν.² ἐνταῦθα Δολοβέλλας Τρεβώνιον ἐκπολιορκήσας ἀνεῖλεν, ἕνα τῶν δολοφονησάντων Καίσαρα τὸν Θεόν, καὶ τῆς πόλεως παρέλυσεν πολλὰ μέρη.

38. Μετὰ δὲ Σμύρναν αἱ Λεῦκαι πολίχμιον, ὃ ἀπέστησεν Ἀριστόνικος μετὰ τὴν Ἀττάλου τοῦ Φιλομήτορος τελευτὴν, δοκῶν τοῦ γένους εἶναι τοῦ τῶν βασιλέων καὶ διανοούμενος εἰς ἑαυτὸν ποιεῖσθαι τὴν ἀρχήν· ἐντεῦθεν μὲν οὖν ἐξέπεσεν, ἡττηθεὶς ναυμαχίᾳ περὶ τὴν Κυμαίαν ὑπὸ Ἐφesiών, εἰς δὲ τὴν μεσόγαιαν ἀνιὼν ἡθροισεν διὰ ταχέων πλῆθος ἀπόρων τε ἀνθρώπων καὶ δούλων ἐπ' ἐλευθερίᾳ κατακεκλημένων, οὓς Ἡλιοπολίτας ἐκάλεσε. πρῶτον μὲν οὖν παρεισέπεσεν εἰς Θυάτειρα, εἰτ' Ἀπολλωνίδα ἔσχευ, εἰτ' ἄλλων ἐφίετο φρουρίων· οὐ πολὺν δὲ διηγέμετο χρόνον, ἀλλ' εὐθὺς αἱ τε πόλεις ἔπεμψαν πλῆθος, καὶ Νικομήδης ὁ Βιθυνὸς ἐπεκούρησεν καὶ οἱ τῶν Καππαδόκων βασιλεῖς. ἔπειτα πρέσβεις Ῥωμαίων πέντε ἦκον, καὶ μετὰ ταῦτα

¹ στορνύντες Meineke, for στρωννύντες B, στορνήντες F, στορύνντες other MSS.

² ἀποσκευῶν, Corais, for παρασκευῶν.

Smyrnaeans also lay especial claim to the poet; and indeed a bronze coin of theirs is called Homereium. The River Meles flows near the walls; and, in addition to the rest of the city's equipment, there is also a harbour that can be closed. But there is one error, not a small one, in the work of the engineers, that when they paved the streets they did not give them underground drainage; instead, filth covers the surface, and particularly during rains, when the cast-off filth is discharged upon the streets. It was here that Dolabella captured by siege, and slew, Trebonius, one of the men who treacherously murdered the deified Caesar; and he set free¹ many parts of the city.

38. After Smyrna one comes to Leucae, a small town, which after the death of Attalus Philometor² was caused to revolt by Aristonicus, who was reputed to belong to the royal family and intended to usurp the kingdom. Now he was banished from Smyrna, after being defeated in a naval battle near the Cymaeian territory by the Ephesians, but he went up into the interior and quickly assembled a large number of resourceless people, and also of slaves, invited with a promise of freedom, whom he called Heliopolitae.³ Now he first fell upon Thyateira unexpectedly, and then got possession of Apollonis, and then set his efforts against other fortresses. But he did not last long; the cities immediately sent a large number of troops against him, and they were assisted by Nicomedes the Bithynian and by the kings of the Cappadocians. Then came five Roman

¹ Others translate the verb "destroyed," or the like, but cf. its use in 8. 6. 14 and Herodotus 1. 149.

² See 13. 4. 2. ³ Citizens of the city of Helios (Sun-god).

στρατιά¹ καὶ ὑπατος Πόπλιος Κράσσος, καὶ μετὰ ταῦτα Μάρκος Περπέρνας, ὃς καὶ κατέλυσε τὸν πόλεμον, ζωγρία λαβὼν τὸν Ἀριστόνικον καὶ ἀναπέμψας εἰς Ῥώμην. ἐκεῖνος μὲν οὖν ἐν τῷ δεσμοτηρίῳ κατέστρεψε τὸν βίον, Περπέρναν δὲ νόσος διέφθειρε, Κράσσος δὲ περὶ Λεύκας, ἐπιθεμένων τινῶν, ἔπεσεν ἐν μάχῃ. Μάνιος δ' Ἀκύλλιος, ἐπελθὼν ὑπατος μετὰ δέκα πρεσβευτῶν, διέταξε τὴν ἐπαρχίαν εἰς τὸ νῦν ἔτι συμμένον
 O 647 τῆς πολιτείας σχῆμα. μετὰ δὲ Λεύκας Φώκαια ἐν κόλπῳ· περὶ δὲ ταύτης εἰρήκαμεν ἐν τῷ περὶ Μασσαλίας λόγῳ. εἴθ' οἱ ὄροι τῶν Ἰώνων καὶ τῶν Αἰολέων· εἰρηται δὲ καὶ περὶ τούτων. ἐν δὲ τῇ μεσογαίᾳ τῆς Ἰωνικῆς παραλίας λοιπὰ ἔστι τὰ περὶ τὴν ὁδὸν τὴν ἐξ Ἐφέσου μέχρι Ἀντιοχείας καὶ τοῦ Μαιάνδρου. ἔστι δὲ καὶ τὰ χωρία ταῦτα Λυδοῖς καὶ Καρσὶν ἐπίμικτα καὶ τοῖς Ἑλλήσι.

39. Πρώτη δ' ἐστὶν ἐξ Ἐφέσου Μαγνησία, πόλις Αἰολίς, λεγομένη δὲ ἐπὶ Μαιάνδρῳ· πλησίον γὰρ αὐτοῦ ἴδρυται· πολὺ δὲ πλησιαιότερον ὁ Ληθαῖος, ἐμβάλλων εἰς τὸν Μαιάνδρον, τὴν δ' ἀρχὴν ἔχων ἀπὸ Πακτύου² τοῦ τῶν Ἐφεσίων ὄρους· ἕτερος δ' ἐστὶ Ληθαῖος ὁ ἐν Γορτύνῃ καὶ ὁ περὶ Τρίκκην, ἐφ' ᾧ ὁ Ἀσκληπιὸς γεννηθῆναι λέγεται, καὶ ἔτι ἐν τοῖς Ἑσπερίταις Λίβυσι. κεῖται δ' ἐν πεδίῳ πρὸς ὄρει καλουμένῳ Θώρακι ἢ πόλις, ἐφ' ᾧ σταυρωθῆναί φασι Δαφίταν τὸν γραμματικόν, λοιδορήσαντα τοὺς βασιλέας διὰ διστίχου.³

¹ στρατιά, Corais, for στρατεία.

² Πακτύου, Xylander, for Πακτίου.

ambassadors, and after that an army under Publius Crassus the consul,¹ and after that Marcus Perpernas, who brought the war to an end, having captured Aristonicus alive and sent him to Rome. Now Aristonicus ended his life in prison; Perpernas died of disease; and Crassus, attacked by certain people in the neighbourhood of Leucæ, fell in battle. And Manius Aquillius came over as consul² with ten lieutenants and organised the province into the form of government that still now endures. After Leucæ one comes to Phocæa, on a gulf, concerning which I have already spoken in my account of Massalia. Then to the boundaries of the Ionians and the Aeolians; but I have already spoken of these. In the interior above the Ionian seaboard there remain to be described the places in the neighbourhood of the road that leads from Ephesus to Antiocheia and the Maeander River. These places are occupied by Lydians and Carians mixed with Greeks.

39. The first city one comes to after Ephesus is Magnesia, which is an Aeolian city and is called "Magnesia on the Maeander," for it is situated near that river. But it is much nearer the Lethæus River, which empties into the Maeander and has its beginning in Mt. Pactyes, the mountain in the territory of the Ephesians. There is another Lethæus in Gortyna, and another near Triccê, where Asclepius is said to have been born, and still another in the country of the Western Libyans. And the city lies in the plain near the mountain called Thorax, on which Daphitas the grammarian is said to have been crucified, because he reviled the kings in a distich:

¹ 131 B.C.² 129 B.C.³ διστίχου F, στίχου other MSS.

πορφύρεοι μώλωπες, ἀπορρινήματα γάλης
Λυσιμάχου, Λυδῶν ἄρχετε καὶ Φρυγίης.

καὶ λόγιον δ' ἐκπεσεῖν αὐτῷ λέγεται, φυλάττεσθαι
τὸν Θώρακα.

40. Δοκοῦσι δ' εἶναι Μάγνητες Δελφῶν ἀπό-
γονοι, τῶν ἐποικησάντων τὰ Δίδυμα ὄρη ἐν
Θετταλίᾳ, περὶ ὧν φησὶν Ἡσίοδος·

ἢ οἷη Διδύμους ἱεροὺς ναίονσα κολωνούς,
Δωτίῳ ἐν πεδίῳ πολυβότρυος ἀντ' Ἀμύροιο,
νίψατο Βοιβιάδος λίμνης πόδα παρθένος ἀδμής.

ἐνταῦθα δ' ἦν καὶ τὸ τῆς Δινδυμήνης ἱερόν,
Μητρὸς θεῶν· ἱεράσασθαι¹ δ' αὐτοῦ τὴν Θεμι-
στοκλέους γυναῖκα, οἱ δὲ θυγατέρα παραδιδόασιν
νῦν δ' οὐκ ἔστι τὸ ἱερόν διὰ τὸ τὴν πόλιν εἰς
ἄλλον μετωκίσθαι τόπον· ἐν δὲ τῇ νῦν πόλει τὸ
τῆς Λευκοφρυγῆς ἱερόν ἐστίν Ἀρτέμιδος, ὃ τῷ
μὲν μεγέθει τοῦ ναοῦ καὶ τῷ πλήθει τῶν ἀναθη-
μάτων λείπεται τοῦ ἐν Ἐφέσῳ, τῇ δ' εὐρυθμία
καὶ τῇ τέχνῃ τῇ περὶ τὴν κατασκευὴν τοῦ σηκοῦ
πολὺν διαφέρει· καὶ τῷ μεγέθει ὑπεραίρει πάντας
τοὺς ἐν Ἀσίᾳ πλὴν δυεῖν, τοῦ ἐν Ἐφέσῳ καὶ
τοῦ ἐν Διδύμοις. καὶ τὸ παλαιὸν δὲ συνέβη
τοῖς Μάγνησιν ὑπὸ Τρηρῶν ἄρδην ἀναιρεθῆναι,
Κιμμερικοῦ ἔθνους, εὐτυχήσαντας² πολὺν χρόνον·
τῷ δ' ἐξῆς ἔτει Μιλησίους κατασχεῖν τὸν τόπον.
Καλλίνος μὲν οὖν ὥς εὐτυχούντων ἔτι τῶν
Μαγνήτων μέμνηται καὶ κατορθούντων ἐν τῷ
πρὸς τοὺς Ἐφεσίους πολέμῳ, Ἀρχίλοχος δὲ ἤδη
φαίνεται γνωρίζων τὴν γενομένην αὐτοῖς συμφο-
ράν·

"Purpled with stripes, mere filings of the treasure of Lysimachus, ye rule the Lydians and Phrygia." It is said that an oracle was given out that Daphitas should be on his guard against Thorax.

40. The Magnetans are thought to be descendants of Delphians who settled in the Didyman hills, in Thessaly, concerning whom Hesiod says: "Or as the unwedded virgin who, dwelling on the holy Didyman hills, in the Dotian Plain, in front of Amyrus, bathed her foot in Lake Boebeis."¹ Here was also the temple of Dindymenê, Mother of the gods. According to tradition, the wife of Themistocles, some say his daughter, served as a priestess there. But the temple is not now in existence, because the city has been transferred to another site. In the present city is the temple of Artemis Leucophryenê, which in the size of its shrine and in the number of its votive offerings is inferior to the temple at Ephesus, but in the harmony and skill shown in the structure of the sacred enclosure is far superior to it. And in size it surpasses all the sacred enclosures in Asia except two, that at Ephesus and that at Didymi. In ancient times, also, it came to pass that the Magnetans were utterly destroyed by the Treres, a Cimmerian tribe, although they had for a long time been a prosperous people, but the Milesians took possession of the place in the following year. Now Callinus mentions the Magnetans as still being a prosperous people and as being successful in their war against the Ephesians, but Archilochus is obviously already aware of the

¹ Also quoted in 9. 5. 22.

¹ *λεπασσθαι* Dh, *λεπᾶσθαι* other MSS.

² *εὐτυχήσαντας* F, *εὐτυχίσαντας* other MSS.

κλαίειν τὰ Θασίων,¹ οὐ² τὰ Μαγνήτων κακά·

C 648 ἐξ οὗ καὶ αὐτὸν νεώτερον εἶναι τοῦ Καλλίνου τεκμαίρεσθαι πάρεστιν. ἄλλης δέ τινος ἐφόδου τῶν Κιμμερίων μέμνηται πρεσβυτέρας ὁ Καλλίνος, ἐπ' αὖν φη·

νῦν δ' ἐπὶ Κιμμερίων στρατὸς ἔρχεται ὀβριμοεργῶν·

ἐν ᾗ τὴν Σάρδεων ἄλωσιν δηλοῖ.

41. Ἄνδρες δ' ἐγένοντο γνώριμοι Μάγνητες Ἠγησίας τε ὁ ῥήτωρ, ὃς ἤρξε μάλιστα τοῦ Ἀσιανοῦ λεγομένου ζήλου, παραφθείρας τὸ καθεστηκὸς ἔθος τὸ Ἀττικόν, καὶ Σίμος³ ὁ μελοποιός, παραφθείρας καὶ αὐτὸς τὴν τῶν προτέρων μελοποιῶν ἀγωγὴν καὶ τὴν Σιμφδίαν εἰσαγαγών, καθάπερ ἔτι μᾶλλον Λυσιφδοὶ καὶ Μαγφδοί, καὶ Κλεόμαχος ὁ πύκτης, ὃς εἰς ἔρωτα ἐμπεσὼν κιναίδου τινὸς καὶ παιδίσκης ὑπὸ τῷ⁴ κιναίδῳ τρεφομένης ἀπεμιμήσατο τὴν ἀγωγὴν τῶν παρὰ τοῖς κιναίδοις διαλέκτων καὶ τῆς ἡθοποιίας· ἤρξε δὲ Σωτάδης μὲν πρῶτος τοῦ κιναιδολογεῖν, ἔπειτα Ἀλέξανδρος ὁ Αἰτωλός· ἀλλ' οὗτοι μὲν ἐν ψιλῷ λόγῳ, μετὰ μέλους δὲ Λῦσις, καὶ ἔτι πρότερος τούτου ὁ Σίμος. Ἀναξήνορα δὲ τὸν κιθαρωδὸν ἐξῆρε μὲν καὶ τὰ θεάτρα, ἀλλ' ὅτι⁵ μάλιστα Ἀντώνιος, ὃς⁶ γε καὶ τεττάρων πόλεων ἀπέδειξε φορολόγον, στρατιώτας αὐτῷ συστήσας. καὶ ἡ

¹ τὰ Θασίων, Tyrwhitt, for θάσ(σ)ων; so Tzschucke and Corais.

² οὐ, Tzschucke and Corais, for οὐδ.

³ Σίμος, Tzschucke, for Σίμων; so Meineke.

⁴ τῷ, Corais inserts; so Meineke.

misfortune that befell them: "to bewail the woes of the Thasians, not those of the Magnetans";¹ whence one may judge that he was more recent than Callinus. And Callinus recalls another, and earlier, invasion of the Cimmerians when he says: "And now the army of the Cimmerians, mighty in deeds, advanceth,"² in which he plainly indicates the capture of Sardeis.

41. Well-known natives of Magnesia are: Hegesias the orator, who, more than any other, initiated the Asiatic style, as it is called, whereby he corrupted the established Attic custom; and Simus the melic poet, he too a man who corrupted the style handed down by the earlier melic poets and introduced the Simoedia,³ just as that style was corrupted still more by the Lysioedi and the Magoedi, and by Cleomachus the pugilist, who, having fallen in love with a certain cinaedus⁴ and with a young female slave who was kept as a prostitute by the cinaedus, imitated the style of dialects and mannerisms that was in vogue among the cinaedi. Sotades was the first man to write the talk of the cinaedi; and then Alexander the Aetolian. But though these two men imitated that talk in mere speech, Lysis accompanied it with song; and so did Simus, who was still earlier than he. As for Anaxenor, the citharoede,⁵ the theatres exalted him, but Antony exalted him all he possibly could, since he even appointed him exactor of tribute from four cities, giving him a body-guard of soldiers.

¹ *Frag.* 20 (Bergk).

² *Frag.* 3 (Bergk).

³ A loose song.

⁴ An obscene talker.

⁵ One who played the cithara and sang to its accompaniment (cf. 9. 3. 10 and note on "the citharoedes").

⁶ ὄτι, Meineke, for ἔτι.

⁶ ὄς, Kramer, for ὅς.

πατρὶς δ' ἱκανῶς αὐτὸν ἠϋξῆσε, πορφύραν ἐνδύ-
σασα, ἱερωμένον¹ τοῦ Σωσιπόλιδος Διός, καθά-
περ καὶ ἡ γραπτὴ εἰκὼν ἐμφανίζει ἢ ἐν τῇ ἀγορᾷ.
ἔστι δὲ καὶ χαλκὴ εἰκὼν ἐν τῷ θεάτρῳ, ἐπιγραφὴν
ἔχουσα·

ἦτοι μὲν τόδε καλὸν ἀκουέμεν ἔστιν ἀοιδοῦ
τοιοῦδ', οἷος ὅδ' ἔστί, θεοῖς ἐναλίγκιος αὐδῇ.

οὐ στοχασάμενος δὲ ὁ ἐπιγράψας τὸ τελευταῖον
γράμμα τοῦ δευτέρου ἔπους παρέλιπε, τοῦ πλά-
τους τῆς βάσεως μὴ συνεξαρκούντος· ὥστε τῆς
πόλεως ἀμαθίαν καταγινώσκειν παρέσχε διὰ τὴν
ἀμφιβολίαν τὴν περὶ² τὴν γραφὴν, εἴτε τὴν
ὀνομαστικὴν δέχοιτο πτῶσιν τῆς ἐσχάτης προση-
γορίας, εἴτε τὴν δοτικὴν· πολλοὶ γὰρ χωρὶς τοῦ ι
γράφουσι τὰς δοτικὰς καὶ ἐκβάλλουσι δὲ³ τὸ
ἔθος φυσικὴν αἰτίαν οὐκ ἔχον.

42. Μετὰ δὲ Μαγνησίαν ἢ ἐπὶ Τράλλεις ἔστιν
ὁδὸς ἐν ἀριστερᾷ μὲν τὴν Μεσωγίδα ἔχουσιν,
ἐν αὐτῇ δὲ τῇ ὁδῷ καὶ ἐν δεξιᾷ τὸ Μαιάνδρου
πέδιον, Λυδῶν ἅμα καὶ Καρῶν νεμομένων καὶ
Ἰώνων, Μιλησίων τε καὶ Μυησίων, ἔτι δὲ Αἰολέων
τῶν ἐν Μαγνησίᾳ· ὁ δ' αὐτὸς τρόπος⁴ τῆς το-
ποθεσίας καὶ μέχρι Νύσης καὶ Ἀντιοχείας.
Ἰδρυταὶ δ' ἢ μὲν τῶν Τραλλιανῶν πόλις ἐπὶ
C 649 κύκλῳ δ' ἱκανῶς εὐερκῇ· συνοικεῖται δὲ καλῶς,
εἴ τις ἄλλη τῶν κατὰ τὴν Ἀσίαν, ὑπὸ εὐπόρων
ἀνθρώπων, καὶ αἰεὶ τινες ἐξ αὐτῆς εἰσὶν οἱ
πρωτεύοντες κατὰ τὴν ἐπαρχίαν, οὓς Ἀσιάρχας

¹ Instead of ἱερωμένον, CDmaz have ἱερωμένην.

² περὶ, Kramer, for παρά.

Further, his native land greatly increased his honours, having clad him in purple as consecrated to Zeus Sosipolis,¹ as is plainly indicated in his painted image in the market-place. And there is also a bronze statue of him in the theatre, with the inscription, "Surely this is a beautiful thing, to listen to a singer such as this man is, like unto the gods in voice."² But the engraver, missing his guess, left out the last letter of the second verse, the base of the statue not being wide enough for its inclusion; so that he laid the city open to the charge of ignorance, because of the ambiguity of the writing, as to whether the last word should be taken as in the nominative case or in the dative;³ for many write the dative case without the iota, and even reject the ordinary usage as being without natural cause.

42. After Magnesia comes the road to Tralleis, with Mt. Mesogis on the left, and, at the road itself and on the right, the plain of the Maeander River, which is occupied by Lydians and Carians, and by Ionians, both Milesians and Myesians, and also by the Aeolians of Magnesia. And the same kind of topographical account applies as far as Nysa and Antiocheia. The city of the Tralleians is situated upon a trapezium-shaped site, with a height fortified by nature; and the places all round are well defended. And it is as well peopled as any other city in Asia by people of means; and always some of its men hold the chief places in the province, being called Asiarchs.

¹ City-Saviour.

² *Odyssey* 9. 3.

³ *i.e.* as ΑΤΑΗ or ΑΤΑΗΙ.

² δέ, Meineke, for γε; Corais τε.

⁴ καί, after πρότος, omitted by mozz.

καλοῦσιν· ὧν Πυθόδωρός τε ἦν, ἀνὴρ Νυσαεὺς τὸ ἐξ ἀρχῆς, ἐκείσε δὲ μεταβεβηκὼς διὰ τὴν ἐπιφάνειαν, καὶ ἐν τῇ πρὸς Πομπήιον φιλίᾳ διαπρέπων μετ' ὀλίγων· περιεβέβλητο δὲ καὶ οὐσίαν βασιλικὴν πλειόνων ἢ δισχιλίων ταλάντων, ἣν ὑπὸ Καίσαρος τοῦ Θεοῦ πραθεῖσαν διὰ τὴν πρὸς Πομπήιον φιλίαν ἐξωνησάμενος οὐχ ἥττω τοῖς παισὶ κατέλιπε· τούτου δ' ἐστὶ θυγάτηρ Πυθοδωρίς, ἣ νῦν βασιλεύουσα ἐν τῷ Πόντῳ, περὶ ἧς εἰρήκαμεν. οὗτος δὲ καθ' ἡμᾶς ἤκμασε καὶ Μηνόδωρος, ἀνὴρ λόγιος καὶ ἄλλως σεμνὸς καὶ βαρὺς, ἔχων τὴν ἱερωσύνην τοῦ Διὸς τοῦ Λαρισαίου· κατεστασιάσθη δ' ὑπὸ τῶν Δομετίου τοῦ Ἀηνοβάρβου φίλων, καὶ ἀνείλεν αὐτὸν ἐκεῖνος, ὥς ἀφιστάντα τὸ ναυτικόν, πιστεύσας τοῖς ἐνδειξαμένοις. ἐγένοντο δὲ καὶ ῥήτορες ἐπιφανεῖς Διονυσοκλῆς τε καὶ μετὰ ταῦτα Δάμασος ὁ Σκόμβρος. κτίσμα δὲ φασιν εἶναι τὰς Τράλλεις Ἀργείων καὶ τινων Θρακῶν Τραλλίων, ἀφ' ὧν τοῦνομα. τυραννηθῆναι δ' ὀλίγον συνέπεσε χρόνον τὴν πόλιν ὑπὸ τῶν Κρατίππου παίδων κατὰ τὰ Μιθριδατικά.

43. Νῦσα δ' ἵδρυται πρὸς τῇ Μεσωγίδι τὸ πλεον τῷ ὄρει προσανακεκλιμένη, ἔστι δ' ὥσπερ δίπολις, διαιρεῖ γὰρ αὐτὴν χαράδρα τις, ποιοῦσα φάραγγα, ἧς τὸ μὲν γέφυραν ἐπικειμένην ἔχει, συνάπτουσιν τὰς δύο πόλεις, τὸ δ' ἀμφιθεάτρῳ κεκόσμηται, κρυπτὴν ἔχοντι τὴν ὑπόρρυσιν τῶν χαραδρωδῶν ὑδάτων· τῷ δὲ θεάτρῳ δύο ἄκραι, ὧν τῇ μὲν ὑπόκειται τὸ γυμνάσιον τῶν νέων,

¹ 12. 3. 29, 31, 37.

Among these was Pythodorus, originally a native of Nysa, but he changed his abode to Tralleis because of its celebrity; and with only a few others he stood out conspicuously as a friend of Pompey. And he came into possession of the wealth of a king, worth more than two thousand talents, which, though sold by the deified Caesar, was redeemed by him through his friendship with Pompey and was left by him unimpaired to his children. He was the father of Pythodoris, the present queen in Pontus, of whom I have already spoken.¹ Pythodorus, then, flourished in my time, as also Menodorus, a man of learning, and otherwise august and grave, who held the priesthood of Zeus Larisaeus. But he was overthrown by a counter-party friendly to Dometius Ahenobarbus; and Dometius, relying on his informers, slew him, as guilty of causing the fleet to revolt. Here were born famous orators: Dionysocles and afterwards Damasus Scombrus. Tralleis is said to have been founded by Argives and by certain Tralleian Thracians, and hence the name. And the city was ruled for a short time by tyrants, the sons of Cratippus, at the time of the Mithridatic war.

43. Nysa is situated near Mt. Mesogis, for the most part lying upon its slopes; and it is a double city, so to speak, for it is divided by a torrential stream that forms a gorge, which at one place has a bridge over it, joining the two cities, and at another is adorned with an amphitheatre, with a hidden underground passage for the torrential waters. Near the theatre are two heights, below one of which is the gymnasium of youths; and below the other is the market-place and the gymnasium for

τῇ δ' ἀγορὰ καὶ τὸ γερωντικόν· πρὸς δὲ νότον ὑποπέπτωκε τῇ πόλει τὸ πεδίον, καθάπερ καὶ ταῖς Τράλλεσιν.

44. Ἐν δὲ τῇ ὁδῷ τῇ μεταξὺ τῶν Τράλλεων καὶ τῆς Νύσης, κώμη τῶν Νυσαέων ἐστὶν οὐκ ἄπωθεν τῆς πόλεως Ἀχάρακα, ἐν ᾗ τὸ Πλουτώνιον, ἔχον καὶ ἄλσος πολυτελὲς καὶ νεῶν Πλούτωνός τε καὶ Κόρης,¹ καὶ τὸ Χαρώνιον, ἄντρον ὑπερκείμενον τοῦ ἄλσους θαυμαστὸν τῇ φύσει· λέγουσι γὰρ δὴ καὶ τοὺς νοσώδεις καὶ προσέχοντας ταῖς τῶν θεῶν τούτων θεραπείαις φοιτᾶν ἐκεῖσε καὶ διαιτᾶσθαι ἐν τῇ κώμῃ πλησίον τοῦ ἄντρου παρὰ τοῖς ἐμπείροις τῶν ἱερέων, οἱ ἐγκοιμῶνται τε ὑπὲρ αὐτῶν καὶ διατάττουσιν ἐκ τῶν ὀνείρων τὰς θεραπείας. οὗτοι δ' εἰσὶ καὶ οἱ ἐγκαλοῦντες τὴν τῶν θεῶν ἰατρείαν· ἄγουσι δὲ πολλάκις εἰς τὸ ἄντρον καὶ ἰδρύουσι μένοντας καθ' ἡσυχίαν ἐκεῖ, καθάπερ ἐν φωλεῷ σιτίων
C 650 χωρὶς ἐπὶ πλείους ἡμέρας. ἔστι δ' ὅτε καὶ ἰδίους ἐνυπνίοις οἱ νοσηλευόμενοι προσέχουσι, μυσταγωγοῖς δ' ὅμως καὶ συμβούλοις ἐκείνοις χρῶνται, ὥς ἂν ἱερεῦσι τοῖς δ' ἄλλοις ἄδυτός ἐστιν ὁ τόπος καὶ ὀλέθριος. πανήγυρις δ' ἐν τοῖς Ἀχαράκοις συντελεῖται κατ' ἔτος, καὶ τότε μάλιστα ὁρᾶν ἔστι καὶ ἀκούειν περὶ τῶν τοσούτων² τοὺς πανηγυρίζοντας· τότε δὲ καὶ περὶ τὴν μεσημβρίαν ὑπολαβόντες ταῦρον οἱ ἐκ τοῦ γυμνασίου νέοι καὶ ἔφηβοι, γυμνοὶ λίπ' ἀληλιμμένοι,³ μετὰ σπουδῆς ἀνακομίζουσιν εἰς τὸ ἄντρον· ἀφεθείς δέ, μικρὸν προελθὼν πίπτει καὶ ἐκπνους γίνεται.

¹ Κόρης, second hand in C, for *Hpas elsewhere.

older persons. The plain lies to the south of the city, as it does to the south of Tralleis.

44. On the road between the Tralleis and Nysa is a village of the Nysaeans, not far from the city, Acharaca, where is the Plutonium, with a costly sacred precinct and a shrine of Pluto and Coré, and also the Charonium, a cave that lies above the sacred precinct, by nature wonderful; for they say that those who are diseased and give heed to the cures prescribed by these gods resort thither and live in the village near the cave among experienced priests, who on their behalf sleep in the cave and through dreams prescribe the cures. These are also the men who invoke the healing power of the gods. And they often bring the sick into the cave and leave them there, to remain in quiet, like animals in their lurking-holes, without food for many days. And sometimes the sick give heed also to their own dreams, but still they use those other men, as priests, to initiate them into the mysteries and to counsel them. To all others the place is forbidden and deadly. A festival is celebrated every year at Acharaca; and at that time in particular those who celebrate the festival can see and hear concerning all these things; and at the festival, too, about noon, the boys and young men of the gymnasium, nude and anointed with oil, take up a bull and with haste carry him up into the cave; and, when let loose, the bull goes forward a short distance, falls, and breathes out his life.

² τοσοῦτων is emended by Corais and Meineke to νοσοῦντων.

³ λίπ' ἀηλιμένοι, Meineke, for ἀπαηλιμένοι.

45. Ἀπὸ δὲ τριάκοντα σταδίων τῆς Νύσης ὑπερβάσι Τμῶλον καὶ¹ τὸ ὄρος τὴν Μεσωγίδα ἐπὶ τὰ πρὸς τὸν νότον μέρη καλεῖται τόπος Λειμών, εἰς ὃν ἐξοδεύουσι πανηγυριοῦντες Νυσαιεῖς τε καὶ οἱ κύκλῳ πάντες· οὐ πόρρω δὲ τούτου στόμιόν ἐστιν ἱερὸν τῶν αὐτῶν θεῶν, ὃ φασὶ καθήκειν μέχρι τῶν Ἀχαράκων. τοῦτον δὲ τὸν λειμῶνα ὀνομάζειν τὸν ποιητὴν φασιν, ὅταν φῇ,

Ἀσίῳ ἐν λειμῶνι,

δεικνύντες Καῦστρίου καὶ Ἀσίου τινὸς ἡρῶν καὶ τὸν Κάϋστρον πλησίον ἀπορρέοντα.

46. Ἱστοροῦσι δὲ τρεῖς ἀδελφούς, Ἀθυμβρόν τε καὶ Ἀθύμβραδον καὶ Ὑδρηλον, ἐλθόντας ἐκ Λακεδαιμόνος, τὰς ἐπωνύμους αὐτῶν κτίσαι πόλεις, λειπανδρῆσαι δ' ὕστερον, ἐξ ἐκείνων δὲ συνοικισθῆναι τὴν Νύσαν· καὶ νῦν Ἀθυμβρον ἀρχηγέτην νομίζουσιν οἱ Νυσαιεῖς.

47. Περίκεινται δὲ ἀξιόλογοι κατοικίαι πέραν τοῦ Μαιάνδρου, Κοσκίνια καὶ Ὀρθωσία· ἐντὸς δὲ Βρίουλα, Μάσταυρα, Ἀχάρακα, καὶ ὑπὲρ τῆς πόλεως ἐν τῷ ὄρει τὰ Ἀρομα² (συστέλλοντες τὸ ῥῶ γράμμα)·³ ὅθεν ἄριστος Μεσωγίτης οἶνος ὁ Ἀρομεύς.

¹ καί, before τὸ ὄρος, Jones inserts. E reads τὸ ὄρος καὶ τὴν Μεσωγίδα.

² Ἀρομα, Corais, for Ἀρώματα CDF (the *o* being above *ω* in D), Ἀρώματα Εὐέμιος.

³ The words in parenthesis are probably a gloss, and are ejected by Meineke.

¹ The text, which seems to be corrupt, is recast and emended by Groskurd to read, "having crossed the Mesogis

45. Thirty stadia from Nysa, after one crosses over Mt. Tmolus and the mountain called Mesogis, towards the region to the south of the Mesogis,¹ there is a place called Leimon,² whither the Nysaeans and all the people about go to celebrate their festivals. And not far from Leimon is an entrance into the earth sacred to the same gods, which is said to extend down as far as Acharaca. The poet is said to name this meadow when he says, "On the Asian meadow"; and they point out a hero-temple of Caÿster and a certain Asius, and the Caÿster River that streams forth near by.

46. The story is told that three brothers, Athymbrus and Athymbradus and Hydrelus, who came from Lacedaemon, founded the three cities which were named after them, but that the cities later became scantily populated, and that the city Nysa was founded by their inhabitants; but that Athymbrus is now regarded by Nysaeans as their original founder.

47. Near Nysa, on the far side of the Maeander River, are situated noteworthy settlements; I mean Coscinia and Orthosia; and this side the river, Briula, Mastaura and Acharaca, and above the city, on the mountain, Aroma (in which the letter *rho*³ is short), whence comes the best Mesogitan wine, I mean the Aromian.

towards the region to the south of Tmolus." But the simple rectification of the text made by the present translator solves the difficulty quite as well (see critical note).

¹ *i.e.* meadow.

² Apparently an error for "in which name the letter *omega* is shortened to *omicron* (cp. the well-known Greek word *Arōma*, which may mean either "spice" or "arable land.")

48. Ἄνδρες δὲ γεγόνασιν ἐνδοξοὶ Νυσαεῖς Ἀπολλωνίος τε ὁ Στωικὸς φιλόσοφος, τῶν Παναϊτίου γνωρίμων ἄριστος, καὶ Μενεκράτης, Ἀριστάρχου μαθητῆς, καὶ Ἀριστόδημος, ἐκείνου υἱός, οὗ διηκούσαμεν ἡμεῖς ἐσχατόγηρῳ νέῳ παντελῶς ἐν τῇ Νύσῃ· καὶ Σώστρατος δέ, ὁ ἀδελφὸς τοῦ Ἀριστοδήμου, καὶ ἄλλος Ἀριστόδημος, ἀνεψιὸς αὐτοῦ, ὁ παιδεύσας Μάγνον Πομπήιον, ἀξιόλογοι γεγόνασι γραμματικοί· ὁ δ' ἡμέτερος καὶ ἐρρητόρευσεν, καὶ ἐν τῇ Ῥόδῳ καὶ ἐν τῇ πατρίδι δύο σχολὰς συνείχε, πρῶτὴ μὲν τὴν ῥητορικὴν, δεύτη δὲ τὴν γραμματικὴν σχολήν· ἐν δὲ τῇ Ῥώμῃ τῶν Μάγνου παίδων ἐπιστατῶν ἤρκειτο τῇ γραμματικῇ σχολῇ.

II

C 651 1. Τὰ δὲ πέραν ἤδη τοῦ Μαιάνδρου, τὰ λειπό-
μενα τῆς περιουσίας, πάντ' ἐστὶ Καρικία, οὐκέτι τοῖς Λυδοῖς ἐπιμεμιγμένων ἐνταῦθα τῶν Καρῶν, ἀλλ' ἤδη καθ' αὐτοὺς ὄντων, πλὴν εἴ τι Μιλήσιοι καὶ Μυήσιοι τῆς παραλίας ἀποτέτμηνται. ἀρχὴ μὲν οὖν τῆς παραλίας ἐστὶν ἡ τῶν Ῥοδίων περαιὰ πρὸς θαλάττης, τέλος δὲ τὸ Ποσειδίου τῶν Μιλησίων· ἐν δὲ τῇ μεσογαίᾳ τὰ ἄκρα τοῦ Ταύρου μέχρι Μαιάνδρου. λέγουσι γὰρ ἀρχὴν εἶναι τοῦ Ταύρου τὰ ὑπερκείμενα ὄρη τῶν Χελιδονίων καλουμένων νήσων, ἅπερ ἐν μεθορίῳ τῆς Παμφυλίας καὶ τῆς Λυκίας πρόκεινται· ἐντεῦθεν γὰρ ἐξαίρεται πρὸς ὕψος ὁ Ταῦρος· τὸ δ' ἀληθὲς καὶ

¹ For map of Asia Minor, see Vol. V. (at end).

48. Famous men born at Nysa are: Apollonius the Stoic philosopher, best of the disciples of Panæti-
 tius; and Menecrates, pupil of Aristarchus; and
 Aristodemus, his son, whose entire course, in his
 extreme old age, I in my youth took at Nysa; and
 Sostratus, the brother of Aristodemus, and another
 Aristodemus, his cousin, who trained Pompey the
 Great, proved themselves notable grammarians.
 But my teacher also taught rhetoric and had two
 schools, both in Rhodes and in his native land, teach-
 ing rhetoric in the morning and grammar in the
 evening; at Rome, however, when he was in charge
 of the children of Pompey the Great, he was content
 with the teaching of grammar.

II

1. COMING now to the far side of the Maeander,¹
 the parts that remain to be described are all Carian,
 since here the Lydians are no longer intermingled
 with the Carians, and the latter occupy all the country
 by themselves, except that a segment of the sea-
 board is occupied by Milesians and Myesians. Now
 the beginning of the seaboard is the Peraea² of the
 Rhodians on the sea, and the end of it is the
 Poseidium of the Milesians; but in the interior are
 the extremities of the Taurus, extending as far as
 the Maeander River. For it is said that the moun-
 tains situated above the Chelidonian islands, as they
 are called, which islands lie off the confines of
 Pamphylia and Lycia, form the beginning of the
 Taurus, for thence the Taurus rises to a height;

² Mainland territory.

τὴν Λυκίαν ἄπασαν ὀρεινὴ ράχης τοῦ Ταύρου διέρ-
γει πρὸς τὰ ἐκτὸς καὶ τὸ νότιον μέρος ἀπὸ τῶν
Κιβυρατικῶν μέχρι τῆς περαιᾶς τῶν Ῥοδίων.
κάνταῦθα δ' ἐστὶ συνεχῆς ὀρεινὴ, πολὺ μέντοι
ταπεινότερα, καὶ οὐκέτι τοῦ Ταύρου νομίζεται,
οὐδὲ τὰ μὲν ἐκτὸς αὐτοῦ, τὰ δ' ἐντός, διὰ τὸ
σποράδας εἶναι τὰς ἐξοχὰς καὶ τὰς εἰσοχὰς
ἐπίσης εἰς¹ τε πλάτος καὶ μῆκος τῆς χώρας
ἀπάσης καὶ μηδὲν ἔχειν ὅμοιον διατειχίσματι.
ἐστὶ δ' ἅπας μὲν ὁ περίπλους κατακολπίζοντι
σταδίων τετρακισχιλίων ἐννακοσίων, αὐτὸς δὲ
ὁ τῆς περαιᾶς τῶν Ῥοδίων ἐγγὺς χιλίων καὶ
πεντακοσίων.

2. Ἀρχὴ δὲ τὰ Δαίδαλα, τῆς Ῥοδίας χωρίον,
πέρας δὲ τὸ καλούμενον ὄρος Φοῖνιξ, καὶ τοῦτο
τῆς Ῥοδίας. πρόκειται δ' Ἐλαιούσσα² νῆσος
διέχουσα τῆς Ῥόδου σταδίους ἑκατὸν εἴκοσι.
μεταξὺ δὲ πρῶτον μὲν ἀπὸ Δαιδάλων πλέουσιν
ἐπὶ τὴν δύσιν ἐπ' εὐθείας τῇ ἐκ Κιλικίας καὶ
Παμφυλίας καὶ Λυκίας παραλίᾳ κόλπος ἐστὶν εὐλό-
μενος, Γλαῦκος καλούμενος, εἶτα τὸ Ἀρτεμίσιον
ἄκρα καὶ ἱερόν, εἶτα τὸ Λητῶν ἄλσος· ὑπὲρ
αὐτοῦ δὲ καὶ τῆς θαλάττης ἐν ἐξήκοντα σταδίοις
Κάλυνδα³ πόλις· εἶτα Καῦνος καὶ ποταμὸς
πλησίον Κάλβις βαθύς, ἔχων εἰσαγωγὴν, καὶ
μεταξὺ Πίσιλις.

3. Ἐχει δ' ἡ πόλις νεώρια καὶ λιμένα κλειστόν·
ὑπέρκειται δὲ τῆς πόλεως ἐν ὕψει φρούριον

¹ eis, Kramer inserts; so the later editors.

² Ἐλαιούσσα, Tzschucke, for Ἐλεούσσα; so Corais and Meineke.

³ Κάλυνδα, Casaubon, for Κάλυμνα; so the later editors.

but the truth is that the whole of Lycia, towards the parts outside and on its southern side, is separated by a mountainous ridge of the Taurus from the country of the Cibyrans as far as the Peraea of the Rhodians. From here the ridge continues, but is much lower and is no longer regarded as a part of the Taurus; neither are the parts outside the Taurus and this side of it so regarded, because of the fact that the eminences and depressions are scattered equally throughout the breadth and the length of the whole country, and present nothing like a wall of partition. The whole of the voyage round the coast, following the sinuosities of the gulfs, is four thousand nine hundred stadia, and merely that round the Peraea of the Rhodians is close to fifteen hundred.

2. The Peraea of the Rhodians begins with Daedala, a place in the Rhodian territory, but ends with Mt. Phoenix, as it is called, which is also in the Rhodian territory. Off the Peraea lies the island Elaeussa, distant one hundred and twenty stadia from Rhodes. Between the two, as one sails towards the west from Daedala in a straight line with the coast of Cilicia and Pamphylia and Lycia, one comes to a gulf called Glaucus, which has good harbours; then to the Artemisium, a promontory and temple; then to the sacred precinct of Leto, above which, and above the sea, at a distance of sixty stadia, lies Calynda, a city; then to Caunus and to the Calbis, a river near Caunus, which is deep and affords passage for merchant vessels; and between the two lies Pisilis.

3. The city¹ has dockyards, and a harbour that can be closed. Above the city, on a height, lies

¹ Caunus

Ἰμβρος. τῆς δὲ χώρας εὐδαίμονος οὔσης, ἡ πόλις τοῦ θέρους ὁμολογεῖται παρὰ πάντων εἶναι δυσάερος καὶ τοῦ μετοπώρου διὰ τὰ καύματα καὶ τὴν ἀφθονίαν τῶν ὠραίων· καὶ δὴ καὶ τὰ τοιαῦτα διηγημάτια θρυλεῖται, ὅτι Στρατόνικος ὁ κιθαριστῆς ἰδὼν ἐπιμελῶς¹ χλωροὺς τοὺς Καυνίους, τοῦτ' εἶναι ἔφη τὸ τοῦ ποιητοῦ·

οἷη περ φύλλων γενεή, τοιήδε καὶ ἀνδρῶν.

μεμφομένων δέ, ὡς σκώπτοιο αὐτῷ² ἡ πόλις ὡς νοσερά, Ἐγώ, ἔφη, ταύτην θαρρήσαιμ' ἂν λέγειν
C 652 νοσεράν, ὅπου καὶ οἱ νεκροὶ περιπατοῦσιν; ἀπέστησαν δέ ποτε Καύνιοι τῶν Ῥοδίων· κριθέντες δ' ἐπὶ τῶν Ῥωμαίων ἀπελήφθησαν· πάλιν καὶ ἔστι λόγος Μόλωνος κατὰ Καυνίων. φασὶ δ' αὐτοὺς ὁμογλώττους μὲν εἶναι τοῖς Καρσίν, ἀφίχθαι δ' ἐκ Κρήτης³ καὶ χρῆσθαι νόμοις ἰδίοις.

4. Ἐξῆς δὲ Φύσκος πολίχνη, λιμένα ἔχουσα καὶ ἄλσος Λητῶν· εἴτα Λώρυμα, παραλία τραχεία, καὶ ὄρος ὑψηλότατον τῶν ταύτη· ἐπ' ἄκρῳ δὲ φρούριον ὁμώνυμον τῷ ὄρει Φοῖνιξ· πρόκειται δ' ἡ Ἐλαιούσσα⁴ νῆσος ἐν τέτρασι σταδίοις κύκλον ἔχουσα ὅσον ὀκτωστάδιον.

¹ ἐπιμελῶς seems to be corrupt. For various conjectures, see Müller, *Ind. Var. Lect.*, p. 1030.

² αὐτῷ, the editors (except Corais), for αὐτῶν.

³ δ' ἐκ Κρήτης (from Herod. 1. 172), Corais, for δὲ Κρήτης.

⁴ Ἐλαιούσσα, Tzschucke, for Ἐλεούσσα; so Corais and Meineke.

¹ An attempt to translate ἐπιμελῶς, which seems to be

Imbrus, a stronghold. Although the country is fertile, the city is agreed by all to have foul air in summer, as also in autumn, because of the heat and the abundance of fruits. And indeed little tales of the following kind are repeated over and over, that Stratonicus the citharist, seeing that the Caunians were pitifully¹ pale,² said that this was the thought of the poet in the verse, "Even as is the generation of leaves, such is that also of men"; and when people complained that he was jeering at the city as though it were sickly, he replied, "Would I be so bold as to call this city sickly, where even the corpses walk about?" The Caunians once revolted from the Rhodians, but by a judicial decision of the Romans they were restored to them. And there is extant a speech of Molon³ entitled *Against the Caunians*. It is said that they speak the same language as the Carians, but that they came from Crete and follow usages of their own.⁴

4. Next one comes to Physcus, a small town, which has a harbour and a sacred precinct of Leto; and then to Loryma, a rugged coast, and to the highest mountain in that part of the country; and on top of the mountain is Phoenix, a stronghold bearing the same name as the mountain; and off the mountain, at a distance of four stadia, lies Elaeussa, an island, which is about eight stadia in circuit.

corrupt. Others translate the word either "somewhat" or "very."

² Or, more strictly, "pale green."

³ Apollonius Molon of Alabanda, the rhetorician and orator; ambassador of the Rhodians at Rome (81 B.C.), and teacher of Cicero and Julius Caesar.

⁴ On their origin, language, and usages, cf. Herodotus 1. 172.

5. Ἡ δὲ τῶν Ῥοδίων πόλις κείται μὲν ἐπὶ τοῦ ἑθνικοῦ ἀκρωτηρίου, λιμέσι δὲ καὶ ὁδοῖς καὶ τείχεσι καὶ τῇ ἄλλῃ κατασκευῇ τοσοῦτον διαφέρει τῶν ἄλλων, ὥστ' οὐκ ἔχομεν εἰπεῖν ἑτέραν, ἀλλ' οὐδὲ πάρισον, μὴ τί γε κρείττω ταύτης τῆς πόλεως. θαυμαστὴ δὲ καὶ ἡ εὐνομία καὶ ἡ ἐπιμέλεια πρὸς τε τὴν ἄλλην πολιτείαν καὶ τὴν περὶ τὰ ναυτικά, ἀφ' ἧς ἐθαλαττοκράτησε πολὺν χρόνον καὶ τὰ ληστήρια καθεῖλε καὶ Ῥωμαίοις ἐγένετο φίλη καὶ τῶν βασιλέων τοῖς φιλορωμαίοις τε καὶ φιλέλλησιν· ἀφ' ὧν αὐτόνομός τε διετέλεσε καὶ πολλοῖς ἀναθήμασιν ἐκοσμήθη, ἃ κείται τὰ μὲν πλείστα ἐν τῷ Διονυσίῳ καὶ τῷ γυμνασίῳ, ἄλλα δ' ἐν ἄλλοις τόποις. ἄριστα δὲ ὅ τε τοῦ Ἡλίου κολοσσός, ὃν φησιν ὁ ποιήσας τὸ ἱαμβεῖον, ὅτι

ἑπτάκις δέκα

Χάρης ἐποίει πηχέων ὁ Λίνδιος.

κείται δὲ νῦν ὑπὸ σεισμῷ πεσών, περικλασθεῖς ἀπὸ τῶν γονάτων· οὐκ ἀνέστησαν δ' αὐτὸν κατὰ τι λόγιον. τοῦτό τε δὴ τῶν ἀναθημάτων κράτιστον (τῶν γοῦν ἑπτὰ θεαμάτων ὁμολογεῖται), καὶ αἱ τοῦ Πρωτογένους γραφαί, ὃ τε Ἰάλυσος καὶ ὁ Σάτυρος παρεστὼς στύλῳ, ἐπὶ δὲ τῷ στύλῳ πέρδιξ ἐφειστήκει· πρὸς δὲ οὕτως ἐκεχήνεσαν, ὥς ἔοικεν, οἱ ἄνθρωποι, νεωστὶ ἀνακειμένου τοῦ πίνακος, ὥστ' ἐκείνον ἐθαύμαζον, ὁ δὲ Σάτυρος παρεωράτο, καίτοι σφόδρα κατωρθωμένος· ἐξέπληττον δ' ἔτι μᾶλλον οἱ περδικοτρόφοι, κομί-

¹ The god of the Sun.

² Unknown.

³ Tutelary hero of Rhodes and reputed grandson of Helius.

5. The city of the Rhodians lies on the eastern promontory of Rhodes; and it is so far superior to all others in harbours and roads and walls and improvements in general that I am unable to speak of any other city as equal to it, or even as almost equal to it, much less superior to it. It is remarkable also for its good order, and for its careful attention to the administration of affairs of state in general; and in particular to that of naval affairs, whereby it held the mastery of the sea for a long time and overthrew the business of piracy, and became a friend to the Romans and to all kings who favoured both the Romans and the Greeks. Consequently it not only has remained autonomous, but also has been adorned with many votive offerings, which for the most part are to be found in the Dionysium and the gymnasium, but partly in other places. The best of these are, first, the Colossus of Helius,¹ of which the author² of the iambic verse says, "seven times ten cubits in height, the work of Chares the Lindian"; but it now lies on the ground, having been thrown down by an earthquake and broken at the knees. In accordance with a certain oracle, the people did not raise it again. This, then, is the most excellent of the votive offerings (at any rate, it is by common agreement one of the Seven Wonders); and there are also the paintings of Protogenes, his Ialysus³ and also his Satyr, the latter standing by a pillar, on top of which stood a male partridge. And at this partridge, as would be natural, the people were so agape when the picture had only recently been set up, that they would behold him with wonder but overlook the Satyr, although the latter was a very great

ζοντες τοὺς τιθασοὺς καὶ τιθέντες καταντικρὺ ἐφθέγγοντο γὰρ πρὸς τὴν γραφὴν οἱ πέρδικες καὶ ὠχλαγώγουν. ὁρῶν δὲ ὁ Πρωτογένης τὸ ἔργον πάρεργον γεγρονὸς ἐδεήθη τῶν τοῦ τεμένους προεστώτων ἐπιτρέψαι παρελθόντα ἐξαλεῖψαι τὸν ὄρνιν, καὶ ἐποίησε. δημοκηδεῖς δ' εἰσὶν οἱ Ῥόδιοι, καίπερ οὐ δημοκρατούμενοι, συνέχειν δ' ὅμως
 C 653 βουλομένοι τὸ τῶν πενήτων πλῆθος. σιταρχεῖται δὴ ὁ δῆμος καὶ οἱ εὐποροὶ τοὺς ἐνδεεῖς ὑπολαμβάνουσιν ἔθει τινὶ πατρίῳ, λειτουργίαι τέ τινές εἰσιν ὀψωνιζόμεναι,¹ ὥσθ' ἅμα τὸν τε πένητα ἔχειν τὴν διατροφὴν καὶ τὴν πόλιν τῶν χρειῶν μὴ καθυστερεῖν, καὶ μάλιστα πρὸς τὰς ναυστολίας. τῶν δὲ ναυστάθμων τινὰ καὶ κρυπτὰ ἦν καὶ ἀπόρρητα τοῖς πολλοῖς, τῷ δὲ κατοπτέυσαντι ἢ παρελθόντι εἶσω θάνατος ὄριστο ἢ ζημία. κἀνταῦθα δέ, ὥσπερ ἐν Μασσαλίᾳ καὶ Κυζίκῳ, τὰ περὶ τοὺς ἀρχιτέκτονας καὶ τὰς ὀργανοποιίας καὶ θησαυροὺς ὅπλων τε καὶ τῶν ἄλλων ἐσπούδασται διαφερόντως, καὶ ἔτι γε τῶν παρ' ἄλλοις μᾶλλον.

6. Δωριεῖς δ' εἰσὶν, ὥσπερ καὶ Ἀλικαρνασεῖς καὶ Κνίδιοι καὶ Κῶοι, οἱ γὰρ Δωριεῖς οἱ τὰ Μέγαρα² κτίσαντες μετὰ τὴν Κόδρου τελευτήν, οἱ μὲν ἔμειναν αὐτόθι, οἱ δὲ σὺν Ἀλθαιμένει τῷ Ἀργεῖῳ τῆς εἰς Κρήτην ἀποικίας ἐκοινώνησαν, οἱ

¹ ὀψωνιζόμεναι F and Corais ; ὀψωνιαζόμεναι other MSS.

² Μέγαρα, Xylander, for μεγάλα ; so the later editors.

¹ Public offices to which the richer citizens were appointed. These citizens were usually appointed by rotation, according

success. But the partridge-breeders were still more amazed, bringing their tame partridges and placing them opposite the painted partridge; for their partridges would make their call to the painting and attract a mob of people. But when Protopogenes saw that the main part of the work had become subordinate, he begged those who were in charge of the sacred precinct to permit him to go there and efface the partridge, and so he did. The Rhodians are concerned for the people in general, although their rule is not democratic; still, they wish to take care of their multitude of poor people. Accordingly, the people are supplied with provisions and the needy are supported by the well-to-do, by a certain ancestral custom; and there are certain liturgies¹ that supply provisions, so that at the same time the poor man receives his sustenance and the city does not run short of useful men, and in particular for the manning of the fleets. As for the roadsteads, some of them were kept hidden and forbidden to the people in general; and death was the penalty for any person who spied on them or passed inside them. And here too, as in Massalia and Cyzicus, everything relating to the architects, the manufacture of instruments of war, and the stores of arms and everything else are objects of exceptional care, and even more so than anywhere else.

6. The Rhodians, like the people of Halicarnassus and Cnidus and Cos, are Dorians; for of the Dorians who founded Megara after the death of Codrus, some remained there, others took part with Althaeus the Argive in the colonisation of Crete, and

to their wealth, and they personally paid all the expenses connected with their offices.

δ' εἰς τὴν Ῥόδον καὶ τὰς λεχθείσας ἀρτίως πόλεις
ἐμερίσθησαν. ταῦτα δὲ νεώτερα τῶν ὑφ' Ὀμήρου
λεγομένων ἐστί· Κνίδος μὲν γὰρ καὶ Ἀλικαρνασὸς
οὐδ' ἦν πω, Ῥόδος δ' ἦν καὶ Κῶς, ἀλλ' ὠκεῖτο
ὑφ' Ἡρακλειδῶν. Τληπόλεμος μὲν οὖν ἀνδρω-
θεὶς

αὐτίκα πατρὸς ἐοῖο φίλον μήτρωα κατέκτα
ἤδη γηράσκοντα, Λικύμνιον.
αἰψα δὲ νῆας ἔπηξε, πολὺν δ' ὃ γε λαὸν ἀγείρας
βῆ φεύγων.

εἰτά φησιν·

εἰς Ῥόδον ἵξεν ἀλώμενος,
τριχθὰ δὲ ὤκηθεν καταφυλαδόν.
καὶ τὰς πόλεις ὀνομάζει τὰς τότε,

Λίνδον, Ἰηλυσὸν τε καὶ ἀργινόεντα Κάμειρον,
τῆς Ῥοδίων πόλεως οὐπω συνωκισμένης. οὐδαμοῦ
δὲ ἐνταῦθα Δωριέας ὀνομάζει, ἀλλ' εἰ¹ ἄρα
Αἰολέας ἐμφαίνει καὶ Βοιωτοὺς, εἴπερ ἐκεῖ ἡ
κατοικία τοῦ Ἡρακλέους καὶ τοῦ Λικυμνίου· εἰ
δ', ὥσπερ καὶ ἄλλοι φασίν, ἐξ Ἀργους καὶ
Τίρυνθος ἀπῆρεν ὁ Τληπόλεμος, οὐδ' οὕτω Δωρικὴ
γίνεται ἡ ἐκεῖθεν ἀποικία· πρὸ γὰρ τῆς Ἡρακλει-
δῶν καθόδου γεγέννηται. καὶ τῶν Κέων δὲ

Φείδιππὸς τε καὶ Ἀντιφὸς ἡγησάσθην,
Θεσσαλοῦ υἱε δὴ δύο Ἡρακλείδαο ἀνακτος·
καὶ οὗτοι τὸ Αἰολικὸν μᾶλλον ἢ τὸ Δωρικὸν γένος
ἐμφαίνοντες.

7. Ἐκαλεῖτο δ' ἡ Ῥόδος πρότερον Ὀφιοῦσσα
καὶ Σταδία, εἰτα Τελχινίς, ἀπὸ τῶν οἰκησάντων

others were distributed to Rhodes and to the cities just now mentioned. But these events are later than those mentioned by Homer, for Cnidus and Halicarnassus were not yet in existence, although Rhodes and Cos were; but they were inhabited by Heracleidae. Now when Tlepolemus had grown to manhood, "he forthwith slew his own father's dear uncle, Licymnius, who was then growing old; and straightway he built him ships, and when he had gathered together a great host he went in flight."¹ The poet then adds, "he came to Rhodes in his wanderings, where his people settled in three divisions by tribes"; and he names the cities of that time, "Lindus, Ialysus, and Cameirus white with chalk,"² the city of the Rhodians having not yet been founded. The poet, then, nowhere mentions Dorians by name here, but perhaps indicates Aeolians and Boeotians, if it be true that Heracles and Licymnius settled there. But if, as others say, Tlepolemus set forth from Argos and Tiryns, even so the colonisation thence could not have been Dorian, for it must have taken place before the return of the Heracleidae. And of the Coans, also, Homer says, "these were led by Pheidippus and Antiphus, the two sons of lord Thessalus, son of Heracles";³ and these names indicate the Aeolian stock of people rather than the Dorian.

7. In earlier times Rhodes was called Ophiussa and Stadia, and then Telchinis, after the Telchines,

¹ *Iliad* 2. 662.

² *Iliad* 2. 656.

³ *Iliad* 2. 678.

¹ εἰ, Corais, for ἧ.

C 654 Τελχίνων τὴν νῆσον· οὗς οἱ μὲν βασκάνους φασὶ καὶ γόητας, θείῳ¹ καταρραίνοντας² τὸ τῆς Στυγὸς ὕδωρ ζάων τε καὶ φυτῶν ὀλέθρου χάριν· οἱ δὲ τέχναις διαφέροντας τοῦναντίον ὑπὸ τῶν ἀντιτέχνων βασκανθῆναι καὶ τῆς δυσφημίας τυχεῖν ταύτης· ἐλθεῖν δ' ἐκ Κρήτης εἰς Κύπρον πρῶτον, εἴτ' εἰς Ῥόδον· πρῶτους δ' ἐργάσασθαι σίδηρόν τε καὶ χαλκόν, καὶ δὴ καὶ τὴν ἄρπην τῷ Κρόνῳ δημιουργῆσαι. εἴρηται μὲν οὖν καὶ πρότερον περὶ αὐτῶν, ἀλλὰ ποιεῖ τὸ πολὺμυθον ἀναλαμβάνειν πάλιν ἀναπληροῦντας, εἴ τι παρελίπομεν.

8. Μετὰ δὲ τοὺς Τελχίνας οἱ Ἡλιάδαι μυθεύονται κατασχεῖν τὴν νῆσον, ὧν ἑνὸς Κερκάφου καὶ Κυδίππης γενέσθαι παῖδας τοὺς τὰς πόλεις κτίσαντας ἐπωνύμους αὐτῶν,

Λίνδον Ἰηλυσόν τε καὶ ἀργινόεντα Κάμειρον·

ἔνιοι δὲ τὸν Τληπόλεμον κτίσαι φασί, θέσθαι δὲ τὰ ὀνόματα ὁμωνύμως τῶν Δαναοῦ θυγατέρων τισίν.

9. Ἡ δὲ νῦν πόλις ἐκτίσθη κατὰ τὰ Πελοποννησιακὰ ὑπὸ τοῦ αὐτοῦ ἀρχιτέκτονος, ὥς φασιν, ὑφ' οὗ καὶ ὁ Πειραιεύς· οὐ συμμένει δ' ὁ Πειραιεύς, κακῶθεις ὑπὸ τε Λακεδαιμονίων πρότερον τῶν τὰ σκέλη καθελόντων καὶ ὑπὸ Σύλλα τοῦ Ῥωμαίων ἡγεμόνος.

10. Ἱστοροῦσι δὲ καὶ ταῦτα περὶ τῶν Ῥοδίων, ὅτι οὐ μόνον ἀφ' οὗ χρόνου συνώκισαν τὴν νῦν

¹ θείῳ (sulphur) is strongly suspected. Meineke conj. φθόνῳ, and Forbiger so translates.

who took up their abode in the island. Some say that the Telchines are "maligners" and "sorcerers," who pour the water of the Styx mixed with sulphur¹ upon animals and plants in order to destroy them. But others, on the contrary, say that since they excelled in workmanship they were "maligned" by rival workmen and thus received their bad reputation; and that they first came from Crete to Cyprus, and then to Rhodes; and that they were the first to work iron and brass, and in fact fabricated the scythe for Cronus. Now I have already described them before,² but the number of the myths about them causes me to resume their description, filling up the gaps, if I have omitted anything.

8. After the Telchines, the Heliadae, according to the mythical story, took possession of the island; and to one of these, Cercaphus, and to his wife Cydippê, were born children who founded the cities that are named after them, "Lindus, Ialysus, and Cameirus white with chalk." But some say that Tlepolemus founded them and gave them the same names as those of certain daughters of Danäus.

9. The present city was founded at the time of the Peloponnesian War by the same architect, as they say, who founded the Peiraeus. But the Peiraeus no longer endures, since it was badly damaged, first by the Lacedaemonians, who tore down the two walls, and later by Sulla, the Roman commander.

10. It is also related of the Rhodians that they have been prosperous by sea, not merely since the

¹ See critical note.

² 10. 3, 7, 19.

² καταρπαινοντας μοσχ; καταρρεοντας other MSS.

πόλιν εὐτύχουν κατὰ θάλατταν, ἀλλὰ καὶ πρὸ
 τῆς Ὀλυμπικῆς θέσεως συχνοῖς ἔτεσιν ἔπλεον
 πόρρω τῆς οἰκείας ἐπὶ σωτηρία τῶν ἀνθρώπων·
 ἀφ' οὗ καὶ μέχρι Ἰβηρίας ἔπλευσαν, κακεῖ μὲν
 τὴν Ῥόδον¹ ἔκτισαν, ἣν ὕστερον Μασσαλιῶται
 κατέσχον, ἐν δὲ τοῖς Ὀπικοῖς τὴν Παρθενόπην,
 ἐν δὲ Δαυνίοις μετὰ Κῶων Ἑλπίας. τινὲς δὲ
 μετὰ τὴν ἐκ Τροίας ἀφοδὸν τὰς Γυμνησίας νήσους
 ὑπ' αὐτῶν κτισθῆναι λέγουσιν, ὧν τὴν μείζω φησὶ
 Τίμαιος μεγίστην εἶναι μετὰ τὰς ἑπτὰ, Σαρδῶ,
 Σικελίαν, Κύπρον, Κρήτην, Εὐβοίαν, Κύρνον,
 Λέσβον, οὐ τάληθῇ λέγων· πολὺ γὰρ ἄλλαι
 μείζους. φασὶ δὲ τοὺς γυμνήτας ὑπὸ Φοινίκων
 βαλεαρίδας λέγεσθαι, διότι τὰς Γυμνησίας
 Βαλεαρίδας λεχθῆναι.² τινὲς δὲ τῶν Ῥοδίων
 καὶ περὶ Σύβαριν ὥκησαν κατὰ τὴν Χωνίαν.
 ἔοικε δὲ καὶ ὁ ποιητὴς μαρτυρεῖν τὴν ἐκ παλαιοῦ
 παροῦσαν τοῖς Ῥοδίοις εὐδαιμονίαν εὐθύς ἀπὸ τῆς
 πρώτης κτίσεως τῶν τριῶν πόλεων·

τριχθὰ δὲ ὥκηθεν καταφυλαδόν, ἥδ' ἐφίληθεν
 ἐκ Διός, ὅστε θεοῖσι καὶ ἀνθρώποισιν ἀνάσσει.
 καὶ σφιν θεσπέσιον πλοῦτον κατέχευε Κρονίων.

C 655 οἱ δ' εἰς μῦθον ἀνήγαγον τὸ ἔπος καὶ χρυσὸν
 ὑσθῆναί φασιν ἐν τῇ νήσῳ κατὰ τὴν Ἀθηνᾶς
 γένεσιν ἐκ τῆς κεφαλῆς τοῦ Διός, ὡς εἶρηκε
 Πίνδαρος. ἡ δὲ νήσος κύκλον ἔχει σταδίων
 ἑννακοσίων εἴκοσιν.

¹ On Ῥόδον (which Meineke emends to Ῥόδην), see Vol. II, p. 92, footnote 2.

² φασὶ δὲ . . . λεχθῆναι, Meineke ejects.

¹ Cf. 3. 4. 8.

² "Light-armed foot-soldiers."

time when they founded the present city, but that even many years before the establishment of the Olympian Games they used to sail far away from their homeland to insure the safety of their people. Since that time, also, they have sailed as far as Iberia; and there they founded Rhodes,¹ of which the Massaliotes later took possession; among the Opici they founded Parthenopê; and among the Daunians they, along with the Coans, founded Elpiae. Some say that the islands called the Gymnesiae were founded by them after their departure from Troy; and the larger of these, according to Timaeus, is the largest of all islands after the seven—Sardinia, Sicily, Cypros, Crete, Euboea, Cynos, and Lesbos, but this is untrue, for there are others much larger. It is said that “gymnetes”² are called “balearides”³ by the Phoenicians, and that on this account the Gymnesiae were called Balearides. Some of the Rhodians took up their abode round Sybaris in Chonia. The poet, too, seems to bear witness to the prosperity enjoyed by the Rhodians from ancient times, forthwith from the first founding of the three cities: “and there his⁴ people settled in three divisions by tribes, and were loved of Zeus, who is lord over gods and men; and upon them wondrous wealth was shed by the son of Cronus.”⁵ Other writers refer these verses to a myth, and say that gold rained on the island at the time when Athena was born from the head of Zeus, as Pindar⁶ states. The island has a circuit of nine hundred and twenty stadia.

³ Also spelled “baliarides” (see 3. 5. 1).

⁴ Referring to Heracles.

⁵ *Iliad* 2. 668.

⁶ *Olympian Odes* 7. 61.

11. Ἔστι δὲ πρώτη μὲν Λίνδος ἀπὸ τῆς πόλεως πλέουσιν ἐν δεξιᾷ ἔχουσι τὴν νῆσον, πόλις ἐπὶ ὄρους ἰδρυμένη, πολὺ πρὸς μεσημβρίαν ἀνατείνουσα καὶ πρὸς Ἀλεξάνδρειαν μάλιστα· ἱερὸν δὲ ἐστὶν Ἀθηνᾶς Λινδίας αὐτόθι ἐπιφανές, τῶν Δαναΐδων ἱδρυμα. πρότερον μὲν οὖν καθ' αὐτοὺς ἐπολιτεύοντο οἱ Λίνδιοι, καθάπερ καὶ Καμειρεῖς καὶ Ἰαλύσιοι, μετὰ ταῦτα δὲ συνήλθον ἅπαντες εἰς τὴν Ῥόδον. ἐντεῦθεν δ' ἐστὶν εἰς τῶν ἑπτὰ σοφῶν, Κλεόβουλος.

12. Μετὰ δὲ Λίνδον Ἰξία χωρίον καὶ Μνασύριον. εἰθ' ὁ Ἀτάβυρις, ὄρος τῶν ἐνταῦθα ὑψηλότατον, ἱερὸν Διὸς Ἀταβυρίου· εἶτα Κάμειρος· εἶτ' Ἰαλυσὸς κώμη, καὶ ὑπὲρ αὐτὴν ἀκρόπολις ἐστὶν Ὀχύρωμα καλουμένη· εἰθ' ἡ τῶν Ῥοδίων πόλις ἐν ὀγδοήκοντά που σταδίοις. μεταξὺ δ' ἐστὶ τὸ Θοάντιον, ἀκτὴ τις, ἥς μάλιστα πρόκεινται αἱ Σποράδες αἱ περὶ τὴν Χαλκίαν, ὧν ἐμνήσθημεν πρότερον.

13. Ἄνδρες δ' ἐγένοντο μνήμης ἄξιοι πολλοὶ στρατηλάται τε καὶ ἀθληταί, ὧν εἰσὶ καὶ οἱ Παναιτίου τοῦ φιλοσόφου πρόγονοι· τῶν δὲ πολιτικῶν καὶ τῶν περὶ λόγους καὶ φιλοσοφίαν¹ ὃ τε Παναιτίος αὐτὸς καὶ Στρατοκλῆς καὶ Ἀνδρόνικος ὁ ἐκ τῶν περιπάτων καὶ Λεωνίδης ὁ στωικός· ἔτι δὲ πρότερον Πραξιφάνης καὶ Ἱερώνυμος καὶ Εὐδημος. Ποσειδώνιος δ' ἐπολιτεύσατο μὲν ἐν Ῥόδῳ καὶ ἐσοφίστευσεν, ἦν δ' Ἀπαμεὺς ἐκ τῆς Συρίας, καθάπερ καὶ Ἀπολ-

¹ φιλοσοφίαν, Corais, for φιλοσοφίας; so Meineke.

11. As one sails from the city, with the island on the right, one comes first to Lindus, a city situated on a mountain and extending far towards the south and approximately towards Alexandria.¹ In Lindus there is a famous temple of Athena Lindia, founded by the daughters of Danaüs. Now in earlier times the Lindians were under a separate government of their own, as were also the Cameirians and the Ialysians, but after this they all came together at Rhodes. Cleobulus, one of the Seven Wise Men, was a native of Lindus.

12. After Lindus one comes to Ixia, a stronghold, and to Mnasyrium; then to Atabyris, the highest of the mountains there, which is sacred to Zeus Atabyrius; then to Cameirus; then to Ialysus, a village, above which there is an acropolis called Ochyroma; then to the city of the Rhodians, at a distance of about eighty stadia. Between these lies Thoantium, a kind of promontory; and it is off Thoantium, generally speaking, that Chalcia and the Sporades in the neighbourhood of Chalcia lie, which I have mentioned before.²

13. Many men worthy of mention were native Rhodians, both commanders and athletes, among whom were the ancestors of Panaetius the philosopher; and, among statesmen and rhetoricians and philosophers, Panaetius himself and Stratoles and Andronicus, one of the Peripatetics, and Leonides the Stoic; and also, before their time, Praxiphanes and Hieronymus and Eudemus. Poseidonius engaged in affairs of state in Rhodes and taught there, although he was a native of Apameia in Syria, as

¹ According to Strabo (1. 4. 1 ff.), Rhodes and Alexandria lie on the same meridian.

² 10. 5. 14.

λώνιος ὁ Μαλακὸς καὶ Μόλων ἦσαν γὰρ Ἀλαβανδεῖς, Μενεκλέους μαθηταὶ τοῦ ῥήτορος. ἐπεδήμησε δὲ πρότερον Ἀπολλώνιος, ὃς δ' ἦκεν ὁ Μόλων, καὶ ἔφη πρὸς αὐτὸν ἐκεῖνος ὃς μολῶν, ἀντὶ τοῦ ἐλθῶν καὶ Πείσανδρος δ' ὁ τὴν Ἡράκλειαν γράψας ποιητῆς Ῥόδιος, καὶ Σιμμίας ὁ γραμματικὸς καὶ Ἀριστοκλῆς ὁ καθ' ἡμᾶς. Διονύσιος δὲ ὁ Θραξ καὶ Ἀπολλώνιος ὁ τοὺς Ἀργοναύτας ποιήσας, Ἀλεξανδρεῖς μὲν, ἐκαλοῦντο δὲ Ῥόδιοι. περὶ μὲν Ῥόδου ἀποχρώντως εἴρηται.

14. Πάλιν δὲ τῆς Καρικῆς παραλίας τῆς μετὰ τὴν Ῥόδον, ἀπὸ Ἐλεοῦντος καὶ τῶν Λωρύμων, καμπτήρ τις ἐπὶ τὰς ἄρκτους ἐστί, καὶ λοιπὸν ἐπ' εὐθείας ὁ πλοῦς μέχρι τῆς Προποντίδος, ὥς ἂν μεσημβρινὴν τινα ποιῶν γραμμὴν ὅσον πεντακισχιλίων σταδίων ἢ μικρὸν ἀπολείπουσιν. ἐνταῦθα δ' ἐστὶν ἡ λοιπὴ τῆς Καρίας καὶ Ἴωνες καὶ Αἰολεῖς καὶ Τροία καὶ τὰ περὶ Κύζικον καὶ Βυζάντιον. μετὰ δ' οὖν C 656 τὰ Λώρυμα τὸ Κυνὸς σῆμά ἐστί καὶ Σύμη νῆσος.

15. Εἶτα Κνίδος, δύο λιμένας ἔχουσα, ὧν τὸν ἕτερον κλειστὸν τριηρικὸν καὶ ναύσταθμον ναυσὶν εἴκοσι. πρόκειται δὲ¹ νῆσος ἐπταστάδιός πως τὴν περίμετρον, ὑψηλὴ, θεατροειδής, συναπτομένη χώμασι πρὸς τὴν ἡπειρον καὶ ποιούσα δίπολιν

¹ 34, Corais, for δ' ἡ.

¹ He taught rhetoric at Rhodes about 120 B.C.

² Apollonius Molon (see 14. 2. 3).

³ Natives of Alabanda in Caria.

was also the case with Apollonius Malacus¹ and Molon,² for they were Alabandians,³ pupils of Menecles the orator. Apollonius Malacus began his sojourn there earlier than Molon, and when, much later, Molon came, the former said to him, "you are a late 'molon,'"⁴ instead of saying, "late 'elthon.'"⁵ And Peisander the poet, who wrote the *Heracleia*, was also a Rhodian; and so was Simmias the grammarian, as also Aristocles of my own time. And Dionysius the Thracian and the Apollonius who wrote the *Argonauts*, though Alexandrians, were called Rhodians. As for Rhodes, I have said enough about it.

14. As for the Carian coast that comes after Rhodes, beginning at Eleus and Loryma, it bends sharply back towards the north, and the voyage thereafter runs in a straight line as far as the Propontis, forming, as it were, a meridian line about five thousand stadia long, or slightly short of that distance. Along this line is situated the remainder of Caria, as are also the Ionians and the Aeolians and Troy and the parts round Cyzicus and Byzantium. After Loryma, then, one comes to Cynos-Sema⁶ and to Symé, an island.

15. Then to Cnidus, with two harbours, one of which can be closed, can receive triremes, and is a naval station for twenty ships. Off it lies an island which is approximately seven stadia in circuit, rises high, is theatre-like, is connected by moles with the

¹ "Molon" means "comer" (note the word-play).

² "Elthon" is the common word for "comer," whereas the other is poetic and comparatively rare.

⁶ Cape Volpo. Cf. the reference to the Cynos-Sema at the entrance of the Hellespont, Vol. III, p. 377, *Frag.* 55.

τρόπον τινὰ τὴν Κνίδον· πολὺ γὰρ αὐτῆς μέρος οἰκεῖ τὴν νῆσον, σκεπάζουσιν ἀμφοτέρους τοὺς λιμένας. κατ' αὐτὴν δ' ἐστὶν ἡ Νίσυρος πελαγία. ἄνδρες δ' ἀξιόλογοι Κνίδιοι πρῶτον μὲν Εὐδοξος ὁ μαθηματικός, τῶν Πλάτωνος ἐταίρων, εἴτ' Ἀγαθαρχίδης ὁ ἐκ τῶν περιπάτων, ἀνὴρ συγγραφεὺς, καθ' ἡμᾶς δὲ Θεόπομπος, ὁ Καίσαρος τοῦ Θεοῦ φίλος τῶν μεγάλα δυναμένων, καὶ υἱὸς Ἀρτεμίδωρος. ἐντεύθεν δὲ καὶ Κτησίας ὁ λατρεύσας μὲν Ἀρταξέρξην, συγγράψας δὲ τὰ Ἀσσυρικὰ καὶ τὰ Περσικά. εἶτα μετὰ Κνίδον Κέραμος καὶ Βάργασα πολίχνη ὑπὲρ θαλάττης.

16. Εἰθ' Ἀλικαρνασός, τὸ βασιλείον τῶν τῆς Καρίας δυναστῶν, Ζεφύρα¹ καλουμένη πρότερον. ἐνταῦθα δ' ἐστὶν ὃ τε τοῦ Μανσώλου τάφος,² τῶν ἐπτὰ θεαμάτων, ἔργον,³ ὅπερ Ἀρτεμισία τῷ ἀνδρὶ κατεσκεύασε, καὶ ἡ Σαλμακίς κρήνη, διαβεβλημένη, οὐκ οἶδ' ὁπόθεν, ὡς μαλακίζουσα τοὺς πιόντας ἀπ' αὐτῆς. ἔοικε δ' ἡ τρυφή τῶν ἀνθρώπων αἰτιᾶσθαι τοὺς ἀέρας ἢ τὰ ὕδατα· τρυφῆς δ' αἷτια οὐ ταῦτα, ἀλλὰ πλοῦτος καὶ ἡ περὶ τὰς διαίτας ἀκολασία. ἔχει δ' ἀκρόπολιν ἡ Ἀλικαρνασός· πρόκειται δ' αὐτῆς ἡ Ἀρκόννησος. οἰκισταὶ δ' αὐτῆς ἐγένοντο ἄλλοι τε καὶ Ἀνθης μετὰ Τροιζηνίων. ἄνδρες δὲ γεγόνασιν ἐξ αὐτῆς Ἡρόδοτος τε ὁ συγγραφεὺς, ὃν ὕστερον Θούριον ἐκάλεσαν διὰ τὸ κοινωνῆσαι τῆς εἰς

¹ Stephanus (s.v. Ἀλικαρνασός) spells the name Ζεφυρία; so Meineke reads.

² Before τῶν Corais and Meineke, following the Epitome, insert ἐν.

³ Corais conjectures that Σκόπια has fallen out after ἔργον;

mainland, and in a way makes Cnidus a double city, for a large part of its people live on the island, which shelters both harbours. Opposite it, in the high sea, is Nisyrus. Notable Cnidians were: first, Eudoxus the mathematician, one of the comrades of Plato; then Agatharchides, one of the Peripatetics, a historian; and, in my own time, Theopompus, the friend of the deified Caesar, being a man of great influence with him, and his son Artemidorus. Thence, also, came Ctesias, who served Artaxerxes as physician and wrote the works entitled *Assyrica* and *Persica*. Then, after Cnidus, one comes to Ceramus and Bargasa, small towns situated above the sea.

16. Then to Halicarnassus, the royal residence of the dynasts of Caria, which was formerly called Zephyra. Here is the tomb of Mausolus,¹ one of the Seven Wonders, a monument erected by Artemisia in honour of her husband; and here is the fountain called Salmacis, which has the slanderous repute, for what reason I do not know, of making effeminate all who drink from it. It seems that the effeminacy of man is laid to the charge of the air or of the water; yet it is not these, but rather riches and wanton living, that are the cause of effeminacy. Halicarnassus has an acropolis; and off the city lies Arconnesus. Its colonisers were, among others, Anthes and a number of Troezenians. Natives of Halicarnassus have been: Herodotus the historian, whom they later called a Thurian, because

¹ Hence "mausoleum."

Groskurd, *Σκόπευτα καὶ τεχνιτῶν*. Meineke indicates a lacuna before *ἔργον*, conjecturing *θauμαστόν*.

Θουρίους ἀποικίας, καὶ Ἡράκλειτος ὁ ποιητής, ὁ Καλλιμάχου ἑταῖρος, καὶ καθ' ἡμᾶς Διονύσιος ὁ συγγραφεὺς.

17. Ἐπταισε δὲ καὶ αὕτη ἡ πόλις βία ληφθεῖσα ὑπὸ Ἀλεξάνδρου. Ἐκατόμνω γὰρ τοῦ Καρῶν βασιλέως ἦσαν υἱοὶ τρεῖς, Μαύσωλος καὶ Ἰδριεὺς καὶ Πιξῳδάρους, καὶ θυγατέρες δύο, ὧν τῇ πρεσβυτέρᾳ Ἀρτεμισίᾳ Μαύσωλος συνώκησεν, ὁ πρεσβύτατος τῶν ἀδελφῶν, ὁ δὲ δεύτερος Ἰδριεὺς Ἄδα, τῇ ἑτέρᾳ ἀδελφῇ· ἐβασίλευσε δὲ Μαύσωλος· τελευτῶν δ' ἄτεκνος τὴν ἀρχὴν κατέλιπε τῇ γυναικί, ὑφ' ἧς αὐτῷ κατεσκευάσθη ὁ λεχθεὶς τάφος· φθίσει δ' ἀποθανούσης διὰ πένθος τοῦ ἀνδρός, Ἰδριεὺς ἤρξε· καὶ τοῦτον ἡ γυνὴ Ἄδα διεδέξατο νόσφ' τελευτήσαντα· ἐξέβαλε δὲ ταύτην Πιξῳδάρους, ὁ λοιπὸς τῶν Ἐκατόμνω παίδων. περσίσας δὲ μεταπέμπεται σατράπην ἐπὶ κοινωσίᾳ τῆς ἀρχῆς· ἀπελθόντος δ' ἐκ τοῦ ζῆν καὶ τούτου, κατείχεν ὁ σατράπης τὴν Ἀλικαρνασόν· ἐπελθόντος δὲ Ἀλεξάνδρου, πολιορκίαν ὑπέμεινε, ἔχων Ἄδαν γυναῖκα, ἣτις θυγάτηρ ἦν Πιξῳδάρου ἐξ Ἀφνηίδος, Καππαδοκίσης γυναικός. ἡ δὲ τοῦ Ἐκατόμνω θυγάτηρ Ἄδα, ἣν ὁ Πιξῳδάρους ἐξέβαλεν, ἰκετεύει τὸν Ἀλέξανδρον καὶ πείθει κατὰγειν αὐτὴν εἰς τὴν ἀφαιρεθεῖσαν βασιλείαν, ὑποσχομένη ἐπὶ τὰ ἀφεστῶτα συμπράξειν αὐτῷ· τοὺς γὰρ ἔχοντας οἰκείους ὑπάρχειν αὐτῇ· παρεδίδου δὲ καὶ τὰ Ἄλινδα, ἐν ᾧ διέτριβεν αὐτή· ἐπαινέσας δὲ καὶ βασιλίσσαν ἀναδείξας, ἀλούσης τῆς πόλεως πλὴν τῆς ἄκρας (διττὴ δ' ἦν), ἐκείνη πολιορκεῖν ἔδωκεν· ἑάλω δὲ ὀλίγω

he took part in the colonisation of Thuri; and Heracleitus the poet, the comrade of Callimachus; and, in my time, Dionysius the historian.

17. This city, too, met a reverse when it was forcibly seized by Alexander. For Hecatomnus, the king of the Carians, had three sons, Mausolus and Hidrieus and Pixodarus, and two daughters. Mausolus, the eldest of the brothers, married Artemisia, the elder of the daughters, and Hidrieus, the second son, married Ada, the other sister. Mausolus became king and at last, childless, he left the empire to his wife, by whom the above-mentioned tomb was erected. But she pined away and died through grief for her husband, and Hidrieus then became ruler. He died from a disease and was succeeded by his wife Ada; but she was banished by Pixodarus, the remaining son of Hecatomnos. Having espoused the side of the Persians, he sent for a satrap to share the empire with him; and when he too departed from life, the satrap took possession of Halicarnassus. And when Alexander came over, the satrap sustained a siege. His wife was Ada, who was the daughter of Pixodarus by Aphenis, a Cappadocian woman. But Ada, the daughter of Hecatomnos, whom Pixodarus had banished, entreated Alexander and persuaded him to restore her to the kingdom of which she had been deprived, having promised to co-operate with him against the parts of the country which were in revolt, for those who held these parts, she said, were her own relations; and she also gave over to him Alinda, where she herself was residing. He assented and appointed her queen; and when the city, except the acropolis (it was a double city), had been captured, he assigned to her the siege of the acro-

ὑστερον¹ καὶ ἡ ἄκρα, πρὸς ὀργὴν ἤδη καὶ ἀπέχθειαν τῆς πολιορκίας γενομένης.

18. Ἐξῆς δ' ἐστὶν ἄκρα Τερμέριον Μυνδίων, καθ' ἣν ἀντίκειται τῆς Κώας ἄκρα Σκανδαρία, διέχουσα τῆς ἡπείρου σταδίους τετταράκοντα· ἔστι δὲ καὶ χωρίον Τέρμερον ὑπὲρ τῆς Κώας.

19. Ἡ δὲ τῶν Κῶων πόλις ἐκαλεῖτο τὸ παλαιὸν Ἀστυπάλαια, καὶ ὤκειτο ἐν ἄλλῳ τόπῳ ὁμοίως ἐπὶ θαλάττῃ· ἔπειτα διὰ στάσιν μετώκησαν εἰς τὴν νῦν πόλιν περὶ τὸ Σκανδάριον,² καὶ μετωνόμασαν Κῶν ὁμωνύμως τῇ νήσῳ. ἡ μὲν οὖν πόλις οὐ μεγάλη, κάλλιστα δὲ πασῶν συμφικισμένη καὶ ιδέσθαι τοῖς καταπλέουσιν ἡδίστη. τῆς δὲ νήσου τὸ μέγεθος ὅσον πεντακοσίων σταδίων καὶ πεντήκοντα· εὐκαρπος δὲ πᾶσα, οἶνω δὲ καὶ ἀρίστη, καθάπερ Χίος καὶ Λέσβος· ἔχει δὲ πρὸς νότον μὲν ἄκραν τὸν Λακητήρα, ἀφ' οὗ ἐξήκοντα εἰς Νίσυρον (πρὸς δὲ τῷ Λακητήρι χωρίον³ Ἀλίσαρνα), ἀπὸ δύσεως δὲ τὸ Δρέκανον καὶ κόμην καλουμένην Στομαλίμνην· τοῦτο μὲν οὖν ὅσον διακοσίους τῆς πόλεως διέχει σταδίους· ὁ δὲ Λακητῆρ προσλαμβάνει πέντε καὶ τριάκοντα τῷ μήκει τοῦ πλοῦ. ἐν δὲ τῷ προαστείῳ τὸ Ἀσκληπιεῖον ἐστὶ, σφόδρα ἔνδοξον καὶ πολλῶν ἀναθημάτων μεστὸν ἱερόν,⁴ ἐν οἷς ἐστὶ καὶ ὁ Ἀπελλοῦ Ἀντίγονος. ἦν δὲ καὶ ἡ ἀναδυομένη Ἀφροδίτη,

¹ The MSS. read ἀλίγῃ δ' ὑστερον.

² Σκανδάριον, Tzschucke, for Σκάνδαλον Ε, Σκανδύλιον other MSS. ; so the later editors.

³ Λακητήρι χωρίον, Corais, for Λακητηρίῳ χωρίῳ ; so the later editors.

polis. This too was captured a little later, the siege having now become a matter of anger and personal enmity.

18. Next one comes to a promontory, Termerium, belonging to the Myndians, opposite which lies Scandaria, a promontory of Cos, forty stadia distant from the mainland. And there is a place called Termerum above the promontory of Cos.

19. The city of the Coans was in ancient times called Astypalaea; and its people lived on another site, which was likewise on the sea. And then, on account of a sedition, they changed their abode to the present city, near Scandarium, and changed the name to Cos, the same as that of the island. Now the city is not large, but it is the most beautifully settled of all, and is most pleasing to behold as one sails from the high sea to its shore. The size¹ of the island is about five hundred and fifty stadia. It is everywhere well supplied with fruits, but like Chios and Lesbos it is best in respect to its wine. Towards the south it has a promontory, Laceter, whence the distance to Nisyros is sixty stadia (but near Laceter there is a place called Halisarna), and on the west it has Drecanum and a village called Stomalinnê. Now Drecanum is about two hundred stadia distant from the city, but Laceter adds thirty-five stadia to the length of the voyage. In the suburb is the Asclepæium, a temple exceedingly famous and full of numerous votive offerings, among which is the Antigonus of Apelles. And Aphrodite

¹ *i.e.* the circuit.

* *ἱερὸν* is perhaps rightly omitted by F and Meineke.

ἡ νῦν ἀνάκειται τῷ θεῷ Καίσαρι ἐν Ῥώμῃ, τοῦ Σεβαστοῦ ἀναθέντος τῷ πατρὶ τὴν ἀρχηγέτιν τοῦ γένους αὐτοῦ· φασὶ δὲ τοῖς Κῳοῖς ἀντὶ τῆς γραφῆς ἑκατὸν ταλάντων ἄφεςιν γενέσθαι τοῦ προσταχθέντος φόρου. φασὶ δ' Ἱπποκράτην μάλιστα ἐκ τῶν ἐνταῦθα ἀνακειμένων θεραπειῶν γυμνάσασθαι τὰ περὶ τὰς διαίτας· οὗτός τε δὴ ἐστὶ τῶν ἐνδόξων Κῳος ἀνὴρ καὶ Σῖμος ὁ ἰατρός, Φιλητᾶς τε ποιητὴς ἄμα καὶ κριτικός, καὶ καθ' C 658 ἡμᾶς Νικίας ὁ καὶ τυραννήσας Κῳων, καὶ Ἀρίστων ὁ ἀκροασάμενος τοῦ περιπατητικοῦ καὶ κληρονομήσας ἐκείνον· ἦν δὲ καὶ Θεόμηστος ὁ ψάλτης ἐν ὀνόματι, ὃς καὶ ἀντεπολιτεύσατο τῷ Νικίᾳ.

20. Ἐν δὲ τῇ παραλίᾳ τῆς ἡπείρου κατὰ τὴν Μυνδίαν Ἀστυπάλαιά¹ ἐστὶν ἄκρα καὶ Ζεφύριον εἴτ' εὐθύς ἡ Μύνδος, λιμένα ἔχουσα, καὶ μετὰ ταύτην Βαργύλια, καὶ αὕτη πόλις· ἐν δὲ τῷ μεταξὺ Καρύανδα λιμὴν καὶ νῆσος ὁμώνυμος,² ἣν ᾠκουν Καρυανδεῖς. ἐντεῦθεν δ' ἦν καὶ Σκύλαξ ὁ παλαιὸς συγγραφεύς. πλησίον δ' ἐστὶ τῶν Βαργυλίων τὸ τῆς Ἀρτέμιδος ἱερὸν τῆς Κινδυάδος, ὃ πεπιστεύκασιν περιέσεσθαι· ἦν δέ ποτε καὶ χωρίον Κινδύη. ἐκ δὲ τῶν Βαργυλίων ἀνὴρ ἐλλόγιμος ἦν ὁ Ἐπικούρειος Πρώταρχος ὁ Δημητρίου καθηγησάμενος τοῦ Λάκωνος προσαγορευθέντος.

¹ Ἀστυπάλαια, the editors, for Ἀστυπαλεῖα E, Ἀστυπαλία other MSS.

² ταύτη, after ὁμώνυμος, is omitted by F and by Stephanus (s.v. Καρύανδα).

¹ Emerging from the sea.

Anadyomenê¹ used to be there,² but it is now dedicated to the deified Caesar in Rome, Augustus thus having dedicated to his father the female founder of his family. It is said that the Coans got a remission of one hundred talents of the appointed tribute in return for the painting. And it is said that the dietetics practised by Hippocrates were derived mostly from the cures recorded on the votive tablets there. He, then, is one of the famous men from Cos; and so is Simus the physician; as also Philetas, at the same time poet and critic; and, in my time, Nicias, who also reigned as tyrant over the Coans; and Ariston, the pupil and heir of the Peripatetic;³ and Theomnestus, a renowned harper, who was a political opponent of Nicias, was a native of the island.

20. On the coast of the mainland near the Myndian territory lies Astypalaea, a promontory; and also Zephyrium. Then forthwith one comes to Myndus, which has a harbour; and after Myndus to Bargylia, which is also a city; between the two is Caryanda, a harbour, and also an island bearing the same name, where the Caryandians lived. Here was born Scylax, the ancient historian. Near Bargylia is the temple of Artemis Cindyas, round which the rain is believed to fall without striking it. And there was once a place called Cindyê. From Bargylia there was a man of note, the Epicurean Protarchus, who was the teacher of Demetrius called Lacon.⁴

¹ This, too, was a painting by Apelles.

² Ariston the Peripatetic (fl. third century B.C.), of Iulis in Ceos (see 10. 5. 6). See Pauly-Wissowa.

⁴ i.e. the Laconian.

21. Εἴτ' Ἰασὸς ἐπὶ νήσῳ κεῖται προσκειμένη τῇ ἡπείρῳ, ἔχει δὲ λιμένα, καὶ τὸ πλεῖστον τοῦ βίου τοῖς ἐνθάδε ἐκ θαλάττης· εὖοψεῖ γὰρ χώραν τ' ἔχει παράλυπρον. καὶ δὴ καὶ διηγήματα τοιαῦτα πλάττουσιν εἰς αὐτήν· κιθαρωδοῦ γὰρ ἐπιδεικνυμένου, τέως μὲν ἀκροᾶσθαι πάντας, ὥς δ' ὁ κώδων ὁ κατὰ τὴν ὄψωπωλίαν ἐψόφησε, καταλιπόντας ἀπελθεῖν ἐπὶ τὸ ὄψον, πλὴν ἐνὸς δυσκώφου· τὸν οὖν κιθαρωδὸν προσιόντα εἰπεῖν, ὅτι, ὦ ἄνθρωπε, πολλήν σοι χάριν οἶδα τῆς πρὸς με τιμῆς καὶ φιλομουσίας· οἱ μὲν γὰρ ἄλλοι ἅμα τῷ κώδωνος ἀκοῦσαι ἀπύοντες οἴχονται. ὁ δέ, τί λέγεις; ἔφη, ἤδη γὰρ ὁ κώδων ἐψόφηκεν; εἰπόντος δέ, Εὖ σοι εἴη, ἔφη καὶ ἀναστὰς ἀπῆλθε καὶ αὐτός. ἐντεῦθεν δ' ἦν ὁ διαλεκτικὸς Διόδωρος ὁ Κρόνος προσαγορευθεὶς, κατ' ἀρχὰς μὲν ψευδῶς· Ἀπολλώνιος γὰρ ἐκαλεῖτο ὁ Κρόνος, ὁ ἐπιστατήσας ἐκείνου· μετήνεγκαν δ' ἐπ' αὐτὸν διὰ τὴν ἀδοξίαν τοῦ κατ' ἀλήθειαν Κρόνου.

22. Μετὰ δ' Ἰασὸν τὸ τῶν Μιλησίων Ποσειδίων ἐστίν. ἐν δὲ τῇ μεσογαίᾳ τρεῖς εἰσὶ πόλεις ἀξιόλογοι, Μύλασα, Στρατονίκη, Ἀλάβανδα· αἱ δὲ ἄλλαι περιπόλιοι τούτων ἢ τῶν παραλίων, ὧν εἰσιν Ἀμυζών, Ἡράκλεια, Εὐρώμος, Χαλκήτωρ¹ τούτων μὲν οὖν ἐλάττων λόγος.

¹ Χαλκήτωρ is emended by Meineke to Χαλκήτορες (cp. 14. 1. 8).

¹ One who played the cithara and sang to its accompaniment.

² "Cronus" was a nickname for "Old Timer," "Old

21. Then one comes to Iasus, which lies on an island close to the mainland. It has a harbour; and the people gain most of their livelihood from the sea, for the sea here is well supplied with fish, but the soil of the country is rather poor. Indeed, people fabricate stories of this kind in regard to Iasus: When a citharoede¹ was giving a recital, the people all listened for a time, but when the bell that announced the sale of fish rang, they all left him and went away to the fish-market, except one man who was hard of hearing. The citharoede, therefore, went up to him and said: "Sir, I am grateful to you for the honour you have done me and for your love of music, for all the others except you went away the moment they heard the sound of the bell." And the man said, "What's that you say? Has the bell already rung?" And when the citharoede said "Yes," the man said, "Fare thee well," and himself arose and went away. Here was born the dialectician Diodorus, nicknamed Cronus, falsely so at the outset, for it was Apollonius his master who was called Cronus, but the nickname was transferred to him because of the true Cronus' lack of repute.²

22. After Iasus one comes to the Poseidium of the Milesians. In the interior are three noteworthy cities: Mylasa, Stratoniceia, and Alabanda. The others are dependencies of these or else of the cities on the coast, among which are Amyzon, Heracleia, Euromus, and Chalcetor. As for these, there is less to be said.

Dotard." Diodorus is said to have been given the nickname by Ptolemy Soter because he was unable immediately to solve some dialectic problem put forth by Stilpo. He became the head of the Megarian school of philosophy.

23. Τὰ δὲ Μύλασα ἵδρυται ἐν πεδίῳ σφόδρα εὐδαίμονι· ὑπέρκειται δὲ κατὰ κορυφὴν ὄρος αὐτοῦ,¹ λατόμιον λευκοῦ λίθου κάλλιστον ἔχον· τοῦτο μὲν οὖν ὄφελός ἐστιν οὐ μικρόν, τὴν λιθίαν πρὸς τὰς οἰκοδομίας ἄφθονον καὶ ἐγγύθεν ἔχον, καὶ μάλιστα πρὸς τὰς τῶν ἱερῶν καὶ τῶν ἄλλων δημοσίων ἔργων κατασκευάς· τοιγάρτοι στοαῖς C 659 τε καὶ ναοῖς, εἴ τις ἄλλη, κεκόσμηται παγκάλως. θαυμάζειν δ' ἔστι τῶν ὑποβαλόντων οὕτως ἀλόγως τὸ κτίσμα ὀρθίῳ καὶ ὑπερδεξίῳ κρημνῷ· καὶ δὴ τῶν ἡγεμόνων τις εἰπεῖν λέγεται, θαυμάσας τὸ πρᾶγμα· Ταύτην γάρ, ἔφη, τὴν πόλιν ὁ κτίσας, εἰ μὴ ἐφοβεῖτο, ἄρ' οὐδ' ἡσχύνετο; ἔχουσι δ' οἱ Μυλασεῖς ἱερὰ δύο τοῦ Διός, τοῦ τε Ὅσογῶ καλουμένου, καὶ Λαβρανδηνοῦ· τὸ μὲν ἐν τῇ πόλει, τὰ δὲ Λάβρανδα κώμη ἐστὶν ἐν τῷ ὄρει κατὰ τὴν ὑπέρθεσιν τὴν ἐξ Ἀλαβάνδων εἰς τὰ Μύλασα, ἄπωθεν τῆς πόλεως· ἐνταῦθα νεῶς ἐστὶν ἀρχαῖος καὶ ξόανον Διὸς Στρατίου· τιμᾶται δὲ ὑπὸ τῶν κύκλῳ καὶ ὑπὸ τῶν Μυλασέων, ὁδός τε ἔστρωται σχεδόν τι καὶ ἐξήκοντα σταδίων μέχρι τῆς πόλεως, ἱερὰ καλουμένη, δι' ἧς πομποστολεῖται τὰ ἱερά· ἱερῶνται δ' οἱ ἐπιφανέστατοι τῶν πολιτῶν ἀεὶ διὰ βίου. ταῦτα μὲν οὖν ἴδια² τῆς πόλεως, τρίτον δ' ἐστὶν ἱερὸν τοῦ Καρίου Διὸς κοινὸν ἁπάντων Καρῶν, οὗ μέτεστι καὶ Λυδοῖς καὶ Μυσοῖς ὡς ἀδελφοῖς. ἱστορεῖται δὲ κώμη ὑπάρξαι τὸ

¹ For αὐτοῦ C. Müller (*Ind. Var. Lect.* p. 1030) cleverly conj. αἰπύ.

² ἴδια, Casaubon, for διὰ; so the later editors.

23. But as for Mylasa: it is situated in an exceedingly fertile plain; and above the plain, towering into a peak, rises a mountain, which has a most excellent quarry of white marble. Now this quarry is of no small advantage, since it has stone in abundance and close at hand, for building purposes and in particular for the building of temples and other public works;¹ accordingly this city, as much as any other, is in every way beautifully adorned with porticoes and temples. But one may well be amazed at those who so absurdly founded the city at the foot of a steep and commanding crag. Accordingly, one of the commanders, amazed at the fact, is said to have said, "If the man who founded this city, was not afraid, was he not even ashamed?" The Mylasians have two temples of Zeus, Zeus Osogo, as he is called, and Zeus Labrandenus. The former is in the city, whereas Labranda is a village far from the city, being situated on the mountain near the pass that leads over from Alabanda to Mylasa. At Labranda there is an ancient shrine and statue of Zeus Stratius. It is honoured by the people all about and by the Mylasians; and there is a paved road of almost sixty stadia from the shrine to Mylasa, called the Sacred Way, on which their sacred processions are conducted. The priestly offices are held by the most distinguished of the citizens, always for life. Now these temples belong peculiarly to the city; but there is a third temple, that of the Carian Zeus, which is a common possession of all Carians, and in which, as brothers, both Lydians and Mysians have a share. It is

¹ *i.e.* "works" of art (see Vol. II, p. 349 and footnote 5, and p. 407 and footnote 4).

παλαιόν, πατρίς δὲ καὶ βασίλειον τῶν Καρῶν τῶν περὶ τὸν Ἑκατόμνω· πλησιάζει δὲ μάλιστα τῇ κατὰ Φύσκον θαλάττῃ ἢ πόλιν, καὶ τοῦτ' ἐστὶν αὐτοῖς ἐπίνειον.

24. Ἀξιολόγους δ' ἔσχεν ἄνδρας καθ' ἡμᾶς τὰ Μύλασα, ῥήτοράς τε ἅμα καὶ δημαγωγούς τῆς πόλεως, Εὐθύδημόν τε καὶ Ὑβρέαν. ὁ μὲν οὖν Εὐθύδημος ἐκ προγόνων παραλαβὼν οὐσίαν τε μεγάλην καὶ δόξαν, προσθεὶς καὶ τὴν δεινότητα, οὐκ ἐν τῇ πατρίδι μόνον μέγας ἦν, ἀλλὰ καὶ ἐν τῇ Ἀσίᾳ τῆς πρώτης ἡξιούτο τιμῆς. Ὑβρέα δ' ὁ πατήρ, ὥς αὐτὸς διηγείτο ἐν τῇ σχολῇ καὶ παρὰ τῶν πολιτῶν ὁμολόγητο, ἡμίονον κατέλιπε ξυλοφοροῦντα καὶ ἡμιονηγόν· διοικούμενος δ' ὑπὸ τούτων ὀλίγον χρόνον Διοτρέφους τοῦ Ἀντιοχέως ἀκροασάμενος ἐπανῆλθε καὶ τῷ ἀγορανομίῳ παρέδωκεν αὐτόν· ἐνταῦθα δὲ κυλινδηθεὶς καὶ χρηματισάμενος μικρὰ ὥρμησεν ἐπὶ τὸ πολιτεύεσθαι καὶ τοῖς ἀγοραίοις συνακολουθεῖν. ταχὺ δὲ αὐξήσιν ἔσχε καὶ ἐθαυμάσθη¹ ἔτι μὲν καὶ Εὐθυδήμου ζῶντος, ἀλλὰ τελευτήσαντος μάλιστα, κύριος γενόμενος τῆς πόλεως. ζῶν δ' ἐπεκράτει πολὺ ἐκείνος, δυνατὸς ὢν ἅμα καὶ χρήσιμος τῇ πόλει, ὥστ', εἰ καὶ τι τυραννικὸν προσῆν, τοῦτ' ἀπελύετο τῷ παρακολουθεῖν τὸ χρήσιμον. ἐπαινοῦσι γοῦν τοῦτο τοῦ Ὑβρέου, ὅπερ δημηγορῶν ἐπὶ τελευτῆς εἶπεν· Εὐθύδημε, κακὸν εἴ τῆς πόλεως ἀναγκαῖον· οὔτε γὰρ μετὰ σοῦ δυνάμεθα C 660 ζῆν οὔτ' ἄνευ σοῦ. αὐξηθεὶς οὖν ἐπὶ πολὺ καὶ δό-

¹ μάλιστα, after ἐθαυμάσθη, is ejected by Meineke.

related that Mylasa was a mere village in ancient times, but that it was the native land and royal residence of the Carians of the house of Hecatomnos. The city is nearest to the sea at Phycus; and this is their seaport.

24. Mylasa has had two notable men in my time, who were at once orators and leaders of the city, Euthydemus and Hybreas. Now Euthydemus, having inherited from his ancestors great wealth and high repute, and having added to these his own cleverness, was not only a great man in his native land, but was also thought worthy of the foremost honour in Asia. As for Hybreas, as he himself used to tell the story in his school and as confirmed by his fellow-citizens, his father left him a mule-driver and a wood-carrying mule. And, being supported by these, he became a pupil of Diotrophes of Antiocheia for a short time, and then came back and "surrendered himself to the office of market-clerk." But when he had been "tossed about" in this office and had made but little money, he began to apply himself to the affairs of state and to follow closely the speakers of the forum. He quickly grew in power, and was already an object of amazement in the lifetime of Euthydemus, but in particular after his death, having become master of the city. So long as Euthydemus lived he strongly prevailed, being at once powerful and useful to the city, so that even if there was something tyrannical about him, it was atoned for by the fact that it was attended by what was good for the city. At any rate, people applaud the following statement of Hybreas, made by him towards the end of a public speech: "Euthydemus: you are an evil necessary to the city, for we

ξας καὶ πολίτης ἀγαθὸς εἶναι καὶ ῥήτωρ ἔπταισεν ἐν τῇ πρὸς Λαβιῆνον ἀντιπολιτεία. οἱ μὲν γὰρ ἄλλοι μεθ' ὅπλων ἐπιόντι καὶ Παρθικῆς συμμάχιας, ἥδη τῶν Παρθυαίων τὴν Ἀσίαν ἐχόντων, εἶξαν, ἅτε ἄοπλοι καὶ εἰρηνικοί. Ζήνων δ' ὁ Λαοδικεὺς καὶ Ὑβρέας οὐκ εἶξαν, ἀμφοτέρω ῥήτορες, ἀλλὰ ἀπέστησαν τὰς ἑαυτῶν πόλεις· ὁ δ' Ὑβρέας καὶ προσπαρώξυνε φωνῇ τινὶ μειράκιον εὐερέθιστον καὶ ἀνοίας πλήρες. ἐκείνου γὰρ ἀνειπόντος ἑαυτὸν Παρθικὸν αὐτοκράτορα, Οὐκοῦν, ἔφη, κἀγὼ λέγω ἑμαυτὸν Καρικὸν αὐτοκράτορα. ἐκ τούτου δὲ ἐπὶ τὴν πόλιν ὥρμησε, τάγματα ἔχων ἥδη συντεταγμένα Ῥωμαίων τῶν ἐν τῇ Ἀσίᾳ· αὐτὸν μὲν οὖν οὐ κατέλαβε, παραχωρήσαντα εἰς Ῥόδον, τὴν δ' οἰκίαν αὐτοῦ διελυσμήνατο, πολυτελεῖς ἐχουσιν κατασκευάς, καὶ διήρπασεν· ὥς δ' αὐτῶς καὶ τὴν πόλιν ὅλην ἐκάκωσεν. ἐκλιπόντος δ' ἐκείνου τὴν Ἀσίαν, ἐπανῆλθε καὶ ἀνέλαβεν ἑαυτὸν τε καὶ τὴν πόλιν. περὶ μὲν οὖν Μυλάσων ταῦτα.

25. Στρατονίκη δ' ἐστὶ κατοικία Μακεδόνων· ἐκοσμήθη δὲ καὶ αὕτη κατασκευαῖς πολυτελέσιν ὑπὸ τῶν βασιλέων. ἔστι δ' ἐν τῇ χώρᾳ τῶν Στρατονικέων δύο ἱερά, ἐν μὲν Λαγίνοις τὸ τῆς Ἐκάτης ἐπιφανέστατον, πανηγύρεις μεγάλας συναγον κατ' ἐνιαυτόν· ἐγγὺς δὲ τῆς πόλεως τὸ τοῦ Χρυσαιορέως Διὸς κοινὸν ἀπάντων Καρῶν, εἰς δ' συνίασι θύσοντές τε καὶ βουλευσόμενοι περὶ τῶν

¹ The Greek word might mean "legions" rather than "cohorts."

² Of the golden sword.

can live neither with you nor without you." However, although he had grown very strong and had the repute of being both a good citizen and orator, he stumbled in his political opposition to Labienus; for while the others, since they were without arms and inclined to peace, yielded to Labienus when he was coming against them with an army and an allied Parthian force, the Parthians by that time being in possession of Asia, yet Zeno of Laodiceia and Hybreas, both orators, refused to yield and caused their own cities to revolt. Hybreas also provoked Labienus, a lad who was irritable and full of folly, by a certain pronouncement; for when Labienus proclaimed himself Parthian Emperor, Hybreas said, "Then I too call myself Carian Emperor." Consequently Labienus set out against the city with cohorts¹ of Roman soldiers in Asia that were already organised. Labienus did not seize Hybreas, however, since he had withdrawn to Rhodes, but he shamefully maltreated his home, with its costly furnishings, and plundered it. And he likewise damaged the whole of the city. But though Hybreas abandoned Asia, he came back and rehabilitated both himself and the city. So much, then, for Mylasa.

25. Stratoniceia is a settlement of Macedonians. And this too was adorned with costly improvements by the kings. There are two temples in the country of the Stratoniceians, of which the most famous, that of Hecatê, is at Lagina; and it draws great festal assemblies every year. And near the city is the temple of Zeus Chrysaoreus,² the common possession of all Carians, whither they gather both to offer sacrifice and to deliberate on their common interests.

κοινῶν· καλεῖται δὲ τὸ σύστημα αὐτῶν Χρυσασορέων, συνεστηκὸς ἐκ κωμῶν· οἱ δὲ πλείστας παρεχόμενοι κώμας προέχουσι τῇ ψήφῳ, καθάπερ Κεραμιῆται· καὶ Στρατονικεῖς δὲ τοῦ συστήματος μετέχουσιν, οὐκ ὄντες τοῦ Καρικοῦ γένους, ἀλλ' ὅτι κώμας ἔχουσι τοῦ Χρυσασορικοῦ συστήματος. κἀνταῦθα δ' ἀνὴρ ἀξιόλογος γεγένηται ῥήτωρ Μένιππος κατὰ τοὺς πατέρας ἡμῶν, Κατόκας ἐπικαλούμενος, ὃν μάλιστα ἐπαινεῖ τῶν κατὰ τὴν Ἀσίαν ῥητόρων, ὧν ἠκροάσατο, Κικέρων, ὡς φησιν ἐν τινὶ γραφῇ αὐτός, συγκρίνων Ξενοκλεῖ καὶ τοῖς κατ' ἐκεῖνον ἀκμάζουσιν. ἔστι δὲ καὶ ἄλλη Στρατονίκη, ἡ πρὸς τῷ Ταυρῷ καλουμένη, πολίχνιον προσκείμενον τῷ ὄρει.

26. Ἀλάβανδα δὲ καὶ αὕτη μὲν ὑπόκειται λόφοις δυσὶ συγκειμένοις οὕτως, ὥστ' ὄψιν παρέχεσθαι κανθήλιου κατεστρωμένου. καὶ δὴ καὶ ὁ Μαλακὸς Ἀπολλώνιος σκώπτων τὴν πόλιν εἰς τε ταῦτα καὶ εἰς τὸ τῶν σκορπίων πλῆθος, ἔφη αὐτὴν εἶναι σκορπίων κανθήλιον κατεστρωμένον.¹ μεστὴ δ' ἐστὶ καὶ αὕτη καὶ ἡ τῶν Μυλασέων πόλις τῶν θηρίων τούτων καὶ ἡ μεταξὺ πᾶσα ὀρεινὴ. τρυφητῶν δ' ἐστὶν ἀνθρώπων καὶ καπυριστῶν, ἔχουσα ψαλτρίας πολλὰς. ἄνδρες δ' ἐγένοντο λόγου ἄξιοι δύο ῥήτορες ἀδελφοὶ Ἀλαβανδεῖς, Μενεκλῆς τε, οὗ ἐμνήσθημεν μικρὸν ἐπάνω, καὶ Ἰεροκλῆς καὶ οἱ μετοικῆσαντες εἰς τὴν Ῥόδον ὃ τε Ἀπολλώνιος καὶ ὁ Μόλων.

¹ κατεστρωμένον, Casaubon, for κατεστραμμένον; so the editors in general.

¹ Cf. the votes of the Lycian cities, 14. 3. 3.

Their League, which consists of villages, is called "Chrysaorian." And those who present the most villages have a preference in the vote,¹ like, for example, the people of Ceramus. The Stratoniceians also have a share in the League, although they are not of the Carian stock, but because they have villages belonging to the Chrysaorian League. Here, too, in the time of our fathers, was born a noteworthy man, Menippus, surnamed Catocas, whom Cicero, as he says in one of his writings,² applauded above all the Asiatic orators he had heard, comparing him with Xenocles and with the other orators who flourished in the latter's time. But there is also another Stratoniceia, "Stratoniceia near the Taurus," as it is called; it is a small town situated near the mountain.

26. Alabanda is also situated at the foot of hills, two hills that are joined together in such a way that they present the appearance of an ass laden with panniers. And indeed Apollonius Malacus, in ridiculing the city both in regard to this and in regard to the large number of scorpions there, said that it was an "ass laden with panniers of scorpions." Both this city and Mylasa are full of these creatures, and so is the whole of the mountainous country between them. Alabanda is a city of people who live in luxury and debauchery, containing many girls who play the harp. Alabandians worthy of mention are two orators, brothers, I mean Menecles, whom I mentioned a little above,³ and Hierocles, and also Apollonius and Molon,⁴ who changed their abode to Rhodes.

¹ *Brutus* 91 (315).

² § 13.

⁴ See § 13.

27. Πολλῶν δὲ λόγων εἰρημένων περὶ Καρῶν, ὁ μάλισθ' ὁμολογούμενός ἐστιν οὗτος, ὅτι οἱ Κᾶρες ὑπὸ Μίνω ἐτάττοντο, τότε Λέλεγες καλούμενοι, καὶ τὰς νήσους ὥκου· εἴτ' ἠπειρῶται γενόμενοι, πολλὴν τῆς παραλίας καὶ τῆς μεσογαίας κατέσχον, τοὺς προκατέχοντας ἀφελόμενοι· καὶ οὗτοι δ' ἦσαν οἱ πλείους Λέλεγες καὶ Πελασγοί· πάλιν δὲ τούτους ἀφείλοντο μέρος οἱ Ἕλληνες, Ἰωνές τε καὶ Δωριεῖς. τοῦ δὲ περὶ τὰ στρατιωτικὰ ζήλου τά τε ὄχανα ποιοῦνται τεκμήρια καὶ τὰ ἐπίσημα καὶ τοὺς λόφους· ἅπαντα γὰρ λέγεται Καρικὰ· Ἀνακρέων μὲν γε φησὶν·

δία δηῦτε Καρικευργέος
ὄχάνοιο χεῖρα τιθέμεναι.

ὁ δ' Ἀλκαῖος,

λόφον τε σείων Καρικόν.

28. Τοῦ ποιητοῦ δ' εἰρηκότος οὕτωςί·

Μάσθλης¹ αὖ Καρῶν ἠγήσατο βαρβαροφώνων,
οὐκ ἔχει λόγον, πῶς τοσαῦτα εἰδὼς ἔθνη βάρβαρα
μόνους εἴρηκε βαρβαροφώνους τοὺς Κᾶρας, βαρ-
βάρους δ' οὐδένας. οὐτ' οὖν Θουκυδίδης ὀρθῶς·
οὐδὲ γὰρ λέγεσθαι φησι βαρβάρους διὰ τὸ μηδὲ
Ἕλληνάς πω ἀντίπαλον εἰς ἓν ὄνομα ἀποκεκρίσ-
θαι· τό τε γὰρ μηδὲ Ἕλληνάς πω ψεῦδος αὐτὸς
ὁ ποιητὴς ἀπελέγχει·

ἀνδρός, τοῦ κλέος εὐρὺ καθ' Ἑλλάδα καὶ μέσον
Ἄργος.

¹ Μάσθλης, Corais emends to Νάστης.

27. Of the numerous accounts of the Carians, the one that is generally agreed upon is this, that the Carians were subject to the rule of Minos, being called Leleges at that time, and lived in the islands; then, having migrated to the mainland, they took possession of much of the coast and of the interior, taking it away from its previous possessors, who for the most part were Leleges and Pelasgians. In turn these were deprived of a part of their country by the Greeks, I mean Ionians and Dorians. As evidences of their zeal for military affairs, writers adduce shield-holders, shield-emblems, and crests, for all these are called "Carian." At least Anacreon says, "Come, put thine arm through the shield-holder, work of the Carians." And Alcaeus¹ says, "shaking the Carian crest."

28. When the poet says, "Masthles² in turn led the Carians, of barbarian speech,"³ we have no reason to inquire how it is that, although he knew so many barbarian tribes, he speaks of the Carians alone as "of barbarian speech," but nowhere speaks of "barbarians." Thucydides,⁴ therefore, is not correct, for he says that Homer "did not use the term 'barbarians' either, because the Hellenes on their part had not yet been distinguished under one name as opposed to them"; for the poet himself refutes the statement that the Hellenes had not yet been so distinguished when he says, "My husband, whose fame is wide through Hellas and

¹ *Frag.* 22 (Bergk).

² An error, apparently, for "Nastes."

³ *Iliad* 2. 867 (note "Mesthles" in line 864).

⁴ 1. 3.

καὶ πάλιν·

· εἴτ' ἐθέλεις τραφῆναι¹ ἀν' Ἑλλάδα καὶ μέσον
Ἄργος.

μὴ λεγομένων τε βαρβάρων, πῶς ἔμελλεν εὖ
λεχθήσεσθαι τὸ βαρβαροφώνων; οὔτε δὴ οὗτος
εὖ, οὔτ' Ἀπολλόδωρος ὁ γραμματικός, ὅτι τῷ
κοινῷ ὀνόματι ἰδίως καὶ λοιδόρως ἐχρῶντο οἱ
Ἕλληνες κατὰ τῶν Καρῶν, καὶ μάλιστα οἱ
Ἴωνες, μισοῦντες αὐτοὺς διὰ τὴν ἔχθραν καὶ τὰς
συνεχεῖς στρατείας· ἐχρῆν γὰρ οὕτως βαρβάρους
ὀνομάζειν. ἡμεῖς δὲ ζητοῦμεν, διὰ τί βαρβαρο-
φώνους καλεῖ, βαρβάρους δ' οὐδ' ἄπαξ. ὅτι,
φησί, τὸ πληθυντικὸν εἰς τὸ μέτρον οὐκ ἐμπίπτει,
διὰ τοῦτ' οὐκ εἶρηκε βαρβάρους. ἀλλ' αὕτη μὲν
ἡ πτωσις οὐκ ἐμπίπτει, ἡ δ' ὀρθὴ οὐ διαφέρει τῆς

C 662 Δάρδανοι·

Τρῶες καὶ Λύκιοι καὶ Δάρδανοι.

τοιούτων δὲ καὶ τὸ

οἱοὶ Τρώιοι Ἴπποιοι.

οὐδέ γε ὅτι τραχυτάτη ἡ γλῶττα τῶν Καρῶν· οὐ
γάρ ἐστιν, ἀλλὰ καὶ πλεῖστα Ἑλληνικὰ ὀνόματα
ἔχει καταμεμιγμένα, ὥς φησι Φίλιππος ὁ τὰ
Καρικὰ γράψας. οἶμαι δέ, τὸ βάρβαρον κατ'
ἀρχὰς ἐκπεφωνῆσθαι οὕτως κατ' ὀνοματοποιίαν
ἐπὶ τῶν δυσεκφόρως καὶ σκληρῶς καὶ τραχέως
λαλούντων, ὥς τὸ βατταρίζειν καὶ τραυλίζειν καὶ
ψελλίζειν· εὐφνέστατοι γὰρ ἐσμεν τὰς φωνὰς

¹ τραφῆναι, Corais, for τερφῆναι CDFHs, τερφῆναι other MSS.

¹ i.e. throughout the whole of Greece.

mid-Argos."¹ And again, "And if thou dost wish to journey through Hellas and mid-Argos." Further, if they were not called "barbarians," how could they properly be called a people "of barbarian speech"? So neither Thucydides is correct, nor Apollodorus the grammarian, who says that the general term was used by the Hellenes in a peculiar and abusive sense against the Carians, and in particular by the Ionians, who hated them because of their enmity and the continuous military campaigns; for it was right to name them barbarians in this sense. But I raise the question, Why does he call them people "of barbarian speech," but not even once calls them barbarians? "Because," Apollodorus replies, "the plural does not fall in with the metre; this is why he does not call them barbarians." But though this case² does not fall in with metre, the nominative case³ does not differ metrically from that of "Dardanians":⁴ "Trojans and Lycians and Dardanians."⁵ So, also, the word "Trojan," in "of what kind the Trojan horses are."⁶ Neither is he correct when he says that the language of the Carians is very harsh, for it is not, but even has very many Greek words mixed up with it, according to the Philip who wrote *The Carica*.⁷ I suppose that the word "barbarian" was at first uttered onomatopoeically in reference to people who enunciated words only with difficulty and talked harshly and raucously, like our words "battarizein," "traulizein," and "psellizein";⁸ for we are by nature

¹ The genitive (βαρβαρίων).

² βαρβαροι.

³ Δάρδανοι.

⁴ *Iliad* 11. 286.

⁵ *Iliad* 5. 222.

⁶ *The History of Caria*.

⁷ Meaning respectively, "stutter," "lisp," and "speak falteringly."

ταῖς ὁμοίαις φωναῖς κατονομάζειν διὰ τὸ ὁμογενές· ἢ δὴ¹ καὶ πλεονάζουσι² ἐνταῦθα αἱ ὀνοματοποιαί, οἷον τὸ κελαρύζειν καὶ κλαγγή δὲ καὶ ψόφος καὶ βοή καὶ κρότος, ὧν τὰ πλεῖστα ἤδη καὶ κυρίως ἐκφέρεται· πάντων δὲ τῶν παχυστομόντων οὕτως βαρβάρων λεγομένων, ἐφάνη τὰ τῶν ἁλλοεθνῶν στόματα τοιαῦτα, λέγω δὲ τὰ τῶν μὴ Ἑλλήνων. ἐκείνους οὖν ἰδίως ἐκάλεσαν³ βαρβάρους, ἐν ἀρχαῖς μὲν κατὰ τὸ λοιδορον, ὡς ἂν παχυστόμους ἢ τραχυστόμους, εἶτα κατεχρησάμεθα ὡς ἐθνικῶ κοινῶ ὀνόματι, ἀντιδιαιροῦντες πρὸς τοὺς Ἕλληνας. καὶ γὰρ δὴ τῇ πολλῇ συνηθείᾳ καὶ ἐπιπλοκῇ⁴ τῶν βαρβάρων οὐκέτι ἐφαίνεται κατὰ παχυστομίαν καὶ ἀφυΐαν τινὰ τῶν φωνητηρίων ὀργάνων τοῦτο συμβαῖνον, ἀλλὰ κατὰ τὰς τῶν διαλέκτων ἰδιότητας. ἄλλη δέ τις ἐν τῇ ἡμετέρᾳ διαλέκτῳ ἀνεφάνη κακοστομία καὶ οἷον βαρβαροστομία, εἴ τις ἑλληνίζων μὴ κατορθοίη, ἀλλ' οὕτω λέγοι τὰ ὀνόματα, ὡς οἱ βάρβαροι οἱ εἰσαγόμενοι εἰς τὸν ἑλληνισμόν, οὐκ ἰσχύοντες ἀρτιστομεῖν, ὡς οὐδ' ἡμεῖς ἐν ταῖς ἐκείνων διαλέκτοις. τοῦτο δὲ μάλιστα συνέβη τοῖς Καρσί· τῶν γὰρ ἄλλων οὐτ' ἐπιπλεκομένων πω⁵ σφόδρα τοῖς Ἕλλησιν, οὐδ' ἐπιχειρούντων Ἑλληνικῶς ζῆν ἢ μανθάνειν τὴν ἡμετέραν διάλεκτον, πλὴν εἴ τινες

¹ ἢ δὴ, Corais, for ἤδη; so the later editors.

² μὲν, after πλεονάζουσι, Corais and Meineke omit.

³ ἐκάλεσαν, Xylander, for ἐκάλεσε; so the later editors.

⁴ τῇ πολλῇ συνηθείᾳ καὶ ἐπιπλοκῇ F, ἢ πολλῇ συνηθείᾳ καὶ ἐπιπλοκῇ other MSS.; so the editors.

⁵ πω (omitted by F), Corais and Meineke, for πωσ.

very much inclined to denote sounds by words that sound like them, on account of their homogeneity. Wherefore onomatopoetic words abound in our language, as, for example, "celaryzein," and also "clangê," "psophos," "boê," and "crotos,"¹ most of which are by now used in their proper sense. Accordingly, when all who pronounced words thickly were being called barbarians onomatopoetically, it appeared that the pronunciations of all alien races were likewise thick, I mean of those that were not Greek. Those, therefore, they called barbarians in the special sense of the term, at first derisively, meaning that they pronounced words thickly or harshly; and then we misused the word as a general ethnic term, thus making a logical distinction between the Greeks and all other races. The fact is, however, that through our long acquaintance and intercourse with the barbarians this effect was at last seen to be the result, not of a thick pronunciation or any natural defect in the vocal organs, but of the peculiarities of their several languages. And there appeared another faulty and barbarian-like pronunciation in our language, whenever any person speaking Greek did not pronounce it correctly, but pronounced the words like barbarians who are only beginning to learn Greek and are unable to speak it accurately, as is also the case with us in speaking their languages. This was particularly the case with the Carians, for, although the other peoples were not yet having very much intercourse with the Greeks nor even trying to live in Greek fashion or to learn our language—with the exception, perhaps, of rare

¹ Meaning respectively, "gurgle," "clang," "empty sound," "outcry," and "rattling noise."

σπάνιοι καὶ κατὰ τύχην ἐπεμίχθησαν καὶ κατ' ἄνδρα ὀλίγοις¹ τῶν Ἑλλήνων τισίν, οὗτοι δὲ καθ' ὅλην ἐπλανήθησαν τὴν Ἑλλάδα, μισθοῦ στρατεύοντες. ἤδη οὖν τὸ βαρβαρόφωνον ἐπ' ἐκείνων πυκνὸν ἦν, ἀπὸ τῆς εἰς τὴν Ἑλλάδα αὐτῶν στρατείας· καὶ μετὰ ταῦτα ἐπεπόλασε πολὺ μᾶλλον, ἀφ' οὗ τὰς τε νήσους μετὰ τῶν Ἑλλήνων ὤκησαν, κακείθεν εἰς τὴν Ἀσίαν ἐκπεσόντες, οὐδ' ἐνταῦθα χωρὶς Ἑλλήνων οἰκεῖν ἠδύ-
 C 663 ναντο, ἐπιδιαβάντων τῶν Ἰώνων καὶ τῶν Δωριέων. ἀπὸ δὲ τῆς αὐτῆς αἰτίας καὶ τὸ βαρβαρίζειν λέγεται· καὶ γὰρ τοῦτο ἐπὶ τῶν κακῶς ἐλληνιζόντων εἰώθαμεν λέγειν, οὐκ ἐπὶ τῶν καριστὶ λαλούντων. οὕτως οὖν καὶ τὸ βαρβαροφωνεῖν καὶ τοὺς βαρβαροφώνους δεκτέον τοὺς κακῶς ἐλληνίζοντας· ἀπὸ δὲ τοῦ καρίζειν καὶ τὸ βαρβαρίζειν μετήνεγκαν εἰς τὰς περὶ ἐλληνισμοῦ τέχνας καὶ τὸ σολοικίζειν, εἴτ' ἀπὸ Σόλων, εἴτ' ἄλλως τοῦ ὀνόματος τούτου πεπλασμένου.

29. Φησὶ δὲ Ἀρτεμίδωρος ἀπὸ Φύσκου τῆς Ῥοδίων περαίας ἰοῦσιν εἰς Ἐφεσον μέχρι μὲν Λαγίνων ὀκτακοσίους εἶναι καὶ πεντήκοντα σταδίου, ἐντεῦθεν δ' εἰς Ἀλάβανδα πεντήκοντα ἄλλους καὶ διακοσίους, εἰς δὲ Τράλλεις ἑκατὸν ἐξήκοντα· ἀλλ' ἢ εἰς Τράλλεις ἐστὶ διαβάντι τὸν Μαίανδρον κατὰ μέσσην πρὸς τὴν ὁδόν, ὅπου τῆς Καρίας οἱ ὄροι γίνονται δ' οἱ πάντες ἀπὸ Φύσκου

¹ ὀλίγοις, Kramer, for ὀλίγοι; so Meineke.

¹ The city in Cilicia, if not that in Cyprus.

² Strabo means that grammarians used the word in its original, or unrestricted sense, i.e. as applying to speech

persons who by chance, and singly, mingled with a few of the Greeks—yet the Carians roamed throughout the whole of Greece, serving on expeditions for pay. Already, therefore, the barbarous element in their Greek was strong, as a result of their expeditions in Greece; and after this it spread much more, from the time they took up their abode with the Greeks in the islands; and when they were driven thence into Asia, even here they were unable to live apart from the Greeks, I mean when the Ionians and Dorians later crossed over to Asia. The term "barbarise," also, has the same origin; for we are wont to use this too in reference to those who speak Greek badly, not to those who talk Carian. So, therefore, we must interpret the terms "speak barbarously" and "barbarously-speaking" as applying to those who speak Greek badly. And it was from the term "Carise" that the term "barbarise" was used in a different sense in works on the art of speaking Greek; and so was the term "soloecise," whether derived from Soli,¹ or made up in some other way.²

29. Artemidorus says that, as one goes from Physcus, in the Peraea of the Rhodians, to Ephesus, the distance to Lagina is eight hundred and fifty stadia; and thence to Alabanda, two hundred and fifty more; and to Tralleis, one hundred and sixty. But one comes to the road that leads into Tralleis after crossing the Maeander River, at about the middle of the journey,³ where are the boundaries of Caria. The distance all told from Physcus to

only. In the meantime it had been used in a broad sense, "to behave like, or imitate, barbarians."

³ Between Alabanda and Tralleis.

ἐπὶ τὸν Μαίανδρον κατὰ τὴν εἰς Ἐφεσον ὁδὸν
 χίλιοι ἑκατὸν ὀγδοήκοντα. πάλιν ἀπὸ τοῦ Μαίαν-
 δρου τῆς Ἰωνίας ἐφεξῆς μῆκος ἐπιόντι κατὰ τὴν
 αὐτὴν ὁδὸν ἀπὸ μὲν τοῦ ποταμοῦ εἰς Τράλλεις,
 ὀγδοήκοντα, εἴτ' εἰς Μαγνησίαν ἑκατὸν τετταρά-
 κοντα, εἰς Ἐφεσον δ' ἑκατὸν εἴκοσιν, εἰς δὲ Σμύρναν
 τριακόσιοι εἴκοσιν, εἰς δὲ Φώκαιαν καὶ τοὺς ὅρους
 τῆς Ἰωνίας ἐλάττους τῶν διακοσίων· ὥστε τὸ ἐπ'
 εὐθείας μῆκος τῆς Ἰωνίας εἴη ἂν κατ' αὐτὸν¹
 μικρῷ πλέον τῶν ὀκτακοσίων. ἐπεὶ δὲ κοινὴ
 τις ὁδὸς τέτριπται ἅπασι τοῖς ἐπὶ τὰς ἀνατολὰς
 ὁδοιποροῦσιν ἐξ Ἐφέσου, καὶ ταύτην ἔπεισιν.²
 ἐπὶ μὲν τὰ Κάρουρα τῆς Καρίας ὅριον πρὸς τὴν
 Φρυγίαν διὰ Μαγνησίας καὶ Τραλλέων, Νύσης,
 Ἀντιοχείας ὁδὸς ἐπτακοσίων καὶ τετταράκοντα
 σταδίων· ἐντεῦθεν δὲ ἡ Φρυγία διὰ Λαοδικείας
 καὶ Ἀπαμείας καὶ Μητροπόλεως καὶ Χελιδονίων·
 ἐπὶ μὲν οὖν τὴν ἀρχὴν τῆς Παρωρείου, τοὺς
 Ὀλμους, στάδιοι περὶ ἐννακοσίους καὶ εἴκοσιν
 ἐκ τῶν Καρούρων· ἐπὶ δὲ τὸ πρὸς τῇ Λυκαονίᾳ
 πέρας τῆς Παρωρείου τὸ Τυριαῖον διὰ Φιλομη-
 λίου μικρῷ πλείους τῶν πεντακοσίων. εἰθ' ἡ
 Λυκαονία μέχρι Κοροπασσοῦ διὰ Λαοδικείας τῆς
 κατακεκαυμένης ὀκτακόσιοι τετταράκοντα· ἐκ δὲ
 Κοροπασσοῦ τῆς Λυκαονίας εἰς Γαρσαύουρα, πο-
 λίχνιον τῆς Καππαδοκίας, ἐπὶ τῶν ὄρων αὐτῆς
 ἰδρυμένον, ἑκατὸν εἴκοσιν· ἐντεῦθεν δ' εἰς Μάζακα
 τὴν μητρόπολιν τῶν Καππαδόκων διὰ Σοάνδου

¹ κατ' αὐτόν, Corais, for κατὰ ταῦτ' ἢ mss, κατ' αὐτὸ ἢ other MSS. ; so the later editors.

² ταύτην ἔπεισιν, Corais, for ταύτη μὲν ἔπεισιν ; so the later editors.

the Maeander along the road to Ephesus amounts to one thousand one hundred and eighty stadia. Again, from the Maeander, traversing next in order the length of Ionia along the same road, the distance from the river to Tralleis is eighty stadia; then to Magnesia, one hundred and forty; to Ephesus, one hundred and twenty; to Smyrna, three hundred and twenty; and to Phocaea and the boundaries of Ionia, less than two hundred; so that the length of Ionia in a straight line would be, according to Artemidorus, slightly more than eight hundred stadia. Since there is a kind of common road constantly used by all who travel from Ephesus towards the east, Artemidorus traverses this too: from Ephesus to Carura, a boundary of Caria towards Phrygia, through Magnesia, Tralleis, Nysa, and Antiocheia, is a journey of seven hundred and forty stadia; and, from Carura, the journey in Phrygia, through Laodiceia, Apameia, Metropolis and Chelidonia.¹ Now near the beginning of Paroreius,² one comes to Holmi, about nine hundred and twenty stadia from Carura, and, near the end of Paroreius near Lycaonia, through Philomelium, to Tyriaeum, slightly more than five hundred. Then Lycaonia, through Laodiceia Catacecaumenê,³ as far as Coropassus, eight hundred and forty stadia; from Coropassus in Lycaonia to Garsaura, a small town in Cappadocia, situated on its borders, one hundred and twenty; thence to Mazaca, the metropolis of the Cappadocians, through Soandum

¹ "Chelidonia" is thought to be corrupt (see C. Müller, *Ind. Var. Lect.*, p. 1030).

² i.e. Phrygia "alongside the mountain."

³ "Burnt."

καὶ Σαδακόρων ἑξακόσιοι ὀγδοήκοντα· ἐντεῦθεν δ' ἐπὶ τὸν Εὐφράτην μέχρι Τομίσων¹ χωρίου τῆς Σωφηνῆς διὰ Ἑρφῶν πολίχνης χίλιοι τετρακόσιοι τετταράκοντα. τὰ δ' ἐπ' εὐθείας τούτοις μέχρι τῆς Ἰνδικῆς τὰ αὐτὰ κεῖται καὶ παρὰ τῷ Ἀρτεμιδώρῳ, ἅπερ καὶ παρὰ τῷ Ἑρατοσθένει. λέγει δὲ καὶ Πολύβιος, περὶ τῶν ἐκεῖ μάλιστα δεῖν C 664 πιστεύειν ἐκείνῳ. ἄρχεται δὲ ἀπὸ Σαμοσάτων τῆς Κομμαγηνῆς, ἥ πρὸς τῇ διαβάσει καὶ τῷ Ζεύγματι κεῖται· εἰς δὲ Σαμόσατα ἀπὸ τῶν ὄρων τῆς Καππαδοκίας τῶν περὶ Τόμισα ὑπερθέντι τὸν Ταῦρον σταδίους εἶρηκε τετρακοσίους καὶ πεντήκοντα.

III

1. Μετὰ δὲ τὴν Ῥοδίων περαίαν, ἥς ὄριον τὰ Δαίδαλα, ἐφεξῆς πλέουσι πρὸς ἀνίσχοντα ἥλιον ἢ Λυκία κεῖται μέχρι Παμφυλίας, εἰθ' ἢ Παμφυλία μέχρι Κιλικίων τῶν τραχέων, εἰθ' ἢ τούτων μέχρι τῶν ἄλλων Κιλικίων τῶν περὶ τὸν Ἰστικὸν κόλπον· ταῦτα δ' ἐστὶ μέρη μὲν τῆς χερρονήσου, ἥς τὸν Ἰσθμὸν ἔφαμεν τὴν ἀπὸ Ἰσσοῦ ὁδὸν μέχρι Ἀμισοῦ, ἢ Σινώπης, ὥς τινες, ἐκτὸς δὲ τοῦ Ταύρου ἐν στενῇ παραλίᾳ τῇ ἀπὸ Λυκίας μέχρι τῶν περὶ Σόλους τόπων, τὴν νῦν Πομπηϊόπολιν.² ἔπειτα ἤδη εἰς πεδία ἀναπέπταται ἢ κατὰ τὸν Ἰστικὸν κόλπον παραλία ἀπὸ Σόλων καὶ Ταρσοῦ ἀρξάμενη. ταύτην οὖν ἐπελθούσιν ὁ πᾶς περὶ τῆς

¹ Τομίσων, the editors, for τὸ μισοῦ CD, Τελμισοῦ α, Τομισοῦ other MSS.

² τὴν νῦν Πομπηϊόπολιν, Corais, for τῇ νῦν Πομπηϊουπόλει; so the later editors.

and Sadacora, six hundred and eighty; and thence to the Euphrates River, as far as Tomisa, a place in Sophenê, through Herphae, a small town, one thousand four hundred and forty. The places on a straight line with these as far as India are the same in Artemidorus as they are in Eratosthenes. But Polybius says that we should rely most on Artemidorus in regard to the places here. He begins with Samosata in Commagenê, which lies at the river-crossing and at Zeugma, and states that the distance to Samosata, across the Taurus, from the boundaries of Cappadocia round Tomisa is four hundred and fifty stadia.

III

1.¹ AFTER the Peræa of the Rhodians, of which Daedala is a boundary, sailing next in order towards the rising sun, one comes to Lycia, which extends as far as Pamphylia; then to Pamphylia, extending as far as the Tracheian Cilicians;² and then to the country of these, extending as far as the other Cilicians living round the Gulf of Issus. These are parts of the peninsula, the isthmus of which, as I was saying, is the road from Issus to Amisus, or, according to some, Sinopê, but they lie outside the Taurus on the narrow coast which extends from Lycia as far as the region of Soli, the present Pompeiopolis. Then forthwith the coast that lies on the Issic Gulf, beginning at Soli and Tarsus, spreads out into plains. So then, when I have traversed this coast, my account of the whole

¹ See map of Asia Minor at end of Vol. V.

² Referring to "Cilicia Tracheia" ("Rugged Cilicia").

χερρονήσου λόγος ἔσται περιωδευμένος· εἴτα μεταβησόμεθα ἐπὶ τὰ ἄλλα μέρη τῆς Ἀσίας τὰ ἐκτὸς τοῦ Ταύρου. τελευταία δ' ἐκθήσομεν τὰ περὶ τὴν Λιβύην.

2. Μετὰ τοίνυν Δαίδαλα τὰ τῶν Ῥοδίων ὄρος ἐστὶ τῆς Λυκίας ὁμώνυμον αὐτοῖς Δαίδαλα, ἀφ' οὗ λαμβάνει τὴν ἀρχὴν ὁ παράπλους ἅπας ὁ Λυκιακός, σταδίων μὲν ὧν χιλίων ἑπτακοσίων εἴκοσι, τραχὺς δὲ καὶ χαλεπός, ἀλλ' εὐλίμενος σφόδρα καὶ ὑπὸ ἀνθρώπων συνοικούμενος σωφρόνων· ἐπεὶ ἢ γε τῆς χώρας φύσις παραπλησία καὶ τοῖς Παμφύλοις ἐστὶ καὶ τοῖς Τραχειώταις Κίλιξιν· ἀλλ' ἐκεῖνοι μὲν ὀρμητηρίοις ἐχρήσαντο τοῖς τόποις πρὸς τὰ ληστήρια, αὐτοὶ πειρατεύοντες ἢ τοῖς πειραταῖς λαφυροπώλια καὶ ναύσταθμα παρέχοντες· ἐν Σίδῃ γοῦν πόλει τῆς Παμφυλίας τὰ ναυπήγια συνίστατο τοῖς Κίλιξιν, ὑπὸ κήρυκά τε ἐπώλουν ἐκεῖ τοὺς ἀλόντας ἐλευθέρους ὁμολογοῦντες· Λύκιοι δ' οὕτω πολιτικῶς καὶ σωφρόνως ζῶντες διετέλεσαν, ὥστ', ἐκείνων διὰ τὰς εὐτυχίας θαλαττοκρατησάντων μέχρι τῆς Ἰταλίας, ὅμως ὑπ' οὐδενὸς ἐξήρθησαν αἰσχροῦ κέρδους, ἀλλ' ἔμειναν ἐν τῇ πατρίφ διοικησεὶ τοῦ Λυκιακοῦ συστήματος.

3. Εἰσὶ δὲ τρεῖς καὶ εἴκοσι πόλεις αἱ τῆς ψήφου μετέχουσai· συνέρχονται δὲ ἐξ ἐκάστης πόλεως εἰς κοινὸν συνέδριον, ἣν ἂν δοκιμάσωσι πόλιν ἐλόμενοι· τῶν δὲ πόλεων αἱ μέγισται μὲν τριῶν ψήφων ἐστὶν ἐκάστη κυρία, αἱ δὲ μέσαι C 665 δυεῖν, αἱ δ' ἄλλαι μιᾶς· ἀνὰ λόγον δὲ καὶ τὰς εἰσφοράς εἰσφέρουσι καὶ τὰς ἄλλας λειτουργίας.

peninsula will have been completed. Then I shall pass to the other parts of Asia that are outside the Taurus. And lastly I shall set forth my account of Libya.

2. After Daedala of the Rhodians, then, one comes to a mountain in Lycia which bears the same name as the city, Daedala, whence the whole voyage along the Lycian coast takes its beginning; this coast extends one thousand seven hundred and twenty stadia, and is rugged and hard to travel, but is exceedingly well supplied with harbours and inhabited by decent people. Indeed, the nature of the country, at least, is similar to both that of the Pamphylians and the Tracheian Cilicians, but the former used their places as bases of operation for the business of piracy, when they engaged in piracy themselves or offered them to pirates as markets for the sale of booty and as naval stations. In Sidê, at any rate, a city in Pamphylia, the dockyards stood open to the Cilicians, who would sell their captives at auction there, though admitting that these were freemen. But the Lycians continued living in such a civilised and decent way that, although the Pamphylians through their successes gained the mastery of the sea as far as Italy, still they themselves were stirred by no desire for shameful gain, but remained within the ancestral domain of the Lycian League.

3. There are twenty-three cities that share in the vote. They come together from each city to a general congress, after choosing whatever city they approve of. The largest of the cities control three votes each, the medium-sized two, and the rest one. In the same proportion, also, they make

ἔξ δὲ τὰς μεγίστας ἔφη ὁ Ἀρτεμίδωρος, Ξάνθον, Πάταρα, Πίναρα, Ὀλυμπον, Μύρα, Τλῶν, κατὰ τὴν ὑπέρθεσιν¹ τὴν εἰς Κίβυραν κειμένην. ἐν δὲ τῷ συνεδρίῳ πρῶτον μὲν Λυκιάρχης αἰρεῖται, εἰτ' ἄλλαι ἀρχαὶ αἱ τοῦ συστήματος· δικαστήριά τε ἀποδείκνυται κοινῇ· καὶ περὶ πολέμου δὲ καὶ εἰρήνης καὶ συμμαχίας ἐβουλευόντο πρότερον, νῦν δ' οὐκ εἰκός, ἀλλ' ἐπὶ τοῖς Ῥωμαίοις ταύτ' ἀνάγκη κεῖσθαι, πλὴν εἰ ἐκείνων ἐπιτρεψάντων, ἢ ὑπὲρ αὐτῶν εἴη χρήσιμον· ὁμοίως δὲ καὶ δικασταὶ καὶ ἄρχοντες ἀνὰ λόγον ταῖς ψήφοις ἐξ ἐκάστης προχειρίζονται πόλεως. οὕτω δ' εὐνομούμενοις αὐτοῖς συνέβη παρὰ Ῥωμαίοις ἐλευθέροις διατελέσαι, τὰ πάτρια νέμουνσι, τοὺς δὲ ληστὰς ἐπιδεῖν ἄρδην ἠφανισμένους, πρότερον μὲν ὑπὸ Σερουιλίου τοῦ Ἰσαυρικοῦ, καθ' ὃν χρόνον καὶ τὰ Ἰσαυρα ἐκεῖνος καθεῖλεν, ὕστερον δὲ Πομπηίου τοῦ Μάγνου, πλείω τῶν χιλίων καὶ τριακοσίων σκαφῶν ἐμπρήσαντος, τὰς δὲ κατοικίας ἐκκόψαντος, τῶν δὲ περιγενομένων ἀνθρώπων ἐν ταῖς μάχαις τοὺς μὲν καταγαγόντος εἰς Σόλους, ἦν ἐκεῖνος Πομπηιοῦπολιν² ὠνόμασε, τοὺς δ' εἰς Δύμην³ λειπανδρήσασαν, ἦν νυνὶ Ῥωμαίων ἀποικία νέμεται. οἱ ποιηταὶ δέ, μάλιστα οἱ τραγικοί, συγχέοντες τὰ ἔθνη, καθάπερ τοὺς Τρῶας καὶ τοὺς Μυσοὺς καὶ τοὺς Λυδοὺς Φρύγας προσαγορεύουσιν, οὕτω καὶ τοὺς Λυκίους Κᾶρας.

4. Μετὰ δ' οὖν τὰ Δαίδαλα, τὸ τῶν Λυκίων

¹ ὑπέρθεσιν, Corais, for θέσιν; so the later editors.

² Πομπηιοῦπολιν *mozze*.

³ Δύμην, Casaubon, for Δυμήνην *ODFhio*, Δυσμένην *i*, Διδυμήνην *mozze*; so the later editors.

contributions and discharge other liturgies.¹ Artemidorus said that the six largest were Xanthus, Patara, Pinara, Olympus, Myra, and Tlos, the last-named being situated near the pass that leads over into Cibyra. At the congress they first choose a "Lyciarch," and then other officials of the League; and general courts of justice are designated. In earlier times they would deliberate about war and peace and alliances, but now they naturally do not do so, since these matters necessarily lie in the power of the Romans, except, perhaps, when the Romans should give them permission or it should be for their benefit. Likewise, judges and magistrates are elected from the several cities in the same proportion. And since they lived under such a good government, they remained ever free under the Romans, thus retaining their ancestral usages; and they saw the pirates utterly wiped out, first by Servilius Isauricus, at the time that he demolished Isaura, and later by Pompey the Great, when he set fire to more than thirteen hundred boats and laid waste their settlements. Of the pirates who survived the fights,² he brought some down to Soli, which he named Pompeiopolis, and the others to Dymê, where there was a dearth of population; it is now occupied by a colony of Romans. The poets, however, and especially the tragic poets, confuse the tribes, as, for example, the Trojans and the Mysians and the Lydians, whom they call Phrygians; and likewise the Lycians, whom they call Carians.

4. After Daedala, then, I mean the mountain in

¹ i.e. public services performed at private expense.

² See 8. 7. 5.

ὄρος, πλησίον ἐστὶ Τελμησσός, πολίχνη Λυκίων, καὶ Τελμησσίς ἄκρα, λιμένα ἔχουσα. ἔλαβε δὲ τὸ χωρίον τοῦτο παρὰ Ῥωμαίων Εὐμένης ἐν τῷ Ἀντιοχικῷ πολέμῳ, καταλυθείσης δὲ τῆς βασιλείας ἀπέλαβον πάλιν οἱ Λύκιοι.

5. Εἰθ' ἐξῆς ὁ Ἀντίκραγος, ὄρθιον ὄρος, ἐφ' ᾧ Καρμυλησσός, χωρίον ἐν φάραγγι ᾠκημένον,¹ καὶ μετὰ τοῦτον ὁ Κράγος, ἔχων ἄκρας² ὀκτώ³ καὶ πόλιν ὁμώνυμον. περὶ ταῦτα μυθεύεται τὰ ὄρη τὰ περὶ τῆς Χιμαίρας· ἔστι δ' οὐκ ἄπωθεν καὶ ἡ Χίμαιρα, φάραγξ τις ἀπὸ τοῦ αἰγιαλοῦ ἀνατείνουσα. ὑπόκειται δὲ τῷ Κράγῳ Πίναρα ἐν μεσογαίᾳ, τῶν μεγίστων οὔσα πόλεων ἐν τῇ Λυκίᾳ. ἐνταῦθα δὲ Πάνδαρος τιμᾶται, τυχὸν ἴσως ὁμώνυμος τῷ Τρωικῷ· ὥς καὶ

Πανδαρέου κούρη χλωρῆς ἀηδών.⁴

καὶ γὰρ τοῦτον ἐκ Λυκίας φασίν.

6. Εἰθ' ὁ Ξάνθος ποταμός, ὃν Σίρβιν ἐκάλουν οἱ πρότερον.⁵ ἀναπλεύσαντι δ' ὑπηρετικοῖς δέκα σταδίοις τὸ Λητῶν ἐστίν· ὑπὲρ δὲ τοῦ ἱεροῦ C 666 προσελθόντι ἐξήκοντα ἡ πόλις ἡ τῶν Ξανθίων ἐστί, μεγίστη τῶν ἐν Λυκίᾳ. μετὰ δὲ τὸν Ξάνθον Πάταρα, καὶ αὕτη μεγάλη πόλις, λιμένα ἔχουσα καὶ ἱερὸν Ἀπόλλωνος,⁶ κτίσμα Πατάρου. Πτολεμαῖος δ' ὁ Φιλάδελφος ἐπισκευάσας Ἀρσινόην ἐκάλεσε τὴν ἐν Λυκίᾳ, ἐπεκράτησε δὲ τὸ ἐξ ἀρχῆς ὄνομα.

¹ ἐν φάραγγι ᾠκημένον E, ἐν φαράγγειον κείμενον F, ἐν φαράγγει κείμενον other MSS.

² ἄκρας, the editors (following Eustathius on *Iliad* 6. 181), for κράγας.

³ For ὀκτώ Eustathius (*l.c.*) reads δύο.

Lycia, one comes to a Lycian town near it, Telmessus, and to Telmessis, a promontory with a harbour. Eumenes¹ received this place from the Romans in the Antiochian War, but when his kingdom was dissolved the Lycians got it back again.

5. Then, next, one comes to Anticragus, a steep mountain, where is Carmylessus, an inhabited place situated in a ravine; and, after this, to Cragus, which has eight promontories and a city of the same name. The scene of the myth of Chimaera is laid in the neighbourhood of these mountains. Chimaera, a ravine extending up from the shore, is not far from them. At the foot of Cragus, in the interior, lies Pinara, one of the largest cities in Lycia. Here Pandarus is held in honour, who may, perhaps, be identical with the Trojan hero, as when the poet says, "the daughter of Pandareus, the nightingale of the greenwood," for Pandareus is said to have been from Lycia.

6. Then one comes to the Xanthus River, which the people of earlier times called the Sirbis. Sailing up this river by rowboat for ten stadia one comes to the Letoûm; and proceeding sixty stadia beyond the temple one comes to the city of the Xanthians, the largest city in Lycia. After Xanthus, to Patara, which is also a large city, has a harbour, has a temple of Apollo, and was founded by Patarus. When Ptolemy Philadelphus repaired it, he called it Lycian Arsinoë, but the original name prevailed.

¹ King of Pergamum 197-159 B.C.

⁴ ὡς καὶ . . . ἀηδάν, Meineke ejects.

⁵ Instead of οἱ πρότερον, F and Meineke read τὰ πρότερον.

⁶ ἱερὸν Ἀπόλλωνος, the editors, for ἱερὰ πολλά.

7. Εἴτα Μύρα ἐν εἴκοσι σταδίοις ὑπὲρ τῆς θαλάττης ἐπὶ μετεώρου λόφου. εἴθ' ἡ ἐκβολὴ τοῦ Λιμύρου¹ ποταμοῦ καὶ ἀνιόντι πεζῇ σταδίους εἴκοσι τὰ Λίμυρα πολίχνη. μεταξύ δ' ἐν τῷ λεχθέντι παράπλῳ νησία πολλὰ καὶ λιμένες, ὧν καὶ Μεγίστη νῆσος καὶ πόλις ὁμώνυμος, καὶ² ἡ Κισθήνη. ἐν δὲ τῇ μεσογαίᾳ χωρία Φελλὸς καὶ Ἀντίφελλος καὶ ἡ Χίμαιρα, ἧς ἐμνήσθημεν ἐπάνω.

8. Εἴθ' Ἱερὰ ἄκρα καὶ αἱ Χελιδόνιαι, τρεῖς νῆσοι τραχεῖαι, πάρισοι τὸ μέγεθος, ὅσον πέντε σταδίοις ἀλλήλων διέχουσαι· τῆς δὲ γῆς ἀφεστᾶσιν ἑξαστάδιον· μία δ' αὐτῶν καὶ πρόσορμον ἔχει. ἐντεῦθεν νομίζουσιν οἱ πολλοὶ τὴν ἀρχὴν λαμβάνειν τὸν Ταῦρον, διὰ τε τὴν ἄκραν ὑψηλὴν οὖσαν καὶ καθήκουσαν ἀπὸ τῶν Πισιδικῶν ὁρῶν τῶν ὑπερκειμένων τῆς Παμφυλίας καὶ διὰ τὰς προκειμένας νήσους, ἐχούσας ἐπιφανές τι σημεῖον ἐν τῇ θαλάττῃ κρασπέδου δίκην. τὸ δ' ἀληθὲς ἀπὸ τῆς Ῥοδίων περαιᾶς ἐπὶ τὰ πρὸς Πισιδίαν μέρη συνεχῆς ἐστίν ἡ ὀρεινὴ, καλεῖται δὲ καὶ αὕτη Ταῦρος. δοκοῦσι δὲ καὶ αἱ Χελιδόνιαι κατὰ Κανωβὸν πῶς πίπτειν· τὸ δὲ διάρμα λέγεται τέτρακισχιλίων σταδίων. ἀπὸ δὲ τῆς Ἱερᾶς ἄκρας ἐπὶ τὴν Ὀλβίαν λείπονται στάδιοι τριακόσιοι ἑξήκοντα ἑπτὰ· ἐν τούτοις δ' ἐστὶν ἡ τε Κράμβουσα καὶ Ὀλυμπος, πόλις μεγάλῃ καὶ ὄρος ὁμώνυμον, ὃ καὶ Φοινικοῦς καλεῖται· εἴτα Κώρυκος αἰγιαλός.

¹ Λιμύρου EF, Λιρύμου other MSS.

² καί, before ἡ, Groskurd inserts.

¹ i.e. approximately on the same meridian as Canopus in Egypt.

7. Then one comes to Myra, at a distance of twenty stadia above the sea, on a lofty hill. Then to the outlet of the Limyrus River, and then, going twenty stadia inland on foot, to Limyra, a small town. In the intervening distance on the coasting voyage there are numerous isles and harbours, among which are the island Megistê, with a city of the same name, and Cisthenê. And in the interior are places called Phellus and Antiphellus and Chimaera, which last I have mentioned above.

8. Then one comes to the promontory Hierâ; and to the Chelidoniae, three rugged islands, which are about equal in size and are about five stadia distant from one another. They lie about six stadia off the shore, and one of them has a landing-place for vessels. Here it is, according to the majority of writers, that the Taurus takes its beginning, not only because of the loftiness of the promontory and because it extends down from the Pisidian mountains that lie above Pamphylia, but also because of the islands that lie off it, presenting, as they do, a sort of conspicuous sign in the sea, like outskirts of a mountain. But in truth the mountainous tract is continuous from the Peraea of the Rhodians to the parts near Pisidia; and this tract too is called the Taurus. The Chelidoniae are likewise thought to lie approximately opposite to Canobus;¹ and the passage thence to Canobus is said to be four thousand stadia. From the promontory Hierâ to Olbia there remain three hundred and sixty-seven stadia; and on this stretch lie, not only Crambusa, but also Olympus, a large city and a mountain of the same name, which latter is also called Phoenicus. Then one comes to Corycus, a tract of sea-coast.

9. Εἴτα Φασηλὶς,¹ τρεῖς ἔχουσα λιμένας, πόλις ἀξιόλογος καὶ λίμνη.² ὑπέρκειται δ' αὐτῆς τὰ Σόλυμα ὄρος καὶ Τερμησσός, Πισιδικὴ πόλις ἐπικειμένη τοῖς στενοῖς, δι' ὧν ὑπέρβασίς ἐστιν εἰς τὴν Μιλυάδα. καὶ ὁ Ἀλέξανδρος διὰ τοῦτο ἐξεῖλεν αὐτήν, ἀνοῖξαι βουλόμενος τὰ στενά. περὶ Φασηλίδα³ δ' ἐστὶ κατὰ θάλατταν στενά, δι' ὧν Ἀλέξανδρος παρήγαγε τὴν στρατιάν. ἐστὶ δ' ὄρος Κλίμαξ καλούμενον, ἐπὶ κεῖται δὲ τῷ Παμφυλίῳ πελάγει, στενὴν ἀπολείπον πάροδον ἐπὶ τῷ αἰγιαλῷ, ταῖς μὲν ἰννεμίαις γυμνουμένην, ὥστε εἶναι βάσιμον τοῖς ὁδεύουσι, πλημμύροντος δὲ τοῦ πελάγους ὑπὸ τῶν κυμάτων καλυπτομένην ἐπὶ πολὺ· ἡ μὲν οὖν διὰ τοῦ ὄρους ὑπέρβασις περίοδον ἔχει καὶ προσάντης ἐστὶ, τῷ δ' αἰγιαλῷ χρῶνται κατὰ τὰς εὐδίας. ὁ δὲ Ἀλέξανδρος εἰς χεῖμεριον ἐμπεσὼν καιρὸν καὶ τὸ πλέον ἐπιτρέπων C 667 τῇ τύχῃ, πρὶν ἀνεῖναι τὸ κῦμα ὥρμησε, καὶ ὅλην τὴν ἡμέραν ἐν ὕδατι γενέσθαι τὴν πορείαν συνέβη, μέχρι ὀμφαλοῦ βαπτίζομένων. ἐστὶ μὲν οὖν καὶ αὕτη ἡ πόλις Λυκιακὴ, ἐπὶ τῶν ὄρων⁴ ἰδρυμένη τῶν πρὸς Παμφυλίαν, τοῦ δὲ κοινοῦ τῶν Λυκίων οὐ μετέχει, καθ' αὐτὴν δὲ συνέστηκεν.

10. Ὁ μὲν οὖν ποιητὴς ἐτέρους τῶν Λυκίων ποιεῖ τοὺς Σολύμους· ὑπὸ γὰρ τοῦ τῶν Λυκίων βασιλέως πεμφθεὶς ὁ Βελλεροφόντης ἐπὶ δεῦτερον τοῦτον ἄθλον

Σολύμοισι μαχέσσατο κυδαλίμοισιν.

οἱ δὲ τοὺς Λυκίους πρότερον καλεῖσθαι Σολύμους

¹ Φασηλὶς, the editors (following Eustathius on *Dionys.* 855).

9. Then one comes to Phaselis, with three harbours, a city of note, and to a lake. Above it lies Solyma, a mountain, and also Termessus, a Pisidian city situated near the defiles, through which there is a pass over the mountain to Milyas. Alexander destroyed Milyas for the reason that he wished to open the defiles. Near Phaselis, by the sea, there are defiles, through which Alexander led his army. And here there is a mountain called Climax, which lies near the Pamphylian Sea and leaves a narrow pass on the shore; and in calm weather this pass is free from water, so that it is passable for travellers, but when the sea is at flood-tide it is to a considerable extent hidden by the waves. Now the pass that leads over through the mountain is circuitous and steep, but in fair weather people use the pass along the shore. Alexander, meeting with a stormy season, and being a man who in general trusted to luck, set out before the waves had receded; and the result was that all day long his soldiers marched in water submerged to their navels. Now this city too is Lycian, being situated on the borders towards Pamphylia, but it has no part in the common League and is a separate organisation to itself.

10. Now the poet makes the Solymi different from the Lycians, for when Bellerophon was sent by the king of the Lycians to the second struggle, "he fought with the glorious Solymi."¹ But others, who assert that the Lycians were in earlier times

¹ *Iliad* 6. 184.

² Instead of *λίμνη*, F and Eustathius (*l.c.*) have *λίμνην*.

³ *CDhos* spell the word *Φασίλιδα*, F *Φιλίδα*.

⁴ *δρων*, Kramer, for *δρῶν*.

φάσκοντες, ὕστερον δὲ Τερμίλας, ἀπὸ τῶν ἐκ Κρήτης συγκατελθόντων τῷ Σαρπηδόνι, μετὰ δὲ ταῦτα Λυκίους ἀπὸ Λύκου τοῦ Πανδίωνος, ὃν ἐκπεσόντα τῆς οἰκείας ἐδέξατο Σαρπηδὼν ἐπὶ μέρει τῆς ἀρχῆς, οὐχ ὁμολογούμενα λέγουσιν Ὅμηρῳ¹ βελτίους δ' οἱ φάσκοντες λέγεσθαι Σολύμους ὑπὸ τοῦ ποιητοῦ τοὺς νῦν Μιλύας προσαγορευομένους, περὶ ὧν εἰρήκαμεν.

IV

1. Μετὰ Φασηλίδα¹ δ' ἐστὶν ἡ Ὀλβία, τῆς Παμφυλίας ἀρχή, μέγα ἔρυμα, καὶ μετὰ ταύτην ὁ Καταράκτης λεγόμενος, ὑφ' ὑψηλῆς πέτρας καταράττων ποταμὸς πολὺς καὶ χειμαρρῶδης, ὥστε πόρρωθεν ἀκούεσθαι τὸν ψόφον. εἴτα πόλις Ἀττάλεια, ἐπώνυμος τοῦ κτίσαντος Φιλαδέλφου, καὶ οἰκίσαντος εἰς Κώρυκον, πολίχνιον ὁμορον,² ἄλλην κατοικίαν καὶ μείζω³ περίβολον περιθέντος. φασὶ δ' ἐν τῷ μεταξὺ Φασηλίδος⁴ καὶ Ἀτταλείας δείκνυσθαι Θήβην τε καὶ Λυρνησσόν, ἐκπεσόντων ἐκ τοῦ Θήβης πεδίου τῶν Τρωικῶν Κιλικῶν εἰς τὴν Παμφυλίαν ἐκ μέρους, ὡς εἶρηκε Καλλισθένης.

2. Εἰθ' ὁ Κέστρος ποταμός, ὃν ἀναπλεύσαντι σταδίους ἐξήκοντα Πέργη πόλις, καὶ πλησίον ἐπὶ μετεώρου τόπου τὸ τῆς Περγαίας Ἀρτέμιδος

¹ Φασηλίδα E, Φασιλίδα other MSS.

² ὁμορον, Kramer and later editors transfer as above from a position after κατοικίαν.

called Solymi, but in later times were called Termilae¹ from the Termilae who came there from Crete with Sarpedon, and after this were called Lycians, from Lycius the son of Pandion, who, after having been banished from his homeland, was admitted by Sarpedon as a partner in his empire, are not in agreement with Homer. Better is the opinion of those who assert that by "Solymi" the poet means the people who are now called the Milyae, of whom I have already spoken."²

IV

1. After Phaselis one comes to Olbia, the beginning of Pamphylia, a large fortress; and after this to the Cataractes River, so called, which dashes down³ from a lofty rock in such volume and so impetuously that the noise can be heard from afar. Then to a city, Attaleia, so named after its founder Attalus Philadelphus, who also sent a colony to Corycus, a small neighbouring town, and surrounded it with a greater circuit-wall. It is said that both Thebê and Lyrnessus are to be seen between Phaselis and Attaleia, a part of the Trojan Cilicians having been driven out of the plain of Thebê into Pamphylia, as Callisthenes states.

2. Then one comes to the Cestrus River; and, sailing sixty stadia up this river, one comes to Pergê, a city; and near Pergê, on a lofty site, to the temple of

¹ See 12. 8. 5.

² 12. 8. 5 and 12. 3. 27.

³ The Greek verb is "cataracts."

³ *μείζω μικρόν* Cw, merely *μικρόν* other MSS., except F, which has merely *μείζω*.

⁴ *Φασηλίδος* E, *Φασιλίδος* other MSS.

ἱερόν, ἐν ᾧ πανήγυρις κατ' ἔτος συντελείται. εἰθ' ὑπὲρ τῆς θαλάττης ὅσον τετταράκοντα σταδίοις Σύλλιον¹ πόλις ἐστὶν ὑψηλὴ τοῖς ἐκ Πέργης ἔποπτος· εἶτα λίμνη εὐμεγέθης Καπρία, καὶ μετὰ ταῦτα ὁ Εὐρυμέδων ποταμός, ὃν ἀναπλεύσαντι ἐξήκοντα σταδίους Ἀσπενδος πόλις, εὐανδροῦσα ἱκανῶς, Ἀργείων κτίσμα· ὑπέρκειται δὲ ταύτης Πετνηλισσός· εἰτ' ἄλλος ποταμός, καὶ νησία προκείμενα πολλά· εἶτα Σίδη, Κυμαίων ἀποικος· ἔχει δ' Ἀθηναῖς ἱερόν. πλησίον δ' ἐστὶ καὶ ἡ Κιβυρατῶν παραλία τῶν μικρῶν· εἰθ' ὁ Μέλας ποταμός καὶ ὕφορμος· εἶτα Πτολεμαῖς πόλις· καὶ μετὰ ταῦθ' οἱ ὄροι τῆς Παμφυλίας καὶ τὸ Κορακήσιον, ἀρχὴ τῆς τραχείας Κιλικίας. ὁ δὲ παράπλους ἅπας ὁ Παμφύλιος σταῖδιοί εἰσιν ἑξακόσιοι τεσσαράκοντα.

- C 668 3. Φησὶ δ' Ἡρόδοτος τοὺς Παμφύλους τῶν μετὰ Ἀμφιλόχου καὶ Κάλχαντος εἶναι λαῶν, μιγάδων τινῶν ἐκ Τροίας συνακολουθησάντων· τοὺς μὲν δὴ πολλοὺς ἐνθάδε καταμεῖναι, τινὰς δὲ σκεδασθῆναι πολλαχοῦ τῆς γῆς. Καλλίνος δὲ τὸν μὲν Κάλχαντα ἐν Κλάρῳ τελευτῆσαι τὸν βίον φησὶ, τοὺς δὲ λαοὺς μετὰ Μόψου τὸν Ταῦρον ὑπερθέοντας, τοὺς μὲν ἐν Παμφυλίᾳ μεῖναι, τοὺς δ' ἐν Κιλικίᾳ μερισθῆναι καὶ Συρίᾳ μέχρι καὶ Φοινίκης.

¹ Σύλλιον, Jones inserts, following Tzschucke, who first noted that this was the city meant. Meineke emends σταδίοις to Σόλλιον.

Artemis Pergaea, where a general festival is celebrated every year. Then, about forty stadia above the sea, one comes to Syllium, a lofty city that is visible from Pergê. Then one comes to a very large lake, Capria; and after this, to the Eurymedon River; and, sailing sixty stadia up this river, to Aspendus, a city with a flourishing population and founded by the Argives. Above Aspendus lies Petnelissus. Then comes another river; and also numerous isles that lie off it. Then Sidê, a colony of the Cymaeans, which has a temple of Athena; and near by is the coast of the Lesser Cibyratae. Then the Melas River and a mooring-place. Then Ptolemaïs, a city. And after this come the boundaries of Pamphylia, and also Coracesium, the beginning of Cilicia Tracheia. The whole of the voyage along the coast of Pamphylia is six hundred and forty stadia.

3. Herodotus¹ says that the Pamphylians are the descendants of the peoples led by Amphilochoi and Calchas, a miscellaneous throng who accompanied them from Troy; and that most of them remained here, but that some of them were scattered to numerous places on earth. Callinus says that Calchas died in Clarus, but that the peoples led by Mopsus passed over the Taurus, and that, though some remained in Pamphylia, the others were dispersed in Cilicia, and also in Syria as far even as Phoenicia.

¹ 7. 91.

1. Τῆς Κιλικίας δὲ τῆς ἔξω τοῦ Ταύρου ἡ μὲν λέγεται τραχεῖα, ἡ δὲ πεδιάς· τραχεῖα μὲν, ἥς ἡ παραλία στενὴ ἐστὶ, καὶ οὐδὲν ἡ σπανίως ἔχει τι χωρίον ἐπίπεδον, καὶ ἔτι ἥς ὑπέρκειται ὁ Ταῦρος, οἰκούμενος κακῶς, μέχρι καὶ τῶν προσβόρων πλευρῶν τῶν περὶ Ἰσαυρα καὶ τοὺς Ὀμοναδέας μέχρι τῆς Πισιδίας· καλεῖται δ' ἡ αὕτη καὶ Τραχειώτις καὶ οἱ ἐνοικοῦντες Τραχειώται· πεδιάς δ' ἡ ἀπὸ Σόλων καὶ Ταρσοῦ μέχρι Ἰσσοῦ, καὶ ἔτι ὧν ὑπέρκεινται κατὰ τὸ πρόσβορον τοῦ Ταύρου πλευρὸν Καππάδοκες· αὕτη γὰρ ἡ χώρα τὸ πλεον πεδίῳ εὐπορεῖ καὶ χώρας ἀγαθῆς. ἐπεὶ δὲ τούτων τὰ μὲν ἐστὶν ἐντὸς τοῦ Ταύρου, τὰ δ' ἐκτὸς, περὶ μὲν τῶν ἐντὸς εἴρηται, περὶ δὲ τῶν ἐκτὸς λέγωμεν, ἀπὸ τῶν Τραχειωτῶν ἀρξάμενοι.

2. Πρῶτον τοίνυν ἐστὶ τῶν Κιλικίων φρούριον τὸ Κορακήσιον, ἰδρυμένον ἐπὶ πέτρας ἀπορρῶγος, ᾧ ἐχρήσατο Διόδοτος ὁ Τρύφων προσαγορευθεὶς ὀρμητηρίῳ, καθ' ὃν καιρὸν ἀπέστησε τὴν Συρίαν τῶν βασιλέων καὶ διεπολέμει πρὸς ἐκείνους, τότε μὲν κατορθῶν τότε δὲ πταίων. τοῦτον μὲν οὖν Ἀντίοχος ὁ Δημητρίου κατακλείσας εἰς τι χωρίον ἠνάγκασε διεργάσασθαι τὸ σῶμα. τοῖς δὲ Κίλιξιν ἀρχὴν¹ τοῦ τὰ πειρατικά συνίστασθαι Τρύφων αἴτιος κατέστη, καὶ ἡ τῶν βασιλέων οὐδένεια τῶν τότε ἐκ διαδοχῆς ἐπιστατούντων τῆς Συρίας ἅμα καὶ τῆς Κιλικίας· τῷ γὰρ ἐκείνου νεωτερισμῷ

¹ ἀρχήν, Groskurd, for ἀρχή; so the later editors.

V

1. As for Cilicia outside the Taurus, one part of it is called Tracheia¹ and the other Pedias.² As for Tracheia, its coast is narrow and has no level ground, or scarcely any; and, besides that, it lies at the foot of the Taurus, which affords a poor livelihood as far as its northern side in the region of Isaura and of the Homonadeis as far as Pisidia; and the same country is also called Tracheiotis, and its inhabitants Tracheiotae. But Cilicia Pedias extends from Soli and Tarsus as far as Issus, and also to those parts beyond which, on the northern side of the Taurus, Cappadocians are situated; for this country consists for the most part of plains and fertile land. Since some parts of this country are inside the Taurus and others outside it, and since I have already spoken of those inside it, let me now speak of those outside it, beginning with the Tracheiotae.

2. The first place in Cilicia, then, to which one comes, is a stronghold, Coracesium, situated on an abrupt rock, which was used by Diodotus, called Tryphon, as a base of operations at the time when he caused Syria to revolt from the kings and was fighting it out with them, being successful at one time and failing at another. Now Tryphon was hemmed up in a certain place by Antiochus, son of Demetrius, and forced to kill himself; and it was Tryphon, together with the worthlessness of the kings who by succession were then reigning over Syria and at the same time over Cilicia, who caused the Cilicians to organise their gangs of pirates; for on account of his revolutionary attempts others made

¹ *Rugged Cilicia.*² *Level Cilicia.*

συνενεωτέρισαν καὶ ἄλλοι, διχοστατοῦντές τε
 ἀδελφοὶ πρὸς ἀλλήλους ὑποχείριον ἐποιοῦν τὴν
 χώραν τοῖς ἐπιτιθεμένοις. ἡ δὲ τῶν ἀνδραπόδων
 ἐξαγωγή προῦκαλεῖτο μάλιστα εἰς τὰς κακουργίας,
 ἐπικερδεστάτη γενομένη· καὶ γὰρ ἡλίσκοντο
 ῥαδίως, καὶ τὸ ἐμπόριον οὐ παντελῶς ἄπωθεν ἦν
 μέγα καὶ πολυχρήματον, ἡ Δῆλος, δυναμένη
 μυριάδας ἀνδραπόδων αὐθημερόν καὶ δέξασθαι
 καὶ ἀποπέμψαι, ὥστε καὶ παροιμίαν γενέσθαι διὰ
 τοῦτο· ἔμπορε, κατάπλευσον, ἐξελοῦ, πάντα
 πέπραται. αἴτιον δ', ὅτι πλούσιοι γενόμενοι
 Ῥωμαῖοι μετὰ τὴν Καρχηδόνης καὶ Κορίνθου
 κατασκαφὴν οἰκετείαις ἐχρῶντο πολλαῖς· ὁρῶντες
 δὲ τὴν εὐπέτειαν οἱ λησταὶ ταύτην ἐξήνθησαν
 C 669 ἀθρώως, αὐτοὶ καὶ ληιζόμενοι καὶ σωματεμπο-
 ροῦντες. συνήρουν δ' εἰς ταῦτα καὶ οἱ τῆς
 Κύπρου καὶ οἱ τῆς Αἰγύπτου βασιλεῖς, ἐχθροὶ
 τοῖς Σύροις ὄντες· οὐδ' οἱ Ῥόδιοι δὲ φίλοι ἦσαν
 αὐτοῖς, ὥστ' οὐδὲν ἐβοήθουν· ἅμα δὲ καὶ οἱ λησταὶ
 προσποιούμενοι σωματεμπορεῖν, ἄλυστον τὴν
 κακουργίαν εἶχον. ἀλλ' οὐδὲ Ῥωμαῖοί πω τοσοῦ-
 τον ἐφρόντιζον τῶν ἔξω τοῦ Ταύρου, ἀλλ' ἔπεμψαν
 μὲν καὶ Σκιπίωνα τὸν Αἰμιλιανόν, ἐπισκεψόμενον
 τὰ ἔθνη καὶ τὰς πόλεις, καὶ πάλιν ἄλλους τινάς·
 ἔγνωσαν δὲ κακία τῶν ἀρχόντων συμβαῖνον τοῦτο,
 εἰ καὶ τὴν¹ κατὰ γένος διαδοχὴν τὴν ἀπὸ Σελεύ-
 κου τοῦ Νικάτορος, αὐτοὶ κεκυρωκότες, ἡδοῦντο
 ἀφαιρεῖσθαι. τοῦτο δὲ συμβὰν τῆς μὲν χώρας
 ἐποίησε κυρίου Παρθυαίου, οἱ τὰ πέραν τοῦ

¹ εἰ καὶ τὴν z (by correction), εἰ τὴν x, εἰς τὴν other MSS.

like attempts at the same time, and thus the dissensions of brethren with one another put the country at the mercy of any who might attack it. The exportation of slaves induced them most of all to engage in their evil business, since it proved most profitable; for not only were they easily captured, but the market, which was large and rich in property, was not extremely far away, I mean Delos, which could both admit and send away ten thousand slaves on the same day; whence arose the proverb, "Merchant, sail in, unload your ship, everything has been sold." The cause of this was the fact that the Romans, having become rich after the destruction of Carthage and Corinth, used many slaves; and the pirates, seeing the easy profit therein, bloomed forth in great numbers, themselves not only going in quest of booty but also trafficking in slaves. The kings both of Cyprus and of Egypt co-operated with them in this, being enemies to the Syrians. Neither were the Rhodians friendly to the Syrians, and they therefore afforded them no assistance. And at the same time the pirates, pretending to be slave-dealers, carried on their evil business unchecked. Neither were the Romans concerning themselves as yet so much about the peoples outside the Taurus; but they sent Scipio Aemilianus, and again certain others, to inspect the tribes and the cities; and they decided that the above-mentioned piracy was due to the incompetence of the rulers, although they were ashamed, since they themselves had ratified the hereditary succession from Seleucus Nicator, to deprive them of it. And this is what made the Parthians masters of the country, who got possession of the region on the far

Εὐφράτου κατέσχον· τὸ τελευταῖον δὲ καὶ Ἀρμενίους, οἳ καὶ τὴν ἐκτὸς τοῦ Ταύρου προσέλαβον μέχρι καὶ Φοινίκης, καὶ τοὺς βασιλέας κατέλυσαν εἰς δύναμιν καὶ τὸ γένος αὐτῶν σύμπαν, τὴν δὲ θάλατταν τοῖς Κίλιξι παρέδωκαν. εἴτ' αὐξηθέντας ἠναγκάσθησαν καταλύειν Ῥωμαῖοι πολέμῳ καὶ μετὰ στρατιᾶς, οὓς αὐξομένους οὐκ ἐκώλυσαν. ὀλυγωρίαν μὲν οὖν αὐτῶν χαλεπὸν καταγνῶναι· πρὸς ἑτέροις δὲ ὄντες τοῖς ἐγγυτέρῳ καὶ κατὰ χεῖρα μᾶλλον οὐχ οἰοί τε ἦσαν τὰ ἀπωτέρω σκοπεῖν. ταῦτα μὲν οὖν ἔδοξεν ἡμῖν ἐν παρεκβάσει διὰ βραχέων εἰπεῖν.

3. Μετὰ δὲ τὸ Κορακήσιον Ἀρσινόη¹ πόλις, εἴθ' Ἀμαξία, ἐπὶ βουνοῦ κατοικία τις ὕφορμον ἔχουσα, ὅπου κατάγεται ἡ ναυπηγήσιμος ὕλη. κέδρος δ' ἐστὶν ἡ πλείστη, καὶ δοκεῖ ταῦτα τὰ μέρη πλεονεκτεῖν τῇ τοιαύτῃ ξυλείᾳ· καὶ διὰ τοῦτ' Ἀντώνιος Κλεοπάτρα τὰ χωρία ταῦτα προσένειμεν, ἐπιτήδεια ὄντα πρὸς τὰς τῶν στόλων κατασκευάς. εἴτα Λαέρτης, φρούριον ἐπὶ λόφου μαστοειδοῦς ὕφορμον ἔχον· εἴτα Σελινοῦς πόλις καὶ² ποταμός· εἴτα Κράγος, πέτρα περίκρημνος πρὸς θαλάττῃ· εἴτα Χαραδροῦς, ἔρυμα καὶ αὐτὸ ὕφορμον ἔχον (ὑπέρκειται δ' ὄρος Ἀνδρικλος) καὶ παράπλους τραχύς, Πλατανιστῆς³ καλούμενος· εἴτ' Ἀνεμούριον ἄκρα, καθ' ἣν ἡ ἡπειρος ἐγγυ-

¹ Ἀρσινόη appears to be corrupt. Hopper conj. *Συδρή*, Tzschucke *Συέδρα*, C. Müller *Ἀθήνσις*.

² πόλις καί, Jones inserts, from conj. of C. Müller (*Ind. Var. Lect.* p. 1031). Meineke, following Groskurd, emends ποταμός to πόλις.

³ Πλατανιστῆς, Meineke, for Πλατανιστής E, Πλατανιστός other MSS.

side of the Euphrates; and at last made also the Armenians masters, who not only seized the country outside the Taurus even as far as Phoenicia, but also, so far as they could, overthrew the kings and the whole royal stock; the sea, however, they gave over to the Cilicians. Then, after these people had grown in power, the Romans were forced to destroy them by war and with an army, although they had not hindered their growing power. Now it is hard to condemn the Romans of negligence, since, being engaged with matters that were nearer and more urgent, they were unable to watch those that were farther away. So much I have decided to say by way of a brief digression from my geographical description.

3. After Coracesium, one comes to Arsinoë,¹ a city; then to Hamaxia, a settlement on a hill, with a harbour, where ship-building timber is brought down. Most of this timber is cedar; and it appears that this region beyond others abounds in cedar-wood for ships; and it was on this account that Antony assigned this region to Cleopatra, since it was suited to the building of her fleets. Then one comes to Laertes, a stronghold on a breast-shaped hill, with a mooring-place. Then to Selinus, a city and river. Then to Cragus, a rock which is precipitous all round and near the sea. Then to Charadrus, a fortress, which also has a mooring-place (above it lies Mt. Andriclus); and the coast alongside it, called Platanistes, is rugged. Then to Anemurium, a promontory, where the mainland approaches closest to Cyprus, in the direction of the promontory of

¹ "Arsinoë" is thought to be an error for "Sydrî," or "Syedra" or "Aunesis" (see critical note).

τάτω τῆς Κυπρίας ἐστὶν ἐπὶ Κρομμύου ἄκραν, ἐν διάρματι σταδίων τριακοσίων πεντήκοντα. εἰς μὲν οὖν τὸ Ἀνεμούριον ἀπὸ τῶν ὄρων τῆς Παμφυλίας ὁ Κιλικίος παράπλους σταδίων ἐστὶν ὀκτακοσίων εἴκοσι, λοιπὸς δ' ἐστὶ μέχρι Σόλων ὅσον C 670 πεντακοσίων παράπλους σταδίων. τούτου¹ δ' ἐστὶ Νάγιδος² πρώτη³ μετὰ τὸ Ἀνεμούριον πόλις· εἴτ' Ἀρσινόη πρόσορμον ἔχουσα· εἴτα τόπος Μελανία καὶ Κελένδεραι, πόλις λιμένα ἔχουσα. τινὲς δὲ ταύτην ἀρχὴν τίθενται τῆς Κιλικίας, οὐ τὸ Κορακήσιον, ὧν ἐστὶ καὶ ὁ Ἀρτεμίδωρος· καὶ φησιν ἀπὸ μὲν τοῦ Πηλουσιακοῦ στόματος εἶναι τρισχιλίους ἐννακοσίους⁴ σταδίους εἰς Ὀρθωσίαν, ἐπὶ δὲ τὸν Ὀρόντην ποταμὸν χίλια ἑκατὸν τριάκοντα, ἐπὶ δὲ τὰς πύλας ἑξῆς πεντακόσια εἰκοσιπέντε, ἐπὶ δὲ τοὺς ὄρους τῶν Κιλικίων χίλια διακόσια⁵ ἑξήκοντα.

4. Εἰθ' Ὀλμοι, ὅπου πρότερον ὥκουν οἱ νῦν Σελευκεῖς· κτισθείσης δ' ἐπὶ τῷ Καλυκάδνῳ τῆς Σελευκείας, ἐκεῖ μετῴκισθησαν· εὐθὺς γάρ ἐστιν ἡ τοῦ Καλυκάδνου ἐκβολὴ κάμψαντι ἡίονα,

¹ τούτου, Meineke, for τοῦτο; others, following Casaubon, read ἐν τούτῳ.

² ἐστὶ Νάγιδος, Tzschucke, for ἐστὶν ἁγίδος Δί, ἐστὶν ἁγίδος other MSS.

³ πρώτη, Groskurd, for πρώτοι; so the later editors.

⁴ ἐννακοσίους, Meineke (following Casaubon and Groskurd) emends to ἑξακοσίους.

⁵ διακόσια, Meineke (following Casaubon and Groskurd) emends to ἐνακόσια.

¹ Cp. 14. 6. 3.

² Elsewhere (16. 2. 33) referred to as "Melacnae or Melaniae."

Crommyus,¹ the passage across being three hundred and fifty stadia. Now the coasting-voyage along Cilicia from the borders of Pamphylia to Anemurium is eight hundred and twenty stadia, whereas the rest, as far as Soli, is about five hundred stadia. On this latter one comes to Nagidus, the first city after Anemurium; then to Arsinoë, which has a landing-place; then to a place called Melania,² and to Celenderis, a city with a harbour. Some writers, among whom is Artemidorus, make Celenderis, not Coracesium, the beginning of Cilicia. And he says that the distance from the Pelusian mouth³ to Orthosia is three thousand nine hundred stadia; to the Orontes River, one thousand one hundred and thirty; to the Gates⁴ next thereafter, five hundred and twenty-five; and to the borders⁵ of the Cilicians, one thousand two hundred and sixty.⁶

4. Then one comes to Holmi, where the present Seleuceians formerly lived; but when Seleuceia on the Calycadnus was founded, they migrated there; for immediately on doubling the shore, which forms a promontory called Sarpedon, one comes to the

¹ The mouth of the Nile at Pelusium.

² Elsewhere (14. 5. 19), "Pylae" ("Gates") is called "a boundary between the Cilicians and the Syrians."

³ *i.e.* the western borders (Celenderis, according to Artemidorus).

⁴ Elsewhere (16. 2. 33) the MSS. give the figures of Artemidorus as follows: "From Orthosia to Pelusium, 3650 stadia, including the sinuosities of the gulfs: from Melaenae, or Melaniae, in Cilicia near Celenderis, to the common boundaries of Cilicia and Syria, 1900; thence to the Orontes, 520; and then to Orthosia, 1130." Groskurd, Forbiger, and Meineke (see critical note) accept these figures and emend the present passage correspondingly.

ποιοῦσαν ἄκραν, ἣ καλεῖται Σαρπηδών. πλησίον δ' ἐστὶ τοῦ Καλυκάδου καὶ τὸ Ζεφύριον, καὶ αὕτη ἄκρα· ἔχει δὲ ὁ ποταμὸς ἀνάπλουν εἰς τὴν Σελεύκειαν, πόλιν εὖ συνοικουμένην καὶ πολὺ ἀφεστῶσαν τοῦ Κιλικίου καὶ Παμφυλίου τρόπου. ἐνταῦθα ἐγένοντο καθ' ἡμᾶς ἄνδρες ἀξιόλογοι τῶν ἐκ τοῦ περιπάτου φιλοσόφων Ἀθηναῖός τε καὶ Ξέναρχος, ὧν ὁ μὲν Ἀθηναῖος καὶ ἐπολιτεύσατο καὶ ἐδημαγωγῶνσε χρόνον τινὰ ἐν τῇ πατρίδι· εἴτ' ἐμπεσὼν εἰς τὴν Μουρῆνα φιλίαν ἐκείνῳ συνεάλω φεύγων, φωραθείσης τῆς κατὰ Καῖσαρος τοῦ Σεβαστοῦ συσταθείσης ἐπιβουλῆς· ἀναίτιος δὲ φανείς ἀφείθη ὑπὸ Καῖσαρος. ὥς δ' ἐπανιόντα εἰς Ῥώμην¹ ἡσπάζοντο καὶ ἐπυνθάνοντο οἱ πρῶτοι ἐντυγχάνοντες, τὸ τοῦ Εὐριπίδου ἔφη·

ἦκω, νεκρῶν κευθμῶνα καὶ σκότου πύλας
λιπών.

ὀλίγον δ' ἐπιβιούς χρόνον ἐν συμπτώσει τῆς οἰκίας, ἐν ᾗ ᾔκει, διεφθάρη, νύκτωρ γενομένη. Ξέναρχος δέ, οὗ ἠκροασάμεθα ἡμεῖς, ἐν οἴκῳ μὲν οὐ πολὺ διέτριψεν, ἐν Ἀλεξανδρείᾳ δὲ καὶ Ἀθήνησι καὶ τὸ τελευταῖον ἐν Ῥώμῃ, τὸν παιδευτικὸν βίον ἐλόμενος· χρησάμενος δὲ καὶ τῇ Ἀρείου² φιλίᾳ καὶ μετὰ ταῦτα τῇ Καῖσαρος τοῦ Σεβαστοῦ διετέλεσε μέχρι γήρως ἐν τιμῇ ἀγόμενος· μικρὸν δὲ πρὸ τῆς τελευτῆς πηρωθεὶς τὴν ὄψιν κατέστρεψε νόσῳ τὸν βίον.

5. Μετὰ δὲ τὸν Καλύκαδον ἡ Ποικίλη λεγο-

¹ εἰς Ῥώμην appears to be an error for ἐκ Ῥώμης, as Casaubon and Kramer suggest.

outlet of the Calycadnus. Near the Calycadnus is also Zephyrium, likewise a promontory. The river affords a voyage inland to Seleuceia, a city which is well-peopled and stands far aloof from the Cilician and Pamphylian usages. Here were born in my time noteworthy men of the Peripatetic sect of philosophers, Athenaeus and Xenarchus. Of these, Athenaeus engaged also in affairs of state and was for a time leader of the people in his native land; and then, having fallen into a friendship with Murena, he was captured along with Murena when in flight with him, after the plot against Augustus Caesar had been detected, but, being clearly proven guiltless, he was released by Caesar. And when, on his return to ¹ Rome, the first men who met him were greeting him and questioning him, he repeated the following from Euripides: ² "I am come, having left the vaults of the dead ³ and the gates of darkness." But he survived his return only a short time, having been killed in the collapse, which took place in the night, of the house in which he lived. Xenarchus, however, of whom I was a pupil, did not tarry long at home, but resided at Alexandria and at Athens and finally at Rome, having chosen the life of a teacher; and having enjoyed the friendship both of Areius and later of Caesar Augustus, he continued to be held in honour down to old age; but shortly before the end he lost his sight, and then died of a disease.

5. After the Calycadnus one comes to the rock

¹ "To" is apparently an error for "from."

² *Hecuba* 1.

³ *i.e.* Hades.

² *Ἀπέλου*, Tzschucke, for *Ἀπίου*; so the later editors.

μένη πέτρα, κλίμακα ἔχουσα λατομητὴν ἐπὶ Σελεύκειαν ἄγουσαν. εἴτ' Ἀνεμούριον ἄκρα, ὁμώνυμος τῇ προτέρᾳ, καὶ Κράμβουσα νήσος καὶ Κώρυκος ἄκρα, ὑπὲρ ἧς ἐν εἴκοσι σταδίοις ἐστὶ τὸ Κωρύκιον ἄντρον, ἐν ᾧ ἡ ἀρίστη κρόκος φύεται. ἔστι δὲ κοιλὰς μεγάλη κυκλοτερής, C 671 ἔχουσα περικειμένην ὀφρὺν πετρώδη, πανταχόθεν ἱκανῶς ὑψηλήν· καταβάντι δ' εἰς αὐτὴν ἀνώμαλόν ἐστιν ἔδαφος καὶ τὸ πολὺ πετρώδες, μεστὸν δὲ τῆς θαμνώδους ὕλης ἀειθαλοῦς τε καὶ ἡμέρου· παρέσπартαι δὲ καὶ τὰ ἐδάφη τὰ φέροντα τὴν κρόκον. ἔστι δὲ καὶ ἄντρον αὐτόθι, ἔχον πηγὴν μεγάλην, ποταμὸν ἐξιῆσαν καθαροῦ τε καὶ διαφανοῦς ὕδατος, εὐθὺς καταπίπτοντα ὑπὸ γῆς· ἐνεχθεὶς δ' ἀφανὴς ἔξισιν εἰς τὴν θάλατταν· καλοῦσι δὲ Πικρὸν ὕδωρ.

6. Εἴθ' ἡ Ἐλαιούσσα¹ νήσος μετὰ τὴν Κώρυκον, προσκειμένη τῇ ἡπείρῳ, ἣν συνάκισεν Ἀρχέλαος καὶ κατεσκευάσατο βασιλεῖον, λαβὼν τὴν Τραχειῶτιν Κιλικίαν ὅλην πλὴν Σελευκείας, καθ' ὃν τρόπον καὶ Ἀμύντας πρότερον εἶχε καὶ ἔτι πρότερον Κλεοπάτρα. εὐφροῦς γὰρ ὄντος τοῦ τόπου πρὸς τὰ ληστήρια καὶ κατὰ γῆν καὶ κατὰ θάλατταν (κατὰ γῆν μὲν διὰ τὸ μέγεθος τῶν ὁρῶν καὶ τῶν ὑπερκειμένων ἐθνῶν, πεδία καὶ γεώργια ἐχόντων μεγάλα καὶ εὐκατατρόχαστα, κατὰ θάλατταν δὲ διὰ τὴν εὐπορίαν τῆς τε

¹ Ἐλαιούσσα, the editors, for Ἐλεοῦσσα (and Ἐλεοῦσα).

² i.e. the Pictured Rock.

³ § 3 above.

⁴ *Crocus sativus*, which yields saffron.

⁵ Bitter Water.

⁶ See 12. 2. 7.

Poecilê,¹ as it is called, which has steps hewn in it that lead to Seleuceia; then to Anemurium, a promontory, bearing the same name as the former,² and to Crambusa, an island, and to Corycus, a promontory, above which, at a distance of twenty stadia, is the Corycian cave, in which the best crocus³ grows. It is a great circular hollow, with a rocky brow situated all round it that is everywhere quite high. Going down into it, one comes to a floor that is uneven and mostly rocky, but full of trees of the shrub kind, both the evergreen and those that are cultivated. And among these trees are dispersed also the plots of ground which produce the crocus. There is also a cave here, with a great spring, which sends forth a river of pure and transparent water; the river forthwith empties beneath the earth, and then, after running invisible underground, issues forth into the sea. It is called Picrum Hydor.⁴

6. Then, after Corycus, one comes to Elaeussa, an island lying close to the mainland, which Archelaüs settled, making it a royal residence,⁵ after he had received⁶ the whole of Cilicia Tracheia except Seleuceia—the same way in which it was obtained formerly by Amyntas⁷ and still earlier by Cleopatra;⁸ for since the region was naturally well adapted to the business of piracy both by land and by sea—by land, because of the height of the mountains and the large tribes that live beyond them, tribes which have plains and farm-lands that are large and very easily overrun, and by sea, because of the good

⁶ i.e. from the Romans (see 12. 1. 4).

⁷ See 12. 5. 1.

⁸ See § 3 above.

ναυπηγησίμου ὕλης καὶ τῶν λιμένων καὶ ἔρματων καὶ ὑποδυτηρίων), ἐδόκει πρὸς ἅπαν τὸ τοιοῦτο βασιλεύεσθαι μᾶλλον τοὺς τόπους, ἢ ὑπὸ τοῖς Ῥωμαίοις ἡγεμόσιν εἶναι, τοῖς ἐπὶ τὰς κρίσεις πεμπομένοις, οἳ μήτ' αἰεὶ παρεῖναι ἔμελλον, μήτε μεθ' ὅπλων. οὕτω μὲν Ἀρχέλαος ἔλαβε πρὸς τῇ Καππαδοκίᾳ τὴν τραχεῖαν Κιλικίαν. εἰσὶ δ' ὄροι ταύτης μεταξὺ Σόλων τε καὶ Ἐλαιούσσης ὁ Λάμος¹ ποταμὸς καὶ κώμη ὁμώνυμος.

7. Κατὰ δὲ τὰς ἀκρωρείας τοῦ Ταύρου τὸ Ζηνικέτου πειρατήριόν ἐστιν ὁ Ὀλυμπος, ὄρος τε καὶ φρούριον ὁμώνυμον, ἀφ' οὗ κατοπτεύεται πᾶσα Λυκία καὶ Παμφυλία καὶ Πισιδία καὶ Μιλυάς· ἀλόντος δὲ τοῦ ὄρους ὑπὸ ² τοῦ Ἰσαυρικοῦ, ἐνέπρησεν ἑαυτὸν πανοίκιον. τούτου δ' ἦν καὶ ὁ Κώρυκος καὶ ἡ Φασηλὶς³ καὶ πολλὰ τῶν Παμφύλων χωρία· πάντα δ' εἶλεν ὁ Ἰσαυρικός.

8. Μετὰ δὲ Λάμον Σόλοι πόλις ἀξιόλογος, τῆς ἄλλης Κιλικίας ἀρχὴ τῆς περὶ τὸν Ἰσσόν, Ἀχαιῶν καὶ Ῥοδίων κτίσμα τῶν ἐκ Λίνδου· εἰς ταύτην λειπανδρήσασαν Πομπήιος Μάγνος κατέκτισε τοὺς περιγενομένους τῶν πειρατῶν, οὓς μαλιστα ἔγνω σωτηρίας καὶ προνοίας τινὸς ἀξίους, καὶ μετωνόμασε Πομπηϊόπολιν.⁴ γεγόνασι δ' ἄνδρες ἐνθένδε τῶν ὀνομαστών Χρύσιππός τε ὁ στωικὸς φιλόσοφος, πατρὸς ὧν Ταρσέως ἐκείθεν

¹ Λάμος, Tzschucke, for Λάγμος C, Λάτμος other MSS. ; so the later editors.

² ὑπό, Casaubon inserts ; so the later editors.

³ Φασηλὶς, the editors, for Φασιλὶς.

supply, not only of shipbuilding timber, but also of harbours and fortresses and secret recesses—with all this in view, I say, the Romans thought that it was better for the region to be ruled by kings than to be under the Roman prefects sent to administer justice, who were not likely always to be present or to have armed forces with them. Thus Archelaüs received, in addition to Cappadocia, Cilicia Tracheia; and the boundary¹ of the latter, the river Lamus and the village of the same name, lies between Soli and Elaeussa.

7. Near the mountain ridges of the Taurus² lies the piratical stronghold of Zenicetus—I mean Olympus, both mountain and fortress, whence are visible all Lycia and Pamphylia and Pisidia and Milyas; but when the mountain was captured by Isauricus,³ Zenicetus burnt himself up with his whole house. To him belonged also Corycus and Phaselis and many places in Pamphylia; but all were taken by Isauricus.

8. After Lamus one comes to Soli, a noteworthy city, the beginning of the other Cilicia, that which is round Issus; it was founded by Achacans and Rhodians from Lindus. Since this city was of scant population, Pompey the Great settled in it those survivors of the pirates whom he judged most worthy of being saved and provided for;⁴ and he changed its name to Pompēiopolis. Among the famous natives of Soli were: Chrysippus the Stoic philosopher, whose father had moved there from

¹ i.e. on the east.

² Servilius Isauricus.

³ i.e. in Lycia.

⁴ Cf. 8. 7. 5.

⁴ E has Πομπηιοῦπολιν.

μετοικήσαντος, καὶ Φιλήμων, ὁ κωμικὸς ποιητής, καὶ Ἄρατος, ὁ τὰ φαινόμενα συγγράψας ἐν ἔπεσιν.

9. Εἶτα Ζεφύριον ὁμώνυμον τῷ πρὸς Καλυκάδω¹ εἶτ' Ἀγχιάλῃ μικρὸν ὑπὲρ τῆς θαλάττης, κτίσμα Σαρδαναπάλλου, φησὶν Ἀριστόβουλος· C 672 ἐνταῦθα δ' εἶναι μνῆμα τοῦ Σαρδαναπάλλου καὶ τύπον λίθινον, συμβάλλοντα τοὺς τῆς δεξιᾶς χειρὸς δακτύλους, ὡς ἂν ἀποκροτοῦνται,² καὶ ἐπιγραφὴν εἶναι Ἀσσυρίοις γράμμασι τοιάνδε· Σαρδανάπαλλος ὁ Ἀνακυνδαράξω παῖς, Ἀγχιάλῃν καὶ Ἰαρσὸν ἔδειμεν ἡμέρῃ μιῇ· ἔσθιε, πῖνε, παῖζε, ὡς τᾶλλα³ τούτου οὐκ ἄξια, τοῦ ἀποκροτήματος.⁴ μέμνηται δὲ καὶ Χοιρίλος τούτων· καὶ δὴ καὶ περιφέρεται τὰ ἔπη ταυτί·

ταῦτ' ἔχω, ὅσσ' ἔφαγον καὶ ἀφύβρισα καὶ μετ'
ἔρωτος
τέρπν' ἔπαθον, τὰ δὲ πολλὰ καὶ ὀλβια κεῖνα
λέλειπται.

10. Ὑπέρκειται δὲ τὰ Κύνδα τῆς Ἀγχιάλῃς ἔρυμα, ᾧ ἐχρήσαντό ποτε οἱ Μακεδόνες γαζοφυ-

¹ Καλυκάδω Εἰσοισζ, Καλύδω other MSS.

² Before καί, all MSS. except E read ἐνιοι δέ.

³ After τᾶλλα, Ald. adds ἀνθρώπινα, apparently from Arrian 2. 5.

⁴ After ἀποκροτήματος, the following verses (obviously an interpolation), inserted by all editors from Cusaubon to Cornis, are in DFlé found only in the margin and in Ogsr preceded by the words τὸ ὕλον ἐπίγραμμα:

εὖ εἰδώς, ὅτι θνητὸς ἔφυς, σὸν θυμὸν ἔεξε,
τερπόμενος θαλίῃσι· θανόντι τοι οὐ τις ὕνησις.
καὶ γὰρ ἐγὼ σποδὸς εἰμι, Νίρου μεγάλης βασιλεύσας·

Tarsus; Philemon, the comic poet; and Aratus, who wrote the work entitled *The Phaenomena*, in verse.

9. Then to Zephyrium, which bears the same name as the place near Calycadnus.¹ Then, a little above the sea, to Anchialê, which, according to Aristobulus, was founded by Sardanapallus. Here, he says, is the tomb of Sardanapallus, and a stone figure which represents the fingers of the right hand as snapping together, and the following inscription in Assyrian letters: "Sardanapallus, the son of Anacyndaraxes, built Anchialê and Tarsus in one day. Eat, drink, be merry, because all things else are not worth this," meaning the snapping of the fingers. Choerilus also mentions this inscription; and indeed the following verses are everywhere known: "Mine are all that I have eaten, and my loose indulgences and the delights of love that I have enjoyed; but those numerous blessings have been left behind."²

10. Above Anchialê lies Cyinda, a fortress, which at one time was used as a treasury by the Mace-

¹ 14. 5. 4.

² The whole of the epigram, as found in some of the MSS. (see critical note), is as follows: "Well aware that thou art by nature mortal, magnify the desires of thy heart, delighting thyself in merriments; there is no enjoyment for thee after death. For I too am dust, though I have reigned over great Ninus. Mine are all the food that I have eaten, and my loose indulgences, and the delights of love that I have enjoyed; but those numerous blessings have been left behind. This to mortal men is wise advice on how to live."

ταῦτ' ἔχω, ὅσα' ἔφαγον καὶ ἐφύβρισα καὶ μετ' ἔρωτος
τέρπν' ἔπαθον, τὰ δὲ πολλὰ καὶ ὀλβία κείνα λείπεται.
ἦδε σοφὴ βίότῳ παραινέσις ἀνθρώποισιν.

λακίῳ· ἦρε δὲ τὰ χρήματα Εὐμένης, ἀποστὰς Ἀντιγόνου. ἔτι δ' ὑπερθεν τοῦτου τε καὶ τῶν Σόλων ὀρεινὴ ἐστίν, ἐν ᾗ Ὀλβη πόλις, Διὸς ἱερὸν ἔχουσα, Αἶαντος Ἱδρυμα τοῦ Τεύκρου· καὶ ὁ ἱερεὺς δυνάστης ἐγίνετο τῆς Τραχειώτιδος· εἴτ' ἐπέθεντο τῇ χώρᾳ τύραννοι πολλοί, καὶ συνέστη τὰ ληστήρια. μετὰ δὲ τὴν τούτων κατάλυσιν ἐφ' ἡμῶν ἤδη τὴν τοῦ Τεύκρου δυναστείαν ταύτην ἐκάλουν, τὴν δ' αὐτὴν καὶ ἱεροσύνην· καὶ οἱ πλεῖστοί γε τῶν ἱερασαμένων ὠνομάζοντο Τεῦκροι ἢ Αἶαντες. εἰσιούσα δ' Ἀβα κατ' ἐπιγαμίαν εἰς τὸν οἶκον τοῦτον, ἡ Ζηνοφάνους θυγάτηρ, ἐνὸς τῶν τυράννων, αὐτὴ κατέσχε τὴν ἀρχήν, προλαβόντος τοῦ πατρὸς ἐν ἐπιτρόπου σχήματι· ὕστερον δὲ καὶ Ἀντώνιος καὶ Κλεοπάτρα κατεχαρίσαντο ἐκείνῃ, θεραπείαις ἐκλιπαρηθέντες· ἐπειθ' ἡ μὲν κατελύθη, τοῖς δ' ἀπὸ τοῦ γένους διέμεινεν ἡ ἀρχή. μετὰ δὲ τὴν Ἀγχιάλῃν αἰ τοῦ Κύδνου ἐκβολαὶ κατὰ τὸ Ῥῆγμα καλούμενον. ἔστι δὲ λιμνάζων τόπος, ἔχων καὶ παλαιὰ νεώρια, εἰς ὃν ἐκπίπτει ὁ Κύδνος ὁ διαρρέων μέσῃ τὴν Ταρσόν, τὰς ἀρχὰς ἔχων ἀπὸ τοῦ ὑπερκειμένου τῆς πόλεως Ταύρου· καὶ ἔστιν ἐπίνειον ἡ λίμνη τῆς Ταρσοῦ.

- Ο 673 11. Μέχρι μὲν δὴ δεῦρο ἢ παραλία πᾶσα, ἀπὸ τῆς Ῥοδίων περαιᾶς ἀρξαμένη, πρὸς ἰσημερινὰς ἀνατολὰς ἀπὸ τῶν ὁμωνύμων ἐκτείνεται δύσεων· εἴτ' ἐπὶ τὴν χειμερινὴν ἀνατολὴν ἐπιστρέφει μέχρι Ἰσσοῦ, κἀντεῦθεν ἤδη καμπὴν λαμβάνει πρὸς νότον μέχρι Φοινίκης, τὸ δὲ λοιπὸν πρὸς

¹ i.e. straight east and west.

donians. But the treasures were taken away by Eumenes, when he revolted from Antigonus. And still above this and Soli is a mountainous country, in which is a city Olbê, with a temple of Zeus, founded by Ajax the son of Teucer. The priest of this temple became dynast of Cilicia Tracheia; and then the country was beset by numerous tyrants, and the gangs of pirates were organised. And after the overthrow of these they called this country the domain of Teucer, and called the same also the priesthood of Teucer; and most of the priests were named Teucer or Ajax. But Aba, the daughter of Xenophanes, one of the tyrants, came into this family by marriage and herself took possession of the empire, her father having previously received it in the guise of guardian. But later both Antony and Cleopatra conferred it upon her as a favour, being moved by her courteous entreaties. And then she was overthrown, but the empire remained with her descendants. After Anchialê one comes to the outlets of the Cydnus, near the Rhegma, as it is called. It is a place that forms into a lake, having also ancient arsenals; and into it empties the Cydnus River, which flows through the middle of Tarsus and has its sources in the city Taurus, which lies above Tarsus. The lake is also the naval station of Tarsus.

11. Now thus far the seaboard as a whole, beginning at the Peraea of the Rhodians, extends towards the equinoctial east from the equinoctial west,¹ and then bends in the direction of winter sunrise² as far as Issus, and then forthwith takes a bend towards the south as far as Phoenicia; and the

² South-east (see Vol. I, p. 105, note 2).

δύσιν μέχρι στηλῶν τελευτᾶ. τὸ μὲν οὖν ἀληθές ὁ ἰσθμὸς τῆς περιωδευμένης χερρονήσου οὗτός ἐστιν ὁ ἀπὸ Ταρσοῦ καὶ τῆς ἐκβολῆς τοῦ Κύδνου μέχρι Ἀμισοῦ· τὸ γὰρ ἐλάχιστον ἐξ Ἀμισοῦ διάστημα ἐπὶ τοὺς Κιλικῶν ὄρους τοῦτ' ἐστίν· ἐντεῦθεν δὲ ἑκατὸν εἰκοσὶν εἰσιν εἰς Ταρσὸν στάδιοι, καὶ κεῖθεν οὐ πλείους¹ ἐπὶ τὴν ἐκβολὴν τοῦ Κύδνου. καὶ μὴν ἐπὶ γε Ἴσσον καὶ τὴν κατ' αὐτὴν θάλατταν οὗτ' ἄλλη ὁδὸς συντομωτέρα ἐστίν ἐξ Ἀμισοῦ τῆς διὰ Ταρσοῦ, οὗτ' ἐκ Ταρσοῦ ἐπὶ Ἴσσον ἐγγυτέρω ἐστίν ἢ ἐπὶ Κύδνον, ὥστε δῆλον, ὅτι ταῖς μὲν ἀληθείαις οὗτος ἂν εἴη ὁ ἰσθμὸς, λέγεται δ' ὅμως ὁ μέχρι τοῦ Ἰσικίου κόλπου, παρακλεπτόντων διὰ τὸ σημειῶδες. διὰ δὲ τοῦτ' αὐτὸ καὶ τὴν ἐκ τῆς Ῥοδίας γραμμὴν, ἣν μέχρι τοῦ Κύδνου κατηγάγομεν, τὴν αὐτὴν ἀποφαίνομεν² τῇ μέχρι Ἴσσοῦ, οὐδὲν παρὰ τοῦτο ποιούμενοι, καὶ τὸν Ταῦρόν φαμεν διήκειν ἐπ' εὐθείας τῇδε τῇ γραμμῇ μέχρι τῆς Ἰνδικῆς.

12. Ἡ δὲ Ταρσὸς κεῖται μὲν ἐν πεδίῳ, κτίσμα δ' ἐστὶ τῶν μετὰ Τριπτολέμου πλανηθέντων Ἀργείων κατὰ ζήτησιν Ἰοῦς· διαρρεῖ δ' αὐτὴν μέσσην ὁ Κύδνος παρ' αὐτὸ τὸ γυμνάσιον τῶν νέων· ἄτε δὴ τῆς πηγῆς οὐ πολὺ ἄπωθεν οὔσης, καὶ τοῦ ρείθρου διὰ φάραγγος βαθείας ἰόντος, εἴτ' εὐθὺς εἰς τὴν πόλιν ἐκπίπτουτος, ψυχρόν τε καὶ

¹ πέντε, after πλείους, all MSS. except F. The translator believes, with O. Müller, that Strabo wrote ἐβδομήκοντα (i.e. 6' and not 6').

² ἀποφαίνομεν, Groskurd and the later editors, instead of ἀποφαινόμενοι.

¹ i.e. the Pillars of Heracles at Gibraltar.

remainder extends towards the west as far as the Pillars¹ and there ends. Now the truth is that the actual isthmus of the peninsula which I have described is that which extends from Tarsus and the outlet of the Cydnus to Amisus, for this is the shortest distance from Amisus to the boundaries of Cilicia; and the distance thence to Tarsus is one hundred and twenty stadia, and the distance from there to the outlet of the Cydnus is no more than that. And in fact to Issus, and the sea near it, there is no other road from Amisus which is shorter than that through Tarsus, and Tarsus is not nearer to Issus than to the Cydnus;² and therefore it is clear that in reality this would be the isthmus; but still people call that which extends as far as the Gulf of Issus the true isthmus, thus betraying the facts because of the significance of the gulf. And it is because of this very thing that I, without making any accurate distinctions, represent the line from Rhodes, which I have prolonged to the Cydnus, to be the same as the line extending as far as Issus, and also assert that the Taurus extends in a straight line with that line as far as India.

12. As for Tarsus, it lies in a plain; and it was founded by the Argives who wandered with Triptolemus in quest of Io; and it is intersected in the middle by the Cydnus River, which flows past the very gymnasium of the young men. Now inasmuch as the source of the river is not very far away and its stream passes through a deep ravine and then empties immediately into the city, its discharge is both cold and swift; and hence it is helpful both

² i.e. the outlet of the Cydnus, at Rhegma.

ταχὺ τὸ ρεῦμά ἐστιν, ὅθεν καὶ τοῖς παχυνευροῦσι
 ροίζομένοις καὶ κτήνεσι καὶ ἀνθρώποις ἐπικουρεῖ.

13. Τοσαύτη δὲ τοῖς ἐνθάδε ἀνθρώποις σπουδὴ
 πρὸς τε φιλοσοφίαν καὶ τὴν ἄλλην παιδείαν
 ἐγκύκλιον ἅπασαν γέγονεν, ὥσθ' ὑπερβέβληνται
 καὶ Ἀθήνας καὶ Ἀλεξάνδρειαν καὶ εἰ τινα ἄλλον
 τόπον δυνατόν εἰπεῖν, ἐν ᾧ σχολαὶ καὶ διατριβαὶ
 φιλοσόφων γεγόνασι. διαφέρει δὲ τοσοῦτον, ὅτι
 ἐνταῦθα μὲν οἱ φιλομαθοῦντες ἐπιχώριοι πάντες
 εἰσὶ, ξένοι δ' οὐκ ἐπιδημοῦσι ῥαδίως· οὐδ' αὐτοὶ
 οὔτοι μένουσιν αὐτόθι, ἀλλὰ καὶ τελειοῦνται
 ἐκδημήσαντες, καὶ τελειωθέντες ξενιτεύουσιν
 ἠδέως, κατέρχονται δ' ὀλίγοι. ταῖς δ' ἄλλαις
 πόλεσιν, ἃς ἄρτίως εἶπον, πλὴν Ἀλεξανδρείας,
 συμβαίνει τὰναντία· φοιτῶσι γὰρ εἰς αὐτὰς
 C 674 πολλοὶ καὶ διατρίβουσιν αὐτόθι ἄσμενοι, τῶν δ'
 ἐπιχωρίων οὐ πολλοὺς οὔτ' ἂν ἔξω φοιτῶντας
 ἴδοις κατὰ φιλομάθειαν, οὔτ' αὐτόθι περὶ τοῦτο
 σπουδάζοντας· Ἀλεξανδρεῦσι δ' ἀμφοτέρω συμ-
 βαίνει· καὶ γὰρ δέχονται πολλοὺς τῶν ξένων
 καὶ ἐκπέμπουσι τῶν ἰδίων οὐκ ὀλίγους. καὶ εἰσι
 σχολαὶ παρ' αὐτοῖς παντοδαπαὶ τῶν περὶ λόγους
 τεχνῶν, καὶ τὰλλὰ τ' εὐανδρεῖ καὶ πλείστον
 δύναται, τὸν τῆς μητροπόλεως ἐπέχουσα λόγον.

14. Ἄνδρες δ' ἐξ αὐτῆς γεγόνασι τῶν μὲν
 στωικῶν Ἀντίπατρός τε καὶ Ἀρχέδημος καὶ
 Νέστωρ· ἔτι δ' Ἀθηνόδωροι δύο, ὧν ὁ μὲν,
 Κορδυλίῳ καλούμενος, συνεβίωσε Μάρκῳ

¹ i.e. to their schools.

to men and to cattle that are suffering from swollen sinews, if they immerse themselves in its waters.

13. The people at Tarsus have devoted themselves so eagerly, not only to philosophy, but also to the whole round of education in general, that they have surpassed Athens, Alexandria, or any other place that can be named where there have been schools and lectures of philosophers. But it is so different from other cities that there the men who are fond of learning are all natives, and foreigners are not inclined to sojourn there; neither do these natives stay there, but they complete their education abroad; and when they have completed it they are pleased to live abroad, and but few go back home. But the opposite is the case with the other cities which I have just mentioned except Alexandria; for many resort to them and pass time there with pleasure, but you would not see many of the natives either resorting to places outside their country through love of learning or eager about pursuing learning at home. With the Alexandrians, however, both things take place, for they admit¹ many foreigners and also send not a few of their own citizens abroad. Further, the city of Tarsus has all kinds of schools of rhetoric; and in general it not only has a flourishing population but also is most powerful, thus keeping up the reputation of the mother-city.²

14. The following men were natives of Tarsus: among the Stoics, Antipater and Archedemus and Nestor; and also the two Athenodoruses, one of whom, called Cordylion, lived with Marcus Cato

² i.e. in spite of the fact that so many able men leave the city and never return.

Κάτωνι, καὶ ἐτελεύτα¹ παρ' ἐκείνῳ, ὁ δὲ τοῦ Σάνδωνος, ὃν καὶ Κανανίτην φασὶν ἀπὸ κώμης τινός, Καίσαρος καθηγῆσατο καὶ τιμῆς ἔτυχε μεγάλης· κατιῶν τε εἰς τὴν πατρίδα ἤδη γηραιὸς κατέλυσε τὴν καθεστῶσαν πολιτείαν, κακῶς φερομένην ὑπὸ τε ἄλλων καὶ Βοηθοῦ, κακοῦ μὲν ποιητοῦ, κακοῦ δὲ πολίτου, δημοκοπίαις ἰσχύσαντος τὸ πλεόν. ἐπήρε δ' αὐτὸν καὶ Ἀντώνιος, κατ' ἀρχὰς ἀποδεξάμενος τὸ γραφέν εἰς τὴν ἐν Φιλίπποις νίκην ἔπος, καὶ ἔτι μᾶλλον ἢ εὐχέρεια ἢ ἐπιπολάζουσα παρὰ τοῖς Ταρσεῦσιν, ὥστ' ἀπαύστως σχεδιάζειν παρὰ χρήμα πρὸς τὴν δεδομένην ὑπόθεσιν· καὶ δὴ καὶ γυμνασιάρχίαν ὑποσχόμενος Ταρσεῦσι τοῦτον ἀντὶ γυμνασιάρχου² κατέστησε, καὶ τὰ ἀναλώματα ἐπίστευσεν αὐτῷ. ἐφωράθη δὲ νοσφισάμενος τὰ τε ἄλλα καὶ τοῦλαιον· ἐλεγχόμενος δ' ὑπὸ τῶν κατηγόρων ἐπὶ τοῦ Ἀντωνίου, παρητεῖτο τὴν ὀργήν, σὺν ἄλλοις καὶ ταῦτα λέγων, ὅτι, "Ὡς περ Ὀμηρος ἐξύμνησεν Ἀχιλλέα καὶ Ἀγαμέμνονα καὶ Ὀδυσσέα, οὕτως ἐγὼ σέ· οὐ δίκαιος οὖν εἰμὶ εἰς τοιαύτας ἄγεσθαι διαβολὰς ἐπὶ σοῦ. παραλαβὼν οὖν ὁ κατήγορος τὸν λόγον, Ἀλλ' Ὀμηρος μὲν, ἔφη, ἔλαιον³ Ἀγαμέμνονος οὐκ ἔκλεψεν, ἀλλ' οὐδὲ Ἀχιλλέως, σὺ δέ· ὥστε δώσεις δίκην. διακρουσάμενος δ' οὖν θεραπείαις τισὶ τὴν ὀργήν, οὐδὲν ἥττον διετέλεσεν ἄγων καὶ φέρων τὴν πόλιν μέχρι τῆς καταστροφῆς τοῦ Ἀντωνίου. τοιαύτην δὲ τὴν πόλιν κατα-

¹ ἐτελεύτα, Corais, for τελεύτα.

² ἀντὶ γυμνασιάρχου *sic*, ἀντιγυμνασίάρχον other MSS.

³ μὲν, after ἔλαιον, omitted by *moisozz*.

and died at his house; and the other, the son of Sandon, called Cananites after some village, was Caesar's teacher and was greatly honoured by him; and when he returned to his native land, now an old man, he broke up the government there established, which was being badly conducted by Boethus, among others, who was a bad poet and a bad citizen, having prevailed there by currying the favour of the people. He had been raised to prominence by Antony, who at the outset received favourably the poem which he had written upon the victory at Philippi, but still more by that facility prevalent among the Tarsians whereby he could instantly speak offhand and unceasingly on any given subject. Furthermore, Antony promised the Tarsians an office of gymnasiarch, but appointed Boethus instead of a gymnasiarch, and entrusted to him the expenditures. But Boethus was caught secreting, among other things, the olive-oil; and when he was being proven guilty by his accusers in the presence of Antony he deprecated Antony's wrath, saying, among other things, that "Just as Homer had hymned the praises of Achilles and Agamemnon and Odysseus, so I have hymned thine. It is not right, therefore, that I should be brought before you on such slanderous charges." When, however, the accuser caught the statement, he said, "Yes, but Homer did not steal Agamemnon's oil, nor yet that of Achilles, but you did; and therefore you shall be punished." However, he broke the wrath of Antony by courteous attentions, and no less than before kept on plundering the city until the overthrow of Antony. Finding the city in this plight,

λαβὼν ὁ Ἀθηνόδωρος, τέως μὲν ἐπεχείρει λόγῳ
μετάγειν καὶ κεῖνον καὶ τοὺς συστασιώτας· ὥς δ'
οὐκ ἀπείχοντο ὕβρεως οὐδεμιᾶς, ἐχρήσατο τῇ
δοθείσῃ ὑπὸ τοῦ Καίσαρος ἐξουσία καὶ ἐξέβαλεν
αὐτοὺς, καταγνοὺς φυγῇν. οἱ δὲ πρῶτον μὲν
κατετοιχογράφησαν αὐτοῦ τοιαῦτα·

C 675 ἔργα νέων, βουλαὶ δὲ μέσων, πορδαὶ δὲ γερόν-
των.

ἐπεὶ δ' ἐκεῖνος ἐν παιδιᾷς μέρει δεξάμενος
ἐκέλευσε παρεπιγράψαι "—βρονταὶ δὲ γερόν-
των," καταφρονήσας δὲ τις τοῦ ἐπιεικοῦς,
εὖλυτον τὸ κοιλίδιον ἔχων, προσέρρανε πολὺ
τῇ θύρᾳ καὶ τῷ τοίχῳ, νύκτωρ παριὼν τὴν
οἰκίαν. ὁ δὲ τῆς στάσεως κατηγορῶν ἐν ἐκ-
κλησίᾳ, τὴν νόσον τῆς πόλεως, ἔφη, καὶ τὴν
καχεξίαν πολλαχόθεν σκοπεῖν ἔξεστι, καὶ δὴ
καὶ ἐκ τῶν διαχωρημάτων. οὗτοι μὲν στωικοὶ
ἄνδρες· ἀκαδημαϊκὸς δὲ Νέστωρ ὁ καθ' ἡμᾶς, ὁ
Μαρκέλλου καθηγησάμενος, τοῦ Ὀκταουίας
παιδός, τῆς Καίσαρος ἀδελφῆς. καὶ οὗτος δὲ
προέστη τῆς πολιτείας, διαδεξάμενος τὸν Ἀθη-
νόδωρον, καὶ διετέλεσε τιμώμενος παρά τε τοῖς
ἡγεμόσι καὶ ἐν τῇ πόλει.

15. Τῶν δ' ἄλλων φιλοσόφων,

οὓς κεν εὖ γινώην καὶ τοῦνομα μυθησαίμην,

Πλουτιάδης τε ἐγένετο καὶ Διογένης τῶν περι-
πολιζόντων καὶ σχολὰς διατιθεμένων εὐφυῶς·
ὁ δὲ Διογένης καὶ ποιήματα ὥσπερ ἀπεφοίβαζε,
τεθείσης ὑποθέσεως, τραγικὰ ὡς ἐπὶ πολὺ· γραμ-
ματικοὶ δέ, ὧν καὶ συγγράμματά ἐστιν, Ἀρτε-
μίδωρός τε καὶ Διόδωρος· ποιητὴς δὲ τραγῳδίας

Athenodorus for a time tried to induce both Boethus and his partisans to change their course; but since they would abstain from no act of insolence, he used the authority given him by Caesar, condemned them to exile, and expelled them. These at first indicted him with the following inscription on the walls: "Work for young men, counsels for the middle-aged, and flatulence for old men"; and when he, taking the inscription as a joke, ordered the following words to be inscribed beside it, "thunder for old men," someone, contemptuous of all decency and afflicted with looseness of the bowels, profusely bespattered the door and wall of Athenodorus' house as he was passing by it at night. Athenodorus, while bringing accusations in the assembly against the faction, said: "One may see the sickly plight and the disaffection of the city in many ways, and in particular from its excrements." These men were Stoics; but the Nestor of my time, the teacher of Marcellus, son of Octavia the sister of Caesar, was an Academician. He too was at the head of the government of Tarsus, having succeeded Athenodorus; and he continued to be held in honour both by the prefects and in the city.

15. Among the other philosophers from Tarsus, "whom I could well note and tell their names,"¹ are Plutarch and Diogenes, who were among those philosophers that went round from city to city and conducted schools in an able manner. Diogenes also composed poems, as if by inspiration, when a subject was given him—for the most part tragic poems; and as for grammarians whose writings are extant, there are Artemidorus and Diodorus; and

¹ *Iliad* 3. 235.

λαβὼν ὁ Ἀθηνόδωρος, τέως μὲν ἐπεχειρεῖ λόγῳ
μετάγειν καὶ κεῖνον καὶ τοὺς συστασιώτας· ὥς δ'
οὐκ ἀπείχοντο ὕβρεως οὐδεμιᾶς, ἐχρήσατο τῇ
δοθείσῃ ὑπὸ τοῦ Καίσαρος ἐξουσία καὶ ἐξέβαλεν
αὐτοὺς, καταγνοὺς φυγὴν. οἱ δὲ πρῶτον μὲν
κατετοιχογράφησαν αὐτοῦ τοιαῦτα·

C 675 ἔργα νέων, βουλαὶ δὲ μέσων, πορδαὶ δὲ γερόν-
των.

ἐπεὶ δ' ἐκεῖνος ἐν παιδιᾷς μέρει δεξάμενος
ἐκέλευσε παρεπιγράψαι "—βρονταὶ δὲ γερόν-
των," καταφρονήσας δὲ τις τοῦ ἐπιεικοῦς,
εὖλυτον τὸ κοιλίδιον ἔχων, προσέρρανε πολὺ
τῇ θύρᾳ καὶ τῷ τοίχῳ, νύκτωρ παριὼν τὴν
οἰκίαν. ὁ δὲ τῆς στάσεως κατηγορῶν ἐν ἐκ-
κλησίᾳ, τὴν νόσον τῆς πόλεως, ἔφη, καὶ τὴν
καχεξίαν πολλαχόθεν σκοπεῖν ἔξεστι, καὶ δὴ
καὶ ἐκ τῶν διαχωρημάτων. οὗτοι μὲν στωικοὶ
ἄνδρες· ἀκαδημαϊκὸς δὲ Νέστωρ ὁ καθ' ἡμᾶς, ὁ
Μαρκέλλου καθηγησάμενος, τοῦ Ὀκταουίας
παιδός, τῆς Καίσαρος ἀδελφῆς. καὶ οὗτος δὲ
προέστη τῆς πολιτείας, διαδεξάμενος τὸν Ἀθη-
νόδωρον, καὶ διετέλεσε τιμώμενος παρὰ τε τοῖς
ἡγεμόσι καὶ ἐν τῇ πόλει.

15. Τῶν δ' ἄλλων φιλοσόφων,

οὓς κεν εὖ γνοίην καὶ τοῦνομα μνηθσαίμην,

Πλουτιάδης τε ἐγένετο καὶ Διογένης τῶν περι-
πολιζόντων καὶ σχολὰς διατιθεμένων εὐφυῶς·
ὁ δὲ Διογένης καὶ ποιήματα ὥσπερ ἀπεφοίβαζε,
τεθείσης ὑποθέσεως, τραγικὰ ὡς ἐπὶ πολὺ· γραμ-
ματικοὶ δέ, ὧν καὶ συγγράμματά ἐστιν, Ἀρτε-
μίδωρός τε καὶ Διόδωρος· ποιητὴς δὲ τραγῳδίας

Athenodorus for a time tried to induce both Boethus and his partisans to change their course; but since they would abstain from no act of insolence, he used the authority given him by Caesar, condemned them to exile, and expelled them. These at first indicted him with the following inscription on the walls: "Work for young men, counsels for the middle-aged, and flatulence for old men"; and when he, taking the inscription as a joke, ordered the following words to be inscribed beside it, "thunder for old men," someone, contemptuous of all decency and afflicted with looseness of the bowels, profusely bespattered the door and wall of Athenodorus' house as he was passing by it at night. Athenodorus, while bringing accusations in the assembly against the faction, said: "One may see the sickly plight and the disaffection of the city in many ways, and in particular from its excrements." These men were Stoics; but the Nestor of my time, the teacher of Marcellus, son of Octavia the sister of Caesar, was an Academician. He too was at the head of the government of Tarsus, having succeeded Athenodorus; and he continued to be held in honour both by the prefects and in the city.

15. Among the other philosophers from Tarsus, "whom I could well note and tell their names,"¹ are Plutarch and Diogenes, who were among those philosophers that went round from city to city and conducted schools in an able manner. Diogenes also composed poems, as if by inspiration, when a subject was given him—for the most part tragic poems; and as for grammarians whose writings are extant, there are Artemidorus and Diodorus; and

¹ *Iliad* 3, 235.

ἄριστος τῶν τῆς Πλειάδος καταριθμουμένων Διονυσίδης. μάλιστα δ' ἡ Ῥώμη¹ δύναται διδάσκειν τὸ πλῆθος τῶν ἐκ τῆσδε τῆς πόλεως φιλολόγων· Ταρσέων γὰρ καὶ Ἀλεξανδρέων ἐστὶ μεστή. τοιαύτη μὲν ἡ Ταρσός.

16. Μετὰ δὲ τὸν Κύδνον ὁ Πύραμος ἐκ τῆς Καταονίας ῥέων, οὐπερ καὶ πρότερον ἐμνήσθημεν· φησὶ δ' Ἀρτεμίδωρος, ἐντεύθεν εἰς Σόλους εὐθυπλοία σταδίου εἶναι πεντακοσίους. πλησίον δὲ καὶ Μαλλός, ἐφ' ὕψους κειμένη, κτίσμα Ἀμφιλόχου καὶ Μόψου, τοῦ Ἀπόλλωνος καὶ Μαντοῦς,² περὶ ὧν πολλὰ μυθολογεῖται· καὶ δὴ καὶ ἡμεῖς ἐμνήσθημεν αὐτῶν ἐν τοῖς περὶ Κάλχαντος λόγοις καὶ τῆς ἔριδος, ἣν ἤρισαν περὶ τῆς μαντικῆς ὃ τε Κάλχας καὶ ὁ Μόψος· ταύτην τε γὰρ τὴν ἔριν μεταφέρουσιν ἔνιοι, καθάπερ καὶ Σοφοκλῆς, εἰς τὴν Κιλικίαν, καλέσας ἐκεῖνος αὐτὴν Παμφυλίαν τραγικῶς, καθάπερ καὶ τὴν Λυκίαν Καρίαν καὶ τὴν Τροίαν καὶ Λυδίαν³ Φρυγίαν· καὶ τὸν θάνατον δὲ τοῦ Κάλχαντος ἐνταῦθα παραδιδόασιν ἄλλοι τε καὶ Σοφοκλῆς. οὐ μόνον δὲ τὴν περὶ τῆς μαντικῆς ἔριν μεμνησκάσιν, ἀλλὰ καὶ τῆς ἀρχῆς. τὸν γὰρ Μόψον φασὶ καὶ τὸν Ἀμφίλοχον ἐκ Τροίας
 O 676 ἐλθόντας κτίσαι Μαλλόν· εἴτ' Ἀμφίλοχον εἰς Ἄργος ἀπελθεῖν, δυσαρεστήσαντα δὲ τοῖς ἐκεῖ πάλιν ἀναστρέψαι δεῦρο, ἀποκλειόμενον δὲ τῆς κοινωνίας συμβαλεῖν εἰς μονομαχίαν πρὸς τὸν

¹ ἡ Ῥώμη, Sihler (*American Journal of Philology*, 1923, p. 141) would emend to τὴν Ῥώμην.

² Μαντοῦς, Xylander, for Λητοῦς; so the later editors.

³ καί, before Φρυγίαν, Groskurd omits, so Meineke.

the best tragic poet among those enumerated in the "Pleias"¹ was Dionysides. But it is Rome that is best able to tell us the number of learned men from this city;² for it is full of Tarsians and Alexandrians. Such is Tarsus.

16. After the Cydnus River one comes to the Pyramus River, which flows from Cataonia, a river which I have mentioned before.³ According to Artemidorus, the distance thence to Soli in a straight voyage is five hundred stadia. Near by, also, is Mallus, situated on a height, founded by Amphiloehus and Mopsus, the latter the son of Apollo and Manto, concerning whom many myths are told. And indeed I, too, have mentioned them in my account of Calchas⁴ and of the quarrel between Calchas and Mopsus about their powers of divination. For some writers transfer this quarrel, Sophocles, for example, to Cilicia, which he, following the custom of tragic poets, calls Pamphylia, just as he calls Lycia "Caria"⁵ and Troy and Lydia "Phrygia." And Sophocles, among others, tells us that Calchas died there. But, according to the myth, the contest concerned, not only the power of divination, but also the sovereignty; for they say that Mopsus and Amphiloehus went from Troy and founded Mallus, and that Amphiloehus then went away to Argos, and, being dissatisfied with affairs there, returned to Mallus, but that, being excluded from a share in the government there, he fought a duel with Mopsus,

¹ i.e. the "Seven (Alexandrian) Stars," referring to the Pleiades, the seven daughters of Atlas, who were placed by Zeus among the stars and became one of the oldest Greek constellations.

² See critical note.

³ 12. 2. 4.

⁴ 14. 1. 27.

⁵ See 14. 3. 3.

Μόψον, πεσόντας δ' ἀμφοτέρους ταφῆναι μὴ ἐν ἐπόψει ἀλλήλοις· καὶ νῦν οἱ τάφοι δείκνυνται περὶ Μάγαρσα τοῦ Πυράμου πλησίον. ἐντεῦθεν δ' ἦν Κράτης ὁ γραμματικός, οὗ φησὶ γενέσθαι μαθητῆς Παναίτιος.

17. Ὑπέρκειται δὲ τῆς παραλίας ταύτης Ἀλήιον πεδίων, δι' οὗ Φιλώτας διήγαγεν Ἀλεξάνδρῳ τὴν ἵππον, ἐκείνου τὴν φάλαγγα ἀγαγόντος ἐκ τῶν Σόλων διὰ τῆς παραλίας καὶ τῆς Μαλλώτιδος ἐπὶ τε Ἰσσὸν καὶ τὰς Δαρείου δυνάμεις. φασὶ δὲ καὶ ἐναγίσαι τῷ Ἀμφιλόχῳ τὸν Ἀλέξανδρον διὰ τὴν ἐξ Ἀργους συγγένειαν. Ἡσιόδος δ' ἐν Σόλοις ὑπὸ Ἀπόλλωνος ἀναιρεθῆναι τὸν Ἀμφίλοχόν φησιν, οἱ δὲ περὶ τὸ Ἀλήιον πεδίων, οἱ δ' ἐν Συρίᾳ, ἀπὸ τοῦ Ἀληίου ἀπιόντα διὰ τὴν ἔριν.

18. Μετὰ δὲ Μαλλὸν Αἰγαῖαι πολίχμιον, ὕφορμον ἔχον· εἴτ' Ἀμανίδες πύλαι, ὕφορμον ἔχουσαι, εἰς ἃς τελευτᾷ τὸ Ἀμανὸν ὄρος ἀπὸ τοῦ Ταύρου καθῆκον, ὃ τῆς Κιλικίας ὑπερκειται κατὰ τὸ πρὸς ἑὸ μέρος, αἰὲ μὲν ὑπὸ πλειόνων δυναστευόμενον τυράννων, ἐχόντων ἐρύματα· καθ' ἡμᾶς δὲ κατέστη κύριος πάντων ἀνὴρ ἀξιόλογος καὶ βασιλεὺς ὑπὸ Ῥωμαίων ὠνομάσθη διὰ τὰς ἀνδραγαθίας Ταρκονδίμοτος,¹ καὶ τὴν διαδοχὴν τοῖς μετ' αὐτὸν παρέδωκε.

19. Μετὰ δὲ Αἰγαίας Ἰσσοὺς πολίχμιον ὕφορμον ἔχον καὶ ποταμὸς Πίναρος.² ἐνταῦθα ὁ ἀγὼν συνέπεσεν Ἀλεξάνδρῳ καὶ Δαρείῳ· καὶ ὁ

¹ Ταρκονδίμοτος, Casaubon, for Ταρκοδίμεντος CE, Ταρκδήμεντος other MSS.

² Πίναρος, Tzschucke, for Πίδνος D, Πίνδος other MSS.

and that both fell in the duel and were buried in places that were not in sight of one another. And to-day their tombs are to be seen in the neighbourhood of Magarsa near the Pyramus River. This¹ was the birthplace of Crates the grammarian, of whom Panaetius is said to have been a pupil.

17. Above this coast lies the Aleian Plain, through which Philotas led the cavalry for Alexander, when Alexander led his phalanx from Soli along the coast and the territory of Mallus against Issus and the forces of Dareius. It is said that Alexander performed sacrifices to Amphiloehus because of his kinship with the Argives. Hesiod says that Amphiloehus was slain by Apollo at Soli; but others say that he was slain in the neighbourhood of the Aleian Plain, and others in Syria, when he was quitting the Aleian Plain because of the quarrel.

18. After Mallus one comes to Aegaeae, a small town, with a mooring-place; and then to the Amanides Gates, with a mooring-place, where ends the mountain Amanus, which extends down from the Taurus and lies above Cilicia towards the east. It was always ruled by several powerful tyrants, who possessed strongholds; but in my time a notable man established himself as lord of all, and was named king by the Romans because of his manly virtues—I refer to Tarcondimotus, who bequeathed the succession to his posterity.

19. After Aegaeae, one comes to Issus, a small town with a mooring-place, and to the Pinarus River. It was here that the struggle between Alexander and Dareius occurred; and the gulf is

¹ Mallus.

κόλπος εἴρηται Ἰσσικός· ἐν αὐτῷ δὲ πόλις Ῥωσὸς καὶ Μυρίανδρος πόλις καὶ Ἀλεξάνδρεια καὶ Νικόπολις καὶ Μόψου ἐστία καὶ Πύλαι λεγόμεναι, ὄριον Κιλικίων τε καὶ Σύρων. ἐν δὲ τῇ Κιλικίᾳ ἐστὶ καὶ τὸ τῆς Σαρπηδονίας Ἀρτέμιδος ἱερὸν καὶ μαντεῖον, τοὺς δὲ χρησμοὺς ἔνθεοι προθεσπίζουσιν.

20. Μετὰ δὲ τὴν Κιλικίαν πρώτη πόλις ἐστὶ τῶν Σύρων Σελεύκεια, ἢ ἐν Πιερίᾳ, καὶ πλησίον Ὀρόντης ἐκδίδωσι ποταμός. ἔστι δ' ἀπὸ Σελευκείας εἰς Σόλους ἐπ' εὐθείας πλοῦς ὀλίγον ἀπολείπων τῶν χιλίων σταδίων.

21. Τῶν δ' ἐν Τροίᾳ Κιλικίων, ὧν Ὅμηρος μέμνηται, πολὺν διεστώτων ἀπὸ τῶν ἔξω τοῦ Ταύρου Κιλικίων, οἱ μὲν ἀποφαίνουσιν ἀρχηγέτας τοὺς ἐν τῇ Τροίᾳ τούτων καὶ δεικνύουσιν τινὰς τόπους κἀνταῦθα, ὥσπερ ἐν τῇ Παμφυλίᾳ Θήβην καὶ Λυρνησσόν, οἱ δ' ἔμπαλιν καὶ Ἀλλήϊόν τι πεδίον κἀκεῖ δεικνύουσι.

Περιωδευμένων δὲ καὶ τῶν ἔξω τοῦ Ταύρου μερῶν τῆς προειρημένης χερρονήσου, προσθετέον ἐστὶ καὶ ταῦτα.

C 677 22. Ὁ γὰρ Ἀπολλόδωρος ἐν τοῖς περὶ νεῶν ἔτι καὶ τοιαῦτα λέγει· τοὺς γὰρ ἐκ τῆς Ἀσίας ἐπικούρους τῶν Τρώων ἅπαντας καταριθμεῖσθαι φησιν ὑπὸ τοῦ ποιητοῦ τῆς χερρονήσου κατοίκους ὄντας, ἧς ὁ στενωτάτος ἰσθμός ἐστι τὸ μεταξὺ τοῦ κατὰ Σινώπην μυχοῦ καὶ Ἰσσοῦ· αἱ δ' ἐκτὸς πλευραί, φησί, τριγωνοειδοὺς οὐσῃς, εἰσὶ μὲν ἄνισοι, παρήκουσι δὲ ἢ μὲν ἀπὸ Κιλικίας ἐπὶ Χελιδονίαξ, ἢ δ' ἐνθένδε ἐπὶ τὸ στόμα τοῦ Εὐξείνου, ἢ δ' ἐπὶ Σινώπην πάλιν ἐνθένδε. τὸ

called the Issic Gulf. On this gulf are situated the city Rhosus, the city Myriandrus, Alexandria, Nicopolis, Mopsuestia, and Pylae, as it is called, which is the boundary between the Cilicians and the Syrians. In Cilicia is also the temple and oracle of the Sarpedonian Artemis; and the oracles are delivered by persons who are divinely inspired.

20. After Cilicia the first Syrian city is Seleuceia-in-Picria, near which the Orontes River empties. The voyage from Seleuceia to Soli, on a straight course, is but little short of one thousand stadia.

21. Since the Cilicians in the Troad whom Homer mentions are far distant from the Cilicians outside the Taurus, some represent those in Troy as original colonisers of the latter, and point out certain places of the same name there, as, for example, Thebê and Lyrnessus in Pamphylia, whereas others of contrary opinion point out also an Aleïan Plain in the former.

Now that the parts of the aforesaid peninsula outside the Taurus have been described, I must add what follows.

22. Apollodorus, in his work *On the Catalogue of Ships*, goes on to say to this effect, that all the allies of the Trojans from Asia were enumerated by the poet as being inhabitants of the peninsula, of which the narrowest isthmus is that between the innermost recess at Sinopê and Issus. And the exterior sides of this peninsula, he says, which is triangular in shape, are unequal in length, one of them extending from Cilicia to the Chelidonian Islands, another from the Chelidonian Islands to the mouth of the Euxine, and the third thence back to Sinopê. Now the assertion that the allies were

μὲν οὖν μόνους τοὺς ἐν τῇ χερρονήσῳ διὰ τῶν
 αὐτῶν ἐλέγχοιτ' ἂν ψεῦδος ὄν, δι' ὧν ἠλέγξαμεν
 πρότερον, μὴ μόνους τοὺς ἐντὸς Ἀλυσ. οἱ γὰρ
 περὶ Φαρνακίαν τόποι, ἐν οἷς τοὺς Ἀλιζώνους
 ἔφαμεν, ὥσπερ ἔξω τοῦ Ἀλυσ εἰσιν, οὕτω καὶ
 ἔξω τοῦ ἰσθμοῦ, εἶπερ καὶ τῶν στενῶν τῶν
 μεταξὺ Σινώπης καὶ Ἰσσοῦ, καὶ οὐ τούτων γε
 μόνων, ἀλλὰ καὶ τῶν κατ' ἀλήθειαν στενῶν τῶν
 μεταξὺ Ἀμισοῦ τε καὶ Ἰσσοῦ· οὐδὲ γὰρ ἐκεῖνος
 ὀρθῶς ἀφώρισται τὸν ἰσθμόν καὶ τὰ κατ' αὐτὸν
 στενά, ἐκεῖνα ἀντὶ τούτων τιθεῖς. πάντων δ'
 εὐθιθέστατον τὸ τὴν χερρόνησον τριγωνοειδῆ
 φήσαντα τρεῖς ἀποφύνασθαι τὰς ἔξω πλευράς·
 ὁ γὰρ τὰς ἔξω λέγων πλευράς ἔοικεν ὑπεξαι-
 ρουμένῳ τὴν κατὰ τὰ στενά, ὡς καὶ ταύτην
 οὔσαν πλευράν, οὐκ ἔξω δὲ οὐδ' ἐπὶ θαλάττῃ.
 εἰ μὲν τοίνυν τὰ στενά ταῦτα οὕτως ἦν σινηγ-
 μένα, ὥστε μικρὸν ἀπολείπειν τοῦ συνάπτειν ἐπ'
 ἀλλήλαις τὴν τε ἐπὶ Ἰσσὸν καὶ τὴν ἐπὶ Σινώπην
 πίπτουσιν πλευράν, συνεχώρει ἂν τριγωνοειδῆ
 λέγεσθαι τὴν χερρόνησον· νῦν δὲ γε τρισχιλίους
 σταδίους ἀπολειπόντων μεταξὺ τῶν ὑπ' αὐτοῦ
 λεγομένων στενῶν, ἀμαθία τὸ λέγειν τριγωνοειδὲς
 τὸ τοιοῦτον τετράπλευρον, οὐδὲ χωρογραφικόν.
 ὁ δὲ καὶ χωρογραφίαν ἐξέδωκεν ἐν κωμικῇ
 μέτρῳ, γῆς περίοδον ἐπιγράψας. μένει δ' ἡ
 αὐτὴ ἀμαθία, κὰν εἰς τοῦλάχιστον καταγάγῃ
 διάστημά τις τὸν ἰσθμόν, ὅσον εἰρήκασιν οἱ
 πλεῖστον ψευσάμενοι τὸ ἥμισυ τοῦ παντός, ὅσον
 εἶρηκε καὶ Ἀρτεμίδωρος, χιλίους καὶ πεντακο-

¹ 12. 3. 24.

² Iambic verse.

alone those who lived in the peninsula can be proved wrong by the same arguments by which I have previously shown that the allies were not alone those who lived this side the Halys River.¹ For just as the places round Pharnacia, in which, as I said, the Halizoni lived, are outside the Halys River, so also they are outside the isthmus, if indeed they are outside the narrows between Sinopê and Issus; and not outside these alone, but also outside the true narrows between Amisus and Issus, for he too incorrectly defines the isthmus and its narrows, since he substitutes the former for the latter. But the greatest absurdity is this, that, after calling the peninsula triangular in shape, he represents the "exterior sides" as three in number; for when he speaks of the "exterior sides" he seems privily to exclude the side along the narrows, as though this too were a side, but not "exterior" or on the sea. If, then, these narrows were so shortened that the exterior side ending at Issus and that ending at Sinopê lacked but little of joining one another, one might concede that the peninsula should be called triangular; but, as it is, since the narrows mentioned by him leave a distance of three thousand stadia between Issus and Sinopê, it is ignorance and not knowledge of chorography to call such a four-sided figure triangular. Yet he published in the metre of comedy² a work on chorography entitled *A Description of the Earth*. The same ignorance still remains even though one should reduce the isthmus to the minimum distance, I mean, to one-half of the whole distance, as given by those who have most belied the facts, among whom is also Artemidorus,

σίους σταδίους· οὐδὲ γὰρ τοῦτο συναγωγὴν πω
 τριγωνοειδοῦς ποιεῖ σχήματος. ἀλλ' οὐδὲ τὰς
 πλευρὰς ὀρθῶς διήρηται τὰς ἔξω, τὴν ἀπὸ Ἰσσοῦ
 μέχρι Χελιδονίων εἰπών· λοιπὴ γὰρ ἐστὶν ὅλη
 ἐπ' εὐθείας ἡ Λυκτικὴ παραλία ταύτη, καὶ ἡ
 τῶν Ῥοδίων περαία μέχρι Φύσκου· ἐντεῦθεν δὲ
 καμπὴν λαβοῦσα ἡ ἡπειρος ἄρχεται τὴν δευτέραν
 καὶ δυσμικὴν ποιεῖν πλευρὰν ἄχρι Προποντίδος
 καὶ Βυζαντίου.

U 678 23. Φήσαντος δὲ τοῦ Ἐφόρου, διότι τὴν
 χερρόνησον κατοικεῖ ταύτην ἑκατάδεκα γένη,
 τρία μὲν Ἑλληνικά, τὰ δὲ λοιπὰ βάρβαρα
 χωρὶς τῶν μυγίδων, ἐπὶ θαλάττῃ μὲν Κίλικες
 καὶ Πάμφυλοι καὶ Λύκιοι καὶ Βιθυνοὶ καὶ
 Παφλαγόνες καὶ Μαριανδυνοὶ καὶ Τρώες καὶ
 Κᾶρες, Πισίδαι δὲ καὶ Μυσοὶ καὶ Χάλυβες καὶ
 Φρύγες καὶ Μελύαι ἐν τῇ μεσογαίᾳ, διαιτῶν¹
 ταῦτα ὁ Ἀπολλόδωρος ἑπτακαίδεκάτὸν φησὶν
 εἶναι τὸ τῶν Γαλατῶν, ὃ νεώτερόν ἐστι τοῦ
 Ἐφόρου, τῶν δ' εἰρημένων τὰ μὲν Ἑλληνικὰ
 μήπω κατὰ² τὰ Τρωικὰ κατωκίσθαι, τὰ δὲ
 βάρβαρα πολλὴν ἔχειν³ σύγχυσιν διὰ τὸν
 χρόνον καταλέγεσθαι δ' ὑπὸ τοῦ ποιητοῦ τό
 τε τῶν Τρώων⁴ καὶ τῶν νῦν ὀνομαζομένων
 Παφλαγόνων καὶ Μυσῶν καὶ Φρυγῶν καὶ
 Καρῶν καὶ Λυκίων,⁵ Μήονάς τε ἀντὶ Λυδῶν
 καὶ ἄλλους ἀγνώτας, οἷον Ἀλιζῶνας καὶ Καύ-
 κωνας· ἐκτὸς δὲ τοῦ καταλόγου Κητείους τε καὶ

¹ διαιτῶν, Corais, for διαιρῶν.

² κατὰ, Casaubon, for καὶ τά.

³ ἔχειν F, ἔχει other MSS.

⁴ Τρώων ποτ, Τρωικῶν other MSS.

that is, fifteen hundred stadia; for even this does not contract the side along the narrows enough to make the peninsula a triangular figure. Neither does Artemidorus correctly distinguish the exterior sides when he speaks of "the side that extends from Issus as far as the Chelidonian Islands," for there still remains to this side the whole of the Lycian coast, which lies in a straight line with the side he mentions, as does also the Peraea of the Rhodians as far as Physcus. And thence the mainland bends and begins to form the second, or westerly, side extending as far as the Propontis and Byzantium.

23. But though Ephorus said that this peninsula was inhabited by sixteen tribes, of which three were Hellenic and the rest barbarian, except those that were mixed, adding that the Cilicians, Pamphylians, Lycians, Bithynians, Paphlagonians, Mariandynians, Trojans, and Carians lived on the sea, but the Pisidians, Mysians, Chalybians, Phrygians, and Milyans in the interior, Apollodorus, who passes judgment upon this matter, says that the tribe of the Galatians, which is more recent than the time of Ephorus, is a seventeenth, and that, of the afore-said tribes, the Hellenic had not yet, in the time of the Trojan War, settled there, and that the barbarian tribes are much confused because of the lapse of time; and that the poet names in his *Catalogue* the tribes of the Trojans and of the Paphlagonians, as they are now named, and of the Mysians and Phrygians and Carians and Lycians, as also the Meionians, instead of the Lydians, and other unknown peoples, as, for example, the Halizones and Caucones; and, outside the *Catalogue*,

⁵ *Λυκίων*, Corais, for *Λικίων* F, *Κιλίκων* other MSS.

Σολύμους καὶ Κίλικας τοὺς ἐκ Θήβης πεδίου καὶ Λέλεγας· Παμφύλους δὲ καὶ Βιθυνοὺς καὶ Μαριανδυνοὺς καὶ Πισίδας καὶ Χάλυβας καὶ Μιλύας καὶ Καππάδοκας μὴδ' ὠνομάσθαι, τοὺς μὲν διὰ τὸ μὴδέπω τοὺς τόπους κατοικηκέναι τούτους, τοὺς δὲ διὰ τὸ ἑτέροις γένεσι περιέχεσθαι, ὡς Ἰδριεῖς μὲν καὶ Τερμίλαι¹ Καρσί, Δολιόνας δὲ καὶ Βέβρυκες Φρυγί.

24. Φαίνεται δ' οὐτε τοῦ Ἐφόρου τὴν ἀπόφασιν διαιτῶν ἱκανῶς, τὰ τε τοῦ ποιητοῦ ταράττων καὶ καταψευδόμενος. Ἐφόρου τε γὰρ τοῦτο πρῶτον ἀπατεῖν ἐχρῆν, τί δὴ τοὺς Χάλυβας τίθησιν ἐντὸς τῆς χερρονήσου, τοσοῦτον ἀφεστῶτας καὶ Σινώπης καὶ Ἀμισοῦ πρὸς ἑω; οἱ γὰρ λέγοντες τὸν ἰσθμὸν τῆς χερρονήσου ταύτης τὴν ἀπὸ Ἰσσοῦ γραμμὴν ἐπὶ τὸν Εὐξείνον, ὡς ἂν μεσημβρινὴν τινα τιθέασι ταύτην, ἣν² οἱ μὲν εἶναι νομίζουσι τὴν ἐπὶ Σινώπης, οἱ δὲ τὴν ἐπ' Ἀμισοῦ, ἐπὶ δὲ τῶν Χαλύβων οὐδεὶς· λοξὴ γάρ ἐστι τελέως. ὁ γὰρ δὴ διὰ Χαλύβων μεσημβρινὸς διὰ τῆς μικρᾶς Ἀρμενίας γράφουτ' ἂν καὶ τοῦ Εὐφράτου, τὴν Καππαδοκίαν ὅλην ἐντὸς ἀπολαμβάνων καὶ τὴν Κομμαγενὴν καὶ τὸν Ἀμανὸν καὶ τὸν Ἰσσικὸν κόλπον. εἰ δ' οὖν καὶ τὴν λοξὴν γραμμὴν ὀρίζειν τὸν ἰσθμὸν συγχωρήσαιμεν, τὰ πλεῖστά γε τούτων, καὶ μάλιστα ἡ Καππαδοκία, ἐντὸς ἀπολαμβάνουτ' ἂν καὶ ὁ νῦν ἰδίως λεγόμενος Πόντος, τῆς Καππαδοκίας μέρος ὦν τὸ πρὸς τῷ Εὐξείνῳ· ὥστ' εἰ τοὺς Χάλυβας τῆς χερρονήσου θετέον

¹ Τερμίλαι, Xylander, for Τερμίλαι.

the Ceteians and the Solymi and the Cilicians from the plain of Thebê and the Leleges, but nowhere names the Pamphylians, Bithynians, Mariandynians, Pisidians, Chalybians, Milyans, or Cappadocians—some because they had not yet settled in this region, and others because they were included among other tribes, as, for example, the Hidrieis and the Termilae among the Carians, and the Doliones and Bebryces among the Phrygians.

24. But obviously Apollodorus does not pass a fair judgment upon the statement of Ephorus, and also confuses and falsifies the words of the poet; for he ought first to have asked Ephorus this question: Why he placed the Chalybians inside the peninsula when they were so far distant towards the east from both Sinopê and Amisus? For those who say that the isthmus of this peninsula is the line from Issus to the Euxine make this line a kind of meridian, which some think should be the line to Sinopê, and others, that to Amisus, but no one that to the land of the Chalybians, which is absolutely oblique; in fact, the meridian through the land of the Chalybians would be drawn through Lesser Armenia and the Euphrates, cutting off on this side of it the whole of Cappadocia, Commagenê, Mt. Amanus, and the Issic Gulf. If, however, we should concede that the oblique line bounds the isthmus, at least most of these places, and Cappadocia in particular, would be cut off on this side, as also the country now called Pontus in the special sense of the term, which is a part of Cappadocia towards the Euxine; so that, if the land of the Chalybians

² §, Corais inserts.

μέρος, πολὺ μᾶλλον τοὺς Κατάονας καὶ Καππαδόκας ἀμφοτέρους καὶ Λυκάονας δέ, οὓς καὶ αὐτοὺς παρήκε. διὰ τί δ' ἐν τοῖς μεσογαίοις
 C 679 ἔταξε τοὺς Χάλυβας, οὓς ὁ ποιητὴς Ἀλιζώνας¹ ἐκάλεσεν, ὥσπερ καὶ ἡμεῖς ἀπεδείξαμεν; ἄμεινον γὰρ ἦν διελεῖν καὶ τοὺς μὲν ἐπὶ τῇ θαλάττῃ φάναι, τοὺς δὲ ἐν τῇ μεσογαίᾳ· ὅπερ καὶ ἐπὶ τῆς Καππαδοκίας ποιητέον καὶ τῆς Κιλικίας. ὁ δὲ τὴν μὲν οὐδ' ὠνόμακε, τοὺς Κίλικας δὲ τοὺς ἐπὶ τῇ θαλάττῃ μόνον εἶρηκεν. οἱ οὖν ἐπ' Ἀντιπάτρῳ τῷ Δερβήτῃ καὶ οἱ Ὀμοναδεῖς καὶ ἄλλοι πλείους οἱ συνάπτοντες τοῖς Πισίδαις,

οἱ οὐκ ἴσασι θάλατταν
 ἀνέρες, οὐδέ θ'² ἄλεσσι μεμιγμένον εἶδαρ
 ἔδουσι,

τίνα λάβωσι τάξιν; ἀλλ' οὐδὲ Λυδοὺς οὐδὲ Μήονας εἶρηκεν, εἴτε δύο εἴθ' οἱ αὐτοὶ εἰσι, καὶ εἴτε καθ' ἑαυτοὺς εἴτ' ἐν ἐτέρῳ γένει περιεχομένους. οὕτω γὰρ ἐπίσημον ἔθνος οὐκ ἀποκρύψαι δυνατόν, ὃ τε μὴ λέγων περὶ αὐτοῦ μηδὲν οὐκ ἂν δόξειε παραλιπεῖν τι τῶν κυριωτάτων;

25. Τίνες δ' εἰσὶν οἱ μιγάδες; οὐ γὰρ ἂν ἔχοιμεν εἰπεῖν παρὰ τοὺς λεχθέντας τόπους ἢ ὠνομάσθαι ὑπ' αὐτοῦ ἢ παραλελειφθαι ἄλλους, οὓς ἀποδώσομεν τοῖς μιγάσιν, οὐδέ γε αὐτῶν τινὰς τούτων, ὧν ἡ εἶπεν ἡ παρέλιπε. καὶ γὰρ εἰ κατεμίχθησαν, ἀλλ' ἡ ἐπικράτεια πεποίηκεν ἢ Ἑλληνας ἢ βαρβάρους· τρίτον δὲ γένος οὐδὲν ἴσμεν τὸ μικτόν.

¹ Ἀλιζώνους CEF¹⁰.

² οὐδέ θ' F, οὐδ' ἔθ' other MSS.

must be set down as a part of the peninsula, much more should Cataonia and both Cappadocias, as also Lycaonia, which is itself omitted by him. Again, why did Ephorus place in the interior the Chalybians, whom the poet called Halizones, as I have already demonstrated? ¹ For it would have been better to divide them and set one part of them on the sea and the other in the interior, as should also be done in the case of Cappadocia and Cilicia; but Ephorus does not even name Cappadocia, and speaks only of the Cilicians on the sea. Now as for the people who were subject to Antipater Derbetes, and the Homonadeis and several other peoples who border on the Pisidians, "men who do not know the sea and even do not eat food mingled with salt," ² where are they to be placed? Neither does he say in regard to the Lydians or Meiones whether they are two peoples or the same, or whether they live separately by themselves or are included within another tribe. For it would be impossible to lose from sight so significant a tribe; and if Ephorus says nothing about it, would he not seem to have omitted something most important?

25. And who are the "mixed" tribes? For we would be unable to say that, as compared with the aforesaid places, others were either named or omitted by him which we shall assign to the "mixed" tribes; neither can we call "mixed" any of these peoples themselves whom he has mentioned or omitted; for, even if they had become mixed, still the predominant element has made them either Hellenes or barbarians; and I know nothing of a third tribe of people that is "mixed."

¹ 12. 3. 20.

² *Odyssey* 11. 122.

26. Πῶς δὲ τρία γένη τῶν Ἑλλήνων ἐστὶ τὰ τὴν χερρόνησον οἰκοῦντα; εἰ γάρ, ὅτι τὸ παλαιὸν οἱ αὐτοὶ ἦσαν Ἴωνες καὶ Ἀθηναῖοι, λεγέσθωσαν καὶ οἱ Δωριεῖς καὶ οἱ Αἰολεῖς οἱ αὐτοί, ὥστε δύο ἔθνη γίνονται ἂν· εἰ δὲ διαιρετέον κατὰ τὰ ὕστερα ἔθνη, καθάπερ καὶ τὰς διαλέκτους, τέτταρα ἂν εἴη καὶ τὰ ἔθνη, καθάπερ καὶ αἱ διάλεκτοι. οἰκοῦσι δὲ τὴν χερρόνησον ταύτην, καὶ μάλιστα κατὰ τὸν τοῦ Ἐφόρου διορισμόν, οὐκ Ἴωνες μόνον, ἀλλὰ καὶ Ἀθηναῖοι, καθάπερ ἐν τοῖς καθ' ἕκαστα δεδιήλωται. τοιαῦτα μὲν δὴ πρὸς τὸν Ἐφορον διαπορεῖν ἄξιον, Ἀπολλόδωρος δὲ τούτων μὲν ἐφρόντισεν οὐδέν· τοῖς δὲ ἑκαίδεκα ἔθνεσι προστίθωσιν ἑπτακαίδεκατον, τὸ τῶν Γαλατῶν, ἄλλως μὲν χρήσιμον λεχθῆναι, πρὸς δὲ τὴν δίαιταν τῶν ὑπὸ τοῦ Ἐφόρου λεγομένων ἢ παραλειπομένων οὐ δέον· εἶρηκε δὲ τὴν αἰτίαν αὐτός, ὅτι ταῦτα πάντα νεώτερα τῆς ἐκείνου ἡλικίας.

27. Μεταβάς δ' ἐπὶ τὸν ποιητὴν τοῦτο μὲν ὀρθῶς λέγει, διότι πολλὴ σύγχυσις γεγένηται τῶν βαρβάρων ἔθνων ἀπὸ τῶν Τρωικῶν εἰς τὰ νῦν διὰ τὰς μεταπτώσεις· καὶ γὰρ προσγέγονέ τινα καὶ ἐλλέλοιπε καὶ διέσπασται καὶ συνῆκται εἰς ἓν. οὐκ εὖ δὲ τὴν αἰτίαν διττὴν ἀποφαίνει, δι' ἣν οὐ μέμνηται τινων ὁ ποιητής· ἢ τῷ μήπω
 C 680 τότε οἰκεῖσθαι ὑπὸ τοῦ ἔθνους τούτου, ἢ τῷ ἐν ἐτέρῳ γένει περιέχεσθαι. τὴν γὰρ Καππαδοκίαν οὐκ εἶρηκεν, οὐδὲ τὴν Καταονίαν, ὥς δ' αὐτως τὴν

¹ Cf. 8. 1. 2.

² 14. 1. 3 ff.

26. And how can there be three Hellenic tribes that live on the peninsula? For if it is because the Athenians and the Ionians were the same people in ancient times, let also the Dorians and the Aeolians be called the same people; and thus there would be only two tribes. But if one should make distinctions in accordance with the customs of later times, as, for example, in accordance with dialects, then the tribes, like the dialects, would be four in number.¹ But this peninsula, particularly in accordance with the division of Ephorus, is inhabited, not only by Ionians, but also by Athenians, as I have shown in my account of the several places.² Now although it is worth while to raise such questions as these with reference to Ephorus, yet Apollodorus took no thought for them and also goes on to add to the sixteen tribes a seventeenth, that of the Galatians—in general a useful thing to do, but unnecessary for the passing of judgment upon what is said or omitted by Ephorus. But Apollodorus states the reason himself, that all this is later than the time of Ephorus.

27. Passing to the poet, Apollodorus rightly says that much confusion of the barbarian tribes has taken place from the Trojan times to the present because of the changes, for some of them have been added to, others have vanished, others have been dispersed, and others have been combined into one tribe. But he incorrectly sets forth as twofold the reason why the poet does not mention some of them; either because a country was not yet inhabited by this or that tribe or because this or that tribe was included within another; for instance, the poet fails to mention Cappadocia, Cataonia, and

Λυκαονίαν, δι' οὐδέτερον τούτων· οὐ γὰρ ἔχομεν τοιαύτην ἱστορίαν ἐπ' αὐτῶν οὐδεμίαν. γελοῖόν τε τὸ τοὺς Καππάδοκας καὶ Λυκάονας διὰ τί μὲν Ὅμηρος παρέλιπε, φροντίσαι καὶ ἀπολογήσασθαι, διὰ τί δ' Ἐφορος παρῆλθε, παρελθεῖν καὶ αὐτόν, καὶ ταῦτα παραθέμενον πρὸς αὐτὸ τοῦτο τὴν ἀπόφασιν τάνδρός, πρὸς τὸ ἐξετάσαι καὶ διαιτῆσαι· καί, διότι μὲν Μήονας ἀντὶ Λυδῶν Ὅμηρος εἶπε, διδάξαι, ὅτι δ' οὔτε Λυδοὺς οὔτε Μήονας εἶρηκεν Ἐφορος, μὴ ἐπισημήνασθαι.

28. Φήσας δὲ ἀγνώτων τινῶν μεμνήσθαι τὸν ποιητὴν, Καύκωνας μὲν ὀρθῶς λέγει καὶ Σολύμους καὶ Κητείους¹ καὶ Λέλεγας καὶ Κίλικας τοὺς ἐκ Θήβης πεδίου, τοὺς δ' Ἀλιζῶνας αὐτοὺς πλάττει, μᾶλλον δ' οἱ πρῶτοι τοὺς Ἀλιζῶνας ἀγνοήσαντες, τίνες εἰσὶ, καὶ μεταγράφοντες· πλεοναχῶς καὶ πλάττοντες τὴν τοῦ ἀργύρου γενέθλην καὶ ἄλλα πολλὰ μέταλλα,² ἐκλελειμμένα ἅπαντα. πρὸς ταύτην δὲ τὴν φιλοτιμίαν κάκεινας συνήγαγον τὰς ἱστορίας, ἃς ὁ Σκήψιος τίθησι παρὰ Καλλισθένους λαβὼν καὶ ἄλλων τινῶν, οὐ καθαιρεόντων τῆς περὶ τῶν Ἀλιζώνων ψευδοδοξίας· ὥς ὁ μὲν Ταντάλου πλουῖτος καὶ τῶν Πελοποννησίων ἀπὸ τῶν περὶ Φρυγίαν καὶ Σίπυλον μετὰλλων ἐγένετο· ὁ δὲ Κάδμου ἐκ τῶν³ περὶ Θράκην καὶ τὸ Παγγαῖον ὄρος· ὁ δὲ Πριάμου ἐκ τῶν ἐν Ἀστύροις⁴ περὶ Ἀβυδὸν χρυσείων, ὧν καὶ νῦν ἔτι μικρὰ λείπεται.

¹ Κητείους, Xylander, for Κητίους; so later editors.

² μέταλλα, Corais, for μεγάλα; so later editors.

³ ἐκ τῶν, Corais inserts: so later editors.

⁴ Ἀστύροις, Xylander, for Ἀσυρίοις CDFino, περὶ Ἀβυδὸν μοι.

likewise Lycaonia, but for neither of these reasons, for we have no history of this kind in their case. Further, it is ridiculous that Apollodorus should concern himself about the reason why Homer omitted the Cappadocians and Lycaonians and speak in his defence, and yet should himself omit to tell the reason why Ephorus omitted them, and that too when he had cited the statement of the man for the very purpose of examining it and passing judgment upon it; and also to teach us why Homer mentioned Meionians instead of Lydians, but not to remark that Ephorus mentions neither Lydians nor Meionians.

28. After saying that the poet mentions certain unknown tribes, Apollodorus rightly names the Cauconians, the Solymi, the Ceteians, the Leleges, and the Cilicians of the plain of Thebê; but the Halizones are a fabrication of his own, or rather of the first men who, not knowing who the Halizones were, wrote the name in several different ways¹ and fabricated the "birthplace of silver"² and many other mines, all of which have given out. And in furtherance of their emulous desire they also collected the stories cited by Demetrius of Scepsis from Callisthenes and certain other writers, who were not free from the false notions about the Halizones. Likewise the wealth of Tantalus and the Pelopidae arose from the mines round Phrygia and Sipylus: that of Cadmus from those round Thrace and Mt. Pangaeus; that of Priam from the gold mines at Astyra near Abydus (of which still to-day there are small remains; here the amount of earth thrown out is considerable, and the excava-

¹ See 12. 3. 21.

² See 12. 3. 24.

πολλή δ' ἡ ἐκβολὴ καὶ τὰ ὀρύγματα σημεῖα τῆς πάλαι μεταλλείας· ὁ δὲ Μίδου ἐκ τῶν περὶ τὸ Βέρμιον ὄρος· ὁ δὲ Γύγου καὶ Ἀλυάττου καὶ Κροίσου ἀπὸ τῶν ἐν Λυδία καὶ¹ τῆς μεταξὺ Ἀταρνέως τε καὶ Περγάμου, ὅπου² πολίχνη ἐρήμη, ἐκμεταλλευμένα ἔχουσα τὰ χωρία.

29. Ἔτι καὶ ταῦτα μέμφαιτο ἂν τις τοῦ Ἀπολλοδώρου, ὅτι τῶν νεωτέρων καινοτομούντων πολλὰ παρὰ τὰς Ὀμηρικὰς ἀποφάσεις, εἰσθὼς ταῦτ' ἐλέγχειν ἐπὶ πλέον, ἐνταῦθα οὐκ ὠλιγώρηκε μόνον, ἀλλὰ καὶ τὰναντία εἰς ἓν συνάγει τὰ μὴ ὡσαύτως λεγόμενα. ὁ μὲν γὰρ Ξάνθος ὁ Λυδὸς μετὰ τὰ Τρωικὰ φησιν ἐλθεῖν τοὺς Φρύγας ἐκ τῆς Εὐρώπης καὶ τῶν ἀριστερῶν τοῦ Πόντου, ἀγαγεῖν δ' αὐτοὺς Σκαμάνδριον ἐκ Βερεκύντων καὶ Ἀσκανίας, ἐπιλέγει δὲ τούτοις ὁ Ἀπολλόδωρος, ὅτι τῆς Ἀσκανίας ταύτης μνημονεύει καὶ Ὀμηρος, ἧς ὁ Ξάνθος·

Φόρκυς δὲ Φρύγας ἤγε καὶ Ἀσκάnius θεοειδὴς
C 681 τῆλ' ἐξ Ἀσκανίης.

ἀλλ' εἰ οὕτως ἔχει, ἡ μὲν μετανάστασις ὕστερον ἂν εἴη τῶν Τρωικῶν γεγονυῖα, ἐν δὲ τοῖς Τρωικοῖς τὸ λεγόμενον ὑπὸ τοῦ ποιητοῦ ἐπικουρικὸν ἦκεν ἐκ τῆς περαιᾶς ἐκ τῶν Βερεκύντων καὶ τῆς Ἀσκανίας. τίνες οὖν Φρύγες ἦσαν,

οἳ ῥα τότε ἔστρατόωντο παρ' ὄχθας Σαγαγαρίοιο,
ὅτε ὁ Πρίαμος,

ἐπίκουρος ἐὼν μετὰ τοῖσιν ἐλέγχμην,³

¹ καί, before τῆς, Corais inserts.

² ὅπου, before πολίχνη, Jones inserts. Tzschucke and Corais emend πολίχνη ἐρήμη . . . ἔχουσα τὸ πολίχνης ἐρήμη . . . ἔχούσης.

tions are signs of the mining in olden times); and that of Midas from those round Mt. Bermius; and that of Gyges and Alyattes and Croesus from those in Lydia and from the region between Atarneus and Pergamum, where is a small deserted town, whose lands have been exhausted of ore.

29. Still further one might find fault with Apollodorus, because, when the more recent writers make numerous innovations contrary to the statements of Homer, he is wont frequently to put these innovations to the test, but in the present case he not only has made small account of them, but also, on the contrary, identifies things that are not meant alike; for instance, Xanthus the Lydian says that it was after the Trojan War that the Phrygians came from Europe and the left-hand side of the Pontus, and that Scamandrius led them from the Berecyntes and Ascania, but Apollodorus adds to this the statement that Homer refers to this Ascania that is mentioned by Xanthus: "And Phorcys and godlike Ascanius led the Phrygians from afar, from Ascania."¹ However, if this is so, the migration must have taken place later than the Trojan War, whereas the allied force mentioned by the poet came from the opposite mainland, from the Berecyntes and Ascania. Who, then, were the Phrygians, "who were then encamped along the banks of the Sangarius,"² when Priam says, "for I too, being an ally, was numbered among these"?³ And how could Priam have sent

¹ *Iliad* 2. 802.

² *Iliad* 3. 187.

³ *Iliad* 3. 188.

³ *ἐλέγμην* is emended by Tzschucke and Corais to *ἐλέχθην* (as in the Homeric text).

φησί; πῶς δὲ ἐκ μὲν Βερεκύντων μετεπέμπετο Φρύγας ὁ Πρίαμος, πρὸς οὓς οὐδὲν ἦν αὐτῷ συμβόλαιον, τοὺς δ' ὁμόρους καὶ οἷς αὐτὸς πρότερον ἐπεκούρησέ παρέλιπεν; οὕτω δὲ περὶ τῶν Φρυγῶν εἰπὼν ἐπιφέρει καὶ τὰ περὶ τῶν Μυσῶν οὐχ ὁμολογούμενα τούτοις· λέγεσθαι γάρ φησι καὶ τῆς Μυσίας κώμην Ἀσκανίαν περὶ λίμνην ὁμώνυμον, ἐξ ἧς καὶ τὸν Ἀσκάνιον ποταμὸν ρεῖν, οὗ μνημονεύει καὶ Εὐφορίων.

Μυσοῖο παρ' ὕδασιν Ἀσκανίοιο·
καὶ ὁ Αἰτωλὸς Ἀλέξανδρος·

οἱ¹ καὶ ἐπ' Ἀσκανίῳ δώματ' ἔχουσι ῥόφ,
λίμνης Ἀσκανίης ἐπὶ χείλεσιν· ἔνθα Δολίων
υἱὸς Σίληνου νύσσατο καὶ Μελίας.

καλοῦσι δέ, φησί, Δολιονίδα καὶ Μυσίαν τὴν περὶ Κύζικον ἰόντι εἰς Μιλητούπολιν. εἰ οὖν οὕτως ἔχει ταῦτα, καὶ ἐκμαρτυρεῖται ὑπὸ τῶν δεικνυμένων νῦν καὶ ὑπὸ τῶν ποιητῶν, τί ἐκώλυε τὸν Ὅμηρον ταύτης μεμνησθαι τῆς Ἀσκανίας, ἀλλὰ μὴ τῆς ὑπὸ Ξάνθου λεγομένης; εἴρηται δὲ καὶ πρότερον περὶ τούτων ἐν τῷ περὶ Μυσῶν καὶ Φρυγῶν λόγῳ, ὥστε ἐχέτω πέρας.

VI

1. Λοιπὸν δὲ τὴν πρὸς νότου παρακειμένην τῇ χερρονήσῳ ταύτῃ περιοδεῦσαι νῆσον τὴν Κύπρον. εἴρηται δ', ὅτι ἡ περιεχομένη θάλαττα ὑπὸ τῆς Αἰγύπτου καὶ Φοινίκης καὶ Συρίας καὶ τῆς λοιπῆς παραλίας μέχρι τῆς Ῥοδίας σύνθετός πῶς ἐστίν

¹ εἰ CDEFh; but see same passage in 12. 4. 8.

for Phrygians from the Berecynates, with whom he had no compact, and yet leave uninvited those who lived on his borders and to whom he had formerly been ally? And after speaking in this way about the Phrygians he adds also an account of the Mysians that is not in agreement with this; for he says that there is also a village in Mysia which is called Ascania, near a lake of the same name, whence flows the Ascanius River, which is mentioned by Euphorion, "beside the waters of the Mysian Ascanius," and by Alexander the Actolian, "who have their homes on the Ascanian streams, on the lips of the Ascanian Lake, where dwelt Dolion, the son of Silenus and Melia." And he says that the country round Cyzicus, as one goes to Miletapolis, is called Dolionis and Mysia. If this is so, then, and if witness thereto is borne both by the places now pointed out and by the poets, what could have prevented Homer from mentioning this Ascania, and not the Ascania spoken of by Xanthus? I have discussed this before, in my account of the Mysians and Phrygians;¹ and therefore let this be the end of that subject.

VI

1. IT remains for me to describe the island which lies alongside this peninsula on the south, I mean Cyprus. I have already said that the sea surrounded by Egypt, Phoenicia, Syria, and the rest of the coast as far as Rhodia² consists approximately of

¹ 7. 3. 2-3; 12. 3. 3; 12. 4. 5.

² The Peraea of the Rhodians.

ἔκ τε τοῦ Αἰγυπτίου πελάγους καὶ τοῦ Παμφυλίου καὶ τοῦ κατὰ τὸν Ἰσικὸν κόλπον. ἐν δὲ ταύτῃ ἐστὶν ἡ Κύπρος, τὰ μὲν προσάρκτια μέρη συνάπτοντα ἔχουσα τῇ Τραχείᾳ Κιλικίᾳ, καθ' ἣ δὴ καὶ προσεχεστάτῃ τῇ ἡπείρῳ ἐστὶ, τὰ δὲ ἑῷα τῷ Ἰσικῷ κόλπῳ, τὰ δ' ἐσπέρια τῷ Παμφυλίῳ κλυζόμενα πελάγει, τὰ δὲ νότια τῷ Αἰγυπτίῳ. τοῦτο μὲν οὖν σύρρουν ἐστὶν ἀπὸ τῆς ἐσπέρας τῷ Λιβυκῷ καὶ τῷ Καρπαθίῳ πελάγει, ἀπὸ δὲ τῶν νοτίων καὶ τῶν ἐφ' ὧν μερῶν ἡ τε Αἰγυπτὸς ἐστὶ καὶ ἡ ἐφεξῆς παραλία μέχρι Σελευκείας τε καὶ Ἰσσοῦ, πρὸς ἄρκτον δ' ἡ τε Κύπρος καὶ τὸ Παμφύλιον πέλαγος. τοῦτο δὲ ἀπὸ μὲν τῶν ἄρκτων περιέχεται τοῖς τε ἄκροις τῆς Τραχείας Κιλικίας καὶ τῆς Παμφυλίας καὶ Λυκίας μέχρι τῆς Ῥοδίας, ἀπὸ δὲ τῆς δύσεως τῇ Ῥοδίῳ νήσῳ, ἀπὸ δὲ τῆς ἀνατολῆς τῇ Κύπρῳ τῇ κατὰ Πάφον καὶ τὸν Ἀκάμαντα, ἀπὸ δὲ τῆς μεσημβρίας σύρρουν ἐστὶ τῷ Αἰγυπτίῳ πελάγει.

C 682

2. Ἔστι δ' ὁ μὲν κύκλος τῆς Κύπρου σταδίων τρισχιλίων καὶ τετρακοσίων εἴκοσι κατακολπίζοντι· μήκος δὲ ἀπὸ Κλειδῶν ἐπὶ τὸν Ἀκάμαντα πεζῇ σταδίων χιλίων τετρακοσίων ὁδεύοντι ἀπ' ἀνατολῆς ἐπὶ δύσιν. εἰσὶ δὲ αἱ μὲν Κλειδες ἡσιὰ δύο προκείμενα¹ τῇ Κύπρῳ κατὰ τὰ ἐωθινὰ μέρη τῆς νήσου, τὰ διέχοντα τοῦ Πυράμου σταδίους ἑπτακοσίους· ὁ δ' Ἀκάμας ἐστὶν ἄκρα δύο μαστοὺς ἔχουσα καὶ ὕλην πολλήν, κείμενος μὲν ἐπὶ τῶν ἐσπερίων τῆς νήσου μερῶν, ἀνατείνων δὲ πρὸς ἄρκτους, ἐγγυτάτω μὲν πρὸς Σελινούντα τῆς Τραχείας Κιλικίας ἐν διάρματι χιλίων σταδίων, πρὸς Σίδην δὲ τῆς Παμφυλίας χιλίων καὶ ἑξακο-

the Aegyptian and Pamphylian Seas and of the sea at the gulf of Issus. In this last sea lies Cypros; its northern parts closely approach Cilicia Tracheia, where they are closest to the mainland, and its eastern parts border on the Issic Gulf, and its western on the Pamphylian Sea, being washed by that sea, and its southern by the Aegyptian Sea. Now the Aegyptian Sea is confluent on the west with the Libyan and Carpathian Seas, but in its southern and eastern parts borders on Aegypt and the coast next thereafter as far as Seleuceia and Issus, and towards the north on Cypros and the Pamphylian Sea; but the Pamphylian Sea is surrounded on the north by the extremities of Cilicia Tracheia, of Pamphylia, and of Lycia, as far as Rhodia, and on the west by the island of the Rhodians, and on the east by the part of Cypros near Paphos and the Acamas, and on the south is confluent with the Aegyptian Sea.

2. The circuit of Cypros is three thousand four hundred and twenty stadia, including the sinuosities of the gulfs. The length from Cleides to the Acamas by land, travelling from east to west, is one thousand four hundred stadia. The Cleides are two isles lying off Cypros opposite the eastern parts of the island, which are seven hundred stadia distant from the Pyramus. The Acamas is a promontory with two breasts and much timber. It is situated at the western part of the island, and extends towards the north; it lies closest to Selinus in Cilicia Tracheia, the passage across being one thousand stadia, whereas the passage across to Sidê in Pamphylia is

¹ Instead of *προκελευα*, Corais and Meineke, following F, read *προσκελευα*.

σίῳν, πρὸς δὲ Χελιδονίας χιλίων ἐννακοσίων. ἔστι δὲ ἑτερόμηκες τὸ ὅλον τῆς νήσου σχῆμα, καὶ πού καὶ ἰσθμοὺς ποιεῖ κατὰ τὰς τὸ πλάτος διοριζούσας πλευράς· ἔχει δὲ καὶ τὰ καθ' ἕκαστα, ὥς ἐν βραχέσιν εἰπεῖν, οὕτως, ἀρξαμένοις ἀπὸ τοῦ προσεχυστάτου σημείου τῇ ἡπείρῳ.

3. Ἐφάμεν δέ¹ πού κατὰ τὸ Ἀνεμούριον, ἄκραν τῆς Τραχείας Κιλικίας, ἀντικεῖσθαι τὸ τῶν Κυπρίων ἀκρωτήριον τὴν Κρομμύου ἄκραν ἐν τριακοσίοις καὶ πεντήκοντα σταδίοις· ἐντεῦθεν δ' ἤδη δεξιὰν τὴν νήσον ἔχουσιν, ἐν ἀριστερῇ δὲ τὴν ἡπειρον, πρὸς ἄρκτον ὁ πλοῦς ἐστὶ καὶ πρὸς ἕω καὶ πρὸς τὰς Κλεῦδας εὐθυπλοία σταδίων ἑπτακοσίων. ἐν δὲ τῷ μεταξὺ Λάπαθός τέ ἐστι πόλις, ὕφορμον ἔχουσα καὶ νεώρια, Λακώνων κτίσμα καὶ Πραξάνδρου, καθ' ἣν ἡ Νάγιδος·² εἴτ' Ἀφροδίσιον, καθ' ὃ στενὴ ἡ νήσος· εἰς γὰρ Σαλαμίνα ὑπέρβασις σταδίων ἑβδομήκοντα· εἴτ' Ἀχαιῶν ἀκτὴ,³ ὅπου Τεῦκρος προσωρμίσθη πρῶτον ὁ⁴ κτίσας Σαλαμίνα τὴν ἐν Κύπρῳ, ἐκβληθείς, ὥς φασιν, ὑπὸ τοῦ πατρὸς Τελαμώνος· εἴτα Καρπασία πόλις, λιμένα ἔχουσα. κεῖται δὲ κατὰ τὴν ἄκραν τὴν Σαρπηδόνα· ἐκ δὲ τῆς Καρπασίας ὑπέρβασις ἐστὶν ἰσθμοῦ τριάκοντα σταδίων πρὸς τὰς νήσους τὰς Καρπασίας καὶ τὸ νότιον πέλαγος· εἴτ' ἄκρα καὶ ὄρος· ἡ δ' ἀκρόρεια καλεῖται Ὀλυμπος, ἔχουσα Ἀφροδίτης Ἀκραίας ναόν, ἄδυτον γυναιξὶ καὶ ἀόρατον. πρόκεινται δὲ πλησίον αἱ

¹ δέ, Corais emends to δῆ.

² ἡ Νάγιδος, Corais, for ἡν ἄγιδος; so the later editors.

³ εἴτ' Ἀχαιῶν ἀκτὴ μοσζ, εἴτα χάρων ἀκτὴ other MSS.; so the editors.

sixteen hundred and to the Chelidonian islands one thousand nine hundred. The shape of the island as a whole is oblong; and in some places it forms isthmuses on the sides which define its breadth. But the island also has its several parts, which I shall describe briefly, beginning with the point that is nearest to the mainland.

3. I have said somewhere¹ that opposite to Anemurium, a cape of Cilicia Tracheia, is the promontory of the Cyprians, I mean the promontory of Crommyus, at a distance of three hundred and fifty stadia. Thence forthwith, keeping the island on the right and the mainland on the left, the voyage to the Cleides lies in a straight line towards the north-east, a distance of seven hundred stadia. In the interval is the city Lapathus, with a mooring-place and dockyards; it was founded by Laconians and Praxander, and opposite it lies Nagidus. Then one comes to Aphrodisium, where the island is narrow, for the passage across to Salamis is only seventy stadia. Then to the beach of the Achaeans, where Teucer, the founder of Salamis in Cyprus, first landed, having been banished, as they say, by his father Telamon. Then to a city Carpasia, with a harbour. It is situated opposite the promontory Sarpedon; and the passage from Carpasia across the isthmus to the Carpasian Islands and the southern sea is thirty stadia. Then to a promontory and mountain. The mountain peak is called Olympus; and it has a temple of Aphroditê Acraea, which cannot be entered or seen by women. Off

¹ 14. 5. 3.

⁴ δ, before κρίσας, Kramer inserts; so the later editors.

Κλειδες καὶ ἄλλαι δὲ πλείους, εἴθ' αἱ Καρπάσαι
 νῆσοι, καὶ μετὰ ταύτας ἡ Σαλαμῖς, ὅθεν ἦν
 Ἄριστος ὁ συγγραφεύς· εἴτ' Ἀρσινόη πόλις καὶ
 λιμὴν· εἴτ' ἄλλος λιμὴν Λεύκολλα¹· εἴτ' ἄκρα
 Πηδάλιον, ἧς² ὑπέρκειται λόφος τραχὺς, ὑψηλός,
 τραπεζοειδής, ἱερὸς Ἀφροδίτης, εἰς ὃν ἀπὸ Κλει-
 δῶν στάδιοι ἑξακόσιοι ὀγδοήκοντα· εἴτα κολπώ-
 δης καὶ τραχὺς παράπλους ὁ πλείων εἰς Κίτιον·
 ἔχει δὲ λιμένα κλειστόν· ἐντεῦθεν ἐστὶ Ζήνων τε,
 ὁ τῆς στωικῆς αἵρέσεως ἀρχηγέτης, καὶ Ἀπολ-
 C 688 λώνιος ἱατρός· ἐντεῦθεν εἰς Βηρυτὸν στάδιοι χίλιοι
 πεντακόσιοι. εἴτ' Ἀμαθοῦς πόλις καὶ μεταξὺ
 πολίχνη, Παλαιὰ καλουμένη, καὶ ὄρος μαστοειδὲς
 Ὀλυμπος· εἴτα Κουριάς χειρρονησώδης, εἰς ἣν
 ἀπὸ Θρόνων στάδιοι ἑπτακόσιοι. εἴτα πόλις
 Κούριον, ὄρμον ἔχουσα, Ἀργείων κτίσμα. ἤδη
 οὖν πάρεστι σκοπεῖν τὴν ῥαθυμίαν τοῦ ποιήσαντος
 τὸ ἐλεγεῖον τοῦτο, οὗ ἡ ἀρχή·

ἰραὶ τῷ Φοίβῳ, πολλὸν διὰ κύμα θέουσai,
 ἤλθομεν αἱ ταχυναὶ τόξα φυγεῖν ἔλαφοι·
 εἴθ' Ἡδύλος³ ἐστίν, εἴθ' ὅστισούν· φησὶ⁴ μὲν γὰρ
 ὀρμηθῆναι τὰς ἐλάφους Κωρυκίης ἀπὸ δευράδος,
 ἐκ δὲ Κιλίσσης ἡϊόνος εἰς ἀκτὰς διανήξασθαι
 Κουριάδας, καὶ ἐπιφθέγγεται, διότι

μυρίον ἀνδράσι θαῦμα νοεῖν πάρα, πῶς ἀνόδευ-
 τον

χεῦμα δι' εἰαρινῷ⁵ ἐδράμομεν ζεφύρῳ.⁶

¹ Λεύκολλα, Casaubon, for Λεύκολα; so the later editors.

² ἧς F, eis ἦν other MSS.

³ Ἡδύλος F, εἴθ' ἡ δῆλος other MSS.

⁴ φασὶ CDhiosz.

⁵ δι' εἰαρινῷ, Meineke, for δ' αἰρινίῳ μοι, δι' ἐρίῳ other MSS.

it, and near it, lie the Cleides, as also several other islands; and then one comes to the Carpasian Islands; and, after these, to Salamis, where Aristus the historian was born. Then to Arsinoë, a city and harbour. Then to another harbour, Leucolla. Then to a promontory, Pedalium, above which lies a hill that is rugged, high, trapezium-shaped, and sacred to Aphroditê, whereto the distance from the Cleides is six hundred and eighty stadia. Then comes the coasting-voyage to Citium, which for the most part is sinuous and rough. Citium has a harbour that can be closed; and here were born both Zeno, the original founder of the Stoic sect, and Apollonius, a physician. The distance thence to Berytus is one thousand five hundred stadia. Then to the city Amathus, and, in the interval, to a small town called Palaca, and to a breast-shaped mountain called Olympus. Then to Curias, which is peninsula-like, whereto the distance from Throni is seven hundred stadia. Then to a city Curium, which has a mooring-place and was founded by the Argives. One may therefore see at once the carelessness of the poet who wrote the elegy that begins, "we hinds, sacred to Phoebus, racing across many billows, came hither in our swift course to escape the arrows of our pursuers," whether the author was Hedylus or someone else; for he says that the hinds set out from the Corycian heights and swam across from the Cilician shore to the beach of Curias, and further says that "it is a matter of untold amazement to men to think how we ran across the impassable stream by the aid of a vernal west wind"; for while

* ζεφύρῳ, Meineke, for ζεφύρων.

ἀπὸ γὰρ Κωρύκου περίπλους μὲν ἐστὶν εἰς Κουριάδα ἀκτὴν, οὔτε ζεφύρῳ δέ, οὔτε ἐν δεξιᾷ ἔχοντι τὴν νῆσον, οὔτ' ἐν ἀριστερᾷ, διάρμα δ' οὐδέν. ἀρχὴ δ' οὖν τοῦ δυσμικοῦ παράπλου τὸ Κούριον τοῦ βλέποντος πρὸς Ῥόδον, καὶ εὐθύς ἐστὶν ἄκρα, ἀφ' ἧς ρίπτουσι τοὺς ἀψαμένους τοῦ βωμοῦ τοῦ Ἀπόλλωνος· εἴτα Τρήτα καὶ Βοόσουρα καὶ Παλαίπαφος, ὅσον ἐν δέκα σταδίοις ὑπὲρ τῆς θαλάττης ἰδρυμένη, ὕψορμον ἔχουσα, καὶ ἱερὸν ἀρχαῖον τῆς Παφίας Ἀφροδίτης· εἴτ' ἄκρα Ζεφυρία, πρόσορμον ἔχουσα, καὶ ἄλλη Ἀρσινόη, ὁμοίως πρόσορμον ἔχουσα καὶ ἱερὸν καὶ ἄλσος· μικρὸν δ' ἀπὸ τῆς θαλάττης καὶ ἡ Ἱεροκηπίς. εἴθ' ἡ Πάφος, κτίσμα Ἀγαπήνορος, καὶ λιμένα ἔχουσα καὶ ἱερὰ εὖ κατεσκευασμένα. διέχει δὲ πεζῇ σταδίους ἑξήκοντα τῆς Παλαιπάφου, καὶ πανηγυρίζουσι διὰ τῆς ὁδοῦ ταύτης κατ' ἔτος ἐπὶ τὴν Παλαίπαφον ἄνδρες ὁμοῦ γυναιξὶν συνιόντες καὶ¹ ἐκ τῶν ἄλλων πόλεων. φασὶ δ' εἰς Ἀλεξάνδρειάν τινες ἐκ Πάφου σταδίους εἶναι τρισχιλίους ἑξακοσίους. εἴθ' ὁ Ἀκάμας ἐστὶ μετὰ Πάφον· εἴτα πρὸς ἑω μετὰ τὸν Ἀκάμαντα πλοῦς εἰς Ἀρσινόην πόλιν καὶ τὸ τοῦ Διὸς ἄλσος· εἴτα Σόλοι² πόλις, λιμένα ἔχουσα καὶ ποταμὸν καὶ ἱερὸν Ἀφροδίτης καὶ Ἰσίδος· κτίσμα δ' ἐστὶ Φαλήρου καὶ Ἀκάμαντος Ἀθηναίων· οἱ δ' ἐνοικοῦντες Σόλοι καλοῦνται. ἐντεῦθεν ἦν Στάσανωρ τῶν Ἀλεξάνδρου ἐταίρων, ἀνὴρ ἡγεμονίας ἡξιωμένος· ὑπέρκειται δ' ἐν μεσογαίᾳ Λιμενία πόλις· εἴθ' ἡ Κρομμύου ἄκρα.

¹ καὶ is omitted by all MSS. except DF.

² Σόλοι, Tzschucke, for Σόλους.

there is a voyage round the island from Corycus to the beach Curias, which is made neither by the aid of a west wind nor by keeping the island on the right nor on the left, there is no passage across the sea between the two places. At any rate, Curium is the beginning of the westerly voyage in the direction of Rhodes; and immediately one comes to a promontory, whence are flung those who touch the altar of Apollo. Then to Treta, and to Boosura, and to Palaepaphus, which last is situated at about ten stadia above the sea, has a mooring-place, and an ancient temple of the Paphian Aphroditê. Then to the promontory Zephyria, with a landing-place, and to another Arsinoë, which likewise has a landing-place and a temple and a sacred precinct. And at a little distance from the sea is Hierocepis. Then to Paphus, which was founded by Agapenor, and has both a harbour and well-built temples. It is sixty stadia distant from Palaepaphus by land; and on this road men together with women, who also assemble here from the other cities, hold an annual procession to Palaepaphus. Some say that the distance from Paphus to Alexandria is three thousand six hundred stadia. Then, after Paphus, one comes to the Acamas. Then, after the Acamas, towards the east, one sails to a city Arsinoë and the sacred precinct of Zeus. Then to a city Soli, with a harbour and a river and a temple of Aphroditê and Isis. It was founded by Phalerus and Acamas, Athenians; and the inhabitants are called Solians; and here was born Stasanor, one of the comrades of Alexander, who was thought worthy of a chief command; and above it, in the interior, lies a city Limenia. And then to the promontory of Crommyus.

4. Τί δὲ δεῖ τῶν ποιητῶν θαυμάζειν, καὶ
 C 684 μάλιστα τῶν τοιούτων, οἷς ἡ πᾶσα περὶ τὴν
 φράσιν ἐστὶ σπουδὴ, τὰ τοῦ Δαμάστου συγ-
 κρίνοντας, ὅστις τῆς νήσου τὸ μῆκος ἀπὸ τῶν
 ἄρκτων πρὸς μεσημβρίαν ἀποδίδωσιν, ἀπὸ
 Ἱεροκηπίας, ὥς φησιν, εἰς Κλεΐδας; οὐδὲ ὁ
 Ἐρατοσθένης εὖ· αἰτιώμενος γὰρ τοῦτον, οὐκ ἀπ'
 ἄρκτων φησὶν εἶναι τὴν Ἱεροκηπίαν, ἀλλ' ἀπὸ
 νότου· οὐδὲ γὰρ ἀπὸ νότου, ἀλλ' ἀπὸ δύσεως,
 εἴπερ ἐν τῇ δυσμικῇ πλευρᾷ κεῖται, ἐν ᾗ καὶ ἡ
 Πάφος καὶ ὁ Ἀκάμας. διάκειται μὲν οὕτως ἡ
 Κύπρος τῇ θέσει.

5. Κατ' ἀρετὴν δ' οὐδεμιᾶς τῶν νήσων λείπεται·
 καὶ γὰρ εὖοινός ἐστι καὶ εὐέλαιος, σίτω τε αὐτάρ-
 κει χρήται· μέταλλά τε χαλκοῦ ἐστὶν ἄφθονα τὰ
 ἐν Ταμασσῷ,¹ ἐν οἷς τὸ χαλκανθές γίνεται, καὶ ὁ
 ἱὸς τοῦ χαλκοῦ, πρὸς τὰς ἱατρικὰς δυνάμεις
 χρήσιμα. φησὶ δ' Ἐρατοσθένης τὸ παλαιὸν
 ὑλομανούντων τῶν πεδίων, ὥστε κατέχεσθαι
 δρυμοῖς καὶ μὴ γεωργεῖσθαι, μικρὰ μὲν ἐπωφελεῖν
 πρὸς τοῦτο τὰ μέταλλα, δενδροτομούντων πρὸς
 τὴν καύσιν τοῦ χαλκοῦ καὶ τοῦ ἀργύρου, προσ-
 γενέσθαι δὲ καὶ τὴν ναυπηγίαν τῶν στόλων, ἥδη
 πλεομένης ἀδεῶς τῆς θαλάττης καὶ μετὰ δυνά-
 μων· ὥς δ' οὐκ ἐξενίκων, ἐπιτρέψαι τοῖς βου-
 λομένοις καὶ δυναμένοις ἐκκόπτειν καὶ ἔχειν
 ἰδιόκτητον καὶ ἀτελῆ τὴν διακαθαρθείσαν γῆν.

6. Πρότερον μὲν οὖν κατὰ πόλεις ἐτυραννοῦντο
 οἱ Κύπριοι, ἀφ' οὗ δ' οἱ Πτολεμαῖκοι βασιλεῖς

¹ Ταμασσῷ, Xylander, for Ταμασῷ E, Ταμασσῷ other MSS.

4. But why should one wonder at the poets, and particularly at writers of the kind that are wholly concerned about style, when we compare the statements of Damastes, who gives the length of the island as from north to south, "from Hierocepias," as he says, "to Cleides"? Neither is Eratosthenes correct, for, although he censures Damastes, he says that Hierocepias is not on the north but on the south; for it is not on the south either, but on the west, since it lies on the western side, where are also Paphus and the Acamas. Such is the geographical position of Cypros.

5. In fertility Cyprus is not inferior to any one of the islands, for it produces both good wine and good oil, and also a sufficient supply of grain for its own use. And at Tamassus there are abundant mines of copper, in which is found chalcanthite¹ and also the rust of copper, which latter is useful for its medicinal properties. Eratosthenes says that in ancient times the plains were thickly overgrown with forests, and therefore were covered with woods and not cultivated; that the mines helped a little against this, since the people would cut down the trees to burn the copper and the silver, and that the building of the fleets further helped, since the sea was now being navigated safely, that is, with naval forces, but that, because they could not thus prevail over the growth of the timber, they permitted anyone who wished, or was able, to cut out the timber and to keep the land thus cleared as his own property and exempt from taxes.

6. Now in the earlier times the several cities of the Cyprians were under the rule of tyrants,

¹ Sulphate of copper.

κύριοι τῆς Αἰγύπτου κατέστησαν, εἰς ἐκείνους καὶ ἡ Κύπρος περιέστη, συμπραττόντων πολλάκις καὶ τῶν Ῥωμαίων. ἐπεὶ δ' ὁ τελευταῖος ἄρξας Πτολεμαῖος, ἀδελφὸς τοῦ Κλεοπάτρας πατρός, τῆς καθ' ἡμᾶς βασιλίσσης, ἔδοξε πλημμελὲς τε εἶναι καὶ ἀχάριστος εἰς τοὺς εὐεργέτας, ἐκεῖνος μὲν κατελύθη, Ῥωμαῖοι δὲ κατέσχον τὴν νῆσον, καὶ γέγονε στρατηγικὴ ἐπαρχία καθ' αὐτήν. μάλιστα δ' αὐτίος τοῦ ὀλέθρου κατέστη τῷ βασιλεῖ Πόπλιος Κλαύδιος Ποῦλχερ· ἐμπεσὼν γὰρ εἰς τὰ ληστήρια, τῶν Κιλικίων ἀκμαζόντων τότε, λύτρον αἰτούμενος ἐπέστειλε τῷ βασιλεῖ, δεόμενος πέμψαι καὶ ῥύσασθαι αὐτόν· ὁ δ' ἐπεμψε μὲν, μικρὸν δὲ τελέως, ὥστε καὶ τοὺς ληστὰς αἰδεσθῆναι λαβεῖν, ἀλλὰ ἀναπέμψαι πάλιν, τὸν δ' ἄνευ λύτρων ἀπολῦσαι. σωθεὶς δ' ἐκεῖνος ἀπεμνημόνευσεν ἀμφοτέροις τὴν χάριν, καὶ γενόμενος δήμαρχος, ἴσχυσε τοσοῦτον, ὥστε ἐπέμφθη Μάρκος Κάτων, ἀφαιρησόμενος τὴν Κύπρον τὸν κατέχοντα. ἐκεῖνος μὲν οὖν ἔφθη διαχειρισάμενος αὐτόν, Κάτων δὲ ἐπελθὼν παρέ-
C 685 λαβε τὴν Κύπρον, καὶ τὴν βασιλικὴν οὐσίαν διέθετο, καὶ τὰ χρήματα εἰς τὸ δημόσιον ταμιεῖον τῶν Ῥωμαίων ἐκόμισεν· ἐξ ἐκείνου δ' ἐγένετο ἐπαρχία ἡ νῆσος, καθάπερ καὶ νῦν ἐστὶ, στρατηγικὴ· ὀλίγον δὲ χρόνον τὸν μεταξὺ Ἀντώνιος Κλεοπάτρα καὶ τῇ ἀδελφῇ αὐτῆς Ἀρσινόῃ παρέδωκε· καταλυθέντος δὲ ἐκείνου, συγκατελύθησαν καὶ αἱ διατάξεις αὐτοῦ πᾶσαι.

but from the time the Ptolemaic kings became established as lords of Egypt Cyprus too came into their power, the Romans often co-operating with them. But when the last Ptolemy that reigned, the brother of the father of Cleopatra, the queen in my time, was decreed to be both disagreeable and ungrateful to his benefactors, he was deposed, and the Romans took possession of the island; and it has become a praetorian province by itself. The chief cause of the ruin of the king was Publius Claudius Pulcher; for the latter, having fallen into the hands of the bands of pirates, the Cilicians then being at the height of their power, and, being asked for a ransom, sent a message to the king, begging him to send and rescue him. The king indeed sent a ransom, but so utterly small that the pirates disdained to take it and sent it back again, but released him without ransom. Having safely escaped, he remembered the favour of both; and, when he became tribune of the people, he was so powerful that he had Marcus Cato sent to take Cyprus away from its possessor. Now the king killed himself beforehand, but Cato went over and took Cyprus and disposed of the king's property and carried the money to the Roman treasury. From that time the island became a province, just as it is now—a praetorian province. During a short intervening time Antony gave it over to Cleopatra and her sister Arsinoë, but when he was overthrown his whole organisation was overthrown with him.

A PARTIAL DICTIONARY OF PROPER NAMES¹

A

ABA, queen of Oibé, 343
Abydos, 5, 19, 23, 37, 41, 43
Acamas, the promontory, 375, 381
Achilles, 15, 61, 105, 107, 110, 121, 129, 149, 151
Adelmantus of Lampsacus (see footnote 3 on p. 86), 37
Aega, the promontory, 133, 135
Aeolus, 19, 65, 105, 107, 119
Adramyttium, 9, 103, 123, 127, 129
Adramyttium, Gulf of, 13, 97, 103
Adrastus, 27, 29
Adrestus, builder of altar to Nemesis, 31
Aeolians, the, 7, 23
Aeolis, 7, 23
Aegyus, son of Nereus, founder of Priene, 190
Aeschines the orator, contemporary of Cicero, native of Miletus, 207
Aeschylus, on the Caicus River, 139
Aesepus River, the, 3, 7, 85
Agamemnon, 55, 97, 223, 233
Agapenor, on return from Troy founded Paphos, 381
Agatharchides the Peripatetic and historian (fl. apparently about 130 B.C.), native of Onidus, 283
Agathocles, son of Lysimachus, slain by his father, 165
Agrippa, transported a work of Lysippus from Lampsacus to Rome, 37
Alabanda, 27, 299
Alcaeus the poet, threw away his arms in battle, 77; on Antandrus, 101; native of Mitylené, 141; author of *Sisiotic* poems, 143; interpreted by Callias, 147
Alexander the Great, defeated satraps

of Darius, 27; visited Ilum, 51; friendly to Ilum, 55, 57; offered to restore temple of Artemis at Ephesus, 227; extended limits of refuge, 229; sacred precinct of, 239; seized Halicarnassus, 265; destroyed Mityna, 321; led phalanx against Darius from Soli, 355
Alexander Lycinus the orator, native of Ephesus, 231
Althameus the Argive, coloniser of Crete, Rhodes, and other cities, 271
Alyattes, mound of, built by prostitutes, 177, 179
Amphilochus, founder of Mallus, 353; tomb of, near Magarsa, 355
Amyntas (see *Dictionary* in vol. v), received a part of Cilicia Trachela from the Romans, 337
Anacreon the lyric poet (see *Dictionary* in vol. ii), calls Teos "Athamantis," 109; lived with tyrant Polycrates, 217; native of Teos, 237; on warlike zeal of the Carians, 301
Anaxagoras the natural philosopher, a Clazomenian, 245
Anaxarchus, companion of Alexander on Asiatic expedition, 55
Anaxenor the citharoede, exalted by Antony and consecrated to Zeus by his native land, 255
Anaximander (see *Dictionary* in vol. i), native of Miletus, 207
Anaximenes of Lampsacus, accompanied Alexander on Asiatic expedition, wrote histories of Philip and Alexander, a history of Greece in twelve books; on places called Colona, 35; a rhetorician, 37; on the colonies of Miletus, 207
Anaximenes the philosopher, native

¹ A complete index will appear in the last volume.

A PARTIAL DICTIONARY OF PROPER NAMES

- of Miletus, 207; associate of Anaxagoras, 245
- Anchialë, founded by Sardanapallus and the site of his tomb, according to Aristobulus, 341, 343
- Androchus, son of Codrus the king of Athens, leader of the Ionian colonisation and founder of Ephesus (according to Pherecydes), 199; drove Carians and Leleges out of Ephesus, 225
- Andromachë, native of Thebë, 17
- Andronicus the Peripatetic, native of Rhodes, 279
- Antandrus, 101, 103, 123
- Antigonus the son of Philip (see *Dictionary* in vol. v), founder of Alexandria in Troad, 53; founder of Antigonä (Alexandria), 65; incorporated Scopsians into Alexandria, 106; builder of new Smyrna, 245; revolted from, by Eumenes, 345
- Antimachus (see *Dictionary* in vol. iv), on the goddess Nemesis, 31
- Antimenidas, brother of Alcæus, native of Mitylenë, 141
- Antiocheia on the Maeander, 189
- Antiochus the Great (see *Dictionary* in vol. v); expelled by the Romans, 53; fought by Eumenes, 167
- Antiochus Soter (see *Dictionary* in vol. v); conquered by Eumenes, 165
- Antipater Derbetes, the tyrant, 365
- Antipater the Stoic, native of Tarsus, 347
- Antony (see *Dictionary* in vol. v), carried off statue of Aias to Aegypt, 59; carried off statues from the Heraeum, 213; increased limits of refuge at Ephesus, 229; assigned part of Cilicia to Cleopatra, 331; conferred queenship on Aba, 343; friendly to Boethus, ruler of Tarsus, 349; gave Cyprus to Cleopatra and her sister Arsinoë, 385
- Apelles the painter (see *Dictionary* in vol. v), native of Ephesus, 231; painted portrait of Antigonus and the Aphroditë Anadyomenë, 287, 289
- Apellicon of Teos, bought libraries of Aristotle and Theophrastus, 111; "a Tuiian," 230
- Aphroditë Acraea, 377
- Aphroditë the Paphian, 381
- Apocelus, the Athenian, founder of Teos, 201
- Apollo, 159, 243, 245, 317, 381; Actæus, 29; Cillicean, 123, 127; Clarius, 233; Didymæus, 205; Hecatus, 147; Larissæan, 155; Sminthian, 21, 123; Thymbraean, 69; "Ulius," 207
- Apollodorus, of Athens (see *Dictionary* in vol. i), author of works *On the Catalogue of Ships* and *A Description of the Earth*; on the term "barbarians," 303; on the Trojan allies, 357, 359; on the number of tribes in Asia Minor, 361, 363, 367; on the Trojan allies according to Homer, 369; wrongly interprets Homer's "Ascania," 371
- Apollodorus the rhetorician and philosopher, native of Pergamum, 171
- Apollonius the physician, native of Cithium, 379
- Apollonius the Stoic, best of the disciples of Panæctius, native of Nysa, 263
- Apollonius Malacus (teacher of rhetoric at Rhodes about 120 B.C.), native of Alabanda, 281; ridiculed Alabanda, 299
- Apollonius Molon of Alabanda, author of speech entitled *Against the Carians*, 297; pupil of Meneceus the orator, 281; changed his abode to Rhodes, 299
- Apollonius Mius, fellow-pupil with Heraclides the physician in time of Strabo, 243
- Apollonius Rhodius, author of the *Argonauts*, an Alexandrian but called a Rhodian, 281
- Aratus the poet, author of *The Phænomena*, native of Soli, 341
- Arcesilais, of the Academy, and fellow-student of Zeno, 131
- Archædæmus the Stoic, native of Tarsus, 347
- Archelaus, king of Cappadocia, received the whole of Cilicia Tracheia except Seleucia (from Augustus), 337, 339
- Archelaus the natural philosopher (fl. about 450 B.C.), pupil of Anaxagoras, 245
- Archilochus, on the Magnetans, 253

A PARTIAL DICTIONARY OF PROPER NAMES

- Arcus**, contemporary of Augustus, friend of Xenarchus the philosopher, 335
- Archaeanax** of Mitylené, reputed builder of wall round Sigolium, 75
- Arlon**, the citharist, native of Methymna, 145
- Aristarchus** (see *Dictionary* in vol. I), teacher of Menecrates, 263
- Aristeus** of Proconnesus (see *Dictionary* in vol. I), 33; reputed teacher of Homer, 219
- Aristobulus** (see *Dictionary* in vol. v), says that Anchiale was founded by, and was the site of tomb of, Sardannipullus, 341
- Aristoteles** the grammarian, contemporary of Strabo, native of Rhodes, 281
- Aristodemus**, son of Menecrates, teacher of Strabo at Nysa, 263
- Ariston** the Peripatetic (see footnote 3 on p. 289), 289
- Ariston**, pupil and heir of Ariston the Peripatetic, native of Oea, 289
- Aristoniceus**, caused Loucae to revolt after death of his brother Attalus Philometor, 247; ended life in prison at Rome, 249
- Aristotle**, on the Trojan walls, 1; teacher of Nelaus, 111; tarried at Assus, 115; teacher and friend of Hermecles the tyrant, 117; teacher of Theophrastus and Phanias, 145
- Artemidorus** (see *Dictionary* in vol. II), on distances between certain Aeolian cities, 159; on the restoration of temple of Ephesian Artemis, 227; ambassador to Rome, honoured at Ephesus, 233; on certain distances in Asia Minor, 307, 309, 311; on cities in the Lycian League, 315; makes Celenderis, not Coraceolum, the beginning of Cilicia, 333; on the distance from the Pyramus River to Soli, 353; falsifier of distances, 359; on the number of the tribes in Asia Minor, 361
- Artemidorus**, son of Theopompus the contemporary of Strabo, native of Cnidus, 283
- Artemidorus** the grammarian, native of Tarsus, 351
- Artemis**, 29, 207, 231; the Astyrene, 129; Cindyras, 289; Ephesian, 223, 225; Leucophryene, 251; Manychia, 223; Pergaea, 325; Sarpodonian, 357
- Artemisia**, wife of Mausolus the king of Caria, 283
- Asander** the king, slayer of Pharnaces and king of the Bosphorus, 169
- Asclepius**, born near Tricoc, 249
- Assus**, 101, 115, 129
- Astyra**, 45, 129, 131
- Athens**, 81, 83, 135, 215, 277, 325
- Athens India**, 270
- Athenaeus** the Peripatetic, contemporary of Strabo, native of Seleucia, 335
- Athenais** the prophetess (contemporary of Alexander), native of Krynthene, 243
- Athenians**, the, voted, but rescinded, disgraceful decree against the Mitylenaeans, 145; founders of Elaea, 159
- Athenodorus Cananites** (see *Dictionary* in vol. I), teacher of Augustus, native of Tarsus, 349; restored good government at Tarsus, 351
- Athenodorus Cordylion**, lived with Marcus Cato, native of Tarsus, 347
- Attalic kings**, the, 31, 150, 163
- Attalus I**, king of Pergamum (reigned 241-197 B.C.), on the Beautiful Pine, 89; transferred Gergithians of the Troad to Gergitha, 139; son of Attalus and Antiochia, 165; friend of the Romans, 167
- Attalus II**, Philadelphus, king of Pergamum (reigned 159-138 B.C.), deceived in regard to mole at mouth of Ephesian harbour, 229; settled the "Dionysiac artists" in Myonnesus, 237; Attaleia named after him, 323
- Attalus III**, Philometor, king of Pergamum (reigned 138-133 B.C.), left the Romans his heirs, 169; after his death Loucae revolted, 247

B

- Bacchylides**, on the source of the Caicus River, 137
- Bellerophon**, Palisade of, 191
- Blas**, one of the Seven Wise Men, native of Priene, 211

A PARTIAL DICTIONARY OF PROPER NAMES

Boothis, bad poet, bad citizen, and ruler of Tarsus, 349

O

Cæsar Augustus, gave back statue of Asia to Rhœtians, 50; appointed Marcus Pompey procurator of Asia, 145; pupil of Apollodorus, 171; restored statues to the Heraeum, 216; nullified extension of limits of refuge at Ephesus, 220; dedicated a painting of Apelles to his father, 289; friend of Xenarchus the philosopher, 335

Cæsar, Julius, friendly to Ilium, 55, 67; friend to Mithridates of Pergamum, 109; Trebonius one of his murderers, 247; sold wealth of Pythodorus, 267; painting by Apelles dedicated to him by his son Augustus, 289

Calcas River, the, 5, 103, 133, 137, 153, 169

Calchas the prophet, died of grief as result of contest with Mopsus the prophet, 233, 325, 353

Callias, interpreter of Sappho and Alcaeus, 147

Callimachus (see *Dictionary* in vol. I), on Creophilus of Samos, 219; comrade of the poet Heraclitus, 285

Callinus the elegiac poet, on the Tenorians, 95; on the capture of Sardis, 179; calls Ephesians "Smyrniacans," 201; on the Magnetans, 251; on the early invasion of the Cimmericians, 253; on the death of Calchas at Clarus, 325

Callisthenes (see *Dictionary* in vol. V), on the name "Adrasteia," 29; companion of Alexander, 65; on the cities united by Mausolus, 119; on the Arimi, 177; on Sardis, 179; on Phrynichus the tragic poet, 200; had false notions about the Halizones, 309

Cameirus, 275, 279

Cannæ, 5, 13, 106, 133, 141

Caresene, 87, 89

Carians, the, 117, 119, 197, 199, 215, 225, 243, 293, 301

Cato, Marcus, sent from Rome to seize Cyprus, 325

Cauconians, the 151

Cayster Plain, the, 155, 185

Celaenne, 137

Chares the Lindian, built the Colossus of Rhodes, 269

Charon the historian, on the boundaries of the Troad, 9; native of Lampsacus, 37

Cheirocrates the architect, completed the temple of Artemis at Ephesus and proposed to Alexander to fashion Mt. Athos in his likeness, 227

Obelidonian Islands, the, 263, 319

Chersiphron, first architect of temple of Artemis at Ephesus, 225

Chios, founded by Agertius, 201, 243

Chrysa, 93, 121, 123

Chrysippus, successor of Cleanthes as head of the Stoic school of philosophy, 115; native of Soli, 339

Ciliyra, 189, 193

Cicero, applauded Menippus Catocas above all Asiatic orators, 299

Cilicia Pedias, 327

Cilicia Tracheia, 311, 313, 325, 327, 337, 375

Cilicians, the, 121, 149, 163, 331

Citium, home of Zeno, 379

Clazomenae, founded by Parnus, 201, 239, 245

Cleanthes of Assus, the Stoic philosopher, successor of Zeno, 115

Cleides, the, two isles off Cyprus, 375, 379

Cleobulus, one of the Seven Wise Men, native of Lindus, 279

Cleopatra, assigned by Antony a part of Cilicia Tracheia for the building of her fleets, 331; joined Antony in conferring queenship upon Aba, 343; presented Cyprus by Antony, 385

Codrus, king of Athens, 199

Colophon, 109, 203, 233, 235

Colossus of Rhodes, the, 269

Coriscus, Socratic philosopher, 111

Cos, 287

Crates the grammarian, native of Mallus, 355

Cratippus, sons of, tyrants at Tralleis, 267

Creophilus of Samos, reputed teacher of Homer, and by Callimachus called author of the poem entitled *The Capture of Oechalia*, 219

A PARTIAL DICTIONARY OF PROPER NAMES

Orinagoras (fl. in Strabo's time), author of fifty epigrams in the Greek Anthology, native of Mitylenê, 143
 Croesus, 173; origin of wealth of, 371
 Crommyus, the promontory, 333, 377, 381
 Otasias, physician of Artaxerxes and author of works entitled *Assyrica* and *Persica*, native of Cnidus, 283
 Curetes, the, frightened Hera, 223; special college of, 225
 Curium, 379, 381
 Ocyneus, king of Colonnæ, 35
 Cydnus River, the, 343, 345, 353
 Cymê, 5, 153, 155, 161
 Cyprus, 373, 383, 385
 Cyzicênê, 5, 7, 11
 Oyzicus, 23, 33

D.

Dân of Colonnæ, on the temple of Chlaccan Apollo, 123
 Damastes (see *Dictionary* in vol. I), on the boundaries of the Troad, 9; wrong on the geographical position of Cyprus, 383
 Damasus, the Athenian, founder of Teos, 201
 Damasus Scombrus the orator, native of Tralleis, 257
 Daphilas the grammarian, reputed to have been crucified because he reviled the kings in a distich, 249
 Dardania, 47, 66, 99
 Dardanians, the, 19, 101
 Darius, father of Xerxes, burned the cities on the Propontis, 43; gave Syllon the tyranny over Samos, 219
 Delos, great slave market, 329
 Demetrius Lacon, pupil of the Epicurean Protarchus, 289
 Demetrius, son of Seleucus, helped by Attalus to defeat Alexander the son of Antiochus, 169
 Demetrius of Scepsis (see *Dictionary* in vol. I), visited Ilium, 53; on territory subject to Hector, 65; on spurs of Mt. Ida, 67; cites Hecataeus of Alexandria, 73; calls Timaeus a falsifier 77; on Mt. Ida, 85; on the Rhesus River, 87; his commentary on the *Catalogue of the*

Trojans, 91; on Antandrus, 101; on Scepsis, 105; author of *The Marshalling of the Trojan Forces*, 113; calls the Gargarians semi-barbarians, 117; on the Arimi, 177; on the Asloncis, 179; borrowed stories from Callisthenes, 369
 Diodorus the dialectician, nicknamed Cronus, contemporary of Ptolemy Soter, 291
 Diodorus the general (see footnote 2 on p. 125), 129
 Diodorus the grammarian, native of Tarsus, 351
 Diodorus the younger, of Sardis, friend of Strabo, and author of poems and historical treatises, 181
 Diodorus, the; two orators, both natives of Sardis, 179, 181
 Diodotus Tryphon, caused Syria to revolt, but was forced by Antiochus the son of Demetrius to kill himself, 327
 Diogenes the poet and itinerant philosopher, native of Tarsus, 351
 Dionysides the tragic poet, native of Tarsus, 353
 Dionysius the historian and rhetorician, contemporary of Strabo, native of Halicarnassus, 285
 Dionysius Thrax, Alexandrian but called Rhodian, 281
 Dionysodorus the orator, native of Tralleis, 257
 Dionysus, Games in honour of, 237
 Dionysus Pyriligenes, 183
 Diophanes the rhetorician, native of Mitylenê, 143
 Diotrophes of Antiocheia, teacher of Hybreas of Mylasa, 285
 Diotrophes the sophist, native of Antiocheia on the Macander, 191
 Dolabella, captured at Smyrna, and slew Trebonius, one of the murderers of Caesar, 247
 Domestus Ahenobarbus (see *Dictionary* in vol. I), opponent and slayer of Menodorus, 257

E

Egerthius, founder of Chios, 201
 Elnæ, 105, 133, 159
 Elnæssa, the island, royal residence of Archælus, 267, 337

A PARTIAL DICTIONARY OF PROPER NAMES

Elattic Gulf, the, 5, 103, 133
Ephesus, 165, 199, 201, 205, 221, 225, 237

Ephorus (see *Dictionary* in vol. I), on the extent of Aeolis, 9; on the name "Aeolis," 79; native of Cymê, 161; object of ridicule, 163; on the founding of Miletus, 205; on the number of tribes in Asia Minor, 301, 303; does not name Cappadocia, 305; on Homer's Trojan allies, 369
Epictetus the philosopher, in a sense a Lampsacenean, 37; became an ephesus at Athens, 219

Erastus, Socratic philosopher, 111
Eratosthenes (see *Dictionary* in vol. I), wrong on the geographical position of Cyprus, 38; on certain distances in Asia Minor, 311

Erythrae, founded by Onoprus the son of Codrus, 201, 239, 241

Eudemus the philosopher, native of Rhodes, 279

Eudoxus of Cnidus (see *Dictionary* in vol. I), on places on the Propontis, 9; mathematician and comrade of Plato, 283

Eumenes I, brother of Lysimachus and king of Pergamum, 165

Eumenes II, king of Pergamum, 165; received Telmessus from the Romans but later was forced to give it back to the Lycians, 317

Eumenes of Cardia (see *Dictionary* in vol. V), removed Macedonian treasures from Cyinda, 343

Euripides, on Augê the mother of Telephus, 135; on Maryas, 137; pupil of Anaxagoras, 245; quoted by Athenaeus, 336

Euthydemus, orator and statesman, contemporary of Strabo, native of Myiana, 295

F

Fimbria, Roman quaestor, destroyer of Ilium, 55

G

Gargara, 103, 117

Glaucias, the tyrant, refugee to Sidenê, 83

Granicus River, the, 5, 7, 27, 85

H

Halicarnassus, 119, 209, 283, 285

Halizones, the, 365, 369

Hannaxitus, 93, 95, 97, 101

Hecataeus (see *Dictionary* in vol. I), native of Miletus, 207; on the mountain of the Phthoires, 209; native of Teos, 239

Hecatomnos, king of the Carians, father of three sons and two daughters, 285, 296

Hector, 19, 149, 151, 153

Hedylus the elegiac poet, contemporary of Callimachus, 379

Hegesimachus, on the visit of the Galatæ to Ilium, 53

Hegesias the orator, corrupter of the Attic style, native of Magnesia, 253

Hellanicus (see *Dictionary* in vol. I), speaks to gratify the Ilians, 85; calls Assus an Aeolian city, 117; native of Lesbos, 147

Heraclides the Herophileian physician, contemporary of Strabo, native of Erythrae, 243

Heraclides of Pontus (see *Dictionary* in vol. I), on the temple of Apollo, 95

Heraclitus the poet, comrade of Callimachus, native of Halicarnassus, 285

Heraclitus the Obscure, native of Ephesus, 231

Hermocles, tyrant of Assus and Atarneus, 115, 131

Hermocrone, builder of altar at Parium, 29

Hermodorus, called by Heraclitus "the most useful man of Ephesus," and reputed to have written certain laws for the Romans, 231

Hermus River, the, 5, 13, 169, 173, 197

Herodotus, on the priestess of Athena at Pedasus, 119; on Arion of Methymna, 146; on certain rivers near Sardis, 173; on the tomb of Alyattes, 177, 179; native of Halicarnassus, 283; on the Pamphylians, 325

Herostratus, an Ephesian who in 356 B.C. set on fire the temple of Artemis at Ephesus to immortalise himself, 225

Hesiod, knew not of the god Priapus, 29; native of Cymê, 161; on the

A PARTIAL DICTIONARY OF PROPER NAMES

contest between Calchas and Mopsus, 233; says that Amphilo-
chus was slain by Apollo at Soli,
355; on the origin of the Asiatic
Magnetans, 251
Hecataeus of Alexandria, author of a
work on Homer's *Iliad*, 73
Hedreus, second son of king Heca-
tomachus, married his younger sister
Ada, 285
Hierapolis, 185, 189
Hierocles the orator, native of
Alabanda, 299
Hieronymus the philosopher, native
of Rhodes, 279
Hippocrates the great physician,
native of Cos, 289
Hipponax (see *Dictionary* in vol. iv),
on a place called Smyrna that
belonged to Ephesus, 201; on
Hins of Priene, 211; native of
Ephesus, 231
Homer, 9, 11, 15, 23, 49, 71, 81, 93,
105, 109, 117, 121, 135, 137, 153,
161, 175, 179, 219, 237, 243, 247,
273, 301, 321, 349
Hylereus, orator, statesman, con-
temporary of Strabo, native of
Mylasa, 295, 297

I

Ialysus, 275, 279
Ida, Mt., 9, 65, 85, 97
Ilia, the Village of, reputed site of
ancient Ilium, 69, 81
Ilium, territory of, 45; founded by
Ilus, 49, 53, 55, 67, 81, 153
Ion the tragic poet, native of Chios,
243
Ionia, 197
Ionian colonisation, the, 5
Ionian League, the, 201
Ionians, the, 197
Isocrates the orator, teacher of
Ephorus, 161

L

Labienna, Quintus, seized Mylasa, 297
Larius, 153, 155
Lectum, 5, 11, 13, 97, 101
Leleges, the, 17, 97, 117, 119, 121, 149,
151, 153, 199, 225, 301
Lesbians, the, 157

Lesbocles, native of Mitylené, 143
Lesbos, 7, 139, 149
Leto, the mother of Apollo and Artemis
223, 265, 267
Lindus, 275, 279
Lycia, 265, 311
Lycians, the, 19, 179
Lycian League, the, 313, 315
Lycurgus the orator, on the raising of
Ilium, 83
Lydians, the, 181
Lyrnessus, 17, 105, 107, 191, 323
Lysimachus (see *Dictionary* in vol. v,
and footnote 3 on p. 203 of vol. iii),
devoted especial attention to Ilium
and Alexandria, 53; permitted
Scopelians to return home from
Alexandria, 65; founder of the
Asclepeium, 89; king of Pergamum,
163, 165; built wall round Ephesus,
225; builder of the new Smyrna,
245; ridiculed in distich composed
by Daphitis, 251

M

Macander River, the, 185, 211, 249
Magnesia, 159
Magnesia on the Macander, 249
Malus, 353, 355
Marius Aquilius the consul (129 B.C.),
personally organised a province in
Asia Minor, 249
Marcus Perperna, made campaign
against Aristonicus and captured
him alive, 249
Mausolus, king of Caria, 119; tomb
of, 283; married his elder sister
Artemisia, 285
Melenchrus, tyrant of Mitylené, 143
Memnon of Rhodes, served Persians
as general, 117
Menander (see *Dictionary* in vol. v),
says "it (Samos) produces even
bird's milk," 217; became an
ephebus at Athens, 219
Menecles the orator, teacher of
Apollonius Malacus and Apollonius
Molon, 281; native of Alabanda, 299
Menecrates, pupil of Aristarchus,
native of Nyssa, 263
Menecrates of Elaea (see *Dictionary* in
vol. v), author of *On the Founding of
Cities*, on the Pelasgians, 157
Menippus Catoeas, the Asiatic orator,

A PARTIAL DICTIONARY OF PROPER NAMES

applauded by Cicero and native of Stratoniceia, 299
 Menodorus, contemporary of Strabo, scholar and priest, 257
 Mesogia, Mt., 213, 255, 257
 Methymna, 139, 141, 145
 Metrodorus of Lampsacus, comrade of Epicurus, 37
 Metrodorus of Scepsis, philosopher, statesman, and rhetorician, 113
 Midas, origin of wealth of, 371
 Miletus, founded by Neleus of Pylos, 199, 209, 211
 Milyas, destroyed by Alexander, 321
 Mimnermus, says that Colophon was founded by Andraemon of Pylos, 199; on Colophon, 203; native of Colophon, 235
 Minos the king, 301
 Mithridates Eupator (the Great), friend to Metrodorus, 113; the king, 181; extended limits of refuge at Ephesus, 229
 Mithridates of Pergamum, friend of Julius Caesar, 169
 Mitylené, 141
 Mopsus the prophet, victor over Calchas in contest, 233; led peoples over the Taurus, 325, 353; tomb of, near Magarsa, 355
 Murena, ended tyranny at Olbyra, 193; friend of Athenaeus the Peripatetic (contemporary of Strabo), and captured because of plot against Augustus, 335
 Myiassa, 291, 293, 295, 299
 Myrina, 159, 163
 Myron (fl. about 430 B.C.), one of the greatest Greek sculptors, 213
 Myrsilus, the historian, of Methymna, on the founders of Assus, 117
 Myrsilus, tyrant of Mitylené, 143
 Mysia, 181
 Myus, founded by Oydreus, 199, 211

N

Neleus, Socratic philosopher, pupil of Aristotle and Theophrastus, and heir to libraries of Aristotle and Theophrastus, 111
 Neocles the schoolmaster, father of Epicurus, sent by Athenians to Samos, 219
 Neoptolemus the glossographer of

Parium (see footnote 1 on p. 36), 37
 Nestor the Academician, teacher of Marcellus the nephew of Augustus, native of Tarsus and successor of Athenodorus as ruler there, 351
 Nestor, the Stoic, native of Tarsus, 347
 Nicias, contemporary of Strabo, tyrant over the Coans, 289
 Nicomedes the Bithynian, helped to overcome Aristonicus (131 B.C.), 247

P

Pamphylia, 311
 Pannectius the philosopher, native of Rhodes, 279; reputed to have been a pupil of Crates of Mallus, 355
 Paris, tomb of, 65
 Parrhasius the painter, native of Ephesus, 231
 Peiraenus, the, torn down by Sulla, 275
 Peisander the poet, author of the *Heracleia* and native of Rhodes, 281
 Pelasgians, the, 153, 155, 157, 301
 Peracra of the Rhodians, the, 263, 265, 311
 Pergamum, library of, 111, 163
 Pericles, statesman and general, subdued Samos (440 B.C.), 219
 Phanias the Peripatetic, native of Eressus, 145
 Pherecydes of Leros (see *Dictionary* in vol. v), on the Ionian seaboard, 197; on the contest between Calchas and Mopsus, 235
 Philataerus of Tefum, treasurer of Pergamum, 165
 Philemon the comic poet, native of Soli, 341
 Philotas, the poet and critic, native of Cos, 289
 Phillip, author of *The Carica*, on the Carian language, 303
 Philotas of Thebes, coloniser of Priene, 199, 211; leader of Alexander's cavalry, 355
 Phocaea, 5, 201
 Phoenix, Mt., 265
 Phrygia, 23
 Phrynon, Olympian victor, 75; Athenian general, 77
 Pinarus River, the; scene of the struggle between Alexander and Darius, 355

A PARTIAL DICTIONARY OF PROPER NAMES

Pindar, on the Pithecussae, 177; on Polymnastus the musician, 235; on the Homeridae of Ohios, 245; says that gold rained on Rhodes, 277
 Pittacus of Mitylenê, one of the Seven Wise Men, 77; born at Mitylenê, 141; one of the tyrants, 143
 Pixodarus, third son of king Hecatomnos of Caria, 285
 Plato, on the stages of civilisation, 47; teacher of Hermias the tyrant, 117
 Plutades the itinerant philosopher, native of Tarsus, 351
 Plutonium, the, near Acharaca, 259; at Hierapolis, 187
 Polemon, teacher of Zeno and Arcesilais, 131
 Polycrates (hanged 522 B.C.), tyrant of Samos, 217
 Polymedion, 101, 139
 Polymnastus, mentioned by Pindar as a famous musician and as a native of Colophon, 237
 Pompey the Great, insulted by Aeschines the orator, 209; friend of Pythodorus, 257; wiped out piracy, 315; colonised Soli, 315; friend of Theophanes the historian, 143
 Pompey, Marcus, the son of Theophanes of Mitylenê, appointed Procurator of Asia by Augustus, 145
 Poseidon, 81, 213; the Heliconian, 221
 Poseidonius (see *Dictionary* in vol. I), on brick-making in Iberia, 133; statesman at Rhodes, 279
 Potamon the rhetorician, native of Mitylenê, 143
 Praxander the Laconian, founder of Lapathus, 377
 Praxiphanes, native of Rhodes, 279
 Praxiteles the great sculptor, works of in the temple of Artemis at Ephesus, 229
 Priam, the sway of, 13, 17, 63, 81, 107, 369
 Prienê, 199, 211
 Procles, founder of Samos, 201
 Proconnesus, Old and New, 33
 Propontis, the, 3 5
 Protarchus the Epicurean, native of Bargylia and teacher of Demetrius Lacon, 289
 Protesilaus, temple of, 61
 Protogenes the painter; his *Ialysus* and his *Satyrs* at Rhodes, 269

Ptolemy, the last that reigned and uncle of Cleopatra, ruined by Publius Claudius Pulcher, 385
 Ptolemy Philadelphus, repaired Patara and called it Lycian Arsinoê, 317
 Publius Crassus, made campaign against Aristonicus, 249
 Pulcher, Publius Claudius, ruined Ptolemy the uncle of Cleopatra, 385
 Pylaeus, commander of the Lesbians, 157
 Pyrrha, 141, 145, 211
 Pythodorus, queen of the Pontus, daughter of Pythodorus the "Asiarch," 257
 Pythodorus, native of Nysa, "Asiarch" at Tralleis, friend of Pompey, extremely wealthy, and father of Queen Pythodorus, 257

R

Rhodes, 269, 273, 275
 Rhoeteium, 59, 67, 83, 85

S

Samos, founded by Tembrion and Procles, 201, 213, 215
 Sappho, on the promontory called Aega, 135; native of Mitylenê, 143; interpreted by Callias, 147
 Sardeis, 171, 173, 177
 Scamander River, the, 65, 67, 73, 85, 87
 Scepsis, 85, 101, 105, 109
 Scipio Aemilianus, sent by Romans to inspect Cilicia, 329
 Scopas the great sculptor, maker of image of Apollo, 95; maker of work containing statues of Leto and Ortygia (the nurse) with a child in each arm of the latter 223
 Scylax of Caryanda (see *Dictionary* in vol. v), on the boundaries of the Troad, 8; born at Caryanda, 289
 Seleuceia, 333, 335, 337
 Seleuceia-in-Pieria, first Syrian city after Cilicia, 357
 Seleucus Nicator, overthrew Lysimachus and was slain by Ptolemy Ceraunus 165; incompetent hereditary succession of, 329
 Servilius Isauricus, demolished Isaura

A PARTIAL DICTIONARY OF PROPER NAMES

(75 B.C.), 315; captured Olympus, the fortress of Zenicetus the pirate, 339
 Sestus, 5, 41, 43
 Sibylla the prophetess, native of Brythrae, 241
 Sigisum, 61, 67, 73, 75, 79, 85
 Sigrium, promontory of Lesbos, 139, 141, 145
 Simonides, the poet, on "porclarian" clothes, 147
 Simus the physician, native of Oea, 299
 Simus the melic poet, corrupter of the traditional style, 253
 Simmias the grammarian (fl. about 300 B.C.), native of Rhodes, 231
 Sipylus, ruler of Magnesia, 159
 Smyrna, 201, 203, 245
 Soli (Pompeopolis), 315, 339, 355
 Solmissus, Mt., 223
 Sophocles the tragic poet, on the immunity of Antenor's home, 107; helped Pericles to subdue Samos, 219; on the contest between Calchus and Mopsus, 235, 363
 Sostatus, grammarian and teacher of Pompey the Great, 263
 Stratocles the philosopher, native of Rhodes, 279
 Stratoniceia, 297, 299
 Stratoniceus the citharist, on Assus, 115; on the palences of the Caunians, 267
 Sulla, overthrew Pimbrina and came to agreement with Mithridates, 55, 59; carried off Apellion's library to Rome, 113; tore down the Peiraeus, 275
 Sylceon, brother and assistant of his brother Polycrates the tyrant of Samos, 217; later became tyrant of Samos by gift of Darius, 219
 Syrians, the, 177

T

Tamassus in Cyprus, site of copper mines, 383
 Tantalus, origin of wealth of, 369
 Tarcondimotus, named by the Romans king of Mt. Amanus, 355
 Tarsus, 343, 345, 347
 Taurus, Mt., the extremities of, 203
 Telephus the king, 135
 Temnus, birthplace of Hermagoras, author of an *Art of Rhetoric*, 169

Teos, founded at first by Athamas, 199, 237
 Teuthras, king of the Cilicians and Mysians, 135
 Terpander the musical artist, 147
 Thales, one of the Seven Wise Men, native of Miletus, 207
 Thebe, 121, 129, 149, 323
 Themistocles; his wife, or daughter, a priestess in temple of Dindymenê, 251
 Theocritus the sophist, native of Chios, 243
 Theophrastus the historian, of Mitylenê, contemporary of Strabo, 143
 Theophrastus, teacher of Neleus, 111; native of Eressus, 145
 Theopompus (see *Dictionary* in vol. I), on Sestus, 45; on Mt. Mesogis, 185; native of Chios, 243
 Theopompus, contemporary of Strabo, friend of Julius Caesar, native of Onidus, 283
 Thrasion, sculptor of chapel of Hecataë and other works at the temple of Artemis at Ephesus, 239
 Thucydides, on the seizure of Troy by the Athenians, 79; on the term "barbarians," 301, 303
 Thyateira, 171, 247
 Tiberius, friend to Marcus Pompey, 145; restorer of Sardis, 179
 Tigranes the Armenian, 115
 Timaeus the historian (see *Dictionary* in vol. II), called falsifier by Demetrius, 77; on the size of the largest of the Gymnesian Isles, 277
 Timosthenes (see *Dictionary* in vol. I), on islands between Asia and Lesbos, 147
 Timolus, Mt., 173, 183
 Tralleis, 265
 Trebonius, one of the murderers of Caesar, slain by Dolabella at Smyrna, 247
 Treres, the, 179, 251
 Troad, the, 3, 7, 21, 77
 Trojan Plain, the, 65, 67
 Trojans, the, sway and dynasties of, 5, 19, 149
 Troy, 7, 9, 15
 Typhon the giant, 177, 183
 Tyrrankon the grammarian, got possession of Apellion's library at Rome, 118

A PARTIAL DICTIONARY OF PROPER NAMES

V

Valerius Flaccus the consul, in command against Mithridates, 55

X

Xanthus, largest city in Lycia, 317

Xanthus the Lydian, ancient historian, 181, 183; on the Phrygians, 371, 373

Xenarchus the Peripatetic, contemporary of Strabo and friend of Augustus, native of Seleuceia, 335

Xenocles the orator, compared by Cicero with Menippus Oatocns, 131, 299

Xenocrates the philosopher (396-314 B.C.), at the court of Hermeias the tyrant, 117

Xenophanes, tyrant of Olbê and father of Aba, 343

Xenophanes the natural philosopher, native of Colophon, 235

Xerxes, gave Lampsacus to Themistocles, 29; bridged the "Heptastadium," 41; set fire to oracle of Apollo, 205; gave Myus, Magnesia, and Lampsacus to Themistocles, 211

Z

Zelaia, 11, 19, 25

Zenicetus the pirate, burnt himself up with his whole house, 339

Zeno the Stoic (see *Dictionary* in vol. i), native of Citium, 115, 379

Zeus, 215, 277, 343; Atabyrius, 279; Carian, 293; Ohrysaoreus, 297; Lambrandenus, 293; Osogo, 293; Stratius, 293

Zonas, one of the two Diodoruses, native of Sardeis and pleader of the cause of Asia, 181

PRINTED IN GREAT BRITAIN BY
RICHARD CLAY AND COMPANY, LTD.,
BUNGAY, SUFFOLK.



THE LOEB CLASSICAL LIBRARY

VOLUMES ALREADY PUBLISHED

Latin Authors

- AMMIANUS MARCELLINUS. Translated by J. C. Rolfe. 3 Vols.
(Vols. I. and II. 2nd Imp. revised.)
- APULEIUS: THE GOLDEN ASS (METAMORPHOSES). W. Adlington (1566). Revised by S. Gascolee. (7th Imp.)
- ST. AUGUSTINE, CONFESSIONS OF. W. Watts (1631). 2 Vols.
(Vol. I. 6th Imp., Vol. II. 5th Imp.)
- ST. AUGUSTINE, SELECT LETTERS. J. H. Baxter.
- AUSONIUS. H. G. Evelyn White. 2 Vols. (Vol. II. 2nd Imp.)
- BEDE. J. E. King. 2 Vols.
- BOETHIUS: TRACTS and DE CONSOLATIONE PHILOSOPHIAE.
Rev. H. F. Stewart and E. K. Rand. (4th Imp.)
- CAESAR: CIVIL WARS. A. G. Peskett. (4th Imp.)
- CAESAR: GALLIC WAR. H. J. Edwards. (9th Imp.)
- CATO AND VARRO: DE RE RUSTICA. H. B. Ash and W. D. Hooper. (2nd Imp.)
- CATULLUS. F. W. Cornish; TIBULLUS. J. B. Postgate; and
PERVIGILIVM VENERIS. J. W. Mackail. (11th Imp.)
- CELSUS: DE MEDICINA. W. G. Spencer. 3 Vols. (Vol. I.
3rd Imp. revised.)
- CICERO: BRUTUS, and ORATOR. G. L. Hendrickson and H. M. Hubbell. (2nd Imp.)
- CICERO: DE FINIBUS. H. Rackham. (3rd Imp. revised.)
- CICERO: DE INVENTIONE, etc. H. M. Hubbell.
- CICERO: DE NATURA DEORVM and ACADEMICA. H. Rackham.
- CICERO: DE OFFICIIS. Walter Miller. (4th Imp.)
- CICERO: DE ORATORE. 2 Vols. E. W. Sutton and H. Rackham. (2nd Imp.)
- CICERO: DE REPUBLICA and DE LEGIBUS. Clinton W. Keyes.
(3rd Imp.)
- CICERO: DE SENECTUTE, DE AMICITIA, DE DIVINATIONE.
W. A. Falconer. (5th Imp.)
- CICERO: IN CATILINAM, PRO FLACCO, PRO MURENA, PRO SULLA.
Louis E. Lord. (2nd Imp. revised.)
- CICERO: LETTERS TO ATTICUS. E. O. Winstedt. 3 Vols.
(Vol. I. 6th Imp., Vol. II. 3rd Imp. and Vol. III. 3rd Imp.)
- CICERO: LETTERS TO HIS FRIENDS. W. Glynn Williams. 3
Vols. (Vols. I. and II. 2nd Imp. revised.)
- CICERO: PHILIPPICS. W. C. A. Ker. (2nd Imp. revised.)

- CICERO: PRO ARCHIA, POST REDITUM, DE DOMO, DE HARUS-
PICUM RESPONDIS, PRO PLANCIO. N. H. Watts. (2nd Imp.)
- CICERO: PRO CAECINA, PRO LEGE MANILIA, PRO CLUENTIO,
PRO RABIRIO. H. Gross Hodge. (2nd Imp.)
- CICERO: PRO MILONE, IN PISONEM, PRO SCAURO, PRO FONTEIO,
PRO RABIRIO POSTUMO, PRO MARCELLO, PRO LIGARIO, PRO
REGE DEIOTARO. N. H. Watts.
- CICERO: PRO QUINCTIO, PRO ROSCIO AMERINO, PRO ROSCIO
COMOEDO, CONTRA RULLUM. J. H. Freese. (2nd Imp.)
- CICERO: TUSCULAN DISPUTATIONS. J. E. King. (2nd Imp.)
- CICERO: VERGINE ORATIONS. L. H. G. Greenwood. 2 Vols.
(Vol. I. 2nd Imp.)
- CLAUDIAN. M. Platnauer. 2 Vols.
- COLUMELLA: DE RE RUSTICA. H. B. Ash. 3 Vols. Vol. I.
(2nd Imp.)
- CURTIIUS, Q.: HISTORY OF ALEXANDER. J. C. Rolfe. 2 Vols.
- FLORUS. E. S. Forster, and CORNELIUS NEPOS. J. C. Rolfe.
(2nd Imp.)
- FRONTINUS: STRATAGEMS and AQUEDUCTS. C. E. Bennett and
M. B. McElwain. (2nd Imp.)
- FRONTO: CORRESPONDENCE. C. R. Haines. 2 Vols.
- GELLIUS. J. C. Rolfe. 3 Vols. (Vol. I. and II. 2nd Imp.)
- HORACE: ODES and EPODES. C. E. Bennett. (13th Imp.
revised.)
- HORACE: SATIRES, EPISTLES, ARS POETICA. H. R. Fairclough.
(6th Imp. revised.)
- JEROME: SELECTED LETTERS. F. A. Wright.
- JUVENAL and PERSIUS. G. G. Ramsay. (6th Imp.)
- LIVY. B. O. Foster, F. G. Moore, Evan T. Sage, and A. C.
Schlesinger. 14 Vols. Vols. I.-XII. (Vol. I. 3rd Imp.,
Vols. II.-V., VII., IX.-XII., 2nd Imp. revised.)
- LUCAN. J. D. Duff. (2nd Imp.)
- LUCRETIIUS. W. H. D. Rouse. (6th Imp. revised.)
- MARTIAL. W. G. A. Ker. 2 Vols. (Vol. I. 4th Imp., Vol. II.
3rd Imp. revised.)
- MINOR LATIN POETS: from PUBLILIUS SYRUS to RUTILIUS
NAMATIUS, including GRATIUS, CALPURNIUS SICULUS,
NEMESIUS, AVIANUS, and others with "Aetna" and the
"Phoenix." J. Wight Duff and Arnold M. Duff. (2nd Imp.)
- OVID: THE ART OF LOVE and OTHER POEMS. J. H. Mozley.
(3rd Imp.)
- OVID: FASTI. Sir James G. Frazer.
- OVID: HEROIDES and AMORES. Grant Showerman. (4th Imp.)
- OVID: METAMORPHOSES. F. J. Miller. 2 Vols. (Vol. I. 9th
Imp., Vol. II. 7th Imp.)
- OVID: TRISTIA and EX PONTO. A. L. Wheeler. (2nd Imp.)
- PERSIUS. Cf. JUVENAL.
- PETRONIUS. M. Heseltine; SENECA: APOCALYPTOSIS.
W. H. D. Rouse. (7th Imp. revised.)
- PLAUTUS. Paul Nixon. 5 Vols. (Vols. I. and II. 4th Imp.,
Vol. III. 3rd Imp.)

- PLINY : LETTERS. Melmoth's Translation revised by W. M. L. Hutchinson. 2 Vols. (5th Imp.)
- PLINY : NATURAL HISTORY. H. Rackham and W. H. S. Jones. 10 Vols. Vols. I.-V. H. Rackham. (Vols. I.-III. 2nd Imp.)
- PROPERTIUS. H. E. Butler. (5th Imp.)
- PRUDENTIUS. H. J. Thomson. 2 Vols. Vol. I.
- QUINTILIAN. H. E. Butler. 4 Vols. (2nd Imp.)
- REMAINS OF OLD LATIN. E. H. Warmington. 4 Vols. Vol. I. (ENNIUS AND CÆCILIUS.) Vol. II. (LIVIVS, NÆVIUS, PACUVIUS, ACCIUS.) Vol. III. (LUCILIUS and LAWS OF XII TABLES.) Vol. IV. (2nd Imp.) (ARCHAIC INSCRIPTIONS.)
- SALLUST. J. C. Rolfe. (3rd Imp. revised.)
- SCRIPTORES HISTORIAE AUGUSTAE. D. Magie. 3 Vols. (Vol. I. 2nd Imp. revised.)
- SENECA : APOCOCYNTOSIS. Cf. PETRONIUS.
- SENECA : EPISTULAE MORALES. R. M. Gummere. 3 Vols. (Vol. I. 3rd Imp., Vols. II. and III. 2nd Imp. revised.)
- SENECA : MORAL ESSAYS. J. W. Basore. 3 Vols. (Vol. II. 3rd Imp., Vol. III. 2nd Imp. revised.)
- SENECA : TRAGEDIES. F. J. Miller. 2 Vols. (Vol. I. 3rd Imp., Vol. II. 2nd Imp. revised.)
- SIDONIUS : POEMS and LETTERS. W. B. Anderson. 2 Vols. Vol. I.
- SILIUS ITALICUS. J. D. Duff. 2 Vols. (Vol. I. 2nd Imp., Vol. II. 3rd Imp.)
- STATIUS. J. H. Mozley. 2 Vols.
- SUETONIUS. J. C. Rolfe. 2 Vols. (Vol. I. 6th Imp., Vol. II. 5th Imp. revised.)
- TACITUS : DIALOGUS. Sir Wm. Peterson. AGRICOLA and GERMANIA. Maurice Hutton. (6th Imp.)
- TACITUS : HISTORIES and ANNALS. C. H. Moore and J. Jackson. 4 Vols. (Vols. I. and II. 2nd Imp.)
- TERENCE. John Sargeaunt. 2 Vols. (6th Imp.)
- TERTULLIAN : APOLOGIA and DE SPECTACULIS. T. R. Glover.
- MINUCIUS FELIX. G. H. Rendall.
- VALERIUS FLACCIUS. J. H. Mozley. (2nd Imp. revised.)
- VARRO : DE LINGUA LATINA. R. G. Kent. 2 Vols. (2nd Imp.)
- VELLEIUS PATERCULUS and RES GESTAE DIVI AUGUSTI. F. W. Shipley.
- VIRGIL. H. R. Fairclough. 2 Vols. (Vol. I. 16th Imp., Vol. II. 12th Imp. revised.)
- VITRUVIUS : DE ARCHITECTURA. F. Granger. 2 Vols. (Vol. I. 2nd Imp.)

Greek Authors

- ACHILLES TATIUS. S. Gaselee. (2nd Imp.)
- AENEAS TACTICUS, ASCLEPIODOTUS and ONASANDER. The Illinois Greek Club. (2nd Imp.)
- AESCHINES. C. D. Adams. (2nd Imp.)
- AESCHYLUS. H. Weir Smyth. 2 Vols. (Vol. I. 5th Imp., Vol. II. 4th Imp.)
- ALCIPHILON, AELIAN, PHILOSTRATUS: LETTERS. A. R. Benner and F. H. Forbes.
- ANDOCIDES, ANTIPHON. Cf. MINOR ATTIC ORATORS.
- APOLLODORUS. Sir James G. Frazer. 2 Vols. (2nd Imp.)
- APOLLONIUS RHODIUS. R. C. Seaton. (4th Imp.)
- THE APOSTOLIC FATHERS. Kirsopp Lake. 2 Vols. (Vol. I. 6th Imp., Vol. II. 5th Imp.)
- APPIAN'S ROMAN HISTORY. Horace White. 4 Vols. (Vol. I. 3rd Imp., Vols. II., III. and IV. 2nd Imp.)
- ARATUS. Cf. CALLIMACHUS.
- ARISTOPHANES. Benjamin Bickley Rogers. 3 Vols. Verse trans. (4th Imp.)
- ARISTOTLE: ART OF RHETORIC. J. H. Freese. (3rd Imp.)
- ARISTOTLE: ATHENIAN CONSTITUTION, EUDEMIAN ETHICS, VICES AND VIRTUES. H. Rackham. (2nd Imp.)
- ARISTOTLE: GENERATION OF ANIMALS. A. L. Peck. (2nd Imp.)
- ARISTOTLE: METAPHYSICS. H. Tredennick. 2 Vols. (Vol. I. 3rd Imp., Vol. II. 2nd Imp.)
- ARISTOTLE: MINOR WORKS. W. S. Hett. On Colours, On Things Heard, On Physiognomies, On Plants, On Marvellous Things Heard, Mechanical Problems, On Indivisible Lines, On Position and Names of Winds.
- ARISTOTLE: NICOMACHEAN ETHICS. H. Rackham. (5th Imp. revised.)
- ARISTOTLE: OECONOMICA and MAGNA MORALIA. G. C. Armstrong; (with Metaphysics, Vol. II.). (2nd Imp.)
- ARISTOTLE: ON THE HEAVENS. W. K. C. Guthrie. (2nd Imp. revised.)
- ARISTOTLE: ON THE SOUL, PARVA NATURALIA, ON BREATH. W. S. Hett. (2nd Imp. revised.)
- ARISTOTLE: ORGANON. H. P. Cooke and H. Tredennick. 2 Vols. (Vol. I. 2nd Imp.)
- ARISTOTLE: PARTS OF ANIMALS. A. L. Peck; MOTION AND PROGRESSION OF ANIMALS. E. S. Forster. (2nd Imp. revised.)
- ARISTOTLE: PHYSICS. Rev. P. Wicksteed and F. M. Cornford. 2 Vols. (2nd Imp.)
- ARISTOTLE: POETICS and LONGINUS. W. Hamilton Fyfe; DEMETRIUS ON STYLE. W. Rhys Roberts. (3rd Imp. revised.)
- ARISTOTLE: POLITICS. H. Rackham. (3rd Imp. revised.)
- ARISTOTLE: PROBLEMS. W. S. Hett. 2 Vols. (Vol. I. 2nd Imp. revised.)

- ARISTOTLE: RHETORICA AD ALEXANDRUM (with PROBLEMS, Vol. II.). H. Rackham.
- ARRIAN: HISTORY OF ALEXANDER and INDICA. Rev. E. Iliffe Robson. 2 Vols. (2nd Imp.)
- ATHENAEUS: DEIPNOSOPHISTAE. C. B. Gulick. 7 Vols. (Vols. I., V., and VI. 2nd Imp.)
- ST. BASIL: LETTERS. R. J. Deferrari. 4 Vols. (Vols. I., II. and IV. 2nd Imp.)
- CALLIMACHUS and LYCOPHRON. A. W. Mair; ARATUS. G. R. Mair. (2nd Imp.)
- CLEMENT OF ALEXANDRIA. Rev. G. W. Butterworth. (2nd Imp.)
- COLLUTHUS. Cf. OPIAN.
- DAPHNIS AND CHLOE. Thornley's Translation revised by J. M. Edmonds; and PARTHENIUS. S. Gaselee. (3rd Imp.)
- DEMOSTHENES I: OLYNTHIACS, PHILIPPICS and MINOR ORATIONS: I.-XVII. and XX. J. H. Vince.
- DEMOSTHENES II: DE CORONA and DE FALSA LEGATIONE. C. A. Vince and J. H. Vince. (2nd Imp. revised.)
- DEMOSTHENES III: MEIDIAS, ANDROTION, ARISTOCRATES, TIMOCRATES and ARISTOGEITON, I. and II. J. H. Vince.
- DEMOSTHENES IV-VI: PRIVATE ORATIONS and IN NEAERAM. A. T. Murray. (Vol. I. 2nd Imp.)
- DEMOSTHENES VII: FUNERAL SPEECH, EROTTIO ESSAY, EXORDIA and LETTERS. N. W. and N. J. DeWitt.
- DIO CASSIUS: ROMAN HISTORY. E. Cary. 9 Vols. (Vols. I. and II. 2nd Imp.)
- DIO CHRYSOSTOM. J. W. Cohoon and H. Lamar Crosby. 5 Vols. Vols. I.-IV. (Vols. I. and II. 2nd Imp.)
- DIODORUS SICULUS. 12 Vols. Vols. I.-IV. C. H. Oldfather. Vol. IX. R. M. Geer. (Vol. I. 2nd Imp.)
- DIODEGENES LAERTIUS. R. D. Hicks. 2 Vols. (Vol. I. 3rd Imp., Vol. II. 2nd Imp.)
- DIONYSIUS OF HALICARNASSUS: ROMAN ANTIQUITIES. Spelman's translation revised by E. Cary. 7 Vols. Vols. I.-VI. (Vol. IV. 2nd Imp.)
- EPICTETUS. W. A. Oldfather. 2 Vols. (Vols. I. and II. 2nd Imp.)
- EURIPIDES. A. S. Way. 4 Vols. (Vols. I. and II. 6th Imp., Vols. III. and IV. 5th Imp.) Verse trans.
- EUSEBIUS: ECCLESIASTICAL HISTORY. Kirsopp Lake and J. E. L. Oulton. 2 Vols. (Vol. I. 2nd Imp., Vol. II. 3rd Imp.)
- GALEN: ON THE NATURAL FACULTIES. A. J. Brock. (3rd Imp.)
- THE GREEK ANTHOLOGY. W. R. Paton. 5 Vols. (Vols. I. and II. 4th Imp., Vols. III. and IV. 3rd Imp.)
- GREEK ELEGY AND IAMBUS with the ANACREONTEA. J. M. Edmonds. 2 Vols. (Vol. I. 2nd Imp.)
- THE GREEK BUCOLIC POETS (THEOCRITUS, BION, MOSCHUS). J. M. Edmonds. (6th Imp. revised.)

- GREEK MATHEMATICAL WORKS. Ivor Thomas. 2 Vols. (2nd Imp.)
- HERODES. Cf. THEOPHRASTUS: CHARACTERS.
- HERODOTUS. A. D. Godley. 4 Vols. (Vol. I. 4th Imp., Vols. II.-IV. 3rd Imp.)
- HESIOD and THE HOMERIC HYMNS. H. G. Evelyn White. (6th Imp. revised and enlarged.)
- HIPPOCRATES and the FRAGMENTS OF HERACLEITUS. W. H. S. Jones and E. T. Withington. 4 Vols. (Vol. I. 3rd Imp., Vols. II.-IV. 2nd Imp.)
- HOMER: ILIAD. A. T. Murray. 2 Vols. (6th Imp.)
- HOMER: ODYSSEY. A. T. Murray. 2 Vols. (7th Imp.)
- ISAEUS. E. W. Forster. (2nd Imp.)
- ISOCRATES. George Norlin and Lukus Van Hook. 3 Vols.
- ST. JOHN DAMASCENE: BARLAAM AND IOANAPH. Rev. G. R. Woodward and Harold Mattingly. (2nd Imp. revised.)
- JOSEPHUS. H. St. J. Thackeray and Ralph Marcus. 9 Vols. Vols. I.-VII. (Vol. V. 3rd Imp., Vol. VI. 2nd Imp.)
- JULIAN. Wilmer Cave Wright. 3 Vols. (Vol. I. 2nd Imp., Vol. II. 3rd Imp.)
- LUCIAN. A. M. Harmon. 8 Vols. Vols. I.-V. (Vols. I-III. 3rd Imp.)
- LYCOPHRON. Cf. CALLIMACHUS.
- LYRA GRAECA. J. M. Edmonds. 3 Vols. (Vol. I. 3rd Imp., Vol. II. 2nd Ed. revised and enlarged, Vol. III. 3rd Imp. revised.)
- LYSIAS. W. R. M. Lamb. (2nd Imp.)
- MANETHO. W. G. Waddell: PROLEMY: TETRABIBLOS. F. E. Robbins. (2nd Imp.)
- MARCUS AURELIUS. C. R. Haines. (3rd Imp. revised.)
- MENANDER. F. G. Allinson. (2nd Imp. revised.)
- MINOR ATTIC ORATORS (ANTIPHON, ANDOCIDES, DEMADES, DEINARCHUS, HYPERIDES). K. J. Maidment and J. O. Burtt. 2 Vols. Vol. I. K. J. Maidment.
- NONNOS. W. H. D. Rouse. 3 Vols. (Vol. III. 2nd Imp.)
- OPPIAN, COLLUTRUS, TRYPHIODORUS. A. W. Mair.
- PAPYRI. NON-LITERARY SELECTIONS. A. S. Hunt and C. C. Edgar. 2 Vols. (Vol. I. 2nd Imp.) LITERARY SELECTIONS. Vol. I. (Poetry). D. L. Page.
- PARTHENIUS. Cf. DAPHNIS AND CHLOE.
- PAUSANIAS: DESCRIPTION OF GREECE. W. H. S. Jones. 5 Vols. and Companion Vol. (Vols. I. and III. 2nd Imp.)
- PHILO. 11 Vols. Vols. I.-V.; F. H. Colson and Rev. G. H. Whitaker. Vols. VI.-IX.; F. H. Colson. (Vols. I., II., V., VI. and VII. 2nd Imp., Vol. IV. 3rd Imp.)
- PHILOSTRATUS: THE LIFE OF APOLLONIUS OF TYANA. F. C. Conybeare. 2 Vols. (Vol. I. 4th Imp., Vol. II. 3rd Imp.)
- PHILOSTRATUS: IMAGES; CALLISTRATUS: DESCRIPTIONS. A. Fairbanks.
- PHILOSTRATUS and EUNAPIUS: LIVES OF THE SOPHISTS. Wilmer Cave Wright. (2nd Imp.)

- PINDAR. Sir J. E. Sandys. (*7th Imp. revised.*)
- PLATO : CHARMIDES, ALCIBIADES, HIPPARCHUS, THE LOVERS, THEAGES, MINOS and EPINOMIS. W. R. M. Lamb.
- PLATO : CRATYLUS, PARMENIDES, GREATER HIPPIAS, LESSER HIPPIAS. H. N. Fowler. (*2nd Imp.*)
- PLATO : EUTHYPHRO, APOLOGY, CRITO, PHAEDO, PHAEDRUS. H. N. Fowler. (*9th Imp.*)
- PLATO : LACHES, PROTAGORAS, MENO, EUTHYDEMUS. W. R. M. Lamb. (*2nd Imp. revised.*)
- PLATO : LAWS. Rev. R. G. Bury. 2 Vols. (*2nd Imp.*)
- PLATO : LYSIS, SYMPOSIUM, GORGIAS. W. R. M. Lamb. (*4th Imp. revised.*)
- PLATO : REPUBLIC. Paul Shorey. 2 Vols. (Vol. I. *4th Imp.*, Vol. II. *3rd Imp.*)
- PLATO : STATESMAN, PHILEBUS. H. N. Fowler; ION. W. R. M. Lamb. (*3rd Imp.*)
- PLATO : THEAETETUS and SOPHIST. H. N. Fowler. (*3rd Imp.*)
- PLATO : TIMAEUS, CRITIAS, CLITOPHO, MENEXENUS, EPISTULAE. Rev. R. G. Bury. (*2nd Imp.*)
- PLUTARCH : MORALIA. 14 Vols. I.-V. F. C. Babbitt; Vol. VI. W. C. Helmbold; Vol. X. H. N. Fowler. (Vols. I., III., and X. *2nd Imp.*)
- PLUTARCH : THE PARALLEL LIVES. B. Perrin. 11 Vols. (Vols. I., II., and VII. *3rd Imp.*, Vols. III., IV., VI., and VIII.-XI. *2nd Imp.*)
- POLYBIUS. W. R. Paton. 6 Vols.
- PROCOPIUS : HISTORY OF THE WARS. H. B. Dewing. 7 Vols. (Vol. I. *2nd Imp.*)
- PTOLEMY : TETRABIBLOS. Cf. MANETHO.
- QUINTUS SMYRNAEUS. A. S. Way. Verse trans. (*2nd Imp.*)
- SEXTUS EMPIRICUS. Rev. R. G. Bury. 4 Vols. (Vol. III. *2nd Imp.*)
- SOPHOCLES. F. Storr. 2 Vols. (Vol. I. *7th Imp.*, Vol. II. *5th Imp.*) Verse trans.
- STRABO : GEOGRAPHY. Horace L. Jones. 8 Vols. (Vols. I. *3rd Imp.*, Vols. II., V., VI., and VIII. *2nd Imp.*)
- THEOPHRASTUS : CHARACTERS. J. M. Edmonds; HERODES, etc. A. D. Knox. (*2nd Imp.*)
- THEOPHRASTUS : ENQUIRY INTO PLANTS. Sir Arthur Hort, Bart. 2 Vols. (*2nd Imp.*)
- THUCYDIDES. C. F. Smith. 4 Vols. (Vol. I. *3rd Imp.*, Vols. II., III. and IV. *2nd Imp. revised.*)
- TRYPHODORUS. Cf. OPIAN.
- XENOPHON : CYROPAEDIA. Walter Miller. 2 Vols. (*3rd Imp.*)
- XENOPHON : HELLENICA, ANABASIS, APOLOGY, and SYMPOSIUM. C. L. Brownson and O. J. Todd. 3 Vols. (*3rd Imp.*)
- XENOPHON : MEMORABILIA and OECONOMICS. E. C. Marchant. (*2nd Imp.*)
- XENOPHON : SCRIPTA MINORA. E. C. Marchant. (*2nd Imp.*)

IN PREPARATION

Greek Authors

ARISTOTLE : DE MUNDO, ETC. D. Furley and E. M. Forster.
ARISTOTLE : HISTORY OF ANIMALS. A. L. Peck.
ARISTOTLE : METEOROLOGICA. H. P. Lee.
PLOTINUS.


Latin Authors


ST. AUGUSTINE : CITY OF GOD.
[CICERO] : AD HERENNIIUM. H. Caplan.
CICERO : PRO SESTIO, IN VATINIUM, PRO CAELIO, DE PROVINCIIS
CONSULARIBUS, PRO BALBO. J. H. Freese and R. Gardner.
PHAEDRUS. Ben E. Perry.

DESCRIPTIVE PROSPECTUS ON APPLICATION

London - - - - WILLIAM HEINEMANN LTD
Cambridge, Mass. - - HARVARD UNIVERSITY PRESS







CENTRAL ARCHAEOLOGICAL LIBRARY,
NEW DELHI

Issue Record.

Catalogue No. 910/Str/Jon.-2318.

Author— Strabo.

Title— Geography of Strabo.
Vol. VI.

Borrower No.

Date of Issue

Date of Return

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.